

ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING A DEDICATED 3/4" CONDUIT FROM AN ACCESSIBLE LOC TO EACH "IT" DEVICE IN THE HIGH AREA OF THE GYM.

SEE ARCHITECTURAL SHEET SECTIONS FOR RECEPTACLE AND DATA MOUNTING HEIGHTS AND LOCATIONS PRIOR TO ANY ROUGH-INS.

IT CONTRACTOR IS RESPONSIBLE FOR THE BACK, THE PATCH PANEL, THE OUTLETS AND THE CAT-5 CABLE FROM EACH OUTLET TO THE AV/IT ROOM. LEAVE 48" OF SLACK, LABEL AND TEST EACH CABLE. CONDUIT TO PROVIDE EQUIPMENT AND MAKE FINAL TERMINATIONS.

IT CONTRACTOR TO PROVIDE (20) HEARING AIDS TO BE PLACED IN THE GYMNASIUM.

