

Hite associates

ARCHITECTURE / PLANNING / TECHNOLOGY

ADDENDUM NO. 2

September 11, 2023

**Project: Community Center & Gymnasium for Pitt County Office Park Complex
Pitt County, North Carolina**

TO: ALL BIDDERS

The following items clarify, add to, delete from, and / or otherwise change and supersede information previously issued to you in the bidding documents for the referenced project. Please read them carefully and adjust your bid accordingly.

Please note that addendums, and all revised documents are available via Hite Associates website www.hiteassoc.com under the "Contractor Resources" link.

ADDENDUM NO. 2:

1. Specification 08800 Glass and Glazing: Interior Impact Resistant glass is further described.
2. Specification 11150 Basketball Goals, Scoreboards and Athletic Equipment: Scoreboard wireless controller is revised to Model MP-80. Shot clock shall be wireless, and hand switch is revised to Model HS-80. Goal Lights model is revised to wireless Model GL-7248-RF, for all back boards.
3. Drawing C-101: Revised gravel path. Added concrete walkway along Old Creek Road ROW per City of Greenville.
4. Drawing C-201: Revised gravel path. Added concrete walkway along Old Creek Road ROW per City of Greenville. Grades are revised along concrete walk. Revised water main fire line.
5. Drawing L-101: Revised to reflect revisions to C-101 and C-201.
6. Drawings A-101, A-102, A-401, A-402: Pre-engineered rigid frames are revised to be 12" deep in Gymnasium 114, boxed in with metal stud framing and 5/8" impact resistant gypsum wall board, to 14'-0" A.F.F. Exposed corners to be trimmed out with the specified corner guards. Bleachers top row to be notched (custom cut out) for described frame column wraps.
7. Drawing A-105 Clarification: Glazed Partition framing and door frame 105A for Manager 105 is aluminum storefront door frame and framing.
8. Drawing A-301, Door Schedule: Doors 114A and 114B are changed to door type AL-4 aluminum wide stile with impact resistant glass. Door Type AL-4 is added.

COMMUNITY CENTER AND GYMNASIUM FOR PITT COUNTY OFFICE PARK COMPLEX

9. Drawing PME-001 Clarification: Electrical subcontractor provides site lighting fixtures, poles, and pole bases, complete assemblies, as indicated on PME-001.
10. Drawing P-102: Moved a branch valve and added a pipe size.
11. Drawing E-001: Revised the Riser Diagram to make the MDP a Main Circuit Breaker panel and to make P1 a 125A MLO panel. Revised the associated feeder size for P1. Eliminated General Note #39 that required the service conductors to be in concrete. Not required by GUC.
12. Drawing E-101A: Updated the panel schedules for the MDP and P1 changes.
13. Drawing E-102: Added the Keyed switches for the motorized goals.

END OF ADDENDUM NO. 2



James G. Hite, AIA, Project Architect
Hite Associates, PC

BIDDERS PLEASE NOTE THAT REFERENCED REVISED DOCUMENTS AND DRAWING REVISIONS ARE MARKED AS SUCH ON THE REVISION BLOCK ON THE PLANS AND ARE TO BE ACCESSED ON THE HITE ASSOCIATES WEBSITE.

Revised / Added Documents:

Pitt County Complex Gym: Specification 08800 Glass and Glazing
Pitt County Complex Gym: Section 11150 Basketball Goals, Scoreboards, Athletic Equipment
Pitt County Complex Gym Drawing C-101
Pitt County Complex Gym Drawing C-201
Pitt County Complex Gym Drawing L-101
Pitt County Complex Gym Drawings A-101, A-102, A-401, A-402
Pitt County Complex Gym Drawing A-301, Door Schedule
Pitt County Complex Gym Drawing P-102
Pitt County Complex Gym Drawing E-001
Pitt County Complex Gym Drawing E-101A
Pitt County Complex Gym Drawing E-102

cc: All Attendees / All Bidders / Tim Corley / Austin Long

dist.: JGH / RBE / TS / WP / File: Bids & Addenda