LEE COUNTY SCHOOLS
INSPIRED.

Transportation Facility

New Building

Lee County Board of Education
Sanford, NC

PROJECT MANUAL
VOLUME 1

(1 of 2)
Divisions 00 through 13

Bid Documents

2026.06.25

CRA Associates, Inc
100 Europa Drive, Suite 565, Chapel Hill, NC 27517
Project No. 2514

DOCUMENT 000107 - SEALS PAGE

1.1 DESIGN PROFESSIONALS OF RECORD

A. Architect:

1. Theodore B. Clippinger.
2. 13996.
3. Responsible for Divisions 01-33 Sections except where indicated as prepared by other design professionals of record.

B. Civil Engineer:

1. William P. Altman.
2. 045892.
3. Responsible for Section 024113 and Divisions 31, 32 & 33.

C. Structural Engineer:

1. Diane Thompson.
2. 036153.
3. Responsible for Sections 014500, 033000, 051200 & 053100.

D. Fire-Protection Engineer:

1. Mark R. McDowell.
2. 024539.
3. Responsible for Division 21.

E. Plumbing Engineer:

1. Mark R. McDowell.
2. 024539.
3. Responsible for Divisions 22 & 24.

F. HVAC Engineer:

1. Daniel J. Myers.
2. 53041.
3. Responsible for Division 23.

G. Electrical Engineer:

1. Jason S. Denton.
2. 035223.
3. Responsible for Divisions 26, 27 & 28.



END OF DOCUMENT 000107

TABLE OF CONTENTS

VOLUME 1

DIVISION 00-PROCUREMENT AND CONTRACTING REQUIREMENTS

001113	Advertisement for Bids……	001113-1 thru 2
002113	Instructions to Bidders, Lee County Schools…….	002113-1 thru 13
002600	Procurement Substitution Procedures……..	002600-1 thru 2
003132	Geotechnical Data…….003132-1 only	
003132A	Limited Soils Assessment Letter……003132A-1 thru 65	
004113	Bid Form -Single-Prime Contract……004113-1 thru 2	
004213	Non-Collusion Affidavit…….	004213-1 thru 2
004313	Bid Bond…….	004313-1 only
004393	Bid Submittal Checklist……..	004393-1 thru 2
004336	MBE Participation Requirements……	004336-1 only
004539	Identification of Minority Business Participation and MBE Participation Forms……	004539-1 thru 7

General Conditions…….. 72 pp
Supplemental Conditions…… 2 pp
Form of Owner-Contractor Agreement ……..… 5 pp
Form of Performance Bond and Form of Labor and Material Payment Bond ……..… 5 pp

DIVISION 01 - GENERAL REQUIREMENTS

011000	Summary…….	011000-1 thru 3
012300	Alternates……..012300-1 thru 3	
012500	Substitution Procedures……	012500-1 thru 3
012600	Contract Modification Procedures……012600-1 thru 3	
012900	Payment Procedures…….	012900-1 thru 4
013100	Project Management and Coordination……	013100-1 thru 8
013200	Construction Progress Documentation…….	013200-1 thru 6
013300	Submittal Procedures……	013300-1 thru 9
014000	Quality Requirements……..	014000-1 thru 7
014200	References……	014200-1 thru 2
014500	Inspection Requirements……..	014500-1 thru 11
015000	Temporary Facilities and Controls……015000-1 thru 8	
016000	Product Requirements……..	016000-1 thru 7
017300	Execution……..017300-1 thru 8	
017700	Closeout Procedures…….	017700-1 thru 5
017823	Operation and Maintenance Data……	017823-1 thru 7
017839	Project Record Documents……..	017839-1 thru 4
017900	Demonstration and Training……	017900-1 thru 7

DIVISION 02 – EXISTING CONDITIONS

024113	Selective Site Demolition…….024113-1 thru 7	

DIVISION 03 – CONCRETE

033000 Cast-in-Place Concrete……. 033000-1 thru 16
035300 Concrete Topping……. 035300-1 thru 5

DIVISION 04 – MASONRY

042000 Unit Masonry…… 042000-1 thru 18

DIVISION 05 – METALS

051200 Structural Steel……. 051200-1 thru 9
053100 Steel Deck……053100-1 thru 6
055000 Metal Fabrications…… 055000-1 thru 11
055113 Metal Pan Stairs……055113-1 thru 10

DIVISION 06 – WOOD AND PLASTICS

061053 Miscellaneous Rough Carpentry……. 061053-1 thru 6
064116 Plastic-Laminate-Clad Architectural Cabinets…… 064116-1 thru 7

DIVISION 07 – BUILDING ENVELOPE

072100 Thermal Insulation……072100-1 thru 7
075419 Polyvinyl-Chloride (PVC) Roofing……..075419-1 thru 10
077253 Snow Guards…… 077253-1 thru 3
079100 Preformed Joint Seals…….. 079100-1 thru 4
079200 Joint Sealants…… 079200-1 thru 12
079219 Acoustical Joint Sealant……079219-1 thru 4

DIVISION 08 – DOORS AND WINDOWS

081113 Hollow Metal Doors and Frames……. 081113-1 thru 8
081416 Flush Wood Doors……081416-1 thru 7
083323 Overhead Coiling Doors…….. 083323-1 thru 8
084113 Aluminum Framed Entrances and Storefronts…… 084113-1 thru 12
085113 Aluminum Windows……085113-1 thru 8
085619 Pass Windows…….. 085619-1 thru 3
087100 Door Hardware…… 087100-1 thru 30
088000 Glazing……. 088000-1 thru 10

DIVISION 09 – FINISHES

092216 Non-Structural Metal Framing……. 092216-1 thru 7
092900 Gypsum Board……. 092900-1 thru 8
093013 Ceramic Tiling……. 093013-1 thru 13
095113 Acoustical Panel Ceilings…… 095113-1 thru 8
096513 Resilient Base and Accessories…… 096513-1 thru 5
096519 Resilient Tile Flooring……096519-1 thru 6
096723 Resinous Flooring……096723-1 thru 5
097700 Special Ceiling Surfacing……. 097700-1 thru 5

DIVISION 09 – FINISHES (CONTINUED)

099110	Exterior Painting……..	099110-1 thru	10
099120	Interior Painting……	099120-1 thru	12

DIVISION 10 – SPECIALTIES

101100	Visual Display Units……	101100-1 thru	6
101419	Dimensional Letter Signage……..	101419-1 thru	5
102113.19	Plastic Toilet Compartments……	102113.19-1 thru	5
102239	Folding Panel Partitions……	102239-1 thru	8
102800	Toilet Accessories……	108101-1 thru	9
103500	Flagpoles……..	103500-1 thru	4
104413	Fire Protection Cabinets……	104413-1 thru	5
104416	Fire Extinguishers……	104416-1 thru	3
105113	Metal Lockers……..	105113-1 thru	7

DIVISION 11 – EQUIPMENT

117000	Equipment Schedule……	117000-1 only	
117001	Storage Equipment……	117001-1 thru	24
117310	Vehicle Lifts……..	117310-1 thru	8
117510	Shop Equipment……	117510-1 thru	25
117515	Fabricated Equipment……..	117515-1 thru	4
111790	Relocation of Existing Equipment……	117900-1 thru	2

DIVISION 13 – SPECIAL CONSTRUCTION

133419	Metal Building Systems……	133419-1 thru	27

END OF VOLUME 1 TABLE OF CONTENTS

VOLUME 2

DIVISION 21 – FIRE PROTECTION SYSTEMS

210000	Common Work Results for Fire protection……..	210000-1 thru 12
210080	Project Record Documents……..	210080-1 thru 3
210100	Penetration Firestopping……..	210100-1 thru 2
210548	Vibration and Seismic Controls for Fire-Suppression Piping and Equipment……	210548-1 only
211000	Water-Based Fire-Suppression Systems…….	211000-1 thru 10

DIVISION 22 – PLUMBING SYSTEMS

220080	Project Record Documents……..	220080-1 thru 3
220100	Penetration Firestopping……..	220100-1 thru 2
220500	Common Work Results for Plumbing…….	220500-1 thru 12
220513	Common Motor Requirements for Plumbing Equipment……	220513-1 thru 2
220516	Expansion Fittings and Loops for Plumbing Piping……	220516-1 thru 3
220519	Meters and Gages for Plumbing Piping……	220519-1 thru 2
220523	General-Duty Valves for Plumbing Piping……..	220523-1 thru 6
220529	Hangers and Supports for Plumbing Piping and Equipment……	220529-1 thru 6
220548	Vibration and Seismic Controls for Plumbing Piping and Equipment……	220548-1 thru 3
220553	Identification for Plumbing and Equipment……	220553-1 thru 4
220700	Plumbing Insulation……..	220700-1 thru 8
221113	Facility Water Distribution Piping……	221113-1 thru 8
221116	Domestic Water Piping……	221116-1 thru 8
221119	Domestic Water Piping Specialties……..	221119-1 thru 7
221123	Domestic Water Pumps……	221123-1 thru 3
221316	Drain, Waste and Vent Piping…….	221316-1 thru 4
221319	Sanitary Waste Piping Specialties……	221319-1 thru 4
221413	Facility Storm Drainage Piping……	221413-1 thru 3
221423	Storm Drainage Piping Specialties……..	221423-1 thru 3
223400	High Efficiency Gas Domestic Water Heaters……	223400-1 thru 10
224000	Plumbing Fixtures……	224000-1 thru 5
224500	Emergency Plumbing Fixtures……	224500-1 thru 3
224700	Water Coolers……..	224700-1 thru 2

DIVISION 23 – HEATING, VENTILATING AND AIR CONDITIONING (HVAC)

230000	General Requirements for HVAC Work……..	230000-1 thru 16
230100	Penetration Firestopping……..	230100-1 thru 3
230500	Common Work Results for HVAC……..	230500-1 thru 7
230513	Common Motor Requirements for HVAC Equipment……	230513-1 thru 2
230517	Sleeves and Sleeve Seals for HVAC Piping……	230517-1 thru 4
230518	Escutcheons for HVAC Piping……	230518-1 thru 2
230529	Hangers and Supports for HVAC Piping and Equipment……	230529-1 thru 10
230548.13	Vibration Controls for HVAC……	230548.13-1 thru 8
230553	Identification for HVAC Piping and Equipment…….	230553-1 thru 5

DIVISION 23 – HEATING, VENTILATING AND AIR CONDITIONING (CONTINUED)

230566	Antimicrobial Ultraviolet Lamp Systems for HVAC	230566-1 thru	6
230593	Testing, Adjusting, and Balancing for HVAC	230593-1 thru	15
230700	HVAC Insulation	230700-1 thru	19
230713	Duct Insulation	230713-1 thru	18
230716	HVAC Equipment Insulation	230716-1 thru	17
230900	Instrumentation and Control for HVAC	230900-1 thru	6
230923	Direct Digital Control (DDC) System for HVAC	230923-1 thru	29
230923.12	Control Dampers	230923-12-1 thru	12
230923.13	Energy Meters	230923.13-1 thru	7
230923.27	Temperature Instruments	230923.27-1 thru	15
230993.01	Sequence of Operations for DOAS Units	230993.01-1 thru	7
230993.02	Sequence of Operations for Split System HP's	230993.02-1 thru	2
233993.11	Sequence of Operations for HVAC DDC	230993.11-1 only	
231123	Facility Natural-Gas Piping	231123-1 thru	15
232300	Refrigerant Piping	232300-1 thru	8
233113	Metal Ducts	233113-1 thru	19
233300	Air Duct Accessories	233300-1 thru	13
233346	Flexible Ducts	233346-1 thru	3
233413	Axial HVAC Fans	233413-1 thru	8
233416	Centrifugal HVAC Fans	233416-1 thru	5
233423	HVAC Power Ventilators	233423-1 thru	5
233524	Straight Rail Vehicle Exhaust Removal System	233524-1 thru	26
233713.13	Air Diffusers	233713.13-1 thru	5
233713.23	Registers and Grilles	233713.23 thru	2
235400	Furnaces	235400-1 thru	8

DIVISION 24 – PROCESS PIPING SYSTEMS

247140	Service Station Equipment	247140-1 thru	11
247150	Lubrication Equipment	247150-1 thru	30
247160	Fuel Dispensers	247160-1 thru	9
247170	Submersible Pumps	247170-1 thru	7
247180	Air Compressors	247180-1 thru	10
247190	Aboveground Storage Tanks	247190-1 thru	18
247210	Service Fluid Piping	247210-1 thru	8

DIVISION 26 – ELECTRICAL SYSTEMS

260050	Common Work Results for Electrical	260050-1 thru	16
260100	Penetration Firestopping	260100-1 thru	3
260519	Low-Voltage Electrical Power Conductors and Cables	260519-1 thru	4
260526	Grounding and Bonding for Electrical Systems	260526-1 thru	5
260529	Hangers and Supports for Electrical Systems	260529-1 thru	5
260533	Raceway and Boxes for Electrical Systems	260533-1 thru	10
260548	Vibration and Seismic Controls for Electrical Systems	260548-1 thru	3
260553	Identification for Electrical Systems	260533-1 thru	4
260923	Lighting Control Devices	260923-1 thru	5
262200	Low-Voltage Transformers	262200-1 thru	4
262416	Panelboards	262416-1 thru	7

DIVISION 26 – ELECTRICAL SYSTEMS (CONTINUED)

262726	Wiring Devices	262726-1 thru 6
262816	Enclosed Switches and Circuit Breakers	262816-1 thru 3
264313	Transient-Voltage Suppression for Low-Voltage Electrical Power Circuits	264313-1 thru 5
265100	Interior Lighting	265100-1 thru 4

DIVISION 27 – COMMUNICATIONS SYSTEMS

270500	Common Work Results for Communications	2705001 thru 2
271100	Communications Equipment Room Fittings	271100-1 thru 4
271300	Communications Backbone Cabling	271300-1 thru 9
271500	Communications Horizontal Cabling	271500-1 thru 11

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

280513	Conductors and Cables for Electronic Safety and Security	280513-1 thru 9
284621.11	Addressable Fire-Alarm Systems	284621.11-1 thru 30
284800	Emergency Response Systems	284800-1 thru 10

DIVISION 31 – EARTHWORK

310200	General Sitework Requirements	310200-1 thru 3
311000	Site Clearing	311000-1 thru 4
312000	Earthwork	312000-1 thru16
312500	Erosion Control	312500-1 thru 8
313116	Termite Control	313116-1 thru 3

DIVISION 32 – EXTERIOR IMPROVEMENTS

321216	Asphalt Paving	321216-1 thru 5
321313	Concrete Paving	321313-1 thru11
321700	Pavement Markings, Signs and Specialties	321700-1 thru 4
323113	Chain-Link Fences and Gates (Galvanized)	323113-1 thru 6
329200	Turf and Grasses	329200-1 thru11

DIVISION 33 – UTILITIES

331000	Exterior Water System	331000-1 thru24
333000	Sanitary Sewerage	333000-1 thru15
334100	Storm Drainage	334100-1 thru 6

END OF TABLE OF CONTENTS

ADVERTISEMENT FOR BIDS

Sealed proposals for a Single Prime Construction Contract will be received by Lee County Schools in the **Conference Room of Lee County Schools Maintenance Department, 2000 Nash Street, Sanford, NC, until 2 PM on Thursday, July 16, 2026**, and immediately thereafter publicly opened and read, for the furnishing of labor, material, and equipment entering into the work for the following project:

Transportation Facility
416 Cox Maddox Rd, Sanford, NC

After June 25, 2026, complete plans and specifications may be obtained from the Architect, CRA Associates, Inc., Chapel Hill, NC. Construction bid documents will be distributed electronically through the Architect's file transfer site. Interested firms should email Mr. Tedd Clippinger, Project Architect, with a request for the documents and complete contact information at tedd@cra-ae.com

A non-mandatory **Pre-Bid Conference** will be held for interested parties on **Thursday, July 9, 2026, at 9 am at the existing Bus Garage, 416 Cox Maddox Rd, Sanford, NC**. Site visit will begin immediately after the pre-bid conference.

The Owner reserves the unqualified right to reject any and all proposals.

Signed: Mr. Chris McNeill, Director, Facilities & Maintenance
Lee County Schools

DOCUMENT 002113 - INSTRUCTIONS TO BIDDERS

INSTRUCTIONSTO BIDDERS

Lee County Schools / Lee County

A-1. SUBMISSION OF BIDS AND BID OPENING:

A. Bids will be received by Orange County Schools (OCS) and will be opened and read at the times and places set forth in the Advertisement for Bids. Bidders, or their representative, and other interested persons may be present at the opening of proposals.

B. In accordance with the instructions in Section 004393 “Bid Packet Requirements”, the envelope containing the bids must be sealed and addressed to Lee County Schools Maintenance Department, 2000 Nash Street, Sanford, NC 027330 and marked on the outside of the envelope **"Bid Proposal for Transportation Facility"** with the name of the Bidder and his North Carolina State Contractor's Registration Number.

C. The Bidder shall assume full responsibility for timely delivery at the location designated for receipt of Bids.

D. In accordance with the Advertisement for Bids, bids will be received for a Single Prime Construction Contract.

A-2. BIDDING DOCUMENTS:

A. Bidding Documents include the Advertisement for Bids, Information for Bidders, Form of Proposal, the Bid Security and the proposed Contract Documents, including any Addenda issued prior to receipt of bids. All requirements and obligations of the Bidding Documents are hereby incorporated by reference into the Contract Documents and are binding on the Successful Bidder upon award of the contract.

B. Bidders may obtain complete sets of the bidding Documents via CRA Associates. Prospective Bidders should pre-register with CRA Associates in order to be emailed a link to download bid documents.

C. Bidders shall use complete sets of Bidding Documents in preparing Bids; neither the Owner nor the Design Consultant shall assume any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.

D. The Owner in making copies of the Bidding Documents available on the above terms does so only for the purpose of obtaining Bids on the Work and does not confer a license or grant for any other use.

A-3. DEFINITIONS:

A. THE BID:

A Bid is a complete and properly signed proposal to do the work or designated portion thereof for the sums stipulated therein, submitted in accordance with the Bidding Documents and North Carolina law.

B. BASE BID:

The Base Bid is the sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which work may be added or from which work may be deleted for sums stated in Alternate Bids, if any.

C. ALTERNATES:

An Alternate Bid (or Alternate) is an amount stated in the Bid to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents, is accepted.

A-4. QUALIFICATION OF BIDDER:

A. If requested by the Owner prior to the signing of the contract, the successful Bidder shall submit a statement of work to be performed by his own forces.

B. Prior to Contract award or within seven days of the Owner's request to do so, the successful Bidder shall be prepared to demonstrate that his present organization, direct labor force and prior work experience is of adequate size and development to maintain responsible control of the project and to schedule, coordinate and perform the work in an expeditious manner and in accordance with the Contract Documents.

C. Bidders, whether residents or nonresidents in North Carolina will be required to show evidence of a certificate of registration before their bids will be considered.

D. The Owner will consider, in determining the qualifications of a Bidder, his record in the performance of any contracts for construction work into which he may have entered with the Owner or with similar public or private bodies or corporations. The Owner expressly reserves the right to reject the bid of any Bidder if such record discloses that such Bidder, in the opinion of the Owner, has not properly performed such contracts or has habitually and without just cause neglected the payment of bills, or has otherwise disregarded his obligations, Subcontractors, material men, suppliers or employees.

E. The Owner may make such investigation as they deem necessary to determine the ability of the Bidder to perform the work, and the Bidder shall furnish to the Owner all such information and data for this purpose as they may request. The Owner reserves the right to reject any bid if the evidence submitted by, or investigation of such Bidder, fails to satisfy the Owner that such Bidder is a responsive and responsible Bidder in accordance with N.C. Gen. Stat. 143-128 and 143-129, and the criteria set forth herein. Conditional bids will not be accepted.

A-5. BIDDER'S REPRESENTATIONS:

Each Bidder by submitting his Bid represents that:

A. Bidder has read and understands that Bidding Documents and his Bid is made in accordance therewith; and Bidder agrees to be bound by the terms and requirements set forth in the Bidding and Contract Documents;

B. Bidder has visited the site, has familiarized himself with the local conditions under which the Work is to be performed in accordance with Article A-9 herein, and has correlated his observations with the requirements of the proposed Contract Documents;

C. Bidder's Bid is based upon the materials, systems and equipment required by the Bidding Documents without exception; and

D. Bidder has the capability, in all respects, and the moral and business integrity, reliability, technical ability, financial resources, plant, management, superintendence, equipment and materials which will assure effective and efficient good faith performance in full compliance with the Contract Documents and with any and all schedules and Milestone and Completion dates required by the Owner. The Bidder acknowledges and represents that he has made allowances for normal inclement weather indigenous to the Project Site, in his estimating, planning and scheduling of the Work. The Bidder hereby certifies that the work shall be completed, in place, in full accordance with the Contract Documents, within the time limits specified.

E. Bidder agrees that upon receipt of the Notice of Award, he will execute the formal Contract, and will deliver all bonds and proof of insurance coverage as required by the Specifications.

F. Bidder agrees to execute the formal Contract within ten (10) days from the date of Notice of Award, and in case he fails or neglects to appear within the specified time to execute the Contract, he will be considered as having abandoned the Contract, and the Bid Security accompanying this Proposal will be forfeited to the Owner by reason of such failure on the part of the Bidder.

G. Bidder has made a good faith effort to solicit Minority Business Enterprises (MBEs) per N.C. Gen. Stat. 143-128.2, as subcontractors. The Bidders shall provide the Owner a notarized affidavit with its bid stating that it made the good faith effort required pursuant to G.S. 143-128.2. The Bidder's failure to file the affidavit with its bid shall be grounds for rejection of the Bid.

H. Bidder has received the General Conditions dated December 2020.

A-6. <u>BID SECURITY:</u>

A. Each bid must be accompanied by (1) cash; or (2) a Cashier's Check or a Certified Check of the Bidder in an amount not less than 5% of the bid, made payable to the Owner; or (3) a bidder's bond on the Bid Bond Form provided herein or on a similar form which in every respect materially complies with said Bid Bond, in the amount of 5% of his bid. For purposes of this provision, the amount of the bid shall be the Base Bid plus all positive amount alternates. The bidder's bond shall be issued by a surety company licensed to conduct business in North Carolina and acceptable to the Owner.

B. Said bid security is given as a guarantee that the Bidder will enter into a contract if awarded the work and, in the case of refusal or failure to so enter into said contract, the security shall be declared forfeited to the Owner. Such security shall be returned to all but the three lowest Bidders within three days after the opening of bids and the remaining security will be returned within 48 hours after the Owner and the successful Bidder have executed the Contract. If no Contract has been

awarded or the bidder has not been notified of the acceptance of his bid within sixty (60) days of the bid opening, the Bidder may withdraw his bid and request the return of his bid security. If, at the Owner's request, the Bidder agrees to extend and maintain his bid beyond the specified 60 days, his bid security will not be returned until the expiration of the period of extension.

A-7. FORFEITURE OF BID BOND:

The Successful Bidder, upon his failure or refusal to execute the Contract within ten (10) days after he has received Notice of Award, shall forfeit to the Owner the security deposited with his bid in accordance with North Carolina General Statute 143-129

A-8. EQUAL EMPLOYMENT OPPORTUNITY

During the performance of this contract, the contractor agrees as follows:

A. The contractor will not discriminate against any employee or applicant for employment because of race, handicap, age, color, religion, sex, or national origin. The contractor will take affirmative action to ensure that applicants are employed and that employees are treated during employment without regard to race, handicap, age, color, religion, sex or national origin. Such action shall include but not be limited to the following: employment, upgrading, demotion or transfer, recruitment or recruiting advertising, layoff or termination rates of pay or other forms of compensation, and selection for training including apprenticeship. The contractor agrees to post in conspicuous places available to employees and applicants for employment notices setting forth the provisions of the nondiscrimination clause.

B. The contractor will in all solicitations or advertisements for employees placed by or on behalf of the contractor state that all qualified applicants will receive consideration for employment without regard to race, handicap, age, color, religion, sex, or national origin.

C. The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding a notice to be provided advising the labor union or workers' representative of the contractor's commitments under the Equal Employment Opportunity section of this contract and shall post copies of the notice in conspicuous places available to employees and applicants for employment.

D. In the event of the contractor's noncompliance with nondiscrimination clauses of this contract or with any such rules, regulations or orders, this contract may be canceled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further County contracts.

E. The contractor will include the provisions of this section in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Board of County Commissioners of the County of Lee, North Carolina so that such provisions will be binding such subcontractor or vendor.

A-9. MINORITY BUSINESS ENTERPRISES:

A. Bidders are required to submit information about participating M/WBEs with their bid. Each bidder shall identify on its bid the minority businesses that it will use on the project and an affidavit listing the good faith efforts it has made pursuant to N.C. Gen. Stat. § 143-128.2(f). The information must include the name and address of each M/WBE, a description of the work to be performed by each, and the dollar value of the work to be performed by each. Any bidder who fails to achieve the indicated M/WBE participation goal stated above is required to provide the aforementioned documentation demonstrating that good faith efforts were made in an attempt to meet the established goal. AFFIDAVITS A through D and APPENDIX E, are provided to record this information and must be completed and enclosed with your bid. Any bid which does not include M/WBE information and documentation may be considered non-responsive. A complete copy of the County's Minority and Women Business Enterprise Ordinance may be obtained by contacting the Lee County Purchasing Division.

B. The apparent lowest responsible, responsive bidder, within three (3) business days, shall also provide either (1) an affidavit (Affidavit C) that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the applicable goal or (2) documentation of its good faith effort that was identified in the bid to meet the goal (Affidavit D), including any advertisements, solicitations, and evidence of other specific actions demonstrating recruitment and selection of minority businesses for participation in the contract. ***Failure to file the required affidavit or documentation that demonstrates that the contractor made the required good faith effort is grounds for rejection of the bid.***

C. M/WBE: A business which is at least 51% owned and controlled by minority group members or a woman. A M/WBE is bona fide only if the minority group or female ownership interests are real and continuing and not created solely to meet the M/WBE requirement. In addition, the M/WBE must itself perform satisfactory work or service or provide supplies under the contract and not act as a conduit. The contractual relationship must be bona fide.

D. Owned and controlled: (1) A sole proprietorship legitimately owned by an individual who is a minority group member or female; (2) a partnership or joint venture controlled by minorities and/or females; (3) a corporation or other entities controlled by minorities or females, and in which at least 51% of the voting interests and 51% of the beneficial ownership interests are legitimately held by minorities and/or females. These persons must control the management and operations of the business on a day-to-day basis.

E. A person who is a citizen or lawful permanent resident of the United States and who is:

a. "Black American"; a person having origins in any of the Black racial groups of Africa;

b. "Hispanic American"; a person of Spanish culture with origins in Mexico, Central or South America, or the Caribbean, regardless of race;

c. “Native American”; a person who is a member or is eligible to be a member of a federally recognized Indian tribe. A federally recognized Indian tribe means an Indian tribe, or band, nation, ranchero, pueblo, colony, or other organized group or community, including any Alaska native village, which is recognized by the Secretary of the Interior on October 1, 1985 as having special rights and is recognized as eligible for service provided by the United States to Indians because of their status as Indians, and any tribe that has a pending application for federal recognition on October 1, 1985, as having special rights and is recognized as eligible for services provided by the United States to Indians because of their status as Indians, and any tribe that has a pending application for Federal recognition on October 1, 1985.

F. During the construction of a project, if it becomes necessary to replace an M/WBE subcontractor, the prime contractor shall advise the owner. No M/WBE subcontractor may be replaced with a different subcontractor except (1) if the subcontractor’s bid is later determined by the contractor to be nonresponsible or nonresponsive, or the listed subcontractor refuses to enter into a contract for the complete performance of the bid work or (2) with the approval of the Board for good cause.

Good faith efforts as set forth in N.C. Gen. State. § 143-131(b) shall apply to the selection of a substitute subcontractor. Prior to substituting a subcontractor, the contractor shall identify the substitute subcontractor and inform the Board or its designee of its good faith efforts pursuant to N.C. Gen. State. § 143-131(b).

G. If during the construction of a project additional subcontracting opportunities become available, the prime contractor shall make a good faith effort to solicit subbids from M/WBEs.

A-10. SITE CONDITIONS AND CONDITIONS OF THE WORK:

A. Each bidder must acquaint himself thoroughly as to the character and nature of the work to be done. Each bidder furthermore must make a careful examination of the site of the work and inform himself fully as to the difficulties to be encountered in the performance of the work, the facilities for delivering, storing and placing materials and equipment, and other conditions relating to construction and labor.

B. No plea of ignorance of conditions that exist or may hereafter exist on the site of the work, or difficulties that may be encountered in the execution of the work, as a result of failure to make necessary investigations and examinations, will be accepted as an excuse for any failure or omission on the part of the successful Bidder to fulfill in every detail all the requirements of the Contract Documents and to complete the work or the consideration set forth therein, or as a basis for any claim whatsoever.

C. Insofar as possible, the Successful Bidder, in carrying out his work, must employ such methods or means as will not cause interruption of or interference with the work of the Owner or any separate contractor.

A-11. BIDDER'S QUESTIONS, ADDENDA AND INTERPRETATIONS:

A. Bidders and Sub-bidders shall promptly notify the Design Consultant of any ambiguity, inconsistency or error which they may discover upon examination of the Bidding and Contract Documents or of the site and local conditions. No interpretation of the meaning of the drawings, specifications or other contract documents will be made to any Bidder orally.

B. Every request for such interpretation should be in writing addressed to the Design Consultant with a copy forwarded to the Owner.

C. Any and all such interpretations and any supplemental instructions will be in the form of written addenda to the Bidding Documents which, if issued, will be transmitted to all prospective Bidders (at the respective addresses furnished for such purposes) not later than three calendar days prior to the date fixed for the opening of bids. Neither the Design Consultant nor the Owner will be responsible for any other explanations or interpretations of the proposed documents. Failure of any Bidder to receive any such addendum or interpretation shall not relieve any bidder from any obligation under his bid as submitted. All addenda so issued shall become part of the Contract Documents.

D. Each Bidder shall ascertain prior to submitting his bid that he has received all Addenda issued, and he shall acknowledge receipt and inclusion in his proposal of all Addenda.

A-12. SECURITY FOR FAITHFUL PERFORMANCE:

The Successful bidder shall furnish a Performance Bond in an amount equal to one hundred percent (100%) of the Contract Sum as security for the faithful performance of this Contract and also a Labor and Material Payment Bond in an amount not less than one hundred percent (100%) of the Contract Sum, as security for the payment of all persons performing labor and furnishing materials under this Contract. The successfull bidder shall provide a Performance Bond and a Labor and Material Payment Bond using the forms attached as Exhibits A and B. The Performance Bond and the Labor and Material Payment Bond shall be delivered to the Owner not later than the date of execution of the Contract.

A-13. TIME FOR COMPLETION AND LIQUIDATED DAMAGES FOR NON-COMPLETION:

The time for completion of this Contract and liquidated damages for non-completion within the stipulated time shall be as fixed in the General Conditions.

A-14. LOCATION OF WORK:

The site of the proposed work is on Owner owned property, public streets, easements and/or other right-of-ways, as shown on the drawings.

A-15. LIABILITY INSURANCE AND WORKMEN'S COMPENSATION:

The Successful Bidder will be required to carry public liability and workmen's compensation and other insurance in the amounts and under the terms stipulated under the General Conditions.

A-16. BIDDERS REFERRED TO LAWS:

A. The attention of Bidders is called to the provisions of all Municipal, County and State laws, regulations, ordinances and resolutions, as well as laws, regulations, ordinance resolutions and permits relating to obstructing streets, maintaining signals, storing and handling of explosives, or affecting the Bidder, or his employees or his work hereunder in his relation to the Owner or any other person. The Bidder shall obey all such laws, regulations, ordinances, permits or resolutions controlling or limiting Contractors while engaged in the prosecution of work under this Contract.

B. The provisions of this contract shall be interpreted in accordance with the laws of North Carolina and in accordance with the laws, ordinances, regulations, permits and resolutions of Lee County.

A-17. TAXES

All applicable Federal, State and Local Taxes shall be included in the Bidder's proposal. The successful bidder shall provide the Owner with monthly documentation of North Carolina sales taxes paid for all purchases on the project in a form acceptable to the Owner.

Owner has determined this project to be a Capital Improvement as defined by the NC General Statute § 105-164.

A-18. RIGHT TO REJECT BIDS:

The Owner expressly reserves the right to reject any or all bids, to waive any informalities or irregularities in the bids received, and to accept that bid which in its judgment, best serves the interest of the Owner.

A-19. EQUAL PRODUCTS AND SUBSTITUTIONS:

A. Whenever possible, the Design Consultant shall specify in the plans the required performance and design characteristics for materials as required by N.C. Gen. Stat. § 133-3. When it is impossible or impractical to specify the required performance and design characteristics for materials, the Design Consultant may use a certain brand, make, manufacturer, article, device, product, material, fixture, form or type construction by name, make or catalog number to convey the general style, type, character and standard of quality of the aricle desired. Unless specifically stated to the contrary, all materials, supplies and articles furnished under this Contract shall, whenever specified and otherwise practicable, be the standard products of recognized, reputable manufacturers. Unless otherwise specifically provided in the Contract Documents, the naming of a certain brand, make, manufacturer or article, device, product, material, fixture or type of construction shall convey the general style, type, character and standard of quality of the article desired and shall not be construed as limiting competition. If approval by the Design Consultant prior to bid opening is desired, the bidder shall request approval in writing at least ten (10) days prior to the bid date. The Design Consultant’s approval will be in the form of an Addendum to the Specifications issued to all prospective Bidders indicating that the additional makes or brands are equivalent to those specified. Nothing in this paragraph is intended to restrict or inhibit free and open competition on school system projects.

B. The bidder may request approval for substitutions of materials or type of construction in writing up to ten (10) days prior to the bid date. The standard for acceptance of substitutions shall be as expressed in Paragraph 4.15 of the contract General Conditions.

A-20. PREPARATION AND SUBMITTAL OF FORM OF BID:

A. Bids shall be submitted utilizing the Form of Proposal as bound herein, or otherwise provided with the Contract Documents, and shall be complete in every respect. The total bid amount shall be entered in words and figures in the space provided. Where applicable, the unit price or lump sum items, and their extensions, shall be entered in figures in the respective columns provided for each bid item. All entries shall be typewritten or printed in ink. The signatures of all persons shall be in longhand. Any entry of amount that appears on the face of the bid to have involved an erasure, deletion, white-out and/or substitution or other such change or alteration, shall show by them the initials of the person signing the bid and the date of the change or alteration. A failure to comply with this requirement may be cause for disqualification of the bid.

B. For Unit Price bids, in the event of any discrepancies between the unit prices and the extensions thereof or the total bid amount, the unit prices shall govern. For Lump Sum bids, in the event of a discrepancy between the bid amount in writing and that in figures, the written value shall govern.

C. Bids shall not contain any restatement or qualifications of work to be done, and alternate bids will not be considered unless called for. No oral bids or modifications will be considered.

D. The amount of a bid submitted by a subcontractor to the general contractor under the single prime contracting system shall not exceed the total bid.

E. Each single-prime bid shall identify the contractors selected to perform the HVAC, plumbing and electrical work and the subcontractors' respective bid prices for the work.

A-21. MODIFICATION OR WITHDRAWAL OF BID:

A. A Bidder may withdraw his bid from consideration if such bid was based upon a mistake as provided in North Carolina General Statute 143-129.1.

B. Prior to the time and date designated for receipt of bids, any bid submitted may be modified or withdrawn by notice to the party receiving bids at the place designated for receipt of bids. Such notice shall be in writing over the signature of the Bidder or by telegrams; if by telegram, written confirmation over the signature of the Bidder shall be mailed and postmarked on or before the date and time set for receipt of bids, and it shall be so worded as not to reveal the amount of the original bid.

C. Withdrawn bids may be resubmitted up to the time designated for the receipt of Bids provided that they are then fully in conformance with this Information for Bidders.

D. Bid security, if any is required, shall be in an amount sufficient for the bid as modified or resubmitted.

A-22. DETAILED BID BREAKDOWN:

If the Owner directs, the Bidder shall provide a detailed breakdown of his bid acceptable to the Owner. In addition to verifying accounting requirements, the breakdown may be used by the Owner to determine whether the Bidder has grossly misjudged the requirements of any area. Failure to provide the requested detailed breakdown may result in rejection of the bid proposal.

A-23. AWARD OF CONTRACT:

A. Lee County and the Lee County Schools have entered into an Interlocal Agreement under which the Board of Education is the authorized agent for real property sites leased by Lee County in order to facilitate the refund of sales taxes paid to the State of North Carolina for tangible personal property, building materials, supplies, fixtures, and equipment used in the erection, construction and development of school buildings, additions or renovations to school buildings upon these sites.

B. The Lee County Schools as the agent of Lee County is appointed to manage design and construction contracts of school buildings or additions to school buildings on the property leased by the County. As such, all Bidding, Award, and Contract documentation will follow Lee County Procurement Policies and will be received, reviewed, recommended, and managed by Orange County Schools. The contract will be awarded to the lowest responsive and responsible bidder under the single prime system, taking into consideration quality, performance, and the time specified in the bids for the performance of the contract.

C. The lowest bidder shall be determined by the aggregate amount of the unit prices set forth in the form of bid, if work is bid on a unit price basis, or the aggregate amount of the Base Bid, plus any Alternates selected by the Owner. Single prime bids will be received and awarded according to state law.

D. A Responsive Bidder shall mean a Bidder who has submitted a bid which conforms, in all material respects, to the Bidding Documents.

E. A Responsible Bidder shall mean a Bidder who has the capability, in all respects, to perform fully the contract requirements and the moral and business integrity and reliability which will assure good faith performance. In determining responsibility, the following criteria will be considered:

1. The ability, capacity and skill of the Bidder to perform the contract or provide the service required;

2. Whether the bidder can perform the contract or provide the service promptly, or within the time specified, without delay or interference;

3. The character, integrity, reputation, judgment, experience and efficiency of the Bidder;

4. The quality of performance of previous contracts or services. For example the following information will be considered:
    a. the administrative and consultant cost overruns incurred by Owners on previous contracts with Bidder,
    b. the Bidder's compliance record with contract general conditions on other projects,
    c. the submittal by the bidder of excessive and/or unsubstantiated extra cost proposals and claims on other projects,
    d. the Bidder's record for completion of the work within the Contract Time or within Contract Milestones and Bidders compliance with scheduling and coordination requirements on other projects,
    e. the Bidder's demonstrated cooperation with the Owner or the Design Consultant and other contractors on previous contracts,
    f. whether the work performed and materials furnished on previous contracts was in accordance with the Contract Documents;
5. The previous and existing compliance by the bidder with laws and ordinances relating to contracts or services;
6. The sufficiency of the financial resources and ability of the Bidder to perform the contract or provide the service;
7. The quality, availability and adaptability of the goods or services to the particular use required;
8. The ability of the Bidder to provide future maintenance and service for the warranty period of the contract;
9. Whether the Bidder is in arrears to the Owner on debt or contract or is a defaulter on surety to the Owner;
10. Whether the bidder has demonstrated a good faith effort to use MBEs as subcontractors;
11. Such other information as may be secured by the Owner having a bearing on the decision to award the contract, to include, but not limited to:
    a. the ability, experience and commitment of the Bidder to properly and reasonably plan, schedule, coordinate and execute the Work,
    b. whether the Bidder has ever been debarred from bidding or found ineligible for bidding on any other projects.

F. The purpose of the above is to enable the Owner in its opinion, to select the lowest responsible bidder. The ability of the low Bidder to provide the required bonds will not of itself demonstrate responsibility of the Bidder.

G. In addition to the qualifications package submitted with the bid, the Owner reserves the right to require from the Bidder: (1) submissions of references, within seven days of bid opening, to include a listing of previous and current projects and (2) financial statements indicating current financial status, prepared in accordance with

generally accepted accounting principles, by a CPA licensed to do business in North Carolina, and (3) any other information deemed necessary in order to establish the responsiveness and responsibility of the bidder.

H. The Owner reserves the right to defer award of this contract for a period of sixty (60) days after the due date of bids. During this period time, the Bidder shall guarantee the prices quoted in his bid.

A-24. ADDITIONAL REQUIREMENTS:

A. Security of Non-public Records: Pursuant to N.C.G.S. § 132-1.7, entitled, "Sensitive Public Security Information", public records, as defined in G.S. 132-1, shall not include information containing specific details of public security plans and arrangements or the detailed plans and drawings of public buildings and infrastructure facilities. Therefore, all information provided, received, gathered or obtained by Bidder containing specific details of public security plans and arrangements or the detailed plans and drawings of public buildings and infrastructure facilities shall be held confidential and shall be used by the Bidder only for the purpose of responding to this bid. All plans and drawings shall be returned to the Owner no later than the bid closing date. Any breach of this paragraph by the Bidder may result in Bidder being barred from being awarded any contracts with the Owner.

B. To ensure a fair bidding process, questions and/or clarifications requested by contractors will be accepted up to **three (3) days prior to Bid Opening**. Bidders/contractors are required to submit their questions in writing to the Designer of Record **Tedd Clippinger, Project Architect** at **tedd@cra-ae.com** with a copy to the Owner.

C. The following forms must be returned with one (1) original of the Bid Proposal:

a. Bid Forms
b. Non-Collusion Affidavit
c. Bid Bond
d. Power of Attorney
e. MBE Forms:

i. Identification of Minority Business Participation with contract amounts ($)
ii. Affidavit A – Listing of Good Faith Efforts - OR-
iii. Affidavit B – Intent to Perform Contract with Own Workforce

f. Statement of Qualifications: Each proposal shall be accompanied by a statement of qualifications that demonstrates experience in at least five (5) projects of similar scope within the past three (3) years with references.

g. Statement of ability to staff project. Each proposal shall be accompanied by a statement of ability to staff including current project load, current staff levels and individual staff to be committed to this project if awarded.

D. Following the bid opening, the Owner will issue a Determination of Apparent Low Bidder letter to the contractor it has deemed to be the apparent low

responsible, responsive bidder based on the initial bid documentation. The contractor is required to submit Affidavit C or D including all statute-required back-up information within seventy-two (72) hours of the receipt of the letter.

E. Within 30 calendar days of the contract award, the contractor shall submit a complete list of all identified subcontractors the contractor will use on the project.

F. Affidavit C or D is to be submitted only by the apparent lowest responsible, responsive bidder within seventy-two (72) hours after bid closing date with all statute-required back-up information.

G. The apparent lowest responsible Bidder/Offeror shall file within 30 days after the award of the contract a list of all identified subcontractors that the contractor (Bidder/Offeror) will use on the project.

RELATED SECTIONS:

A. Exhibit A – Performance Bond Form (Section 00 61 13)
B. Exhibit B – Material and Labor Payment Bond Form (Section 00 61 13)

END OF INSTRUCTIONS TO BIDDERS

BID FORM – SINGLE PRIME CONTRACT

TO: Lee County Schools
2000 Nash Street
Sanford North Carolina, 27330

FROM: BIDDER _____

ADDRESS _____

CITY_____STATE_____ZIP_____

The undersigned Bidder agrees, if this Bid is accepted, to enter into an agreement with Owner, in the form included in the Bidding Documents, to perform and furnish the work as specified or indicated in the Bidding Documents for the Bid Price and within the Bid Times indicated in this Bid in accordance with the other terms and conditions of the Contract Documents.

1. BASE BID PROPOSAL:

Having become completely familiar with the local conditions affecting the cost of work at the place where work is to be executed, and having carefully examined the site conditions as they currently exist, and having carefully examined Bidding Documents prepared by

Name: **CRA Associates, Inc.**
Address: 100 Europa Drive., Suite 565
City / State / Zip: Chapel Hill, NC 27517

and titled:

Name of Project: **Lee County Schools Transportation Facility**
Address: 416 Cox Maddox Road
City / State / Zip: Sanford, NC 27332

Dated **June 25, 2026** together with any addenda to such Bidding Documents as listed hereinafter, the undersigned hereby proposes and agrees to provide all labor, materials, plant, equipment, transportation and other facilities as necessary and/or required to execute all of the work described by the aforesaid Bidding Documents for the lump sum consideration of:

Base Bid: _____

_____

Dollars ($_____),

Said amount being hereinafter referred to as the Base Bid or Base Bid Proposal.

Base Bid Breakdown:

General	Dollars ($_____)
Mechanical	Dollars ($_____)
Electrical	Dollars ($_____)
Fire Alarm	Dollars ($_____)

2. BID ACKNOWLEDGEMENTS:

In submitting this Bid, Bidder represents, as more fully set forth in the Agreement, that:

1. This Bid will remain subject to acceptance for sixty (60) days after the day of Bid opening;
2. The Owner has the right to reject this bid;
3. Bidder will sign and submit the Agreement with the other documents within 15 days after the date of the Owner's Notice of Award;
4. Bidder has examined copies of all the Bidding Documents.
5. Bidder has visited the site and become familiar with the general and local site conditions;
6. Bidder is familiar with federal, state, and local laws and regulations;
7. Bidder has correlated the information known to Bidder, information and observations obtained from visits to the site, reports and drawings identified in the Bidding Documents and additional examinations, investigations, tests, studies and data with the Bidding Documents;
8. Bidder certifies that this proposal is made in good faith and without collusion or connection with any other person bidding on the same work, or that any official or employee of the County of Durham or Durham Public Schools will be admitted to any share or part of the contract or any benefits that may arise therefrom if the contract is awarded to this company.

3. ALTERNATES:

The undersigned proposes to perform alternatives for stated resulting additions to or deductions from the Base Bid. Additions and deductions shall include any modifications of work or additional work that undersigned may be required to perform by reason of the acceptance of any alternative.

ALTERNATE NO. G-1: ADD Warehouse Construction.

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**)_____ Dollars ($_____)

ALTERNATE NO. G-2: Preferred Brand - Door Hardware.

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. G-3: Preferred Brand - Paint.

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. P-1: Preferred Brands – Water Heaters and Flush Valves

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. M-1: Preferred Brand – HVAC Equipment

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. M-2: Preferred Brands – Pumps, Pump Controllers, Valves

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. E-1: ADD for Site Lighting

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**)_____ Dollars ($_____)

ALTERNATE NO. E-2: Preferred Brand – Electrical Equipment and Devices.

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

ALTERNATE NO. E-3: Preferred Brand – Fire Alarm System.

Adjust Base Bid by ADDING or DEDUCTING

(**ADD**) (**DEDUCT**)_____ Dollars ($_____)

4. ADDENDA ACKNOWLEDGMENT:

The undersigned acknowledges receipt of the following addenda: (List by number and date appearing on addenda.)

Addendum No.	Date	Addendum No.	Date

5. SUBCONTRACTOR LISTING:

Pursuant to N.C.G.S. 143-128(d), all bidders shall identify on their bid the contractors they have selected for the subdivisions or branches of work for:

Subcontract Trade	Subcontractor Name	License #
Heating, Ventilating, Air Cond.		
Electrical		

6. ACKNOWLEDGEMENTS & AUTHORIZATION:

A. The undersigned declares that the person orpersons signing this Proposal is/are fully authorized to sign on behalf of the firm listed and to fully bind the firm listed to all the Proposal's conditions and provisions thereof.

B. It is agreed that no person or persons or company other than the firm listed below or as otherwise indicated has any interest whatsoever in this proposal or the contract that may be entered into as a result of the Proposal and that in all respects the proposal is legal and firm, submitted in good faith without collusion or fraud.

C. It is agreed that the undersigned has complied or will comply with all requirements of local, state, and national laws, and that no legal requirement has been or will be violated in making or accepting this Proposal, in awarding the contract to him and/or in the prosecution of the work required.

D. It is agreed that the undersigned shall provide any information deemed necessary by the Owner to establish the responsiveness and responsibility of the bidder.

E. The Bidder acknowledges that the submission of this bid constitutes the Bidder's certification to the State Treasurer that, as of date of bid, it is not listed on the Final Divestment List created and maintained by the North Carolina Department of State Treasurer (the "Treasurer's Office") pursuant to the Iran Divestment Act of 2015, Chapter 147 Article 6E of the General Statutes of North Carolina (the "Iran Divestment Act")" The individual signing this bid form certifies that he or she is authorized by the bidder to make the foregoing statement.

F. The following information is provided pursuant to the Contract Documents:
Legal Name of Firm:

1. If Firm is a corporation, state that corporation is organized under the laws of the State of _____. Please affix corporate seal to this Form of Bid.
2. If Firm is a partnership, state names of partners:

   _____
   _____
   _____
3. If Firm is an individual using a trade name, state name of individual:

   _____

Contractor Registration Number: _____

Respectfully submitted, this _____ day of _____ 20 _____

_____
(Signature)

_____
(Name Typed)

_____
(Title)

(SEAL IF BIDDER IS A CORPORATION)

END FORM OF PROPOSAL – SINGLE PRIME CONTRACT

DOCUMENT 004313 - BID SECURITY FORMS

FORM OF BID BOND

KNOW ALL MEN BY THESE PRESENTS THAT _____

_____

as principal, and _____

_____

as Surety, who is duly licensed to act as surety in North Carolina, are held and firmly bound unto, Lee County Schools, Sanford, North Carolina as Obligee, in the penal sum of

_____ DOLLARS,
lawful money of the United States of America, for the payment of which, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Signed, sealed and dated this _____ day of _____, 20__

WHEREAS, the said Principal is herewith submitting proposal for

Transportation Facility

and the Principal desires to file this Bid Bond in lieu of making the cash deposit as required by G.S. 143-129.

NOW, THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION is such, that if the Principal shall be awarded the contract for which the bid is submitted and shall execute the contract and give bond for the faithful performance thereof within ten days after the award of same to the Principal, then this obligation shall be null and void; but if the principal fails to so execute such contract and give performance bond as required by G.S. 143-129, the Surety shall, upon demand, forthwith pay to the obligee the amount set forth in the first paragraph hereof. Provided further, that the bid may be withdrawn as provided by G.S. 143-129.1.

_____(SEAL)

_____(SEAL)

_____(SEAL)

_____(SEAL)

_____(SEAL

DOCUMENT 00 43 93 - BID SUBMITTAL CHECKLIST

Bid envelopes will have the following information on the outside of the envelope:

Bidder's name
Bidder's NC License Number
Bidder's Address

Proposal for Construction Contract for
Transportation Facility

Addressed to: Lee County Schools
Attn: Chris McNeill
2000 Nash Street
Sanford, NC 27330

Envelope must be SEALED and delivered by courier or hand delivered ON OR BEFORE the date and time noted on the bid documents. Note: Lee County Schools is not responsible for delays, late arrivals, delivery errors or lost items transported by courier services. Contractor is responsible for ensuring bid packets are delivered during normal business hours from 8:30 am to 4:30 pm Monday-Friday excluding federal holidays. Lee County Schools will be closed on Federal and State Holidays.

The following completed documents will be required in your base bid package:

1. Form of Proposal – Single Prime Contract
   a. NOTE: Part 5, Addenda Acknowledgment **must** be filled out with the correct number of Addenda's Issued before bid date.

2. Non-Collusion Affidavit

3. Bid Bond

4. Bid Bond Power of Attorney

5. M/WBE Forms
   a. Identification of Minority Business Participation **- AND -**
   b. Affidavit A – Listing of Good Faith Efforts – **OR -**
   c. Affidavit B – Intent to Perform Contract with Own Workforce

6. Statement of Qualifications: Each proposal shall be accompanied by a statement of qualifications that demonstrates experience in at least five (5) projects of similar scope within the past three (3) years with references

7. Statement of ability to staff project. Each proposal shall be accompanied by a statement of ability to staff including current project load, current staff levels and individual staff to be committed to this project if awarded

The omission of any of the above forms will constitute the bid as invalid and the contractors bid amount will not be read.

Tax Clarification, Reference "Instructions tor Bidders" Section A-17, "All applicable Federal, State and Local Taxes shall be included in the Bidder's proposal".

Affidavit C or D will be submitted only by the apparent lowest responsible, responsive bidder within seventy-two (72) hours after the bid closing date.

Owner will issue a letter notifying the apparent low bidder of their status subsequent to the bid opening.

DOCUMENT 004319 – NON-COLUSION AFFIDAVIT

NON-COLLUSION AFFIDAVIT

State of North Carolina
County of Lee

I_____, being first duly sworn, deposes and says that:

1. He/She is the_____of_____,
   the offeror that has submitted the attached proposal;

2. He / She is fully informed respecting the preparation and contents of the attached proposal and of all pertinent circumstances respecting such proposal;

3. Such proposal is genuine and is not a **collusive** or **sham** proposal;

4. Neither the said offeror nor any of its officers, partners, owners agents, representatives, employees or parties of interest, including this affidavit, has in any way colluded, conspired, connived or agreed, directly or indirectly, with any other offeror, firm or person to submit a **collusive** or **sham** proposal in connection with the contract for which the attached proposal has been submitted or to refrain from proposaling in connection with such contract, or has in any manner, directly or indirectly, sought by agreement or collusion or communication or conference with any other offeror, firm or person to fix the price or prices in the attached proposal or of any other offeror, or to fix any overhead, profit or cost element of the proposal price of any other offeror or to secure through collusion, conspiracy, connivance or unlawful agreement any advantage against the County of Durham or any person interested in the proposed contract; and

5. The price or prices quoted in the attached proposal are fair and proper and are not tainted by any collusion, conspiracy, connivance or unlawful agreement on the part of the offeror or any of its agents, representatives, owners, employees, or parties in interest, including this affidavit.

_____ _____
Signature of offeror *Date*

Subscribed and sworn before me, (SEAL)
this_____day of_____, 20_____

_____
TITLE

Notary Public
My Commission Expires_____

Minority Business Participation Requirements
Pursuant to Board of Education Policy Lee County Schools has established a verifiable ten percent (10%) participation goal for Minority Business Enterprises in **all** building construction and repair projects carried out by the district.

Under G.S. 143-128.2(c) the undersigned bidder shall identify **on its bid** (Identification of Minority Business Participation Form) the minority businesses that it will use on the project with the total dollar value of the bids that will be performed by the minority businesses. Also list the good faith efforts (Affidavit A) made to solicit minority participation in the bid effort.

NOTE: A contractor that performs all of the work with its own workforce may submit an Affidavit (B) to that effect in lieu of Affidavit (A) required above. The MB Participation Form must still be submitted even if there is zero participation.

After the bid opening—The Owner will consider all bids and alternates and determine the lowest responsible, responsive bidder. Upon notification of being the apparent low bidder, the bidder shall then file within 72 hours of the notification of being the apparent lowest bidder, the following:

An Affidavit (C) that includes a description of the portion of work to be executed by minority businesses, expressed as a percentage of the total contract price, which is equal to or more than the 10% goal established. This affidavit shall give rise to the presumption that the bidder has made the required good faith effort and Affidavit D is not necessary;

OR

If less than the 10% goal, Affidavit (D) of its good faith effort to meet the goal shall be provided. The document must include evidence of all good faith efforts that were implemented, including any advertisements, solicitations and other specific actions demonstrating recruitment and selection of minority businesses for participation in the contract.

Note: Bidders must always **submit with their bid the Identification of Minority Business Participation Form** listing all MB contractors, vendors and suppliers that will be used. **If there is no MB participation then enter none or zero on the form**. **Affidavit A or Affidavit B, as applicable, also must be submitted with the bid**. Failure to file a required affidavit or documentation with the bid or after being notified apparent low bidder is grounds for rejection of bid.

Iran Divestment Act
As of February 26, 2016, each vendor doing business with governmental agencies must certify its name **does not appear** on the Iran Divestment List.

The list may be accessed via the State Treasurer's website at www.nctreasurer.com/Iran

Certifications **shall be** attached to bids at the time of submittal.

Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid

Identification of Minority Business Participation

I,_____,
(Name of Bidder)

do hereby certify that on this project, we will use the following minority business enterprises as construction subcontractors, vendors, suppliers or providers of professional services.

Firm Name, Address and Phone #	Work type	*Category	Value ($)

*Minority categories: Black, African American (**B**), Hispanic (**H**), Asian American (**A**) American Indian (**I**), Female (**F**) Socially and Economically Disadvantaged (**D**)

The total value of minority business contracting will be ($)_____.

Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid

State of North Carolina – AFFIDAVIT A
Listing of Good Faith Efforts

Lee County Schools

(Name of Bidder)

Affidavit of_____

I have made a good faith effort to comply under the following areas checked:

Bidders must earn at least 50 points from the good faith efforts listed for their bid to be considered responsive. (1 NC Administrative Code 30 I.0101)

- ❑ **1 – (10 pts)** Contacted minority businesses that reasonably could have been expected to submit a quote and that were known to the contractor, or available on State or local government maintained lists, at least 10 days before the bid date and notified them of the nature and scope of the work to be performed.
- ❑ **2 --(10 pts)** Made the construction plans, specifications and requirements available for review by prospective minority businesses, or providing these documents to them at least 10 days before the bids are due.
- ❑ **3** – **(15 pts)** Broken down or combined elements of work into economically feasible units to facilitate minority participation.
- ❑ **4 – (10 pts)** Worked with minority trade, community, or contractor organizations identified by the Office of Historically Underutilized Businesses and included in the bid documents that provide assistance in recruitment of minority businesses.
- ❑ **5** – **(10 pts)** Attended prebid meetings scheduled by the public owner.
- ❑ **6** – **(20 pts)** Provided assistance in getting required bonding or insurance or provided alternatives to bonding or insurance for subcontractors.
- ❑ **7 – (15 pts)** Negotiated in good faith with interested minority businesses and did not reject them as unqualified without sound reasons based on their capabilities. Any rejection of a minority business based on lack of qualification should have the reasons documented in writing.
- ❑ **8** – **(25 pts)** Provided assistance to an otherwise qualified minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letters of credit, including waiving credit that is ordinarily required. Assisted minority businesses in obtaining the same unit pricing with the bidder's suppliers in order to help minority businesses in establishing credit.
- ❑ **9** – **(20 pts)** Negotiated joint venture and partnership arrangements with minority businesses in order to increase opportunities for minority business participation on a public construction or repair project when possible.
- ❑ **10** - **(20 pts)** Provided quick pay agreements and policies to enable minority contractors and suppliers to meet cash-flow demands.

The undersigned, if apparent low bidder, will enter into a formal agreement with the firms listed in the Identification of Minority Business Participation schedule conditional upon scope of contract to be executed with the Owner. Substitution of contractors must be in accordance with GS143-128.2(d). Failure to abide by this statutory provision will constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of the minority business commitment and is authorized to bind the bidder to the commitment herein set forth.

Date:_____Name of Authorized Officer:_____

Signature:_____

Title:_____

SEAL

State of North Carolina, County of_____

Subscribed and sworn to before me this_____day of _____20____

Notary Public_____

My commission expires _____

Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid Attach to Bid

State of North Carolina – AFFIDAVIT B
Intent to Perform Contract with Own Workforce

Lee County Schools

Affidavit of _____
(Name of Bidder)

I hereby certify that it is our intent to perform 100% of the work required for the _____

_____ contract.
(Name of Project)

In making this certification, the Bidder states that the Bidder does not customarily subcontract elements of this type project, and normally performs and has the capability to perform and will perform all elements of the work on this project with his/her own current work forces; and

The Bidder agrees to provide any additional information or documentation requested by the owner in support of the above statement.

The undersigned hereby certifies that he or she has read this certification and is authorized to bind the Bidder to the commitments herein contained.

Date: _____ Name of Authorized Officer: _____

Signature: _____

Title: _____

SEAL

State of North Carolina, County of _____

Subscribed and sworn to before me this _____ day of _____ 20_

Notary Public _____

My commission expires _____

Do not submit with bid ***Do not submit with bid*** ***Do not submit with bid*** ***Do not submit with bid***

State of North Carolina – AFFIDAVIT C
Portion of Work to be Performed by Minority Firms

Lee County Schools

NOTE: This form is to be submitted only by the apparent lowest responsible, responsive bidder

Affidavit of_____I do hereby certify that on the
(Name of Bidder)

Project Name: _____

Project ID No._____Amount of Bid $_____

I will expend a minimum of_____% of the total dollar amount of the contract with minority businesses enterprises. Work will be subcontracted to the following firms listed below. Attach additional sheets if needed.

Name and Phone Number	*Minority Category	Work Description	Dollar Value	Percentage of Goal

***Minority categories:** Black, African American (**B),** Hispanic (**H**), Asian American (**A**), American Indian (I), Female (**F**)

Pursuant to GS 143-128.2(d), the undersigned will enter into a formal agreement with Minority Firms for work listed in this schedule conditional upon execution of a contract with the Owner. Failure to fulfill this commitment may constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of this commitment and is authorized to bind the bidder to the commitment herein set forth.

Date:_____

Name of Authorized Officer:_____

Signature:_____

Title:_____

SEAL

State of North Carolina, County of _____
Subscribed and sworn to before me this _____day of_____20__
Notary Public_____
My commission expires_____

Do not submit with bid ***Do not submit with bid*** ***Do not submit with bid*** ***Do not submit with bid***

State of North Carolina – AFFIDAVIT D
Good Faith Efforts

Lee County Schools

*****This form is to be submitted only by the apparent lowest responsible, responsive bidder*****

If the Lee County Schools goal for participation by minority business **is not** achieved, the Bidder shall provide the following documentation to the Owner of his good faith efforts:

Affidavit of_____I do hereby certify that on the
(Name of Bidder)

_____
(Project Name)

Project ID#_____Amount of Bid $_____

I will expend a minimum of_____% of the total dollar amount of the contract with minority business enterprises. Minority businesses will be employed as construction subcontractors, vendors, suppliers or providers of professional services. Such work will be subcontracted to the following firms listed below. (Attach additional sheets if required)

Name and Phone Number	*Minority Category	Work Description	Dollar Value	Percentage of Goal

*Minority categories: Black, African American (**B**), Hispanic (**H**), Asian American (**A**) American Indian (**I**), Female (**F**) Socially and Economically Disadvantaged (**D**)

Examples of documentation that may be required to demonstrate the Bidder's good faith efforts to meet the goals set forth in these provisions include, but are not necessarily limited to, the following:

A. Copies of solicitations for quotes to at least three (3) minority business firms from the source list provided by the State for each subcontract to be let under this contract (if 3 or more firms are shown on the source list). Each solicitation shall contain a specific description of the work to be subcontracted, location where bid documents can be reviewed, representative of the Prime Bidder to contact, and location, date and time when quotes must be received.
B. Copies of quotes or responses received from each firm responding to the solicitation.
C. A telephone log of follow-up calls to each firm sent a solicitation.
D. For subcontracts where a minority business firm is not considered the lowest responsible sub-bidder, copies of quotes received from all firms submitting quotes for that particular subcontract.
E. Documentation of any contacts or correspondence to minority business, community, or contractor organizations in an attempt to meet the goal.
F. Copy of pre-bid roster.
G. Letter documenting efforts to provide assistance in obtaining required bonding or insurance for minority business.
H. Letter detailing reasons for rejection of minority business due to lack of qualification.
I. Letter documenting proposed assistance offered to minority business in need of equipment, loan capital, lines of credit, or joint pay agreements to secure loans, supplies, or letter of credit, including waiving credit that is ordinarily required.

Failure to provide the documentation as listed in these provisions may result in rejection of the bid and award to the next lowest responsible and responsive bidder.

Do not submit with bid ***Do not submit with bid*** ***Do not submit with bid*** ***Do not submit with bid***

Pursuant to GS143-128.2(d), the undersigned will enter into a formal agreement with Minority Firms for work listed in this schedule conditional upon execution of a contract with the Owner. Failure to fulfill this commitment may constitute a breach of the contract.

The undersigned hereby certifies that he or she has read the terms of this commitment and is authorized to bind the bidder to the commitment herein set forth.

Date:_____ Name of Authorized Officer:_____

Signature:_____

Title:_____

SEAL

State of_____, County of _____

Subscribed and sworn to before me this_____day of_____20

Notary Public_____

My commission expires _____

Do not submit with bid ***Do not submit with bid*** ***Do not submit with bid*** ***Do not submit with bid***

State of North Carolina – APPENDIX E
Documentation for Contract Payments

County of Lee / Lee County Schools

Prime Contractor/Architect:

_____

Address & Phone:

_____

Project Name:

_____

Pay Application #:_____Period: _____

The following is a list of payments made to Minority Business Enterprises on this project for the above-mentioned period.

MBE FIRM NAME	* INDICATE TYPE OF MBE	AMOUNT PAID THIS MONTH	TOTAL PAYMENTS TO DATE	TOTAL AMOUNT COMMITTED

*Minority categories: Black, African American (B), Hispanic (H), Asian American (A), American Indian (I), Female (F), Social and Economically Disadvantage (D)

Date:_____
Approved/Certified By:

_____
Name

_____
Title

_____
Signature

SUBMIT WITH ALL APPLICATIONS FOR PAYMENT

OWNER-CONTRACTOR AGREEMENT

PROJECT NUMBER: _____

SCHOOL NAME: _____

THIS AGREEMENT, in four (4) copies, made this **( )** day of_____, Two Thousand and Twenty-four by and between Lee County Schools (herein referred to as the "Owner"), whose mailing address is 106 Gordon Street, Sanford, NC 27330 and_____. (herein referred to as the "Contractor"), whose mailing address is _____. Correspondence, submittals, and notices relating to or required under this Contract shall be sent in writing to the above addresses; unless either party is notified in writing by the other, of a change in address.

WITNESSETH:

WHEREAS, it is the intent of the Owner to obtain the services of the Contractor in connection with the Transportation Facility (hereinafter referred to as the "Project" or the "Work"); and

WHEREAS, the Contractor desires to perform such construction in accordance with the terms and conditions of this Agreement,

NOW, THEREFORE, in consideration of the promises made herein and other good and valuable consideration, the following terms and conditions are hereby mutually agreed to, by and between the Owner and Contractor:

Article 1

DEFINITIONS

1.1 All terms in this Agreement which are defined in the Information for Bidders and the General Conditions shall have the meanings designated therein.

1.2 The Contract Documents are as defined in the General Conditions. Such documents form the Contract, and all are as fully a part thereof as if attached to this Agreement or repeated herein. The Contract Documents consist of the Owner-Contractor Agreement, the General and Supplemental Conditions of the Contract, the Drawings, the Specifications, all Addenda issued prior to bidding, and all Modifications and Change Orders issued after execution of the Contract.

Article 2

STATEMENT OF THE WORK

2.1 The Project is the Work identified in the plans and specifications prepared by CRA & Associates, Inc., 100 Europa Drive, Suite 565, Chapel Hill, NC 27517, dated June 25, 2026 for the Lee County Board of Education, including the following addenda:

Addendum No._____dated_____.

A listing of the plans and specifications included in the Contract Documents is attached as Exhibit A.

2.2 The Parties agree that the Project shall include the following alternates:

_____

2.3 The Parties agree to the following modifications to the Project's plans and specifications, including the noted value engineering items:

List item(s) and proposed deduct/add(s). If none, delete this language list "None"

2.4 The Parties agree that the following allowances are included in the Contract Sum in Section 5.1 below:

List item(s) and proposed allowance(s). If none, delete this language list "None"

2.5 The Contractor shall provide and pay for all materials, tools, equipment, labor and professional and non-professional services, and shall perform all other acts and supply all other things necessary, to fully and properly perform and complete the Work, as required by the Contract Documents.

2.6 The Contractor shall further provide and pay for all related facilities described in any of the Contract Documents, including all work expressly specified therein and such additional work as may be reasonably inferred therefrom, saving and excepting only such items of work as are specifically stated in the Contract Documents not to be the obligation of the Contractor. The totality of the obligations imposed upon the contractor by this Article and by all other provisions of the Contract Documents, as well as the structures to be built and the labor to be performed, is herein referred to as the "Work".

Article 3

DESIGN CONSULTANT

3.1 The Design Consultant (as defined in the General Conditions) shall be CRA & Associates, Inc., 100 Europa Drive, Suite 565, Chapel Hill, NC 27517, however, that the Owner may, without liability to the Contractor, unilaterally amend this Article from tme to time by designating a different person or organization to act as its Design Consultant and soadvising the Contractor in writing, at which ime the person or organization so designated shallbe the Design Consultant for purposes of this Contract.

Article 4

TIME OF COMMENCEMENT AND COMPLETION

4.1 The Contractor shall commence the Work promptly upon the date established in the Notice to Proceed. If there is no Notice to Proceed, the date of commencement of the Work shall be the date of this Agreement or such other date as may be established herein.

4.2 Time is of the essence. The Contractor shall achieve Final Completion, as defined in the General Conditions on or before the date established for Final Completion on in the Supplemental Conditions.

4.3 The Supplemental Conditions contains certain specific dates that shall be adhered to and are the last acceptable dates unless modified in writing by mutual agreement between the Contractor and the Owner. All dates indicate midnight unless otherwise stipulated. The only exceptions to this schedule are defined in the General Conditions under 8.3 DELAYS AND EXTENSIONS OF TIME.

4.4 Should the Contractor fail to complete the Work on or before the dates stipulated for Substantial Completion and/or Final Completion, or such later date as may result from an extension of time granted by the Owner, he shall pay the Owner, as liquidated damages the sums set forth in the General and Supplemental Conditions.

Article 5

CONTRACT SUM

1.1 Provided that the Contractor shall strictly and completely perform all of its obligations under the Contract Documents, and subject only to additions and deductions by Modification or as otherwise provided in the Contract Documents, the Owner shall pay to the Contractor, in current funds and at the time and in the installments hereinafter specified, the sum of _____ Dollars ($_____) herein referred to as the "Contract Sum". This amount includes the base bid and the Alternates in Section 2.2

1.2 The Contract Sum includes the value engineering items and other contract modifications noted in Section 2.3 above that total $_____.

1.3 Unit Prices are established as follows for the Project:

Unit Price No. 1		$
Unit Price No. 2		$
Unit Price No. 3		$
Unit Price No. 4		$

Article 6

PROGRESS PAYMENTS

6.1 The Contractor hereby agrees that on or about the First day of the month for every month during the performance of the Work he will deliver to the Owner's Project Manager an Application for Payment in accordance with the provisions of Article 9 of the General Conditions. This date may

be changed upon mutual agreement, stated in writing, between the Owner and Contractor. Payment under this Contract shall be made as provided in the General Conditions. Payments due and unpaid under the Contract Documents shall not bear interest.

Article 7

OTHER REQUIREMENTS

7.1 The Contractor shall submit the Performance Bond, Labor and Material Payment Bond and Certification of Insurance as required by the Contract Documents.

7.2 The Owner shall furnish to the Contractor one **(1)** set of drawings and one **(1)** set of specifications, at no extra cost, for use in the Construction of the Work. Additional sets of drawings or specifications may be obtained by the Contractor by paying the Owner for the costs of reproduction, handling and mailing.

7.3 The Contractor shall make a good faith effort to utilize Historically Underutilized Businesses (HUB's) per N.C. Gen. Stat. 143-128.2, and as described in the construction documents.

7.4 The General Conditions, Supplemental Conditions and the plans and specifications, including any addenda, are incorporated herein byreference.

IN WITNESS WHEREOF, the Lee County Board of Education (hereinbefore called the "Owner") has caused these presents to be signed and its corporate seal to be hereunto affixed, attested by its Chairperson and Secretary, and _____(hereinbefore called "Contractor") has caused these presents to be signed by its President and its Corporate seal to be hereunto affixed, as hereinafter attested, all as of the day and year first above written.

LEE COUNTY BOARD OF EDUCATION

_____

Sherry Lynn Womack,
Chair [Corporate Seal]

ATTEST:

_____

Dr. Chris Dossenbach, Superintendent

By: _____
, President or Vice-President [Corporate Seal]
(Print Name)

ATTEST:

_____

Corporate Secretary

This instrument has been pre-audited in the manner required by the School Budget and Fiscal Control Act.

_____

Finance Officer Date

LEE COUNTY SCHOOLS
TRANSPORTATION FACILITY

PERFORMANCE BOND

IT IS HEREBY AGREED that (Insert full name and address of Contractor)

as Principal, hereinafter called Contractor, and, (Insert full name and address of Surety)

as Surety, hereinafter called Surety, are held and firmly bound unto the

as Obligee, hereinafter called Owner, in the amount of _____ _____ Dollars ($), for the payment whereof Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these obligations.

WHEREAS, Contractor has by written agreement dated_____, 20__, entered into a contract with Owner for the construction of (Insert the name of the Project)

in accordance with Drawings and Specifications prepared by DTW Architects & Planners, Ltd. (Insert full name and address of Architect/Engineer)

which contract is by reference made a part hereof, and is hereinafter referred to as the Contract.

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if Contractor shall promptly and faithfully perform said Contract, then this obligation shall be null and void; otherwise it shall remain in full force and effect. The Surety hereby waives notice of any alteration or extension of time made by the Owner.

Whenever Contractor shall be, and declared by Owner to be in default, under the Contract, the Owner having performed Owner's obligations thereunder, the Surety may promptly remedy the default, or shall promptly:

1) Complete the Contract in accordance with its terms and conditions, or

2) Obtain a bid or bids for completing the Contract in accordance with its terms and conditions, and upon determination by Surety of the lowest responsible bidder, or, if the Owner elects, upon determination by the Owner and the Surety jointly of the lowest responsible bidder, arrange for a contract between such bidder and Owner, and make available as Work progresses (even though there should be a default or a succession of defaults under the contract or contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the balance of the contract price; but not exceeding, including other costs and damages for which

the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "balance of the contract price," as used in this paragraph, shall mean the total amount payable by Owner to Contractor under the Contract and any amendments thereto, less the amount properly paid by Owner to Contractor.

Any suit under this bond must be instituted before the expiration of any applicable statute of limitations under the Contract.

No right of action shall accrue on this bond to or for the use of any person or corporation other than the Owner named herein or the heirs, executors, administrators or successors of the Owner.

Signed and sealed this_____day of_____20_____.

PRINCIPAL

[Affix corporate seal]

_____

(Name)_____

(Title)_____

_____
(Witness)

SURETY

[Affix corporate seal]

_____

(Name)_____

(Title)_____

_____
(Witness)

LEE COUNTY SCHOOLS
TRANSPORTATION FACILITY

LABOR AND MATERIAL PAYMENT BOND

THIS BOND IS ISSUED SIMULTANEOUSLY WITH PERFORMANCE BOND IN FAVOR OF THE OWNER CONDITIONED ON THE FULL AND FAITHFUL PERFORMANCE OF THE CONTRACT

IT IS HEREBY AGREED that (Insert full name and address of Contractor)

as Principal, hereinafter called "Principal," and, (Insert full name and address of Surety)

as Surety, hereinafter called "Surety," are held and firmly bound unto the

as Obligee, hereinafter called Owner, for the use and benefit of claimants as hereinbelow defined, in the amount of _____ _____ Dollars ($),
for the payment whereof Principal and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these obligations.

WHEREAS, Principal has by written agreement dated_____, 20_____,
entered into a contract with Owner for the construction of (Insert the name of the Project)

in accordance with Drawings and Specifications prepared by DTW Architects & Planners, Ltd. (Insert full name and address of Architect/Engineer)

which contract is by reference made a part hereof, and is hereinafter referred to as the "Contract."

NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that, if Principal shall promptly make payment to all claimants as hereinafter defined, for all labor and material used or reasonably required for use in the performance of the Contract, then this obligation shall be void; otherwise it shall remain in full force and effect, subject, however, to the following conditions:

1. A claimant is defined as one having a direct contract with the principal or with a Subcontractor of the Principal for labor, material, or both, used or reasonably required for use in the performance of the Contract, labor and material being construed to include that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental of equipment directly applicable to the Contract.

2. The above named Principal and Surety hereby jointly and severally agree with the Owner that every claimant as herein defined, who has not been paid in full before the expiration of a period of ninety (90) days after the date on which the last of such claimant's work or labor was done or performed, or materials were furnished by such claimant, may sue on this bond for the use of such claimant, prosecute the suit to final judgment for such sum or sums as may be justly due claimant, and have execution thereon. The Owner shall not be liable for the payment of any costs or expenses of any such suit.

3. No suit or action shall be commenced hereunder by any claimant:

a) Unless claimant, other than one having a direct contract with the Principal, shall have given written notice to any two of the following: the Principal, the Owner, or the Surety above named, within ninety (90) days, after such claimant did or performed the last of the work or labor, or furnished the last of the materials for which said claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were furnished, or for whom the work or labor was done or performed. Such notice shall be served by mailing the same by registered mail or certified mail; postage prepaid, in an envelope addressed to the Principal, Owner or Surety, at any place where an office is regularly maintained for the transaction of business, or served in any manner in which legal process may be served in the state in which the aforesaid project is located, save that such service need not be made by a public officer.

b) After the expiration of one (1) year following the date on which Principal ceased Work on said Contract, it being understood, however, that if any limitation embodied in this bond is prohibited by any law controlling the construction hereof such limitation shall be deemed to be amended so as to be equal to the minimum period of limitation permitted by such law.

c) Other than in a state court of competent jurisdiction in and for the county or other political subdivision of the state in which the Project, or any part thereof, is situated, or in the United States District Court for the district in which the Project, or any part thereof, is situated, and not elsewhere.

4. The amount of this bond shall be reduced by and to the extent of any payment or payments made in good faith hereunder, inclusive of the payment by Surety of mechanics' liens which may be filed of record against said improvement, whether or not claim for the amount of such lien be presented under and against this bond.

Signed and sealed this_____day of_____20_____.

PRINCIPAL

[Affix corporate seal]

_____

(Name)_____

(Title)_____

_____
(Witness)

SURETY

[Affix corporate seal]

_____

(Name)_____

(Title)_____

_____
(Witness)

LEE COUNTY SCHOOLS
STATE SALES AND USE TAX REPORT
SUMMARY TOTALS AND CERTIFICATION
APPENDIX A

CONTRACTOR: _____ Page: _____ of _____

PROJECT: _____ FOR PERIOD: _____

		STATE SALES TAX SUMMARY FOR NC:	TOTAL FOR NORTH CAROLINA
CONTRACTOR		$	$
SUBCONTRACTOR(S)*		$	$
TOTAL		$	$

I certify that the above figures do not include any tax paid on supplies, tools and equipment which were used to perform this contract and only includes those building materials, supplies, fixtures and equipment which actually became a part of or annexed to the building or structure. I certify that, to the best of my knowledge, the information provided here is true, correct, and complete.

Sworn to and subscribed before me,

This the_____ day of _____, 20

_____
Signed

_____
Notary Public

_____
Print or Type Name of Above

My Commission Expires: _____

Seal:

NOTE: This certified statement may be subject to audit.

LEE COUNTY SCHOOLS
COUNTY SALES AND USE TAX REPORT
SUMMARY TOTALS AND CERTIFICATION
APPENDIX A

CONTRACTOR: _____ Page: _____ of _____

PROJECT: _____ FOR PERIOD: _____

	TOTAL FOR COUNTY OF:	TOTAL FOR COUNTY OF:	TOTAL FOR COUNTY OF:	TOTAL FOR COUNTY OF:	TOTAL FOR COUNTY OF:	TOTAL ALL COUNTIES:
CONTRACTOR	$	$	$	$	$	$
SUBCONTRACTOR(S)*	$	$	$	$	$	$
TOTAL	$	$	$	$	$	$

• Attach subcontractor(s) report(s)

** Must balance with Detail Sheet(s)

I certify that the above figures do not include any tax paid on supplies, tools and equipment which were used to perform this contract and only includes those building materials, supplies, fixtures and equipment which actually became a part of or annexed to the building or structure. I certify that, to the best of my knowledge, the information provided here is true, correct, and complete.

Sworn to and subscribed before me,

This the_____ day of _____, 20

_____
Notary Public

My Commission Expires: _____

Seal:

_____
Signed

_____
Print or Type Name of Above

NOTE: This certified statement may be subject to audit.

LEE COUNTY SCHOOLS
SALES AND USE TAX REPORT DETAIL
APPENDIX A

CONTRACTOR: _____

PROJECT: _____ FOR PERIOD: Page: _____ of _____

VENDOR NAME	PURCHASE DATE	TAXABLE AMOUNT ($)	STATE TAX PAID ($)	COUNTY TAX PAID ($)	INVOICE TOTAL ($)	COUNTY OF SALE
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
	TOTAL =		$	$		

I certify that the above figures do not include any tax paid on supplies, tools and equipment which were used to perform this contract and only includes those building materials, supplies, fixtures and equipment which actually became a part of or annexed to the building or structure. I certify that, to the best of my knowledge, the information provided here is true, correct, and complete.

Sworn to and subscribed before me,
This the_____ day of _____, 20___

_____
Notary Public

My Commission Expires: _____

Seal:

_____
Signed

_____
Print or Type Name of Above

NOTE: This certified statement may be subject to audit.

** If this is an out-of-state vendor, the County of Sale should be the county to which the merchandise was shipped.*

LEE COUNTY SCHOOLS
SALES AND USE TAX REPORT DETAIL
APPENDIX A

CONTRACTOR: _____ Page: _____ of _____

PROJECT: _____ FOR PERIOD: _____

VENDOR NAME	PURCHASE DATE	TAXABLE AMOUNT ($)	STATE TAX PAID ($)	COUNTY TAX PAID ($)	INVOICE TOTAL ($)	COUNTY OF SALE
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
		$	$	$	$	
	TOTAL =		$	$		

I certify that the above figures do not include any tax paid on supplies, tools and equipment which were used to perform this contract and only includes those building materials, supplies, fixtures and equipment which actually became a part of or annexed to the building or structure. I certify that, to the best of my knowledge, the information provided here is true, correct, and complete.

Sworn to and subscribed before me,
This the_____ day of _____, 20___

_____
Notary Public

My Commission Expires: _____

Seal:

_____
Signed

_____
Print or Type Name of Above

NOTE: This certified statement may be subject to audit.

Durham Public Schools
DPS Project Name
DPS Project No.

** If this is an out-of-state vendor, the County of Sale should be the county to which the merchandise was shipped.*

CHANGE PROPOSAL
WORKSHEET SUMMARY FORM

Project:		**Proposal #:**	
Contract:		**Project #:**	
Contractor:		**Contractor #:**	

Description of change:

INSTRUCTIONS FOR FORM: Only enter data in yellow boxes - all other fields will automatically calculate.
Contractor's detailed breakdown of material & labor must accompany this form. Percentages shaded in gray boxes are established by contract requirements and should not be modified.

							SUBTOTALS
Materials	(Attach list with Qty, Item, Unit $, Unit mh, Total mh, OT mh, Total $)						
	1 Total Direct Cost of Materials					$0.00	
	2 Overhead & Profit on Item 1.				10.0 %	$0.00	
	(10% maximum, includes small tools & consumables)						
	3 Sales Tax				7.5 %	$0.00	
	4 Shipping & Transportation						$0.00
Labor							
	5 Manhours - Straight Time	0	MH @	$25.00	/hr.	$0.00	
	Overtime Premium	0	MH @	$12.50	/hr.	$0.00	
	6 Overhead & Profit on Item 5.				10.0 %	$0.00	
	(10% maximum on straight labor cost, not premium portion)						
	(O & P includes supervison time)						
	7 Payroll Taxes & Insurance	30.0%	STRAIGHT TIME ONLY			$0.00	
		7.65%	OVERTIME PORTION			$0.00	$0.00
Equipment Rental	(Include quotes)						
	8 Equipment Rental					$0.00	
	9 Overhead & Profit on Item 8.				6.0 %	$0.00	$0.00
	(6% maximum)						
Subcontractors	(Include quotes with material & equipment backup)						
	10 Subcontractors					$0.00	
	11 Overhead & Profit on Item 10.				6.0 %	$0.00	$0.00
	(6% maximum)						
						Subtotal of Proposal	$0.00
	12 Bonds (% of subtotal of proposal)			1.5%			$0.00
						TOTAL OF CHANGE PROPOSAL	$0.00

Time Extension Requests:_____day(s) Schedule Activity # Affected: _____

The Contractor agrees to perform the work outlined in this change proposal for the amount specified above and in accordance with the Contract documents if the work is authorized by the Owner.

Contractor's Signature: _____ **Date:** _____

Recommended by Design Consultant: _____ **Date:** _____

Owner's Representative Approval: _____ **Date:** _____

GENERAL CONDITIONS

NOTICE OF DISCLAIMER

TAKE NOTICE, that these General Conditions may contain language and Article, Section or Paragraph headings or names which appear similar to or the same as the provisions of the "General Conditions of the Contract for Construction", published by the American Institute of Architects, AIA Document A-201.

TAKE NOTICE, however, that these General Conditions are substantially and materially different in many respects from the AIA Document A-201 and that certain additions, deletions or other modifications have been made to provisions similar to those contained in the AIA Document. This document, further, contains provisions, which do not appear in the AIA document.

The use of any language or Article or Paragraph format similar to or the same as AIA Document A-201 does not constitute an endorsement by the American Institute of Architects of this document.

GENERAL CONDITIONS OF THE CONTRACT FORCONSTRUCTION

TABLE OF ARTICLES

1. CONTRACT DOCUMENTS
2. DESIGN CONSULTANT
3. OWNER
4. CONTRACTOR
5. SUBCONTRACTORS
6. WORK BY OWNER OR BY SEPARATE CONTRACTORS
7. MISCELLANEOUS PROVISIONS
8. TIME
9. PAYMENTS AND COMPLETION
10. PROTECTION OF PERSONS AND PROPERTY
11. INSURANCE
12. CHANGES IN THE WORK
13. UNCOVERING AND CORRECTION
14. TERMINATION OF THE CONTRACT
15. DISPUTE RESOLUTION

ARTICLE 1

CONTRACT DOCUMENTS

1.1 DEFINITIONS

1.1.1 AS SHOWN, AS INDICATED, AS DETAILED: These words, and words of like implication, refer to information contained in Drawings and Specifications describing the Work, unless explicitly stated otherwise in the Contract Documents.

1.1.2 CLAIM: A Claim as used in the Contract is a demand or assertion by one of the parties seeking, as a matter of right, adjustment or interpretation of contract terms, payment of money, a credit against the payment of money, extension of time or other relief with respect to the terms of the Contract. The term Claim also includes other disputes and matters in question between the parties to a contract involved in the Owner’s construction and repair projects arising out of or relating to the Contract or the construction process.

1.1.3 CONTRACT: The Contract is the sum of all the Contract Documents. The Contract represents the entire and integrated agreement between the Owner and the Contractor and supersedes all

prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification as defined in Paragraph 1.1.4. The Contract may also be referred to in the Contract Documents as “this Contract”, “this Agreement” or “the Agreement”.

1.1.4 CONTRACT DOCUMENTS: The Contract Documents consist of the Owner-Contractor Agreement, the Conditions of the Contract (General and Supplemental Conditions), the Plans, Drawings, and Specifications, and all Addenda thereto issued prior to and all Modifications thereto issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties; (2) a Change Order or a Construction Change Directive issued pursuant to the provisions of Article 12; (3) a written interpretation issued by the Design Consultant pursuant to Paragraph 2.2.7; or (4) a written order for a minor Change in the Work issued pursuant to Section 12.4. The Contract Documents do not include any other documents including but not limited to soils, geotechnical or other reports, surveys and analysis, which may be printed, bound or assembled with the Contract Documents, or otherwise made available to the Contractor for review or information under this Contract, unless specifically enumerated and directly incorporated by reference in the Contract Documents.

1.1.5 HE/HIS: The term He or His is not intended to be gender specific.

1.1.6 MANUFACTURER: An individual, company, or corporation who manufactures, fabricates, or assembles a standard product. A standard product is one that is not made to special design, and if furnished by either direct sale or by contract to the Contractor, Subcontractor or Vendor.

1.1.7 MATERIAL SUPPLIER OR VENDOR: A person or organization who supplies, but who is not responsible for the installation of, materials, products and equipment.

1.1.8 NOTICE: The term Notice as used herein shall mean and include written notice. Notice shall be deemed to have been given when delivered to the address of the person, firm or corporation for whom intended, or to his, their or its duly authorized agent, representative or officer; or when enclosed in a postage prepaid wrapper or envelope addressed to such person, firm or corporation at his, their or its Notice Address and deposited in a United States mailbox by registered or certified mail. To “Notify” means to give Notice. The Notice Addresses for the Owner and Contractor are stated in the Owner-Contractor Agreement and may be changed by a party by giving Notice to the other of such change.

1.1.9 PLANS OR DRAWINGS: All drawings or reproduction of drawings pertaining to the Work.

1.1.10 PRODUCT: The term Product includes materials, systems and equipment.

1.1.11 PROJECT: The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part.

1.1.12 PROPOSAL: A complete and properly signed document whereby the Contractor proposes to provide additional or a reduced scope of construction work on the Project for the sums stipulated therein, supported by data required by the Design Consultant or Owner.

1.1.13 PROVIDE: As a directive to the Contractor, and as pertaining to labor, materials or equipment, "provide" means "furnish and install completely".

1.1.14 SPECIFICATIONS: Descriptions, provisions and requirements, pertaining to method and manner of performing the Work, or to quantities and qualities of materials or equipment to be

furnished under terms of the Contract.

1.1.15 WORK: The Work comprises the construction and services required of the Contractor by the Contract Documents and includes all labor, supplies and other facilities or things necessary to produce such construction, and all materials, equipment, and supplies incorporated or to be incorporated in such construction.

1.2 EXECUTION, CORRELATION AND INTENT

1.2.1 The Contractor and Owner acknowledge that neither these General Conditions, nor any other Contract Document shall be construed against the Owner due to the fact that they may have been drafted by the Owner or the Owner's agent. For the purposes of construing these General Conditions, and any other Contract Document, both the Contractor and the Owner shall be considered to have jointly drafted them.

1.2.2 The Owner-Contractor Agreement shall be signed in not less than three (3) copies by the Owner and Contractor, and each of which shall be deemed an original, but all of which shall constitute one and the same instrument.

1.2.3 By executing the Contract, the Contractor represents that he has visited the site, familiarized himself with the local conditions under which the Work is to be performed, and correlated his observations with the requirements of the Contract Documents.

1.2.4 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work. The Contract Documents are complementary, and what is required by any one shall be as binding as if required by all. Performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results. Words and abbreviations which have well-known technical or trade meanings are used in the Contract Documents in accordance with such recognized meanings unless otherwise specifically defined herein. The table of contents, titles, headings, running headlines and marginal notes contained herein and in said documents are solely to facilitate reference to various provisions of the Contract Documents and in no way affect, limit or cast light upon the interpretation of the provisions to which they refer.

1.2.5 The organization of the Specifications into divisions, sections and articles, and the arrangement of Drawings are for convenience only. The Contractor may subcontract the Work in such divisions as he sees fit consistent with applicable law and he is ultimately responsible for furnishing all of the Work.

1.2.6 Anything shown on the Drawings and not mentioned in the Specifications or mentioned in the Specifications and not shown on the Drawings shall have the same effect as if shown or mentioned respectively in both. Detailed specifications take priority over general specifications and detailed drawings take precedence over general drawings. Any Work shown on one drawing shall be construed to be shown in all drawings. If any portion of the Contract Documents shall be in conflict with any other portion, the various documents comprising the Contract Documents shall govern in the following order of precedence: The Owner-Contractor Agreement; the Supplemental Conditions; the General Conditions; the Specifications; the Drawings. The Contractor shall notify the Design Consultant and the Owner of all such inconsistencies promptly. Any such conflict or inconsistency between or in the Drawings or Specifications shall be submitted by the Contractor promptly to the Owner and Design Consultant and the Design Consultant's decision thereon shall be final and conclusive.

1.2.7 The Contractor agrees that nothing contained in the Contract Documents or any contract between the Owner and the Design Consultant shall create any contractual relationship between the Design Consultant and the Contractor, or between the Design Consultant and any Subcontractor or Sub-subcontractors. The Contractor acknowledges and agrees that this Contract is not intended to create, nor shall any provision be interpreted as creating, any contractual relationship between the Owner or Contractor and any third parties.

1.2.8 The provisions of this Contract cannot be amended, modified, varied or waived in any respect except by a Modification. The Contractor is hereby given notice that no person has authority to orally waive, or to release the Contractor from any of the Contractor's duties or obligations under or arising out of this Contract. Any waiver, approval or consent granted by Modification to the Contractor shall be limited to those matters specifically and expressly stated thereby to be waived, approved or consented to and shall not relieve the Contractor of the obligation to obtain any future waiver, approval or consent.

1.2.9 Any material or operation specified by reference to published specifications of a Manufacturer, a society, an association, a code, or other published standard, shall comply with requirements of the listed document which is current on date the Owner received bids for the construction of the Project. In case of a conflict between referenced document and the Specifications, Specifications shall govern. In case of a conflict between such listed documents, the one having more stringent requirements shall govern.

1.2.10 The Contractor, if requested, shall furnish an affidavit from each or any Manufacturer certifying that materials or products delivered to the job meets requirements specified.

1.3 OWNERSHIP AND USE OF DOCUMENTS

1.3.1 All Drawings, Specifications and copies thereof furnished by the Design Consultant are and shall remain the property of the Owner. They are to be used by Contractor only with respect to the Project and are not to be used by Contractor on any other project. With the exception of one contract set for each party to the Contract, such documents are to be returned or suitably accounted for to the Owner on request at the completion of the Work. Submission or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of Owner’s rights or the Design Consultant's common law copyright or other reserved rights.

ARTICLE 2

THE DESIGN CONSULTANT

2.1 DEFINITIONS

2.1.1 The term "Design Consultant" or "A/E" or "Architect" or "Engineer" as used or set forth in the Contract Documents, shall mean the entity and its consultants or agents, or their duly authorized representatives, that is responsible for designing or engineering the Work, and performing the activities specified herein, and in the Agreement for Design Consultant Services, including any consultants to said entity or firm acting within the scope of their agreements with the Design Consultant. Such firm or agency and its representatives shall act severally within the scope of particular duties entrusted to them, unless otherwise provided for in the Contract Documents or in the Agreement for Design Consultant Services.

2.1.2 The Design Consultant may be identified in the Owner-Contractor Agreement and is referred to throughout the Contract Documents as if singular in number and masculine in gender. The Design Consultant is further described as and, throughout this document, shall mean one or both of the following:

2.1.2.1 ARCHITECT, a person or other legal entity lawfully licensed to practice architecture in the State wherein the Project is located; or

2.1.2.2 ENGINEER, a person or other legal entity lawfully licensed to practice engineering in the State wherein the Project is located.

2.2 SERVICES OF THE DESIGN CONSULTANT

2.2.1 The Design Consultant will provide certain services as hereinafter described and further described in the Agreement for Design Consultant Services.

2.2.2 Should errors, omissions, or conflicts in the Drawings, Specifications, or other Contract Documents prepared by or on behalf of the Design Consultant be discovered, the Design Consultant will prepare such amendments or supplementary documents and provide consultation as may be required.

2.2.3 The Design Consultant will visit the site at intervals appropriate to the stage of construction to familiarize itself generally with the progress and quality of the Work and to determine in general if the Work is proceeding in accordance with the Contract Documents. The Design Consultant will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work, but it shall make as many inspections as may reasonably be required to fulfill its obligations to the Owner. On the basis of such on-site observations, the Design Consultant and his consultants shall endeavour to guard the Owner against defects and deficiencies in the Work. The Design Consultant will conduct the weekly construction meeting and shall be responsible for preparing accurate and complete minutes of all such meetings and other Project meetings and distributing same to all participants.

2.2.4 The Design Consultant will render written field reports to the Owner in the form required by the Owner relating to the periodic visits and inspections of the Project required by Paragraph 2.2.3.

2.2.5 The Design Consultant will not be responsible for and will not have control or charge of construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work, and he will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents. The Design Consultant will not be responsible for or have control or charge over the acts or omissions of the Contractor, Subcontractors, or any of their agents or employees, or any other persons performing any portion of the Work.

2.2.6 The Design Consultant shall at all times have access to the Work wherever it is in preparation or progress. The Contractor shall provide safe facilities for such access so the Design Consultant may perform his functions under the Contract Documents.

2.2.7 As required, the Design Consultant will render to the Owner, within a reasonable time, interpretations concerning the design and other technical aspects of the Work and the Contract Documents.

2.2.8 All communications, correspondence, submittals, and documents exchanged between the Design Consultant and the Contractor in connection with the Project shall be copied to the Owner, unless the Owner provides otherwise. Further, all communications, correspondence, submittals and documents transmitted from the Owner or Design Consultant will be directed to the Contractor and copied to the Owner or Design Consultant.

2.2.9 All interpretations and decisions of the Design Consultant shall be consistent with the intent of and reasonably inferable from the Contract Documents.

2.2.10 The Design Consultant's decisions in matters relating to artistic effect will be final if consistent with the intent of the Contract Documents.

2.2.11 If the Design Consultant observes any Work that does not conform to the Contract Documents, the Design Consultant shall report this observation to the Owner. The Design Consultant will prepare and submit to the Owner "punch lists" of the Contractor's work, which is not in conformance with the Contract Documents. The Owner will transmit such "punch lists" to the Contractor.

2.2.12 The Design Consultant has the authority to condemn or reject any or all of the Work on behalf of the Owner when, in its opinion, the Work does not conform to the Contract Documents. Whenever, in the Design Consultant's reasonable opinion, it is considered necessary or advisable for the implementation of the intent of the Contract Documents, the Design Consultant will have the authority to require special inspection or testing of any portion of the Work in accordance with the provisions of the Contract Documents whether or not such portion of the Work be then fabricated, installed or completed.

2.2.13 The Design Consultant will review the Contractor's submittals such as Shop Drawings, Product Data and Samples, but only for conformance with the design concept of the Work and for general compliance with the Contract Documents. Such action shall be taken within fourteen (14) days of receipt unless otherwise authorized by the Owner.

2.2.14 The Owner will establish with the Design Consultant procedures to be followed for review and processing of all Shop Drawings, catalogue submittals, project reports, test reports, maintenance manuals, and other necessary documentation, as well as requests for changes and applications for extensions of time.

2.2.15 The Design Consultant will prepare Change Orders and Construction Change Directives when requested by the Owner.

2.2.16 The Design Consultant and the Owner will conduct inspections to determine the dates of Substantial Completion and Final Completion. The Design Consultant will issue a final Certification of Payment.

2.2.17 The Design Consultant will prepare three (3) printed copies and one (1) electronic computer file compatible with the latest version of AutoCAD, or other program designated by Owner, showing significant Changes in the Work made during the construction process, based on neatly and clearly marked-up Drawings, prints, and other data furnished by the Contractor(s) and the applicable Addenda, clarifications and Change Orders which occurred during the Project. The Design Consultant will also provide the Owner assistance in the original operation of any equipment or system such as initial start-up, testing, adjusting, and balancing.

2.2.18 In case of the termination of the employment of the Design Consultant, the Owner may appoint a Design Consultant whose status under the Contract Documents shall be that of the former Design Consultant.

ARTICLE 3

OWNER

3.1 DEFINITION

3.1.1 The Owner is the person or entity identified as such in the Owner-Contractor Agreement and may be referred to throughout the Contract Documents as if singular in number and masculine in gender. The term Owner means the Owner or his authorized representative or agent. The phrase "Owner or its agent" as used in this Agreement, does not include the Separate Contractors or their Subcontractors.

3.1.1.1 Owner; Lee County c/o Lee County Schools
106 Gordon Street
Sanford, NC 27330

3.2 INFORMATION, SERVICES AND RIGHTS OF THE OWNER

3.2.1 The Owner will provide administration of the Contract as herein described. The Design Consultant shall also provide aspects of administration of the Contract as herein described or as specified in the Agreement for Design Consultant Services.

3.2.2 The Owner shall at all times have access to the Work whenever it is in preparation or progress. The Contractor shall provide safe facilities for such access.

3.2.3 The Owner shall not be responsible for or have control or charge of the construction means, methods, techniques, sequences, or procedures, or for safety precautions and programs in connection with the Work, and will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents.

3.2.4 The Owner will have authority to require special inspection or testing of portions of the Work to the same extent as the Design Consultant in accordance with Paragraph 2.2.12 whether or not such portion of the Work be then fabricated, installed, or completed. However, neither the Owner's authority to act under Paragraph 3.2.4, nor any decision made by the Owner in good faith either to exercise or not to exercise such authority shall give rise to any duty or responsibility of the Owner to the Contractor, any Subcontractor, any of their agents or employees, or any other person performing any of the Work.

3.2.5 The Owner shall have the authority and discretion to call, schedule, and conduct job meetings to be attended by the Contractor, representatives of his Subcontractors, and the Design Consultant, to discuss such matters as procedures, progress, problems, and scheduling.

3.2.5.1 The Contractor is requested and required to attend weekly job site progress conferences as called by the Design Consultant. The Contractor shall be represented at these job progress conferences by project personnel authorized by the Contractor to make schedule and financial decision and by project personnel representatives. These meetings shall be open to Subcontractors, Material Suppliers, and any others who can contribute shall be encouraged by the Contractor to attend. It shall be the principal purpose of these meetings, or conferences, to affect coordination,

cooperation and assistance in every practical way toward the end of maintaining progress of the Project on schedule and to complete the Project within the specified Contract Time. The Contractor shall be prepared to assist progress of the Work as required in his particular contract and to recommend remedial measures for the correction of progress as may be appropriate. The Design Consultant shall be the coordinator of the conferences and shall preside as chairman.

3.2.5.2 If the Project is awarded as a single prime construction contract, the Design Consultant shall determine which, if any, Subcontractors and/or Material Suppliers shall be required to attend weekly job site progress conferences. The Contractor shall comply with this request and the meeting shall be conducted as described in Subparagraph 3.2.5.1.

3.2.6 The Owner will establish procedures to be followed for processing all Shop Drawings, catalogues, and other project reports, and other documentation, test reports, and maintenance manuals.

3.2.7 The Owner and Design Consultant will review all requests for changes and shall implement the processing of Change Orders, including applications for extension of the Contract Time.

3.2.8 The Owner, will not be responsible for the failure of the Contractor to plan, schedule, and execute the Work in accordance with the approved schedule or the failure of the Contractor to meet scheduled Completion Dates or the failure of the Contractor to schedule and coordinate the Work of his own trades and Subcontractors or to coordinate and cooperate with any Separate Contractors.

3.2.9 The Owner, in consultation with the Design Consultant, will review and process all Applications for Payment by the Contractor, including the final Application for Payment.

3.2.10 The Owner and Design Consultant shall not be responsible or liable to Contractor for the acts, errors or omissions of the Contractor, Subcontractors, or their agents or employees, or any other persons performing any of the Work or working on the Project.

3.2.11 The Owner shall furnish surveys describing the physical characteristics and legal limitations for the site of the Project, which are in its possession and are relevant to the Work.

3.2.12 The Owner shall secure and pay for necessary easements, required for permanent structures or for permanent changes in existing facilities.

3.2.13 The Owner shall furnish information or services under the Owner’s control with reasonable promptness to avoid unreasonable delay in the orderly progress of the Work.

3.2.14 Unless otherwise provided in the Contract Documents, the Contractor will be furnished, free of charge, copies of Drawings and Specifications in accordance with the Supplemental Conditions.

3.2.15 The Owner will make reasonable efforts to make available for the Contractor's reasonable review, at the Owner's offices or together with the Contract Documents, certain boring logs, geotechnical, soils and other reports, surveys and analyses pertaining to the Project site of which the Owner is aware, has in its possession and are relevant to the Work. Any boring logs that are provided to the Contractor are only intended to reflect conditions at the locations of the borings and do not necessarily reflect site conditions at other locations. Any reports, surveys and analyses provided by Owner are for the Contractor's information only, and their accuracy and completeness are not guaranteed or warranted by the Owner or the Design Consultant, and such reports are not adopted by reference into, nor are they part of the Contract Documents.

Notwithstanding any factual statement, conclusion, or any language or recommendations contained in such reports, the Contractor shall not rely upon the accuracy or completeness of any reports, surveys and analyses.

3.2.16 The foregoing rights are in addition to other rights of the Owner enumerated herein and those provided by law.

3.3 OWNER'S RIGHT TO STOP OR TO SUSPEND THE WORK

3.3.1 If the Contractor fails to correct defective Work as required by Section 13.2 or fails to carry out the Work or supply labor and materials in accordance with the Contract Documents, the Owner by a written Notice may order the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, this right of the Owner to stop the Work shall not give rise to any duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity.

3.3.2 The Owner may order the Contractor in writing to suspend, delay, or interrupt all or any part of the Work for such period of time as he may determine to be appropriate for the convenience of the Owner.

3.3.3 If the performance of all or any part of the Work (including the work of the Contractor and its Subcontractors) is, for an unreasonable period of time, suspended, delayed, or interrupted by an act of the Owner or the Design Consultant , or by failure of any one of them to act within the time specified in this Contract (or if no time is specified, within a reasonable time), an adjustment shall be made for an increase in the actual time required for performance of the Work by the Contractor, due solely to such unreasonable suspension, delay, or interruption and the Contract modified in writing accordingly. However, no Claim shall be made under this Paragraph for any suspension, delay, or interruption pursuant to Paragraph 3.4.1, or for which Claim is provided or excluded under any other provision of this Contract. No Claim under this Paragraph shall be allowed on behalf of the Contractor or its Subcontractors, unless within twenty (20) days after the act or failure to act involved, and for continuing or ongoing acts or failures to act within twenty (20) days of the first day of the act or failure to act, the Contractor submits to the Owner a written statement setting forth, as fully as then practicable, the extent of such Claim, and unless the Claim is asserted in writing within thirty (30) days after the termination of such suspension, delay, or interruption. For continuing or ongoing acts or failures to act, the Contractor shall update its written statement every twenty (20) days until the suspension, delay or interruption is terminated. The Contractor shall waive any and all Claims under this Paragraph 3.3.3 which are not filed in strict conformance with Paragraph 3.3.3. The Contractor shall indemnify, defend and hold the Owner harmless from any Claim by a Subcontractor that is waived because it is not filed in strict conformance with this Paragraph 3.3.3 or any other provision of the Contact regarding Claims.

3.3.4 In the event of a suspension of the Work or delay or interruption of the Work per Paragraph 3.3.3, the Contractor will and will cause his Subcontractors to protect carefully his, and their, materials and Work against damage, loss or injury from the weather and maintain completed and uncompleted portions of the Work as required by the Contract Documents. If, in the opinion of the Owner, any Work or material shall have been damaged or injured by reason of failure on the part of the Contractor or any of his Subcontractors to so protect same, such Work and materials shall be removed and replaced at the expense of the Contractor.

3.3.5 No Claim by the Contractor under Paragraph 3.3.3 shall be allowed if asserted after final payment under this Contract or if it is not asserted in strict conformance with Paragraph 3.3.3.

3.4 OWNER'S RIGHT TO CARRY OUT THE WORK

3.4.1 If the Contractor defaults or otherwise neglects to carry out the Work in accordance with the Contract Documents and fails within ten (10) days after the date written Notice is given by the Owner, with a copy of such Notice sent to the Contractor's Surety, to commence and continue remedy of such default or neglect with diligence and promptness, the Owner may, without prejudice to any other remedy he may have, make good such deficiencies and may further elect to complete all Work thereafter through such means as the Owner may select, including the use of a new contractor pursuant to Paragraph 3.4.2. In such case, the Owner shall provide Notice to the Contractor's Surety and an appropriate Change Order shall be issued deducting from the payments then or thereafter due the Contractor the cost of correcting such deficiencies, including compensation for the Design Consultant's additional services made necessary by such default, neglect or failure and any other damages suffered by Owner as a result of Contractor's breach, including but not limited to Owner's reasonable attorney's fees and litigation costs and expenses. If the payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor or its Surety shall pay the difference to the Owner. Notwithstanding the Owner's right to carry out a portion of the Work, warranty, maintenance and protection of the Work remains the Contractor's and Surety's responsibility. Further, the provisions of this Paragraph do not affect the Owner's right to require the correction of defective or non- conforming Work in accordance with Section 13.2.

3.4.2 Whenever the Contractor shall be, and declared by the Owner to be in default under the Contract, the Owner having substantially performed Owner's obligations thereunder, the Surety shall promptly remedy the default, or shall be liable to Owner for damages pursuant to the Performance Bond and as provided by law. Any action by Surety or by Owner against the Surety shall not relieve Contractor of its duties, responsibilities and liabilities to Owner pursuant to the Contract or as allowed by law.

ARTICLE 4

CONTRACTOR

1.1 DEFINITION

1.1.1 The Contractor is the person or organization identified as such in the Owner-Contractor Agreement and may be referred to throughout the Contract Documents as if singular in number and masculine in gender. The term Contractor means the Contractor or his authorized representative, who shall have authority to bind the Contractor in all matters pertinent to the Contract.

1.1.2 The Contract is not one of agency by the Contractor for Owner but one in which Contractor is engaged independently in the business of providing the services and performing the Work herein described as an independent contractor.

1.2 REVIEW OF CONTRACT DOCUMENTS

1.2.1 The Contractor represents that prior to executing this Contract, the Contractor carefully reviewed and studied the Contract Documents and notified the Owner and Design Consultant of any errors, inconsistencies or omissions of which the Contractor is aware. The Contractor agrees to continuously and carefully study and compare the Contract Documents after the execution of this Contract and shall at once report to the Owner and Design Consultant any

error, inconsistency or omission he may discover, including, but not limited to, any requirement which may be contrary to any law, ordinance, rule, regulation, building code, or order of any public authority bearing on the Work. If the Contractor has reported in writing an error, inconsistency or omission, has promptly stopped the affected Work until otherwise instructed, and has otherwise followed the instructions of the Owner, the Contractor shall not be liable to the Owner or the Design Consultant for any damage resulting from any such errors, inconsistencies or omissions in the Contract Documents. The Contractor shall perform no portion of the Work at any time without it being specified in Contract Documents and, where required, approved Shop Drawings, Product Data or Samples for such portion of the Work.

1.2.2 The Contractor and his Subcontractors shall keep at the site of the Work at least one copy of the Drawings and Specifications and shall at all times give the Owner, the Design Consultant, inspectors, as well as other representatives of the Owner access thereto.

1.3 SUPERVISION AND CONSTRUCTION PROCEDURES

1.3.1 The Contractor shall supervise and direct the Work, using his best skill and attention. He shall be solely responsible for and have control over all construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract.

1.3.1.1 It shall be the Contractor's responsibility to schedule the Work; to maintain a progress schedule for the Project; and to notify the Design Consultant and the Owner of any changes in the progress schedule. He shall be responsible for providing adequate notice to all Subcontractors to insure efficient continuity of all phases of the Project. The Contractor is responsible for keeping the Owner and Design Consultant fully informed as to the work progress, including immediate notification of any work progress changes.

1.3.2 The Contractor shall be responsible to the Owner for the acts and omissions of his employees, Subcontractors and Sub-subcontractors, Suppliers, their agents and employees, and other persons performing any of the Work and for their compliance with each and every requirement of the Contract Documents, in the same manner as if they were directly contracted by the Contractor.

1.3.3 The Contractor shall not be relieved from his obligations to perform the Work in accordance with the Contract Documents either by the acts, failures to act or duties of the Owner or the Design Consultant in their administration of the Contract, or by inspections, tests or approvals (or the lack thereof) required or performed under Section 7.6 by persons other than the Contractor.

1.3.4 Before starting a section of the Work, the Contractor shall carefully examine all preparatory work that has been executed to receive his work to see that it has been completed in accordance with the Contract Documents. He shall check carefully, by whatever means are required, to ensure that his work and adjacent, related work will finish to proper and required standards for quality, contours, planes, and levels.

1.3.5 The Contractor understands and agrees that the Owner and Design Consultant will not be responsible for and will not have control or charge of construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work, and they will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents. The Owner and the Design Consultant will not be responsible for or have control or charge over the acts or omissions of the Contractor, Subcontractors, or any of their agents or employees, or any other persons performing any of the Work.

1.3.6 The Contractor shall not use or provide Subcontractor equipment, materials, methods or persons to which Owner and Design Consultant have a reasonable objection and shall remove no portion of the Work or stored materials from the site of the Work, except for defective Work the Contractor may be required to replace or repair as set forth herein.

1.3.7 The Contractor shall verify all grades, lines, levels and dimensions as indicated and shown on the Drawings and in the Specifications prior to beginning any portion of the Work and shall immediately report in writing any errors or inconsistencies to the Design Consultant before commencing that portion of the Work.

4.4. CONTRACTOR'S REPRESENTATIONS

4.4.1 By entering into this Contract with the Owner, the Contractor represents and warrants the following, together with all other representations and warranties in the Contract Documents:

1. That he is experienced in and competent to perform the type of work required and to furnish the Subcontractors, materials, supplies, equipment and services to be performed or furnished by him;

2. That he is financially solvent, able to pay his debts as they mature, and possessed of sufficient working capital to initiate and complete the Work required under the Contract;

3. That he is familiar with all Federal, State, County, municipal and department laws, ordinances, permits, regulations, building codes and resolutions which may in any way affect the Work or those employed therein, including but not limited to any special laws or regulations relating to the Work or any part thereof;

4. That such temporary and permanent Work required by the Contract Documents will be satisfactorily constructed and fit for use for its intended purpose and that such construction will not injure any person, or damage any property;

5. That he has carefully examined the Contract Documents and the site of the Work and that from his own investigations, he has satisfied himself and made himself familiar with: (1) the nature and location of the Work; (2) the character, quality and quantity of surface and subsurface materials likely to be encountered, including, but not limited to, all structures and obstructions on or at the Project site, both natural and man-made; (3) the character of equipment and other facilities needed for the performance of the Work; (4) the general and local conditions including without limitation its climatic conditions, the availability and cost of labor and the availability and cost of materials, tools and equipment; (5) the quality and quantity of all materials, supplies, tools, equipment, labor and professional services necessary to complete the Work in the manner required by the Contract Documents; and (6) all other matters or things which could in any manner affect the performance of the Work;

6. That he will fully comply with all requirements of the Contract Documents;

7. That he will perform the Work consistent with good workmanship, sound business practice, and in the most expeditious and economical manner consistent with the best interests of the Owner;

8. That he will furnish efficient business administration and experienced project management and supervision, and an adequate supply of workers, equipment, tools and materials at all times;

9. That he has carefully reviewed the Work required and that the Work can be planned and executed in a normal and orderly sequence of Work and reasonably scheduled so as to ensure completion of the Work in accordance with the Contract Documents, allowing for normal and reasonably foreseeable weather, labor and other delays, interruptions and disruptions of the Work;

10. That he will complete the Work within the Contract Time and all portions thereof within any required Completion Dates;

11. That his Contract Sum is based upon the labor, materials, systems and equipment required by the Contract Documents, without exception; and

12. That he will make a good faith effort to utilize minority and Historically Underutilized Businesses (HUBs) as defined and required in N.C. Gen. Stat. 143-128.2 to -128.4, and as described in the Contract Documents.

4.5 LABOR AND MATERIALS

4.5.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all labor, materials, equipment, supplies, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary or proper for or incidental to the execution and completion of the Work required by and in accordance with the Contract Documents and any applicable code or statute, whether specifically required by the Contract Documents or whether their provision may reasonably be inferred as necessary to produce the intended results, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work. Final payment will not be made until the Work is so completed and Contractor has otherwise complied with the Contract Documents in full.

4.5.2 The Contractor shall at all times enforce strict discipline and good order among his employees and Subcontractors performing any of the Work and shall not employ or contract with on the Work any unfit person or entity or anyone not skilled in the task assigned to him. The Owner may, by Notice, require the Contractor to remove from the Work any employee or employee of a Subcontractor performing any of the Work, that the Owner deems incompetent, careless or otherwise objectionable.

4.5.3 The Contractor shall be responsible for ensuring that the Work is completed in a skilful and workmanlike manner.

4.5.4 All equipment, apparatus and/or devices of any kind to be incorporated into the Work that are shown or indicated on the Drawings or called for in the Specifications or required for the completion of the Work shall be entirely satisfactory to the Owner and the Design Consultant as regards operations, capacity and/or performance. No approval, either written or verbal, of any drawings, descriptive data or samples of such equipment, apparatus and/or device shall relieve the Contractor of his responsibility to turn over the same in good working order for its intended purpose at the completion of the Work in complete accordance with the Contract Documents. Any equipment, apparatus and/or device not fulfilling these requirements shall be removed and replaced by proper and acceptable equipment, etc. or put in good working order satisfactory to the Owner and Design Consultant without additional cost to the Owner.

4.6 WARRANTY

4.6.1 The Contractor warrants to the Owner and the Design Consultant that all materials and equipment furnished under this Contract will be new unless otherwise specified, and that all workmanship will be in accordance with generally accepted industry standards, free from faults and defects and in conformance with the Contract Documents and all other warranties and guaranties specified therein. Where no standard is specified for such workmanship or materials, they shall be the best of their respective kinds. All Work not conforming to these requirements, including substitutions not properly approved and authorized, may be considered defective. If required by the Owner or the Design Consultant, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment. This warranty is not limited by the provisions of Article 13.

4.6.2 The Contractor will be required to complete the Work specified and to provide all items needed for construction of the Project, complete and in good order.

4.6.3 The warranties set forth in this Section 4.6 and elsewhere in the Contract Documents shall survive Final Completion of the Work under Section 9.9.

4.6.4 The Contractor guarantees and warrants to the Owner all Work as follows:

1. That all materials and equipment furnished under this Contract will be new and the best of its respective kind unless otherwise specified;

2. That all Work will be in accordance with generally accepted industry standards and free of omissions and faulty, poor quality, imperfect and defective material or workmanship;

3. That the Work shall be entirely watertight and leak proof in accordance with all applicable industry customs and practices, and shall be free of shrinkage and settlement;

4. That the Work, including but not limited to, mechanical and electrical machines, devices and equipment, shall be fit and fully usable for its intended and specified purpose and shall operate satisfactorily with ordinary care;

5. That consistent with requirements of the Contract Documents, the Work shall be installed and oriented in such a manner as to facilitate unrestricted access for the operation and maintenance of fixed equipment;

6. That the Work will be free of abnormal or unusual deterioration which occurs because of poor quality materials, workmanship or unsuitable storage; and

7. That the products or materials incorporated in the Work will not contain asbestos.

4.6.5 All Work not conforming to guarantees and warranties specified in the Contract Documents, including substitutions not properly approved and authorized, may be considered defective. If required by the Design Consultant or Owner, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

4.6.5.1 The Contractor will submit a written affidavit certifying that none of the materials incorporated in the Project contain asbestos.

4.6.6 If, within one (1) year after the date of Substantial Completion of the Work or designated portion thereof as defined in Paragraph 8.1.3 or within such longer period of time as may be prescribed by law or by the terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be defective, not in accordance with the Contract Documents, or not in accordance with the guarantees and warranties specified in the Contract Documents, the Contractor shall correct it within five (5) working days or such other period as mutually agreed, after receipt of Notice from the Owner to do so. The Owner shall give such Notice with reasonable promptness after discovery of the condition. For items that remain incomplete or uncorrected on the date of Substantial Completion, the one (1) year warranty shall begin on the date of Final Completion of the Work or upon correction of the defective Work.

4.6.7 If at any time deficiencies in the Work are discovered which are found to have resulted from fraud or misrepresentation, or an intent or attempt to or conspiracy to defraud the Owner by the Contractor, any Subcontractor or Supplier, the Contractor will be liable for replacement or correction of such Work and any damages which Owner has incurred related thereto, regardless of the time limit of any guarantee or warranty.

4.6.8 Any materials or other portions of the Work, installed, furnished or stored on site which are not of the character or quality required by the Specifications, or are otherwise not acceptable to the Design Consultant or the Owner, shall be immediately removed and replaced by the Contractor to the satisfaction of the Design Consultant and Owner, when notified to do so by the Design Consultant or Owner.

4.6.9 If the Contractor fails to correct defective or non-conforming Work as required by Paragraph 4.6.6, or if the Contractor fails to remove defective or non-conforming Work from the site, as required by Paragraph 4.6.8, the Owner may elect to either correct such Work in accordance with Section 3.4 or remove and store materials and equipment at the expense of the Contractor. If the Contractor does not pay the cost of such removal and storage within ten (10) days thereafter, the Owner may upon ten (10) additional days written Notice sell such Work at auction or at private sale and shall account for the net proceeds thereof, after deducting all the costs that should have been borne by the Contractor, including compensation for the Design Consultant's additional services and Owner’s reasonable attorney’s fees made necessary thereby. If such proceeds of sale do not cover all costs, which the Contractor should have borne, the difference shall be charged to the Contractor and an appropriate Change Order shall be issued. If the payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor shall pay the difference to the Owner.

4.6.10 The Contractor shall bear the cost of making good all of the Work of the Owner, Separate Contractors or others, destroyed or damaged by such correction or removal required under this Article 4, Article 13 or elsewhere in the Contract Documents.

4.7 TAXES

4.7.1 The Contractor shall pay all sales, consumer, use and other similar taxes for the Work or portions thereof provided by the Contractor which are legally enacted at the time the Owner received bids for the construction of the Project, whether or not yet effective.

4.7.2 Sales and Use Tax. Contractor shall be responsible for complying with any applicable sales and use tax obligations imposed by Chapter 105, Article 5 of the North Carolina General Statutes. Where Contractor has been contracted with to oversee “new construction” or “reconstruction”

as defined in G.S. 105-164.4H, Contractor shall be responsible for issuing and maintaining an Affidavit of Capital Improvement.

The Committee Substitute for Senate Bill No. 78, passed by the l961 Legislature, requires that contractors pay North Carolina Sales Tax on materials and equipment purchased for construction of municipal work, and further provides that those taxes on certain items are refundable to municipalities under submission of proper evidence by the Owner to the North Carolina Department of Revenue. Reference is made to "Sales and Use Tax Regulation 42".

The Contractor shall submit to the Owner information which will make it possible to show the sales tax as a separate item on each Application for Payment. The tax may be shown at the bottom of the Application for Payment in the following manner:

"Total of refundable N.C. Sales Tax paid on the above Application for Payment amounted to $_____."

To substantiate the payment of the sales tax indicated, the CONTRACTOR MUST IN ADDITION, submit a SWORN NOTARIZED statement itemizing the tax, showing each amount and to whom paid, and certifying that the articles purchased were used in the work performed for the Owner. Receipts for these amounts must be included with the Application for Payment. Such receipts shall include all taxes paid by the Contractor and any of its subcontractors.

4.8 PERMITS, FEES AND NOTICES

4.8.1 The Contractor shall secure and pay for the building permit and for all other permits and governmental fees, and inspections necessary for the proper execution and completion of the Work. Costs for service, final service connections and meter fees by public utilities will be paid by the Owner. The Contractor shall be responsible for all fees, permits and other costs associated with temporary utilities, including but not limited to installation, use, disconnection, removal and/or relocation.

4.8.3 The Contractor will pay for his own license, inspection and re-inspection fees for the proper execution and completion of the Work.

4.8.4 The Contractor shall give all notices and comply with all laws, ordinances, rules, regulations and lawful orders of any public authority bearing on the performance of the Work, including but not limited to all applicable building codes. If Contractor believes that any part of the Drawings or Specifications are inconsistent with applicable laws, rules, regulations, lawful orders of public authorities or building codes, Contractor shall Notify the Owner and Design Consultant of such inconsistencies immediately.

4.9 ALLOWANCES

4.9.1 The Contractor shall include in the Contract Sum all Allowances stated in the Contract Documents. Items covered by these Allowances shall be supplied for such amount and by such persons as the Owner may direct, but the Contractor will not be required to employ persons against whom he makes a reasonable objection.

4.9.2 Unless otherwise provided in the Contract Documents:

1. Allowances for Work: These allowances shall cover the cost to the Contractor for the materials and equipment required by the allowance delivered at the site, all applicable taxes, unloading, uncrating and storage, protection from elements, labor, installation and

finishing and other expenses and time required to complete the installation, and a fixed percentage for overhead and profit as defined in Article 12.

2. Allowances for Products/Materials: Allowance includes the cost of the product, delivery to the site and applicable taxes. The Contractor's costs for unloading and handling on the site, labor, installation, time, overhead, profit and other expenses contemplated for the material allowance shall be included in the Contract Sum and not in the allowance;

3. Whenever the cost is more than or less than the Allowance, the Contract Sum shall be adjusted accordingly by Change Order, the amount of which will recognize changes, if any, in handling costs on the site, labor, installation costs, overhead, profit and other expense.

4.10 SUPERINTENDENT

4.10.1 The Contractor shall employ, and have approved by the Owner, a competent superintendent and necessary assistants who shall be in attendance at the Project site during the progress of the Work. The superintendent shall represent the Contractor and all communications given to the superintendent shall be as binding as if given to the Contractor. If the Contractor employs more than a single individual in this role, the Owner shall be provided an organizational chart and personnel listing for the staff performing the functions of a superintendent. In such event, all references to the superintendent elsewhere in the Contract Documents shall mean the staff performing the functions of a superintendent.

4.10.2 The superintendent shall be in attendance at the Project site at all times when and where work is in progress, unless the job is closed down due to conditions beyond the control of the Contractor or until termination of the Contract in accordance with the Contract Documents. It is understood that such superintendent shall be acceptable to the Owner and shall be the one who will be continued in that capacity for the duration of the Project, unless he ceases to be on the Contractor's payroll or the Owner otherwise agrees. The superintendent shall not be employed on any other project for or by Contractor or any other entity during the course of the Work.

4.11 PROGRESS SCHEDULE

4.11.1 The Contractor shall prepare and submit to the Design Consultant for its review and approval an estimated progress schedule for the Work pursuant to Division 01, Section 01 32 17 of the General Requirements entitled “Construction Scheduling”.

4.12 RESPONSIBILITY FOR COMPLETION

4.12.1 The Contractor shall furnish such manpower, materials, facilities and equipment and shall work within the normal scheduled working hours to ensure the performance of the Work within the Completion Dates specified in the Owner-Contractor Agreement. If for any reason the Contractor must work outside of the normal scheduled working hours, the contractor and owner will determine a suitable procedure to allow the contractor to access the facility.

4.12.2 If it becomes apparent to the Design Consultant or Owner that the Work will not be completed within required Completion Dates, the Contractor agrees to undertake some or all of the following actions, at no additional cost to the Owner, in order to ensure, in the opinion of the Design Consultant and Owner, that the Contractor will comply with all Completion Date requirements:

1. Increase manpower, materials, crafts, equipment and facilities;

2. Increase the number of working hours per shift, shifts per working day, working days per week, or any combination of the foregoing, including but not limited to night shifts, overtime operations and Sundays and holidays;

3. Reschedule activities to achieve maximum practical concurrence of accomplishment of activities;

4. Require that his superintendent be at the Project site not less than ten (10) hours per day, six (6) days per week; and

5. Reimburse the Owner in accordance with Paragraph 4.12.1 above for all work performed outside of the normal scheduled work hours.

4.12.3 In undertaking the actions required under Paragraph 4.12.1, Contractor shall prepare and adhere to a recovery schedule if the Project is behind schedule by four (4) or more days.

4.12.4 If the actions taken by the Contractor are not satisfactory, the Design Consultant or Owner may direct the Contractor to take any and all actions necessary to ensure completion within the required Completion Dates, without additional cost to the Owner. In such event, the Contractor shall continue to assume responsibility for his performance and for completion within the required dates.

4.12.5 If, in the opinion of the Design Consultant or Owner, the actions taken by the Contractor pursuant to this Article or the progress or sequence of the Work are not accurately reflected on the construction schedule, the Contractor shall revise such schedule to accurately reflect the actual progress and sequence of the Work.

4.12.6 Failure of the Contractor to substantially comply with the requirements of this Article, may be considered grounds for a determination by the Owner, pursuant to Article 14, that the Contractor is failing to prosecute the Work with such diligence as will ensure its completion within the time specified.

4.12.7 The Owner may, at its sole discretion and for any reason, other than due to the fault of Contractor require the Contractor to accelerate the Work by providing overtime, Saturday, Sunday and/or holiday work and/or by having all or any Subcontractors designated by the Owner provide overtime, Saturday, Sunday, and/or holiday work. In the event that the Owner requires such acceleration a Change Order shall be issued in accordance with Article 12.

4.12.8 This Section 4.12 does not eliminate the Contractor's responsibility to comply with the local noise ordinances, all highway permit requirements and all other applicable laws, regulations, rules, ordinances, resolutions, and permit requirements.

4.12.9 The Contractor will provide the Owner assistance in the original operation of any equipment or system installed as Park of the Work, including initial start-up, testing, adjustment and balancing.

4.13 DOCUMENTS AND SAMPLES AT THE SITE

4.13.1 The Contractor shall maintain at the site for the Owner one record copy of all Drawings, Specifications, Addenda, Change Orders and other Modifications, in good order and marked currently to record all changes made during construction, and approved Shop Drawings, Product Data and Samples. These shall be delivered to the Design Consultant upon completion of the Work.

4.14 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

4.14.1 Shop Drawings are drawings, diagrams, schedules and other data specially prepared for the Work by the Contractor or any Subcontractor, Manufacturer, Supplier or distributor to illustrate some portion of the Work.

4.14.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information furnished by the Contractor to illustrate a material, product or system for some portion of the Work.

4.14.3 Samples are physical examples, which illustrate materials, equipment or workmanship and establish standards by which the Work will be judged.

4.14.4 Manuals are manufacturer's installation, start-up, operating, and maintenance and repair instructions together with parts lists, pictures, sketches and diagrams, which set forth the manufacturer's requirements for the benefit of the Contractor and the Owner.

4.14.5 The Contractor shall prepare or have prepared at its expense and shall review, indicate approval thereupon, and submit, with reasonable promptness and in such sequence as to cause no delay in the Work or in the other work of the Owner or any Separate Contractor, all Shop Drawings, Product Data, Manuals and Samples required by the Contract Documents.

4.14.5.1 Unless otherwise directed in writing, the Contractor shall submit no less than three (3) copies of each Shop Drawing, Product Data, or Manuals to the Design Consultant. Routing of said submittals will be from the Contractor to the Design Consultant with a copy of the transmittal to the Owner. The Design Consultant will return one (1) copy of the reviewed submittal to the Contractor.

4.14.5.2 Where the Contract calls for the submittal of manufacturer's data to the Design Consultant for information only, such submittals shall be made before the commencement of any portion of the Work requiring such submission. Work performed without benefit of approved Shop Drawings for any portion of the Work is subject to removal and replacement at no cost to the Owner.

4.14.5.3 For standard manufactured items not requiring special Shop Drawings for manufacture, Contractor shall submit no less than three (3) copies of Manufacturer's catalogue sheets showing illustrated cuts of item to be furnished, scale details, sizes, dimensions, performance characteristics, capacities, wiring diagrams and controls, and all other pertinent information. One (1) copy of reviewed submissions will be returned to the Contractor.

4.14.5.4 Unless otherwise directed in writing, all other Shop Drawings, Contractor shall submit no less than three (3) legible copies of each drawing. Each drawing shall have a clear space for stamps. When phrase "by others" appears on Shop Drawings, the Contractor shall indicate on the Shop Drawing who is to furnish material or operations so marked before submittal. When the Shop

Drawings are checked "revise and resubmit", the Contractor shall make corrections and submit new copies for review. The Shop Drawings shall contain the Contractor's "approval" and corrections.

4.14.5.5 For use of all trades, the Contractor shall provide such number of Shop Drawings as is required for field distribution.

4.14.5.6 The Design Consultant will review submittals and make marks to indicate corrections or revisions required and will stamp each submittal with an action stamp and will mark the stamp with the action required by the Contractor.

4.14.5.7 Contractor shall submit names of proposed Manufacturers, Material Suppliers, dealers, who are to furnish materials, fixtures, appliances or other fittings for approval as early as possible, to afford proper investigation and checking.

4.14.5.8 Transactions with manufacturers, or Subcontractors, shall be through Contractor.

4.14.5.9 Unless otherwise specified, Contractor shall submit samples in duplicate of adequate size showing quality, type, color range, finish, and texture as indicated in the Specifications.

4.14.5.10 Where Specifications require manufacturer's printed installation instructions, Contractor shall submit duplicate copies of such instructions for approval.

4.14.5.11 When several materials are specified by name for one use, Contractor shall select for use any of those so specified.

4.14.5.12 Whenever item or class of material is specified exclusively by trade name, manufacturer's name, or by catalogue reference, Contractor shall use only such item, unless written approval for substitution is secured, as outlined in the Specifications and in Section 4.15 of the General Conditions.

4.14.5.13 Contractor shall not order materials until receipt of written approval. Contractor shall furnish materials equal in every respect to approved samples.

4.14.6 By approving and submitting Shop Drawings, Product Data, Manuals and Samples, the Contractor represents that he has determined and verified all materials, field measurements, and field construction criteria related thereto, and that he has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents. The Contractor shall adhere to any supplementary processing and scheduling instructions pertaining to Shop Drawings, which may be issued by the Design Consultant.

4.14.6.1 Parts and details not fully indicated on the Drawings shall be detailed by the Contractor in accordance with standard engineering practice. Dimensions on the Drawings, as well as detailed drawings themselves are subject in every case to measurements of existing, adjacent, incorporated and completed, which shall be taken by the Contractor before undertaking any Work dependent on such data.

4.14.7 The Contractor shall not be relieved of responsibility for any deviation from the requirements of the Contract Documents by the Design Consultant's review of Shop Drawings, Product Data, Samples or Manuals under Paragraph 2.2.14 unless the Contractor has specifically informed the Design Consultant in writing of such deviation at the time of submission and the Design

Consultant has given written approval to the specific deviation. The Contractor shall not be relieved from responsibility to Owner for errors or omissions in the Shop Drawings, Product Data, Samples, or Manuals by virtue of the Design Consultant's review or approval thereof.

4.14.8 The Contractor shall make corrections required by the Design Consultant and shall resubmit the required number of corrected copies of Shop Drawings or new Product Data or Samples. The Contractor shall direct specific attention, in writing on resubmitted Shop Drawings, Product Data or Samples or Manuals, to revisions other than those requested by the Design Consultant on previous submittals. Re-submittals necessitated by required corrections due to Contractor's errors or omissions shall not be cause for extension of Contract Time or an increase in the Contract Sum.

4.14.8.1 No portion of the Work requiring submission of Shop Drawings, Product Data, Samples or Manuals shall be commenced until the submittal has been approved by the Design Consultant as provided in Article 2. All such portions of the Work shall be in accordance with approved submittals.

4.14.9 Shop Drawings, Product Data and Samples shall be dated and shall bear the name of the Project; a description or the names or equipment, materials and items; and complete identification of locations at which materials or equipment are to be installed. Shop Drawings shall be stamped and signed stating that the Contractor has determined and verified all materials, field measurements, and field construction criteria related thereto and that he has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

4.14.10 Submittals of Shop Drawings, Product Data, Samples or Manuals shall be accompanied by a transmittal letter, in duplicate, containing the name of the Project, the Contractor's name, the number of Shop Drawings, Product Data, Samples, or Manuals, identification of Specification section and other pertinent data.

4.15 EQUAL PRODUCTS AND SUBSTITUTIONS

4.15.1 All materials, supplies and articles furnished under the Contract shall, whenever specified and otherwise practicable, be the standard products of recognized, reputable manufacturers. Unless otherwise specifically provided in the Contract Documents, the naming of a certain brand, make, manufacturer or article, device, product, material, fixture or type of construction shall convey the general style, type, character and standard of quality of the article desired and shall not be construed as limiting competition. The Contractor, in such cases, may with Owner’s written approval, use any brand, make, manufacturer, article, device, product, material, fixture, form or type of construction which in the judgment of the Design Consultant is equal to that specified. An item may be considered equal to the item so named or described if, in the opinion of the Owner and Design Consultant (1) it is at least equal in quality, durability, appearance, strength, and design; (2) it will perform at least equally the specific function imposed by the general design for the Work being contracted for or the material being purchased; and (3) it conforms substantially, even with deviations, to the detailed requirements for the item in the Specifications. Approval by the Owner and Design Consultant will be granted based upon considerations of quality, workmanship, economy of operation, suitability for the purpose intended, warranty and acceptability for use on the Project.

4.15.2 To obtain such approval on makes or brands of material other than those specified in Contract Documents, and not previously approved at the time the Owner received bids for the construction of the Project, the Contractor's request for approval of any substitution shall

include:

1. Complete data substantiating compliance of the proposed substitution with the Contract Documents;

2. Product identification including manufacturers' name, address, and phone number;

3. Manufacturer's literature showing complete product description, performance and test data, and all reference standards;

4. Samples and colors in the case of articles or products;

5. Names and addresses of similar projects on which the product was used and date of installation;

6. For construction methods, include a detailed description for the proposed method and drawings illustrating same;

7. Itemized comparison of proposed substitution with product or method specified and any cost reduction, which shall benefit the Owner;

8. Accurate cost data on proposed substitution in comparison with product or method specified;

9. All directions, specifications, and recommendations by manufacturers for installation, handling, storing, adjustment, and operation; and

10. Item by item comparison of characteristics of substitution item with those items specified.

4.15.3 The Contractor shall also submit with his request for approval a sworn and notarized statement which shall include all of the following representations by the Contractor, namely that:

1. He has investigated the proposed product or method and determined that it is equal or better in all respects to that specified and that it fully complies with all requirements of the Contract Documents;

2. He will meet all contract obligations with regard to this substitution;

3. He will coordinate installation of accepted substitutions into the Work, making all such changes and any required schedule adjustments, at no additional cost to the Owner, as may be required for the Work to be complete in all respects;

4. He waives all Claims for additional costs and additional time related to substitutions, which consequently become apparent. He also agrees to hold the Owner harmless from Claims for extra costs and time incurred by other Subcontractors and suppliers, or additional services which may have to be performed by the Design Consultant, for changes for extra work that may, at some later date, be determined to be necessary in order for the Work to function in the manner intended in the Contract Documents;

5. He will provide the same warranty and guarantee, and perform any work required in accordance therewith, for the substitution that is applicable to the specified item for which the substitution is requested;

6. Material will be installed, handled, stored, adjusted, tested, and operated in accordance with the manufacturers' recommendation and as specified in the Contract Documents.

7. In all cases new materials will be used unless this provision is waived by Notice from the Owner or his Design Consultant, or unless otherwise specified in the Contract Documents;

8. All material and workmanship will be in every respect in accordance with that which, in the opinion of the Owner or Design Consultant, is in conformity with approved modern practice; and

9. He has provided accurate cost data on the proposed substitution in comparison with the product or method specified.

4.15.4 Subject to the provisions of any applicable laws, approval for substitutions or equal products shall be at the sole discretion of the Owner, shall be in writing to be effective, and the decision of the Owner shall be final. The Owner or Design Consultant may require tests of all materials proposed for substitution so submitted to establish quality standards, at the Contractor's expense. After approval of a substitution, if it is determined that the Contractor submitted defective information or data regarding the substitution upon which Owner's approval was based, and that unexpected or uncontemplated extensive redesign or rework of the Project will be required in order to accommodate the substitution, or that the substituted item will not perform or function as well as the specified item for which substitution was requested, the Contractor will be required to furnish the original specified item or obtain approval to use another substitution; the Contractor shall pay all costs, expenses or damages associated with or related to the unacceptability of such a substitution and the resultant utilization of another item and no time extension shall be granted for any delays associated with or related to such substitution.

4.15.5 If a substitution is approved, no further change in brand or make will be permitted unless satisfactory, written evidence is presented to and approved by the Owner that the manufacturer cannot make scheduled delivery of the approved substituted item. The Owner will not consider substitutions for approval if:

1. The proposed substitution is indicated or implied on the Contractor's Shop Drawing or product data submittal and has not been formally submitted for approval by the Contractor in accordance with the above-stated requirements, or

2. Acceptance of the proposed substitution will require substantial design revisions to the Contract Documents or is otherwise not acceptable to the Owner and Design Consultant.

4.15.6 Except as otherwise provided for by the provisions of any applicable laws, the Contractor shall not have any right of appeal from the decision of the Owner rejecting any materials submitted if the Contractor fails to obtain the approval for substitution under this Article.

4.16 USE OF SITE

4.16.1 The Contractor shall confine operations at the site to areas permitted by law, ordinances, permits, easements, right-of-way agreements and within the limits of construction as shown on the Contract Documents. The Contractor shall not unreasonably encumber the site, in the opinion of the Owner, with any materials, equipment or trailers nor shall he block the entrances or otherwise prevent reasonable access to the site, other working and parking areas, completed portions of the Work and/or properties, storage areas, areas of other facilities that are adjacent

to the worksite. If the Contractor fails or refuses to move said material, equipment or trailers within twenty four (24) hours of notification by the Owner, to so do, the Owner shall have the right, without further notice, to remove, at the Contractor's expense, any material, equipment and/or trailers which the Owner deems are in violation of this Paragraph.

4.17 CUTTING AND PATCHING OF WORK

4.17.1 The Contractor shall be responsible for all cutting, fitting or patching that may be required to complete the Work or to make its several parts fit together properly and in accordance with the Contract Documents.

4.17.2 The Contractor shall not damage or endanger any portion of the Work or the work of the Owner or any Separate Contractors by cutting, patching or otherwise altering any work, or by excavation. The Contractor shall not cut or otherwise alter the work of the Owner or any Separate Contractor except with the written consent of the Owner and of such Separate Contractor. The Contractor shall not unreasonably withhold from the Owner or any Separate Contractor his consent to cutting or otherwise altering the Work. The Owner shall not be required to accept work with a cut, splice, or patch when such cut, splice or patch is not generally accepted practice for the particular work involved or is otherwise unworkmanlike in the opinion of the Design Consultant or the Owner.

4.17.3 Existing structures and facilities including but not limited to building, utilities, topography, streets, curbs, walks, etc., that are damaged or removed due to required excavations or other construction work, shall be patched, repaired or replaced by the Contractor to satisfaction of the Design Consultant and the Owner of such structures and facilities and authorities having jurisdiction. In event the local jurisdictional authorities require that such repairing and patching be done with their own labor and materials, the Contractor shall abide by such regulations and pay for such work with no increase in the Contract Sum.

4.18 CLEANING UP

4.18.1 The Contractor at all times shall keep the premises free from accumulation of waste materials or rubbish caused by his operations. At the completion of the Work and before final payment is made, he shall remove all his waste materials and rubbish from and about the Project as well as all his tools, construction equipment, machinery and surplus materials.

4.18.2 If the Contractor fails to clean up during or at the completion of the Work, the Owner may do so as provided in Section 6.3 and the cost thereof shall be charged to the Contractor.

4.19 COMMUNICATIONS

4.19.1 All communications from the Contractor relating to the Contract Documents or the construction schedule will be directed to the Design Consultant and copied to the Owner. Similarly, all correspondence from the Owner or Design Consultant will be directed to the Contractor and copied to the Owner or Design Consultant.

4.20 ROYALTIES AND PATENTS

4.20.1 The Contractor shall pay all royalties and license fees. He shall defend all suits or claims for infringement of any patent rights arising out of the Work and shall save the Owner harmless from loss on account thereof.

4.21 INDEMNIFICATION

4.21.1 To the fullest extent permitted by law, the Contractor shall, at its sole cost and expense, indemnify, defend, and hold harmless the Owner and its agents, representatives, and employees from and against all claims, actions, judgments, costs, liabilities, penalties, damages, losses and expenses, including but not limited to attorneys' fees, arising out of and/or resulting from the performance of the Work, provided that any such claim, action, judgment, cost, liability, penalty, damage, loss or expense is caused by any negligent act, error or omission of the Contractor, any Subcontractor or anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be legally liable. The above obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnity which would otherwise exist as to any party or person described in this Section 4.21.1. The parties agree that this indemnification clause is an "evidence of indebtedness" for purpose of N.C. Gen. Stat. § 6-21.2. The parties also specifically acknowledge that the Owner is a public body and it is the intent of the parties that the Owner not incur any expenses when the Contractor is solely responsible for the claims.

4.21.2 In any and all claims against the Owner or the Design Consultant or any of their agents, representatives, or employees by any employee of the Contractor, any Subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, the indemnification obligation under this Section 4.21 shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for the Contractor or any Subcontractor under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts.

4.21.3 No provision of this Section 4.21 shall give rise to any duties on the part of the Design Consultant or the Owner, or any of their agents, representatives, or employees.

4.22 PERSONS AUTHORIZED TO SIGN DOCUMENTS

4.22.1 The Contractor, within five (5) days after the earlier of the date of a Notice to Proceed or the date of the Owner-Contractor Agreement, shall file with the Owner a list of all persons who are authorized to sign documents such as contracts, certificates, and affidavits on behalf of the Contractor and to fully bind the Contractor to all the conditions and provisions of such documents, except that in the case of a corporation he shall file with the Owner a certified copy of a resolution of the Board of Directors of the corporation in which are listed the names and titles of corporation personnel who are authorized to sign documents on behalf of the corporation and to fully bind the corporation to all the conditions and provisions of such documents.

4.23 CONDITIONS AFFECTING THE WORK

4.23.1 The Contractor shall be responsible for taking all steps necessary to ascertain the nature and location of the Work and the general and local conditions that can affect the Work or the cost thereof. Failure by the Contractor to fully acquaint himself with conditions which may affect the Work, including, but not limited to conditions relating to transportation, handling, storage of materials, availability of labor, water, roads, weather, topographic and subsurface conditions, Multi-Prime Contract conditions, applicable provisions of law, and the character and availability of equipment and facilities needed prior to and during the execution of the Work, shall not relieve the Contractor of his responsibilities under the Contract Documents and shall not constitute a basis for an adjustment in the Contract Sum or the Contract Time under any circumstances. The Owner assumes no responsibility for any understanding or representation

about conditions affecting the Work made by any of his officers, employees, representatives, or agents prior to the execution of the Contract, unless such understandings or representations are expressly stated in the Contract Documents.

4.23.2 If in the execution of the Work any valuable items or materials of any kind are discovered buried or hidden within the Work, such items or materials shall be the property of the Owner. The Contractor shall take reasonable precautions to prevent any persons from removing or damaging such items or materials and shall immediately upon discovery thereof and before removal, acquaint the Owner or the Design Consultant with such discovery and carry out, at the expense of the Owner, the Owner's or the Design Consultant's orders as to disposal of the same.

4.24 COMPLIANCE WITH BOARD POLICIES AND PROCEEDURES

The Contractor acknowledges that Board policies are available for review at the Owner's website and agrees to comply with the policies. The Contractor also agrees to comply with the following provisions:

4.24.1 The Contractor, its Subcontractors and employees shall not possess or carry, whether openly or concealed, any gun, rifle, pistol, or explosive on any property owned by the Owner. This includes firearms locked in containers, vehicles or firearm racks within vehicles. The Contractor, its Subcontractors and employees shall not cause, encourage or aid a minor, who is less than 18 years old to possess or carry, whether openly or concealed, any weapons on any property owned by the Owner.

4.24.2 The Contractor, its Subcontractors and employees, are prohibited from profane, lewd, obscene or offensive conduct or language, including engaging in sexual harassment.

4.24.3 The Contractor and its Subcontractors shall not manufacture, transmit, conspire to transmit, possess, use or be under the influence of any alcoholic or other intoxicating beverage, narcotic drug, hallucinogenic drug, amphetamine, barbiturate, marijuana or anabolic steroids, or possess, use, transmit or conspire to transmit drug paraphernalia on any property owned by the Owner.

4.24.4 The Contractor and its Subcontractors may not at any time use or display tobacco or nicotine-containing products, including but not limited to electronic cigarettes (e-cigarettes), on school premises, both indoor and outdoor. The prohibition of the display of tobacco or nicotine products shall not extend to a display that has a legitimate instructional or pedagogical purpose. For purposes of this Contract, "tobacco product" is defined to include cigarettes, cigars, blunts, bidis, pipes, chewing tobacco, snuff, and any other items containing or reasonably resembling tobacco, tobacco products, or any facsimile thereof. "Tobacco use" includes smoking, chewing, dipping, or any other use of tobacco products.

4.24.5 The Contractor, its Subcontractors and employees shall not solicit from or sell to students or staff within the Owner's facilities or campuses, and shall not give gifts of any value to school system employees.

4.24.6 Operators of all commercial vehicles on any property owned by the Owner shall be subject to post-accident, random, reasonable suspicion and follow-up testing for drugs and alcohol.

4.24.7 The Contractor, its Subcontractors and employees are prohibited from using access to the site pursuant to this Agreement as a means to date, court, or enter into a romantic or sexual relationship with any student enrolled in the Owner's schools. The Contractor agrees to indemnify the Owner for claims against the Owner resulting from relationships which have occurred or may occur between a student and an employee of the Contractor or Subcontractor.

4.24.8 Lunsford Act/Criminal Background Checks. The Contractor shall conduct at its own expense sexual offender registry checks on each of its owners, employees, agents, or Subcontractors ("contractual personnel") who will engage in any service on or delivery of goods to school system property or at a school-system sponsored event, except checks shall not be required for individuals who are solely delivering or picking up equipment, materials, or supplies at: (1) the administrative office or loading dock of a school; (2) non-school sites; (3) schools closed for renovation; or (4) school construction sites.. The checks shall include at a minimum checks of the State Sex Offender and Public Protection Registration Program, the State Sexually Violent Predator Registration Program, and the National Sex Offender Registry ("the Registries"). For the Contractor's convenience only, all of the required registry checks may be completed at no cost by accessing the United States Department of Justice Sex Offender Public Website at **http:// www.nsopw.gov/**. The Contractor shall provide certification that the registry checks were conducted on each of its contractual personnel providing services or delivering goods under this Agreement prior to the commencement of such services or the delivery of such goods. The Contractor shall conduct a current initial check of the registries (a check done more than 30 days prior to the date of this Agreement shall not satisfy this contractual obligation). In addition, Contractor agrees to conduct the registry checks and provide a supplemental certification before any additional contractual personnel are used to deliver goods or provide services pursuant to this Agreement. Contractor further agrees to conduct annual registry checks of all contractual personnel and provide annual certifications at each anniversary date of this Agreement. Contractor shall not assign any individual to deliver goods or provide services pursuant to this Agreement if said individual appears on any of the listed registries. Contractor agrees that it will maintain all records and documents necessary to demonstrate that it has conducted a thorough check of the registries as to each contractual personnel, and agrees to provide such records and documents to the school system upon request. Contractor specifically acknowledges that the school system retains the right to audit these records to ensure compliance with this Section at any time in the school system's sole discretion. Failure to comply with the terms of this provision shall be grounds for immediate termination of the Agreement. In addition, the Owner may conduct additional criminal records checks at the Owner's expense. If the school system exercises this right to conduct additional criminal records checks, Contractor agrees to provide within seven (7) days of request the full name, date of birth, state of residency for the past ten years, and any additional information requested by the school system for all contractual personnel who may deliver goods or perform services under this Agreement. Contractor further agrees that it has an ongoing obligation to provide the school system with the name of any new contractual personnel who may deliver goods or provide services under the Agreement. The Owner reserves the right to prohibit any contractual personnel of Contractor from delivering goods or providing services under this Agreement if the Owner determines, in its sole discretion, that such contractual personnel may pose a threat to the safety or well-being of students, school personnel or others.

4.24.9 Contractor shall not employ any individuals to provide services to the Owner who are not authorized by federal law to work in the United States. Contractor represents and warrants that it is aware of and in compliance with the Immigration Reform and Control Act and North Carolina law (Article 2 of Chapter 64 of the North Carolina General Statutes) requiring use of the E-Verify system for employers who employ twenty-five (25) or more employees and that

it is and will remain in compliance with these laws at all times while providing services pursuant to this Agreement. Contractor shall also ensure that any of its Subcontractors (of any tier) will remain in compliance with these laws at all times while providing subcontracted services in connection with this Agreement. Contractor is responsible for providing affordable health care coverage to all of its full-time employees providing services to the School System. The definitions of "affordable coverage" and "full-time employee" are governed by the Affordable Care Act and accompanying IRS and Treasury Department regulations.

4.24.10 The Contractor, its Subcontractors and employees shall not interact with any students. Nothing in Paragraph 4.24 shall be construed to prevent the Contractor, its Subcontractors and employees from taking necessary measures to protect students, staff or other employees.

4.24.11 The Contractor shall at all times enforce strict discipline and good order among its employees and shall not employ any unfit person or anyone not skilled in the task assigned to it. The Owner may require the Contractor to remove any employee the Owner deems incompetent, careless or otherwise objectionable.

4.24.12 All agents and workers of the Contractor and its Subcontractors shall wear identification badges provided by the Contractor at all times they are on the Owner's property. The identification badges shall at a minimum display the company name, telephone number, employee name and a picture of the employee.

4.24.13 The Contractor shall comply with the Owner's site or school building access procedures when working on any existing school campus.

4.24.14 Anti-Nepotism. The Contractor warrants that, to the best of its knowledge and in the exercise of due diligence, none of its corporate officers, directors, or trustees and none of its employees who will directly provide services under this Agreement are immediate family members of any member of the Owner's Board of Education or of any principal or central office staff administrator employed by the Owner. For purposes of this provision, "immediate family" means spouse, parent, child, brother, sister, grandparent, or grandchild, and includes step, half, and in-law relationships. Should Contractor become aware of any family relationship covered by this provision or should such a family relationship arise at any time during the term of this Agreement, Contractor shall immediately disclose the family relationship in writing to the Superintendent. Unless formally waived by the Owner, the existence of a family relationship covered by this Agreement is grounds for immediate termination by Owner without further financial liability to Contractor.

4.24.15 Restricted Companies Lists. Contractor represents that as of the date of this Agreement, Contractor is not included on the Final Divestment List created by the North Carolina State Treasurer pursuant to N.C. Gen. Stat. § 147-86.58. Contractor also represents that as of the date of this Agreement, Contractor is not included on the list of restricted companies determined to be engaged in a boycott of Israel created by the North Carolina State Treasurer pursuant to N.C. Gen. Stat. § 147-86.81.

ARTICLE 5

SUBCONTRACTORS

5.1 DEFINITION

5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform any of the Work at the site. The term Subcontractor may be referred to throughout the Contract Documents as if singular in number and masculine in gender and means a Subcontractor or his authorized representative. The term Subcontractor does not include any Separate Contractor or his subcontractors.

5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform any of the Work at the site or who contracts to perform or supply any of the Work under the scope of a Subcontractor's subcontract. The term Sub-subcontractor may be referred to throughout the Contract Documents as if singular in number and masculine in gender and means a Sub-subcontractor or an authorized representative thereof.

5.1.3 Nothing contained in the Contract Documents is intended to, nor shall it create, any contractual relationship between the Owner, the Design Consultant, or any of their agents, consultants, employees, independent contractors, or representatives and any Subcontractor, Sub-subcontractor, Supplier or Vendor of the Contractor, except the relationship between Owner and Contractor, but the Owner shall be entitled to performance of all obligations intended for his benefit, and to enforcement thereof.

5.1.4 The Owner and Design Consultant will not deal directly with any Subcontractor, Sub-subcontractor or Material Supplier. Communication will be made only through the Contractor. Subcontractor, Sub-subcontractors or Material Suppliers shall route requests for information or clarification through the Contractor to the Design Consultant.

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

5.2.1 The Contractor, in compliance with the requirements of the Contract Documents and within ten (10) days after the Notice to Proceed, shall furnish in writing to the Owner the names of the persons or entities (including those who are to furnish materials or equipment fabricated to a special design) proposed for each of the principal portions of the Work. The Owner will promptly reply to the Contractor in writing stating whether or not the Owner, after due investigation, has reasonable objection to any such proposed person or entity. Failure of the Owner to reply within a reasonable time shall constitute notice of no reasonable objection. The Contractor understands and agrees that no contractual agreement exists for any part of the Work under this Contract between the Owner and any of the Contractor's Subcontractors or Sub-subcontractors. Further, the Contractor understands and agrees that he alone is responsible to the Owner for the Work under this Contract and that any review of Subcontractors or Sub-subcontractors by the Owner will not in any way make the Owner responsible to any Subcontractor, nor responsible for the actions or failures of any Subcontractor or Sub-subcontractor.

5.2.1.1 The Contractor shall identify in the list of names of the Subcontractors proposed, those Subcontractors that are minority or Historically Underutilized Businesses (HUBs) and indicate the portion of the Work that each Subcontractor will perform.

5.2.2 The Contractor shall not contract with any such proposed person or entity to whom the Owner has made reasonable objection under the provisions of Paragraph 5.2.1. The Contractor shall not be required to contract with anyone to whom he has a reasonable objection.

5.2.3 If the Owner has reasonable objection to any proposed person or entity under Paragraph 5.2.1, the Contractor shall name a substitute to whom the Owner has no reasonable objection. The Contract Sum shall be increased or decreased by the difference in cost occasioned by such substitution and an appropriate Change Order shall be issued, subject to an audit of said difference by the Owner; provided, however, that no increase in the Contract Sum shall be allowed for any such substitution unless the Contractor has acted promptly and responsively in submitting names as required by Paragraph 5.2.1 and the original proposed Subcontractor was: (i) able to carry out his work under his proposed subcontract, (ii) able to comply with all applicable laws, (iii) was an ongoing business in the field of his proposed subcontract, and (iv) had a labor force, capital and a means of supply compatible with the scope of his proposed subcontract.

5.2.4 If the Owner requires a change of any proposed Subcontractor or person or organization previously accepted by him on the Project, the Contract Sum shall be increased or decreased by the difference in cost occasioned by such change and an appropriate Change Order shall be issued, subject to an audit by Owner.

5.2.5 The Contractor shall notify the Owner and the Design Consultant of any substitution for any Subcontractor identified in accordance with Subparagraph 5.2.1.1. The Contractor shall make no substitution for any Subcontractor, person or entity previously selected if the Owner or the Design Consultant makes reasonable objection to such substitution. Also, Contractor may make no substitution of Subcontractors in violation of applicable law.

5.2.6 If during the duration of the Project, the Contractor effects a substitution for any Subcontractor per Paragraph 5.2.5, or if additional subcontract opportunities become available, the Contractor shall make a good faith effort to utilize minority and Historically Underutilized Businesses (HUBs).

5.3 SUBCONTRACTUAL RELATIONS

5.3.1 By an appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by the terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities which the Contractor, by these Contract Documents, assumes toward the Owner. Said agreement shall preserve and protect the rights of the Owner under the Contract Documents with respect to the Work to be performed by the Subcontractor so that the subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the agreement between the Contractor and Subcontractor, the benefit of all rights, remedies and redress against the Contractor that the Contractor, by these Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with his Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract, copies of the Contract Documents to which the Subcontractor will be bound by this Section 5.3, and identify to the Subcontractor any terms and conditions of the proposed Subcontract which may be at variance with the Contract Documents. Each Subcontractor shall similarly make copies of such Contract Documents available to his Sub-subcontractors.

5.3.2 The provisions herein regarding Subcontractor approvals shall in no way affect the liability of the Contractor to the Owner regarding performance of all obligations by or payment of Subcontractors. Approval to subcontract with any given Subcontractor shall not to any degree relieve the Contractor of his obligation to perform or have performed to the full satisfaction of the Owner the Work required by this Contract.

5.3.3 The Contractor shall submit Notice to the Owner of any Claims by Subcontractors for which the Owner is believed to be responsible, in strict conformance with the same time requirements and other procedures established for the submission of the Contractor's Claims to the Owner.

5.4 QUALIFICATION SUBMITTALS

5.4.1 Specific qualification submittals may be required of Subcontractors, installers and suppliers for certain critical items of the Work. Required qualification submittals are set forth in detail in the Specifications and shall be collected and submitted by the Contractor for review and approval by the Design Consultant. All information required of a single Subcontractor, installer or supplier shall be contained in a single, complete submittal. The Contractor shall submit the required qualification information within ten (10) days after receipt of the Design Consultant's request.

5.4.2 The Owner and Design Consultant shall reject any proposed Subcontractor, installer or supplier, or any qualification submittals related thereto, for the following reasons:

1. The Contractor's failure to submit requested information within the specified time; or

2. The Contractor's failure to provide all of the requested information; or

3. The Contractor's submission of a Subcontractor, installer or supplier, or qualifications thereof, which are unacceptable in the judgment of the Owner or Design Consultant.

5.4.3 Should the Owner or Design Consultant have reasonable objection to any proposed Subcontractor, installer or supplier, the Contractor shall submit another person or firm who are reasonably acceptable to the Owner and Design Consultant.

5.5 PREPARATORY WORK

5.5.1 Before starting a portion of the Work, the Contractor and the responsible Subcontractor shall carefully examine all preparatory work that has been executed to receive his work. The Subcontractor shall check carefully, by whatever means are required, to ensure that his work and adjacent related work will finish to proper contours, planes and levels. He shall promptly notify the Contractor and the Design Consultant of any defects or imperfections in preparatory work, which will, in any way, affect satisfactory completion of his work. Absence of such notification will be construed as an acceptance of preparatory work and later Claims of defects therein will not be recognized.

5.5.2 Under no conditions shall a portion of the Work proceed prior to preparatory work having been completed, cured, dried, and otherwise made satisfactory to receive such related work. Responsibility for timely installation of all materials rests solely with the Contractor, who shall maintain coordination control at all times.

ARTICLE 6

WORK BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM WORK AND TO AWARD SEPARATE CONTRACTS

6.1.1 The Owner reserves the right to perform work related to the Project with his own forces, and to award separate contracts in connection with other portions of the Project or other work on the site under these or similar conditions of the Contract.

6.1.2 When separate contracts are awarded for different portions of the Project or other work on the site, the term Contractor in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.

6.2 MUTUAL RESPONSIBILITY

6.2.1 The Contractor shall afford Separate Contractors and the Owner reasonable opportunity for the introduction and storage of their materials and equipment and the execution of their work and shall properly connect and coordinate the Work with that of the Owner and other contractors to store his apparatus, materials, supplies and equipment in such orderly fashion at the site of the Work as will not unduly or unreasonably interfere with the progress of the Work or the work of any other contractors.

6.2.1.1 If the execution or result of any part of the Work depends upon any work of the Owner or of any Separate Contractor, the Contractor shall, prior to proceeding with the Work, inspect and promptly report to the Owner in writing any apparent discrepancies or defects in such work of the Owner or of any Separate Contractor that render it unsuitable for such proper execution or result of any part of the Work.

6.2.1.2 Failure of the Contractor to so inspect and report shall constitute an acceptance of the Owner's or Separate Contractor's work as fit and proper to receive the Work, except as to defects which may develop in the Owner's or Separate Contractor's work after completion of the Work and which the Contractor could not have discovered by its inspection prior to completion of the Work.

6.2.2 Should the Contractor cause damage to the Work or property of the Owner or of any Separate Contractor on the Project, or to other work on the site, or delay or interfere with the Owner's work on ongoing operations or facilities or adjacent facilities or said Separate Contractor's work, the Contractor shall be liable for the same; and, in the case of another contractor, the Contractor shall attempt to settle said Claim with such other contractor prior to such other contractor's institution of litigation or other proceedings against the other contractor.

6.2.2.1 Should a Separate Contractor be declared in default by the Owner, the Owner shall not be obligated to hire a contractor to perform the work of the Separate Contractor during the time the Separate Contractor's surety is remedying the default pursuant to Paragraph 3.4.2.

6.2.2.2 If such Separate Contractor sues the Owner or Design Consultant on account of any damage, delay or interference cause or alleged to have been caused by the Contractor, the Owner shall notify the Contractor, who shall defend the Owner and Design Consultant in such proceedings at the Contractor's expense. If any judgment or award is entered against the Owner or Design Consultant in such proceedings, the Contractor shall satisfy the same and shall reimburse the

Owner and Design Consultant for all damages, expenses, attorney's fees and other costs which the Owner or Design Consultant incurs as a result thereof.

6.2.3 Should a Separate Contractor cause damage to the Work or to the property of the Contractor or cause delay or interference with the Contractor's performance of the Work, the Contractor shall present directly to said Separate Contractor any Claims it may have as a result of such damage, delay or interference (with an information copied to the Owner) and shall attempt to settle its Claim against said Separate Contractor prior to the institution of litigation or other proceedings against said Separate Contractor.

6.2.3.1 In no event shall the Contractor seek to recover from the Owner or the Design Consultant, and the Contractor hereby waives any Claims against the Owner and Design Consultant relating to any costs, expenses (including, but not limited to, attorney's fees) or damages or other losses incurred by the Contractor as a result of any damage to the Work or property of the Contractor or any delay or interference caused by any Separate Contractor.

6.2.4 Whenever Contractor receives items from another contractor or from Owner for storage, erection or installation, the Contractor receiving such items shall give receipt for items delivered, and thereafter will be held responsible for care, storage and any necessary replacing of item or items received.

6.2.5 When certain items of equipment and other work are indicated as "NIC" (not in contract), or to be furnished and installed under other contracts, any requirements set forth in the Contract Documents for preparation of openings, provision of backing, etc., for receipt of such "NIC" work will be furnished upon written request of the Contractor who shall properly form and otherwise prepare his work in a satisfactory manner to receive such "NIC" work.

6.3 OWNER'S RIGHT TO PERFORM DISPUTED WORK

6.3.1 If a dispute arises between the Contractor and Separate Contractors as to their responsibility for cleaning up as required by Section 4.18 or for accomplishing coordination or doing required cutting, filling, excavating or patching as required by Section 4.17, the Owner may carry out such work and charge the cost thereof to the responsible party as the Owner shall determine to be just.

6.4 COORDINATION OF THE WORK

6.4.1 By entering into this Contract, Contractor acknowledges that there may be other contractors on the site whose work will be coordinated with that of his own. Contractor expresses, warrants and guarantees that he will cooperate with other contractors and will do nothing to delay, hinder or interfere with the work of other Separate Contractors, the Owner or Design Consultant. Contractor also expressly agrees that, in the event his work is hindered, delayed, interfered with or otherwise affected by a Separate Contractor, his sole remedy will be a direct action against the Separate Contractor as described in this Article 6. Contractor will have no remedy, and hereby expressly waives any remedy, against the Owner and/or the Design Consultant on account of delay, hindrance, interference or other event caused by a Separate Contractor.

ARTICLE 7

MISCELLANEOUS PROVISIONS

7.1 GOVERNING LAW

7.1.1 This Contract shall be governed by the laws of the State of North Carolina.

7.1.2 Each and every provision of law and clause required by law to be inserted in this Contract shall be deemed to be inserted herein and the Contract shall be read and enforced as though it were included herein. If through mistake or otherwise, any such provision is not inserted or is not correctly or fully inserted, then upon the application of either party, the Contract shall forthwith be physically amended to make such insertion.

7.2 SUCCESSORS AND ASSIGNS

7.2.1 The Owner and the Contractor each binds himself, his partners, successors, assigns and legal representatives to the other party hereto and to the partners, successors, assigns and legal representatives of such other party in respect to all covenants, agreements and obligations contained in the Contract Documents. The Contractor shall not assign the Contract or sublet it as a whole without the written consent of the Owner, nor shall the Contractor assign any moneys due or to become due to him hereunder, without the previous written consent of the Owner and the Contractor's Surety.

7.3 CLAIMS AND DAMAGES

7.3.1 Should the Contractor, Subcontractor or any Sub-subcontractor suffer injury or damage to person or property because of any act or omission of the Owner or Design Consultant, or of any of their employees, agents or others for whose acts either is legally liable, the Claim on behalf of the Contractor its Subcontractors or Sub-subcontractors shall be made by giving Notice to the Owner, as provided in Article 15 ; otherwise, the Contractor, Subcontractors and Sub-subcontractors shall have waived any and all rights he may have against the Owner or the Design Consultant, or their employees, representatives and agents. The Contractor shall indemnify, defend and hold the Owner harmless from any Claim by a Subcontractor that is waived because it is not filed in strict conformance with this Paragraph or any other provision of the Contract regarding Claims.

7.4 PERFORMANCE BOND AND LABOR AND MATERIAL PAYMENT BOND

7.4.1 The Contractor shall furnish bonds covering the faithful performance of the Contract and the payment of all obligations arising thereunder in a form and with a Surety satisfactory to the Owner.

7.4.2 The Contractor is required to furnish in duplicate a Performance Bond and a Labor and Material Payment Bond, each in the amount of one hundred percent (100%) of the Contract Sum, written by a surety company licensed to do business in North Carolina and with a minimum AM Best “A” rating or comparable rating from another service reasonably acceptable to Owner.

7.5 RIGHTS AND REMEDIES

7.5.1 The duties and obligations of the Contractor imposed by the Contract Documents and the rights and remedies of the Owner available thereunder shall be in addition to and not a limitation of any duties, obligations, rights and remedies otherwise imposed or available by law.

7.5.2 Except as may be specifically agreed in writing, the failure of the Owner or the Design Consultant to insist in any one or more instances upon the strict performance of any one or more of the provisions of the Contract, or to exercise any right herein contained or provided by law, shall not be construed as a waiver or relinquishment of the performance of such provisions or right(s) or of the right to subsequently demand such strict performance or exercise such right(s), and the rights shall continue unchanged and remain in full force and effect.

7.5.3 The Contractor agrees that he can be adequately compensated by money damages for any breach of the Contract which may be committed by the Owner and hereby agrees that no default, act, or omission of the Owner or the Design Consultant, except for failure to make progress payments as required by the Contract Documents, shall constitute a material breach of the Contract entitling the Contractor to cancel or rescind the provisions of the Contract or (unless the Owner shall so consent or direct in writing) to suspend or abandon performance of all or any part of the Work. The Contractor hereby waives any and all rights and remedies to which he might otherwise be or become entitled, save only his right to money damages.

7.6 TESTS AND INSPECTIONS

7.6.1 If the Contract Documents, laws, ordinances, rules, regulations or orders of any public authority having jurisdiction require any portion of the Work to be inspected, tested, or approved, the Contractor shall give the Owner and Design Consultant timely Notice of its readiness so the Design Consultant and the Owner may observe such inspection, testing or approval. Unless otherwise specifically provided in the Contract Documents, the Contractor shall bear all costs of such inspections, tests or approvals, except that Owner shall pay for “special inspections”as defined and required in Section 1704, the North Carolina State Building Code, or successor section. In the event that such “special inspections” reveal a failure of the Work to comply with the Contract Documents or applicable laws, ordinances, regulations or orders of public authorities having jurisdiction, Contractor shall reimburse the Owner for the costs of such “special inspections”.

7.6.1.1 Unless otherwise stipulated in the Contract Documents, the Contractor shall pay for all utilities required for testing of installed equipment of all of his work and work of each Subcontractor. Boiler fuel other than gas shall be provided by Subcontractor furnishing boilers. Labor and supervision required for making such tests shall be provided at no additional cost to the Owner.

7.6.2 If the Design Consultant or the Owner determines that any portion of the Work requires additional inspection, testing, or approval which Paragraph 7.6.1 does not include, the Owner will instruct the Contractor to order such additional inspection, testing or approval, and the Contractor shall give Notice as provided in Paragraph 7.6.1. If such additional inspection or testing reveals a failure of any portion of the Work to comply (1) with the requirements of the Contract Documents, or (2) with respect to the performance of the Work, with laws, ordinances, rules, regulations, or orders of any public authority having jurisdiction, the Contractor shall bear all costs thereof, including compensation for the Design Consultant's and Owner's additional construction management expenses made necessary by such failure.

7.6.3 With regard to inspections and tests, the costs of which the Owner is responsible for paying, they will be made by a pre-qualified, independent testing agency selected by the Owner. The cost of the initial services of such agency will be paid by the Owner. When the initial tests indicate non-compliance with the Contract Documents, any subsequent testing occasioned by non-compliance shall be performed by the same agency and the cost thereof shall be borne by the Contractor. Representatives of the testing agency shall have access to the Work at all times. The Contractor shall provide facilities for such access in order that the agency may properly perform its functions.

7.6.4 The independent testing agency, contracted by the Owner, shall prepare the test reports, logs, and certificates applicable to the specific inspections and tests and promptly deliver the specified number of copies to the designated parties. Certificates of inspection, testing or approval required by public authorities shall be secured by the Contractor and promptly delivered by him to the Owner, in adequate time to avoid delays in the Work or final payment therefore.

7.6.5 If the Design Consultant or the Owner is to observe the inspections, tests or approvals required by the Contract Documents, laws, ordinances, rules, regulations, or order of any public authority having jurisdiction or that are required to establish compliance with the Contract Documents, he will do so promptly and, where practicable, at the normal place of testing.

7.6.6 The Contractor shall pay for and have sole responsibility for inspections or testing performed exclusively for his own convenience.

7.7 UNENFORCEABILITY OF ANY PROVISION

7.7.1 If any provision of this Contract is held as a matter of law to be unenforceable or unconscionable, the remainder of the Contract shall be enforceable without such provision.

7.8 ATTORNEYS' FEES AND OTHER EXPENSES

7.8.1 The Contractor hereby agrees that he will not submit, assert, litigate or otherwise pursue any frivolous or unsubstantiated Claims or Claims he has specifically waived under the terms of the Contract Documents. In the event that the Contractor's or its Subcontractor’s or Sub-subcontractor’s Claims, or any separate item of a Claim, is without substantial justification, the Contractor shall reimburse the Owner or Design Consultant for all costs and expenses associated with defending such Claim or separate item, including but not limited to, attorneys' fees, audit costs, accountants' fees, expert witness' fees, additional Design Consultant expenses, additional construction management expenses, or services and any other consultant costs.

7.8.2 If the Contractor breaches any obligation under the Contract Documents, the Contractor shall reimburse the Owner and Design Consultant for all costs and expenses incurred by the Owner relating to such breach, including but not limited to attorneys' fees, audit costs, accountants' fees, expert witness' fees, additional Design Consultant expenses, additional construction management expenses, and any other consultant costs.

7.8.3 If the Owner or Design Consultant substantially prevails in a Claim brought against the Contractor, or in defending a Claim brought by the Contractor, including but not limited to, Claims for fraud or misrepresentation, overpayment, defective work, delay damages, and recovery of termination expenses, the Contractor shall reimburse the Owner and/or Design Consultant for all costs and expenses incurred by them relating to such Claim, including but not limited to attorneys' fees, audit costs, accountants' fees, expert witness' fees, additional Design Consultant expenses, additional construction management expenses, and any other consultant costs.

ARTICLE 8

TIME

8.1 DEFINITIONS

8.1.1 Unless otherwise provided, the Contract Time is the period of time allotted in the Contract Documents for Final Completion of the Work as defined in Paragraph 8.1.4, including authorized adjustments thereto. The Contractor shall achieve Final Completion within the Contract Time.

8.1.2 The date of commencement of the Work is the date established in the Notice to Proceed. If there is no Notice to Proceed, it shall be the date of the Owner-Contractor Agreement or such other date as may be established therein. The Contractor shall not commence work or store materials or equipment on site until written Notice to Proceed is issued or until the Contractor otherwise receives the Owner's written consent.

8.1.3 The date of Substantial Completion of the Work or designated portion thereof is the date certified by the Design Consultant and the Owner when the Work or a designated portion thereof is sufficiently complete, in accordance with the Contract Documents, so the Owner can fully and legally occupy and utilize the Work or designated portion thereof for the use for which it is intended, with all of the parts and systems operable as required by the Contract Documents, including a preliminary test and balance report for the mechanical system. Only incidental corrective work and any final cleaning beyond that needed for the Owner's full use may remain for Final Completion. The Contractor acknowledges and agrees that the intercom, telephone, data security, building automation system (including functional graphics at the site), MATV, and other educational operational systems are required for the Owner’s use of the building for its intended purpose. The Contractor shall provide operation and maintenance manuals to the Owner as required by the Contract Documents prior to Substantial Completion and shall provide the required training on the operation of the equipment and systems within two weeks of Substantial Completion. The Contractor shall achieve Substantial Completion by the date specified in the Supplemental Conditions including authorized adjustments thereto. The Owner’s occupancy of incomplete work shall not alter the Contractor’s responsibilities pursuant to this paragraph. Only incidental corrective work and any final cleaning beyond that needed for the Owner’s full use may remain for Final Completion. The issuance of a temporary or final certificate of occupancy shall not, in itself, constitute Substantial Completion.

8.1.4 Final Completion of the Work occurs on the date certified by the Design Consultant and the Owner when the Work is totally complete, to include punch list work, in accordance with the Contract Documents and the Owner may fully occupy and utilize the Work for the use for which it is intended. The issuance of a temporary or final certificate of occupancy shall not, in itself, constitute Final Completion.

8.1.5 The term Day as used in the Contract Documents shall mean calendar day unless otherwise specifically designated. All dates shall mean midnight of the indicated day unless otherwise stipulated.

8.1.6 Completion Dates shall mean the dates set forth in the Supplemental Conditions for Substantial Completion and Final Completion.

8.2 PROGRESS AND COMPLETION

8.2.1 All time limits stated in the Contract Documents are of the essence of the Contract with respect to the Contractor's performance.

8.2.2 The Contractor shall begin the Work on the date of commencement as defined in Paragraph 8.1.2. He shall carry the Work forward expeditiously with adequate forces and shall achieve Substantial Completion and Final Completion within the time frames stated in the Contract Documents.

8.2.3 Attention is directed to the fact that the Work is urgently needed by the Owner; for this reason, it shall be agreed that the Contractor and its Subcontractors will achieve Substantial Completion of the Work under the Contract within the time established under Paragraph 8.2.4 of the Supplemental Conditions after award of Contract, or Notice to Proceed, and that he will achieve Final Completion of the Work in all its details for final acceptance within the time established under Paragraph 8.2.4 of the Supplemental Conditions.

8.3 DELAYS AND EXTENSIONS OF TIME

8.3.1 The time during which the Contractor or any of the Subcontractors is delayed in the performance of the Work by the issuance of any required permits, acts of god, excessive inclement weather, fires, floods, epidemics, quarantine restrictions, strikes, riots, civil commotions or freight embargoes, or other conditions beyond the Contractor's or the Subcontractors' control and which the Contractor or the Subcontractors could not reasonably have foreseen and provided against, except for delays caused solely by the Owner, Design Consultant or their consultants, shall be added to the time for completion of the Work stated in the Contract. Neither the Owner nor the Design Consultant shall be obligated or liable to the Contractor or the Subcontractors for indirect or direct damages, costs or expenses of any nature which the Contractor, the Subcontractors, or any other person may incur as a result of any of the delays, interferences, changes in sequence in the Work included in this Section 8.3.1. The Contractor hereby expressly waives any Claims against the Owner and the Design Consultant on account of any indirect or direct damages, lost profits, costs or expenses of any nature which the Contractor, the Subcontractors or any other person may incur as a result of any delays, interferences, changes in sequence or the like, and it is understood and agreed that the Contractor's sole and exclusive remedy in any such events shall be an extension of the Contract time in accordance with the Contract Documents.

8.3.2 In the event Project delays arise from or out of any act or omission of the Owner, Design Consultant or their consultants, the time during which the Project is delayed shall be added to the Contract and the Contractor may be reimbursed for its direct Project damages, excluding general overhead expenses and indirect costs, if the Contractor strictly complies with this Article 8.3. Notwithstanding the previous sentence, if the Contractor or Subcontractor in any way shares in responsibility for the delay, neither the Owner nor the Design Consultant shall be obligated or liable to the Contractor or the Subcontractors for indirect or direct damages, costs or expenses of any nature which the Contractor, the Subcontractors, or any other person may incur as a result of any of the delays, interferences, changes in sequence of the Work, and the Contractor's sole remedy, if any, shall be an extension of the Contract time.

8.3.3 In the event Project delays arise solely from or out of any act or omission of the Contractor, Subcontractors or their agents, the Contractor shall not be entitled to extension of the Contract time and shall be subject to the payment of Liquidated Damages as provided in this Contract.

8.3.4 The Contract time shall be adjusted only for changes pursuant to section 12.1, suspension of the Work pursuant to paragraph 3.3.2 or paragraph 3.3.3, and excusable delays pursuant to paragraph 8.3.4. In the event the Contractor requests an extension of the Contract time or files a Claim related to any form of delay, it shall furnish such justification and supporting evidence as the Owner may deem necessary for a determination of whether or not the Contractor is entitled to an extension of time under the provisions of the Contract, and shall further conform to all of the requirements of the specifications and the Contract regarding construction schedules and reports. The burden of proof to substantiate a Claim shall rest with the Contractor, including evidence that the cause was beyond its control. The Owner shall base its findings of fact and decision on such justification and supporting evidence, including a finding that the alleged delay impacted the Project's critical path, and shall advise the Contractor in writing thereof. If the Owner finds that the Contractor is entitled to any extension of the Contract time, the Owner's determination of the total number of days of extension shall be based upon the currently approved progress schedule and on all data relevant to the extension. Such data will be incorporated into the schedule in the form of a revision thereto, accomplished in a timely manner. The Contractor acknowledges and agrees that actual delays (due to said changes, suspension of Work or excusable delays) in activities which, according to the schedule, do not affect the Contract time, do not have any effect upon the Contract time and therefore will not be the basis for a change therein. The Contractor acknowledges and agrees that time extensions will be granted only to the extent that excusable delays exceed the available float in the critical path activities in the Contractor's currently approved schedule.

8.3.4.1 Extensions in the Contract time by Change Orders are subject to extension-in-time audit by the Owner as follows:

8.3.4.1.1 The Contractor agrees that, even though the Owner, Contractor and Design Consultant have previously signed a Change Order containing an extension-in-time resulting from a change in or addition to the Work that said extension in the Contract time may be adjusted by an audit after the fact by the Owner. If such an audit is to be made, the Owner must undertake the audit and make a ruling within thirty (30) days after the completion of the Work under the Change Order.

8.3.4.1.2 The Contractor agrees that any extension of the Contract time to which it is entitled arising out of a Change Order undertaken on a force accounting (labor and materials) basis, shall be determined by an extension-in-time audit by the Owner after the Work of the Change Order is completed. Such rulings shall be made by the Owner within thirty (30) days after a request for same is made by the Contractor or Design Consultant, except said thirty (30) days will not start until the Work under the Change Order is completed.

8.3.4.1.3 Should a time extension be granted for Substantial Completion the date for Final Completion shall be appropriately adjusted unless specifically stated otherwise.

8.3.4.2 Subject to other provisions of the Contract, the Contractor may be entitled to an extension of the Contract time (but no increase in the Contract sum) for delays arising from unforeseeable causes beyond the control and without the fault or negligence of the Contractor, the Subcontractors or suppliers as follows:

8.3.4.2.1 Labor disputes and strikes (including strikes affecting transportation), that do, in fact, directly delay the progress of the Work on the critical path; however, an extension of Contract time on account of an individual labor strike shall not exceed the number of days of said strike;

8.3.4.2.2 Acts of nature: tornado, fire, hurricane, blizzard, earthquake, or flood that damage Work in place or stored materials or adversely impact the schedule's critical path;

8.3.4.2.3 Excessive inclement weather; however, the Contract time will not be extended due to reasonably anticipated inclement weather or for delays in the aftermath of inclement weather, reasonably anticipated or excessive. The time for performance of this Contract, as stated in the Contract Documents, includes an allowance for calendar days which may not be available for construction out-of-doors; for the purposes of this Contract, the Contractor agrees that the number of calendar days per month based on a five-year average shall be considered reasonably anticipated inclement weather and planned for in the construction schedule and the Contract Documents. Unless the Contractor can substantiate to the satisfaction of the Owner that there was greater than the reasonably anticipated inclement weather considering the time from the notice-to-proceed until the date established for Substantial Completion using data from the national weather service station identified in the Supplemental Conditions, or a weather station acceptable to the Owner and that such alleged greater than reasonably anticipated inclement weather actually delayed the Work or portions thereof which had an effect upon the Contract time, the Contractor shall not be entitled to an extension of time.

Also the Contractor agrees that the calculation of the number of excessive inclement weather days shall be the number of days in excess of the five-year average for each month, in which precipitation exceeded one tenth (.10) inch, or in which the highest temperature was 32 degrees F or less as recorded at the approved weather station. Rain days from hurricanes and tropical storms not causing damage in the county in which the project is located shall be deemed inclement weather days.

If the total accumulated number of calendar days lost to excessive inclement weather, from the notice-to-proceed until the date established for Substantial Completion, exceeds the total accumulated number to be reasonably anticipated for the same period from the table above, time for completion will be extended by the number of calendar days needed to include the excess number of calendar days lost. No extension of time will be made for days due to excessive inclement weather occurring after the date established for Substantial Completion. No change in Contract sum will be authorized because of adjustment of Contract time due to excessive inclement weather; and

8.3.4.2.4 Delays in the issuance of the building permit required for construction of the Project, acts of the public enemy, acts of the State, Federal or local government in its sovereign capacity, and acts of another Contractor in the performance of a Contract with the Owner relating to the Project.

8.3.5 If the Contractor shall neglect, fail or refuse to complete the Work within the time herein specified, or any proper extension thereof granted by the Owner, then the Contractor does hereby agree, as a part consideration for the awarding of this Contract, to pay the Owner the amount specified in the Contract, not as a penalty but as Liquidated Damages for such breach of Contract as hereinafter set forth, for each and every calendar day that the Contractor shall be in default after the time stipulated in the Contract for completing the Work. The said amount is fixed and agreed upon by and between the Contractor and the Owner because of the impracticability and extreme difficulty of fixing and ascertaining the actual damages the Owner would in such event sustain, and said amount is agreed to be the amount of damages which the Owner would sustain and said amount shall be retained from time to time by the Owner from current periodical estimates.

8.3.6 The Contractor and the Subcontractors shall not be entitled to and hereby expressly waive any extension of time resulting from any condition or cause unless said Claim for extensions of time

is made in writing to the Owner within ten (10) days of the first instance of delay for all delays, except excessive inclement weather which shall be made in writing to the Owner within forty-five (45) days after the date established for Substantial Completion. Circumstances and activities leading to such Claim shall be indicated or referenced in a daily field inspection report for the day(s) affected. In every such written Claim, the Contractor shall provide the following information:

8.3.6.1 Nature of the delay;

8.3.6.2 Date (or anticipated date) of commencement of delay;

8.3.6.3 Activities on the progress schedule affected by the delay, and/or new activities created by the delay and their relationship with existing activities;

8.3.6.4 Identification of person(s) or organization(s) or event(s) responsible for the delay;

8.3.6.5 Anticipated extent of the delay; and

8.3.6.6 Recommended action to avoid or minimize the delay.

8.3.7 If no schedule or agreement is made stating the dates upon which written interpretations as set forth in Section 2.2 shall be furnished, then no Claim for delay shall be allowed on account of failure to furnish such interpretations until twenty (20) days after request is made for them, and not then unless such Claim is reasonable.

8.3.8 No Claim by the Contractor for an extension of time for delays will be considered unless made in strict compliance with the requirements of this Article. All Claims not filed in accordance with this paragraph shall be waived by the Contractor.

8.4 RESPONSIBILITY FOR COMPLETION

8.4.1 The Contractor shall be responsible for completion in accordance with Paragraph 4.12.1.

8.4.2 The Owner may require the Contractor to submit a recovery schedule demonstrating his program and proposed plan to make up the lag in scheduled progress and to ensure completion of the Work within the Contract Time if the Project is behind schedule by four (4) or more days. If the Owner finds the proposed plan not acceptable, he may require the Contractor to submit a new plan. If the actions taken by the Contractor or the second plan proposed are not satisfactory, the Owner may require the Contractor to take any of the actions set forth in Paragraph 4.12.2 without additional cost to the Owner, to make up the lag in scheduled progress.

8.4.3 Failure of the Contractor to substantially comply with the requirements of this Section 8.4 may be considered grounds for a determination by the Owner, pursuant to Section 14.3, that the Contractor is failing to prosecute the Work with sufficient diligence to ensure its completion within the Contract Time.

8.5 LIQUIDATED DAMAGES FOR DELAY

8.5.1 Owner and Contractor agree that the damages incurred by the Owner due to the Contractor's failure to achieve Substantial Completion by the date specified in the Supplemental Conditions for Substantial Completion, including any extensions thereof, shall be in the amounts set forth in the Supplemental Conditions, for each consecutive day beyond the date of Substantial

Completion that Contractor achieves Substantial Completion, and that the damages incurred by the Owner due to the Contractor's failure to achieve Final Completion by the date specified in the Supplemental Conditions for Final Completion, including any extensions thereof, shall be in the amount set forth in the Supplemental Conditions for each consecutive day beyond the date of Final Completion that Contractor achieves Final Completion. The Liquidated Damages are a reasonable estimate by Contractor and Owner of the damages to be suffered by Owner and are not to be construed as a penalty, it being recognized by the Owner and the Contractor that the injury to the Owner which could result from a failure of the Contractor to complete on schedule is uncertain and cannot be computed exactly or that it would be unreasonably expensive for Owner to calculate its damages exactly.

8.5.2 The amount specified for Substantial Completion is the minimum measure of damages the Owner will sustain due to delay in the completion of the Work, which shall inlcude, but not be limited to the loss of use of the facilities, the relocation of students and services, the cost of the Owner's time and resourses, damage to the Owner's reputation, and storage of furniture and other materials. The amount specified for Final Completion is a reasonable and proper measure of the damages the Owner will sustain due to the delay in the completion of remedial work. This amount includes the disruption to the school and the learning environment, the cost of the Owners time and resources, damage to the Owner's reputation, and the inability to fully use the facilities. The inability of the Owner to quantify actual damages shall not prevent the recovery of Liquidated Damages.

8.5.3 Not withstanding any other provisions of these General Conditions, if there is concurrent delay in the completion of the Work, the Contractor shall be liable for Liquidated Damages as specified in the General Conditions and Supplemental Conditions during such period of concurrent delay. For the purpose of this Paragraph, concurrent delay means (a) a delay event caused in part by the Owner or its agent and in part by the Contractor or its agents, Subcontractors or Sub-subcontractors, or (b) one or more delay event caused solely by the Owner, its agents, or the Design Consultant, and one or more delay event caused in part by the Contractor, its agents, Subcontractors or Sub-subcontractors, each of which would have resulted in a delay without the other and which delays run concurrently, or at the same time. In the event that the foregoing provision making the Contractor liable for Liquidated Damages during a period of concurrent delay is found to be unenforcable, then the parties agree that in the event of a concurrent delay, the extent of the delay will be apportioned between the Owner and the Contractor, and the Contractor will be responsible for Liquidated Damages as set forth in the General Conditions and Supplemental Conditions for those portions of the delay which are apportioned to the Contractor, its agent, Subconctractors, Sub-subcontractors, or Material Suppliers.

8.5.4 The provisions for Liquidated Damages do not bar or limit Owner's other rights and remedies against Contractor, for damages other than for failure to achieve the Substantial Completion date or the Final Completion date as required. The amount of Liquidated Damages set forth in Section 8.5 shall not include additional legal or design professional costs that may result from the Contractor's default. If such legal or design professional costs are incurred by the Owner, the Contractor shall be liable to the Owner for those costs in addition to the Liquidated Damages amount set forth in Section 8.5.

8.5.5 The Liquidated Damages assessed for failure to meet Substantial Completion by the specified date and the Liquidated Damages assessed for failure to meet Final Completion by the specified date shall be assessed cumulatively.

ARTICLE 9

PAYMENTS AND COMPLETION

9.1 CONTRACT SUM

9.1.1 The Contract Sum is stated in the Owner-Contractor Agreement and, including authorized adjustments thereto, is the total amount payable by the Owner to the Contractor for the performance of the Work under the Contract Documents.

9.2 SCHEDULE OF VALUES

9.2.1 Before the first Application for Payment, the Contractor shall submit to the Owner a schedule of values allocated to the various portions of the Work and supported by such data to substantiate its accuracy as the Owner may require. This schedule, unless objected to by the Owner, shall be used as a basis for the Contractor's Applications for Payment and only for this purpose. If approved by the Owner, the Contractor may include in his schedule of values a line item for mobilization which shall include a reasonable amount of mobilization for the Contractor and his Subcontractors. The Contractor shall not front-end load his schedule of values.

9.3 APPLICATIONS FOR PAYMENT

9.3.1 Prior to the date for each progress payment established in the Owner-Contractor Agreement, the Contractor shall submit to the Design Consultant an itemized Application for Payment, notarized if required, supported by such data substantiating the Contractor's right to payment as the Design Consultant and the Owner may require, including but not limited to the Contractor's certification that all work for which payment is requested has been completed in full in accordance with the Contract Documents, and reflecting retainage, if any, as provided elsewhere in the Contract Documents. If requested by the Owner, the Contractor shall also certify that he has paid all due and payable amounts for which previous Applications for Payment were issued and payments received from the Owner, by providing waivers of liens for said payments.

9.3.1.1 The Contractor shall submit with the Application for Payment a list of those minority and Historically Underutilized Businesses (HUBs) Subcontractors whose work is included in the application and the amount due each. In addition, the minority and Historically Underutilized Business (HUBs) must itself perform satisfactory work or services or provide supplies under the Contract and not act as a mere conduit.

9.3.2 The Owner will withhold retainage from Contractor on all Applications for Payment to the maximum extent and in the maximum amount allowed by law (currently codified at N.C.G.S. 143-134.1) and in accordance with that statute or applicable successor statute. In the event that N.C.G.S 143-134.1 or applicable successor statute are not in effect or do not apply at the time the Contract is executed, Owner will retain five percent (5%) of the amount of each Application for Payment from the Contractor as retainage, until Contractor achieves Final Completion, whether or not the Owner has occupied any or all of the Project before such time. However, if the Owner, at any time after fifty percent (50%) of the Work has been completed, finds that satisfactory progress is being made, he may authorize payment to the Contractor in full of each Progress Payment for work performed beyond the fifty percent (50%) stage of completion. If a reduction in retainage has been made, the Owner may increase the retainage back to original percentage at any time if the Owner concludes that the Contractor is not progressing with the Work in a timely or satisfactory manner.

9.3.3 Payments may be made by the Owner, at its sole discretion, on account of materials or equipment not incorporated in the work but delivered and suitably stored at the site or in a bonded warehouse by the Contactor. Payments for materials or equipment stored shall only be considered upon submission by the Contractor of satisfactory evidence (for example, releases or paid invoices from the seller) that the Contractor has acquired title to such material, that it will be utilized on the work under this Contract and that it is satisfactorily stored, protected, and insured or that other procedures satisfactory to the Owner that will protect the Owner's interests have been taken. In the event the materials are stored in a bonded warehouse that is not located in the county of the project, the Contractor shall reimburse the travel cost and hourly billing expenses incurred by the Design Consultant for travel to view and assess whether the materials meet the requirements of the Contract Documents. Materials once paid for by the Owner become the property of the Owner and may not be removed from the work site or bonded warehouse, other than to be delivered from the warehouse to the site, without the Owner's written permission. Responsibility for such stored materials and equipment shall remain with the Contractor regardless of ownership.

9.3.3.1 Owner will not make payment to the Contractor on account of materials or equipment not incorporated in the Work but delivered and stored at the site if the Contractor, in his schedule of values, does not includes line items for such delivered and stored materials or equipment.

9.3.3.2 It is specifically understood and agreed that an inspection and approval of the materials by the Owner, the Design Consultant or any agency retained by any of them shall not in any way subject the Owner to pay for the said materials or any portion thereof, even though incorporated in the Work, if said materials shall in fact turn out to be unfit to be used in the Work, nor shall such inspection be considered as any waiver of objection to the Work on account of the unsoundness or imperfection of the material used.

9.3.4 The Contractor warrants that title to all work, materials and equipment covered by an Application for Payment will pass to the Owner either by incorporation in the construction or upon the receipt of payment by the Contractor, whichever occurs first, free and clear of all liens, claims, security interests or encumbrances, hereinafter referred to in this Article 9 as "liens"; and that no work, materials or equipment covered by an Application for Payment will have been acquired by the Contractor, or by any other person performing work at the site or furnishing materials and equipment for the Project, subject to an agreement under which an interest therein or an encumbrance thereon is retained by the seller or otherwise imposed by the Contractor or such other person.

9.3.5 The Contractor shall submit with the Application for Payment a notarized Contractor’s Sales Tax Report of N.C. State and County sales taxes paid during the payment period with respect to building materials, supplies, fixtures, and equipment that have become a part of, or annexed to, a building or structure erected, altered or repaired for the Owner. The Sales Tax Report shall include the vendor from whom the property was purchased, the dates and number of invoices covering the purchase, the total amount of the invoices of each vendor, the North Carolina State and County sales and use tax paid thereof, and the cost of the property withdrawn from the warehouse stock and North Carolina sales or use taxes paid thereof. Items that should not be included are: scaffolding, forms for concrete, fuel for operation of machinery and equipment, tools, equipment, equipment repair parts and equipment rentals.

9.3.6 Unless an interest rate is required by law, Owner shall not pay any interest on an amount owed to Contractor. No interest shall accrue on amounts Owner is authorized by law or by the Contract to withhold or backcharge to Contractor.

9.4 CERTIFICATION OF PAYMENT

9.4.1 The Design Consultant will, after receipt of the Contractor's Application for Payment either issue a Certification of Payment to the Owner, with a copy to the Contractor, for such amount as the Design Consultant determines is properly due, or notify the Contractor in writing of their reasons for withholding a Certification as provided in Paragraph 9.6.1.

9.4.2 The submission and approval of the progress schedule and monthly updates thereof as required by the Contract Documents shall be an integral part and basic element of the application upon which progress payment shall be made. The Contractor shall be entitled to progress payments only as determined from the currently approved and updated schedule.

9.4.3 The signing of a Certification of Payment will constitute a representation by the Design Consultant to the Owner, based on their observations at the site pursuant to their agreements with the Owner, and the data comprising the Application for Payment, that the Work has progressed to the point indicated; that, to the best of their knowledge, information and belief, the quality of the Work is in accordance with the Contract Documents (subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to the results of any subsequent tests required by or performed under the Contract Documents, to minor deviations from the Contract Documents correctable prior to completion, and to any specific qualifications stated in their Certification); and that the Contractor is entitled to payment in the amount certified. However, by signing a Certification of Payment, the Design Consultant shall not thereby be deemed to represent that it has made exhaustive or continuous on-site inspections to check the quality or quantity of the Work or that it has reviewed the construction means, methods, techniques, sequences, or procedures, or that it has made any examination to ascertain how or for what purpose the Contractor has used the moneys previously paid on account of the Contract Sum.

9.5 PROGRESS PAYMENTS

9.5.1 After a Certification of Payment has been issued, the Owner shall make payment in the manner and within the time provided in the Contract Documents, unless Contractor is in breach of the Contract or otherwise owes the Owner, in which case Owner may withhold an appropriate amount.

9.5.2 The Contractor shall promptly pay each Subcontractor (including suppliers, laborers, and material-men) performing labor or furnishing material or equipment for the Work, upon receipt of payment from the Owner, out of the amount paid to the Contractor on account of such Subcontractor's work, the amount to which said Subcontractor is entitled, reflecting the percentage actually retained, if any, from payments to the Contractor on account of such Subcontractor's work. The Contractor shall, by an appropriate agreement with each Subcontractor, also require each Subcontractor to make payments to his Sub-subcontractors in similar manner. The Owner may at any time require proof of payment to a Subcontractor or Sub-subcontractor for work paid by the Owner. Notwithstanding any other provision of the General Conditions, no Contractor, Subcontractor, Sub-subcontractor or Material Supplier shall have any Claim against the Owner, by virtue of the Contract, under any theory, including breach of contract, or third party beneficiary. The Owner shall not be in privy of any contract with any Subcontractor, Sub-subcontractor or Material Supplier pertaining to the Work, the Project and these General Conditions. Also, neither the Contractor, or any Subcontractor or Sub-subcontractor shall have any right to assert a lien on Owner’s real property or on any funds held by Owner.

9.5.3 The Owner may, on request and at his discretion, furnish to any Subcontractor, if practicable, information regarding the percentages of completion or the amounts applied for by the Contractor and the action taken thereon by the Design Consultant on account of work done by such Subcontractor.

9.5.4 Neither the Owner nor the Design Consultant shall have any obligation to pay or to see to the payment of any moneys to any Subcontractor except as may otherwise be required by law.

9.5.5 No Certification for a progress payment, nor any progress payment or final payment, nor any partial or entire use or occupancy of the Project by the Owner, shall constitute an acceptance of any Work not in accordance with the Contract Documents.

9.5.6 The Contractor agrees to keep the Work and the site of the Project free and clear of all liens related to labor and materials furnished in connection with the Work. Furthermore, pursuant to and in compliance with requirements of Paragraph 9.3.4, the Contractor waives any right he may have to file any type of lien in connection with the Work. Notwithstanding anything to the contrary contained in the Contract Documents, if any such lien is filed or there is evidence to believe that any lien may be filed at any time during the progress of the Work or within the duration of this Contract, the Owner may refuse to make any payment otherwise due the Contractor or may withhold from any payment due the Contractor a sum sufficient in the opinion of the Owner to pay all obligations and expenses necessary to satisfy such lien or the underlying claim represented by such lien. The Owner may withhold such payment unless or until the Contractor, within ten (10) days after demand thereof by the Owner, shall furnish satisfactory evidence that the indebtedness and any lien in respect thereof has been satisfied, discharged and released of record, or that the Contractor has legally caused such lien to be released of record pending the resolution of any dispute between the Contractor and the person or persons filing such lien. If the Contractor shall fail to furnish such satisfactory evidence within ten (10) days of the demand thereof, the Owner may discharge such indebtedness and deduct the amount thereof, together with any and all losses, costs, damages and attorney's fees suffered or incurred by the Owner from any sum payable to the Contractor under the Contract Documents, including but not limited to final payment and retained percentage. This Paragraph 9.5.6 shall be specifically included in all Subcontracts and purchase orders entered into by the Contractor. Notwithstanding any other provision of the Contract, nothing in the Contract shall affect the rights of Subcontractors, Sub-subcontractors, Material Suppliers and Vendors from enforcing any lien rights they have against parties other than the Owner.

9.6 PAYMENTS WITHHELD

9.6.1 The Design Consultant may decline to certify payment and may withhold their Certification of Payment in whole or in part, to the extent necessary to reasonably protect the Owner, if in the Design Consultant's opinion, it is unable to make representations to the Owner as provided in Paragraph 9.4.3. If the Design Consultant is unable to make representations to the Owner as provided in Paragraph 9.4.3 and to certify payment in the amount of the Application for Payment, it will notify the Contractor as provided in Paragraph 9.4.1. If the Contractor and the Design Consultant cannot agree on a revised amount, the Design Consultant will promptly issue a Certification of Payment for the amount for which it is able to make such representations to the Owner. The Design Consultant may also decline to certify payment because of subsequently discovered evidence or subsequent observations that may nullify the whole or any part of any Certification of Payment previously issued to such extent as may be necessary in its opinion to protect the Owner from loss, because of:

1. Defective Work not remedied,

2. Third party claims filed, whether in court, in arbitration or otherwise, or reasonable evidence indicating probable filing of such claims,

3. Failure of the Contractor to make payments properly to Subcontractors or for labor, materials or equipment,

4. Reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum,

5. Damage to the Owner or another contractor,

6. Reasonable evidence that Contractor will not achieve Substantial Completion and/or Final Completion by the dates specified in the Supplemental Conditions.

7. Failure or refusal of the Contractor to carry out the Work in accordance with or to otherwise substantially or materially comply with the Contract Documents,

8. Liens filed or reasonable evidence that a lien may be filed for any portion of the Work,

9. Failure or refusal of the Contractor to properly schedule and coordinate the Work, to provide progress schedules, reports and updates, or to provide and adhere to a recovery schedule as required by the Contract Documents,

10. Failure or refusal of the Contractor to fully comply with the provisions of Section 6.2 requiring the Contractor to direct certain Claims to Separate Contractors and to defend and indemnify the Owner and/or the Design Consultant in the event Separate Contractors file certain Claims,

11. Failure or refusal of the Contractor to submit the required information on minority and Historically Underutilized Businesses (HUBs),

12. Failure or refusal of the Contractor to submit a notarized North Carolina State and County Sales Tax Report,

13. Any other breach of the Contract by Contractor which has or is likely to cause monetary damages or loss to Owner, or

14. Any other reason authorized by the Contract Documents or by law.

9.6.2 When the above grounds in Paragraph 9.6.1 are removed to the Design Consultant's and Owner's satisfaction, payment shall be made for amounts withheld because of them.

9.7 FAILURE OF PAYMENT

9.7.1 If the Owner does not make payment to the Contractor within the forty-five (45) calendar days after receipt of the Contractor's approved Application for Payment from the Design Consultant through no fault of the Contractor, and the Owner otherwise not being entitled under the Contract Documents or applicable law to withhold payment, then the Contractor may, upon seven (7) additional days' Notice to the Owner, stop the Work until payment of the amount owed according to the Contract Documents has been received. In such event, the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shut-down, delay and start- up, which shall be effected by appropriate Change Order as provided herein.

9.8 SUBSTANTIAL COMPLETION

9.8.1 When the Contractor considers that the Work, or a designated portion thereof which is acceptable to the Owner, is substantially complete as defined in Paragraph 8.1.3, the Contractor shall prepare for submission to the Owner a list of items which in his opinion are to be completed or corrected and shall request in writing that the Design Consultant and the Owner perform a Substantial Completion inspection. The Design Consultant and the Owner shall review the Contractor's list and shall compile a punch list of items to be corrected and completed. The failure to include any items on such list does not alter the responsibility of the Contractor to complete the Work in accordance with the Contract Documents. When the Design Consultant and the Owner on the basis of an inspection jointly determine that the Work or designated portion thereof is substantially complete, they will then prepare a Certificate of Substantial Completion which shall establish the date of Substantial Completion, shall state the responsibilities of the Owner and the Contractor for security, maintenance, heat, utilities, damage to the Work, and insurance, and shall fix the time within which the Contractor shall complete the items listed therein. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion. The Certificate of Substantial Completion shall be submitted to the Owner and the Contractor for their written acceptance of the responsibilities assigned to them in such Certificate.

9.8.2 Upon Substantial Completion of the Work or designated portion thereof and upon application by the Contractor and certification by the Design Consultant, the Owner shall make payment, except retainage held pursuant to Paragraph 9.3.2, for such work or portion thereof, as provided in the Contract Documents unless Contractor is in breach of the Contract in which case Owner may withhold an appropriate amount.

9.8.3 The acceptance of Substantial Completion payment shall constitute a waiver of all Claims by the Contractor and its Subcontractors and Sub-subcontractors except those previously made in writing and identified by the Contractor as unsettled at the time the Contractor submits the Application for Payment for Substantial Completion, and except for the retainage sums due at Final Completion. The Contractor shall indemnify and hold the Owner harmless against any Claims by its Subcontractors and Sub-subcontractors that are waived because they were not made in writing and identified by the Contractor as unsettled when the Contractor submitted the Application for Payment for Substantial Completion.

9.8.4 The Owner shall have the option to correct or conclude any and all punch list items not completed by the Contractor to the satisfaction of the Design Consultant and the Owner within thirty (30) days from the actual date of Substantial Completion by utilizing its own forces or by hiring others. The cost of such correction of remaining punch list items by the Owner or others shall be deducted from the final payment to the Contractor. If Contractor does not complete certain punch list items within this time period, specified in Paragraph 9.8.4, all warranties and guarantees for such incomplete punch list items shall become effective upon issuance of final payment for the Project. Paragraph 9.8.4 does not limit the Liquidated Damages provisions related to failure to reach Final Completion by the date stipulated in the Contract Documents.

9.8.5 The issuance of the Certificate of Substantial Completion does not indicate final acceptance of the Project by the Owner, and the Contractor is not relieved of any responsibility for the Project except as specifically stated in the Certificate of Substantial Completion.

9.8.6 Should the Design Consultant and the Owner determine that the Work or a designated portion

thereof is not substantially complete, they shall inform the Contractor in writing stating why the Project or designated portion is not substantially complete. The Contractor shall expeditiously complete the Work and shall re-request in writing that the Design Consultant and the Owner perform a Substantial Completion inspection. Costs, if any, associated with such inspection shall be assessed to the Contractor.

9.8.7 Certificate of Substantial Completion will not be issued until the following is completed by Contractor:

1. Submit Contractor's list of work not yet complete with proposed time for completion signed by Contractor's project superintendent;
2. Submit Certificate of Occupancy;
3. Submit record drawings, maintenance manuals, final project photos, property surveys;
4. Deliver tools, spare parts, extra stock and similar items;
5. Submit warranties, bonds, maintenance agreements and final certifications;
6. Complete start-up testing of all systems and instruction of the Owner's personnel;
7. Coordinate and complete final changeover of permanent locks and transmit keys to Owner;
8. Discontinue and remove temporary facilities from the site;
9. Complete final cleaning;
10. Advise the Owner of pending insurance changeover requirements;
11. Coordinate and complete changeover of security, telephone, cable and other services; and
12. Submit pay application showing 100% complete for work claimed to be substantially complete.

9.8.8 The Contractor acknowledges that the Design Consultant and its consultants are only required to conduct up to two (2) comprehensive substantial completion inspections as part of its basic services. If more than two (2) substantial completion inspections are required through no fault of the Design Consultant, the cost of the additional inspections shall be paid by the Contractor directly to the Design Consultant at the rate of $150 per hour.

9.9 FINAL COMPLETION AND FINAL PAYMENT

9.9.1 Upon receipt of the documentation required by Section 9.8, and of written Notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Design Consultant and the Owner will promptly make such inspection and, when they find the Work acceptable under the Contract Documents and the Contract fully performed, the Design Consultant shall issue a final Certification of Payment stating that to the best of their knowledge, information and belief, and on the basis of their observations and inspections, the Work has been completed in accordance with the terms and conditions of the Contract Documents. The final Certification of Payment will constitute that the conditions precedent to the Contractor's being entitled to final payment as set forth in Section 9.8 have been

fulfilled. Payment shall be made to the Contractor in the amount certified by the Design Consultant within forty-five (45) calendar days after receipt by the Owner of the final Certification of Payment except for any Work for which the Owner is entitled a credit under the Contract Documents.

9.9.1.1 The Contractor acknowledges that the Design Consultant and its consultants are only required to conduct up to two (2) comprehensive final completion inspections as part of its basic services. If more than two (2) final completion inspections are required through no fault of the Design Consultant, the cost of the additional inspections shall be paid by the Contractor directly to the Design Consultant at the rate of $150 per hour.

9.9.2 Neither the final payment nor the remaining retained percentage shall become due until the Work is free and clear of any and all liens and the Contractor submits to the Owner:

1. An affidavit that all payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or his property might in any way be responsible, have been paid or otherwise satisfied;

2. Consent of Surety to final payment;

3. If required by the Owner, other data establishing payment or satisfaction of all such obligations, such as receipts, releases and waivers of liens arising out of the Contract, to the extent and in such form as may be designated by the Owner; and

4. A written certification that:

    a. The Contractor has reviewed the requirements of the Contract Documents,

    b. The Work has been inspected by the Contractor for compliance with all requirements of the Contract Documents,

    c. Pursuant to this inspection, the Contractor certifies and represents that the Work complies in all respects with the requirements of the Contract Documents,

    d. The Contractor further certifies and represents that all equipment and systems have been installed in accordance with the Contract Documents and have been tested in accordance with the Specification requirements and are operational, and

    e. The Contractor hereby certifies and represents that the Work is complete in all respects and ready for final inspection.

9.9.3 If any Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify him against any loss. If any such lien or claim remains unsatisfied after all payments are made, the Contractor shall refund to the Owner all moneys that the latter may be compelled to pay in discharging such lien or claims, including all costs and reasonable attorney's fees. The Owner may withhold from the final payment any sum that the Owner has reason to believe may be needed to satisfy any lien, claim or threat of lien arising from the Work. The Owner may deduct from the final payment an amount equal to any costs, expenses and attorney's fees incurred by the Owner in removing or discharging any liens or claim arising from the Work.

9.9.4 If, after Substantial Completion of the Work, Final Completion thereof is materially delayed through no fault of the Contractor or by the issuance of Change Orders affecting Final Completion, and the Owner so confirms, the Owner shall, upon application by the Contractor and certification by the Design Consultant, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance for the portion of the Work not fully completed or corrected is less than the retainage stipulated in the Contract Documents, and if bonds have been furnished as provided in Section 7.4, the written consent of the Surety to the payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Design Consultant prior to certification of such payment. Such payment shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

9.9.5 The making of final payment shall constitute a waiver of all Claims by the Owner against the Contractor except those arising from:

1. Unsettled liens, and claims against the Owner or the Design Consultant, or their employees, agents, or representatives;

2. Faulty, defective or non-conforming Work;

3. Failure of the Work to comply with the requirements of the Contract Documents;

4. Terms of any warranties contained in or required by the Contract Documents;

5. Damages incurred by the Owner resulting from lawsuits brought against the Owner, the Design Consultant, or their agents, employees or representatives because of failures or actions on the part of the Contractor, his Subcontractors, Sub-subcontractors, or any of their employees, agents or representatives;

6. Fraud or bad faith committed by the Contractor or any Subcontractor or supplier during performance of the Work but discovered by Owner after final payment; or

7. Claims about which Owner did not have actual knowledge or which increase in scope or amount at the time of final payment.

9.9.6 The acceptance of final payment shall constitute a waiver of all Claims by the Contractor except those previously made in writing and identified by the Contractor as unsettled at the time of the final Application for Payment.

9.9.6.1 Notwithstanding any other provision of the Contract, Owner may withhold from Contractor payment otherwise due, as a result of any losses, expenses costs or damages suffered or anticipated to be suffered by Owner as a result of Contractor’s breach of any provision of the Contract, including but not limited to Liquidated Damages or backcharges against Contractor.

9.10 OWNER'S RIGHT TOOCCUPY INCOMPLETE WORK

9.10.1 Should the Project, or any portion thereof, be incomplete for Substantial or Final Completion at the scheduled date or dates, the Owner shall have the right to occupy any portion of the Project. In such an event, the Contractor shall not be entitled to any extra compensation on account of said occupancy by the Owner or by the Owner's use of the Project, nor shall the Contractor interfere in any way with said use of the Project. Further, in such an event, the Contractor shall not be entitled to any extra compensation on account of the Owner's occupancy and use of the

Project, nor shall the Contractor be relieved of any responsibilities of the Contract including the required times of completion. Such occupancy by the Owner shall not, in itself, constitute Substantial or Final Completion.

9.10.2 If the Owner exercises his rights under the foregoing and occupies the full Project, then there shall be no Liquidated Damages on account of failure on the Contractor's part to reach Substantial Completion from that date forward. This provision does not affect, however, any Liquidated Damages that would be assessed for any period of time between the contractual date of Substantial Completion and the date of any such occupancy. Further, this provision would have no effect on Liquidated Damages assessed on account of late Final Completion.

ARTICLE 10

PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

10.1.1 The Owner, the Design Consultant, or their agents, employees or representatives are not responsible for the means, methods, techniques, sequences or procedures utilized by the Contractor, or for safety precautions and programs in connection with the Work. The Contractor shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. The Contractor shall be responsible for any and all citations, assessments, fines penalties and delays in the performance of any work on the project incurred by reason of failure or failure on the part of its agents, employees, assignees or subcontractors to so comply with any program requirement. This requirement applies continuously throughout the Contract performance, until final payment is made and all punch list and warranty work is performed properly, and is not limited to regular working hours.

10.2 SAFETY OF PERSONS AND PROPERTY

10.2.1 The Contractor shall take all reasonable precautions for the safety of, and shall provide all reasonable protection to prevent damage, injury or loss to:

1. All employees on the Work and all other persons who may be affected thereby;

2. All the Work and all materials and equipment to be incorporated therein, whether in storage on or off the site, under the care, custody or control of the Contractor or any of his Subcontractors or Sub-subcontractors, machinery, equipment and all hazards shall be guarded or eliminated in accordance with all applicable safety regulations; and

3. Other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures and overhead or underground utilities not designated for removal, relocation or replacement in the course of construction.

10.2.2 The Contractor shall give all notices and comply with all applicable laws, ordinances, permits, rules, regulations and lawful orders of any public authority bearing on the safety or persons or property or their protection from damage, injury or loss.

10.2.2.1 The Contractor shall at all times safely guard the Owner's property from injury or losses in connection with the Contract. He shall at all times safely guard and protect his own work and adjacent property as provided by law and the Contract Documents, from damage. All passageways, guard fences, lights and other facilities required for protection by applicable safety

regulations must be provided and maintained.

10.2.3 The Contractor shall erect and maintain, as required by existing conditions and progress of the Work, all reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards, promulgating safety regulations and notifying owners and users of adjacent utilities.

10.2.4 When the use or storage of explosives or other hazardous materials or equipment is necessary for the execution of the Work, the Contractor shall exercise the utmost care and shall carry on such activities under the supervision of properly qualified personnel, after ensuring proper approvals by any regulatory agency having jurisdiction have been received.

10.2.5 The Contractor shall promptly remedy at his own cost and expense all damage or loss to any property referred to in Subparagraphs 10.2.1.2 and 10.2.1.3 caused by the Contractor, any Subcontractor, any Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable and for which the Contractor is responsible under Subparagraphs 10.2.1.2 and 10.2.1.3, except damage or loss attributable solely to the acts or omissions of the Owner or Design Consultant or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to his obligations under Section 4.21. The Contractor shall perform such restoration by underpinning, repairing, rebuilding, replanting, or otherwise restoring as may be required or directed by the Owner, or shall make good such damage in a satisfactory and acceptable manner. In case of failure on the part of the Contractor to promptly restore such property or make good such damage, the Owner may, upon two (2) calendar days Notice, proceed to repair, rebuild or otherwise restore such property as may be necessary and the cost thereof, or a sum sufficient in the judgment of the Owner to reimburse the owners of property so damaged, will be deducted from any monies due or to become due the Contractor under the Contract.

10.2.6 The Contractor is responsible for the proper packing, shipping, handling and storage (including but not limited to shipment or storage at the proper temperature and humidity) of materials to be incorporated in the Work, so as to insure the preservation of the quality and fitness of the material for proper installation and incorporation in the Work, as required by the Contract Documents. For example, but not by way of limitation, Contractor shall, when necessary, place material on wooden platforms or other hard and clean surfaces and not on the ground and/or place such material under cover in any appropriate shelter or facility. Stored materials or equipment shall be located so as to facilitate proper inspection. Material and equipment which is delivered crated shall remain crated until ready for installation. Lawns, grass plots or other private property shall not be used for storage purposes without the written permission of the Owner or lessee unless otherwise within the terms of the easements obtained by the Owner.

10.2.6.1 It shall be the responsibility of the Contractor in his preparation of phasing schedule of work operations after consulting with the other Prime Contractors to designate areas in which each Prime Contractor may store materials. Areas designed shall meet with the approval of the Design Consultant.

10.2.7 The Contractor shall give notice in writing at least forty eight (48) hours before breaking ground, to all persons, public utility companies, owners of property having structures or improvements in proximity to site of the Work, superintendents, inspectors, or those otherwise in charge of property, streets, water pipes, gas pipes, sewer pipes, telephone cables, electric cables, railroads or otherwise, who may be affected by the Contractor's operation, in order that they may remove

any obstruction for which they are responsible and have representative on site to see that their property is properly protected. Such notice does not relieve the Contractor of responsibility for all damages, claims, or defense or indemnification of all actions against Owner resulting from performance of such work in connection with or arising out of Contract.

10.2.8 The Contractor shall investigate, locate, mark and protect all utilities encountered or to be encountered while performing the Work, whether indicated on the Drawings or not. The Contractor shall maintain utilities in service until moved or abandoned. The Contractor shall exercise due care when excavating around utilities and shall restore any damaged utilities to the same condition or better as existed prior to starting the Work, at no cost to the Owner. The Contractor shall maintain operating utilities or other services, even if they are shown to be abandoned on the Contract Drawings, in service until new facilities are provided, tested and ready for use.

10.2.9 The Contractor shall return all improvements on or about the site and adjacent property which are not shown to be altered, removed or otherwise changed to conditions which existed prior to starting the Work. The Contractor shall video record all areas or otherwise document the conditions existing at the site and in and around existing buildings prior to starting the Work. Submit documentation to the Design Consultant prior to beginning the Work.

10.2.10 The Contractor shall protect the Work, including but not limited to, the site, stored materials and equipment, excavations, and excavated or stockpiled soil or other material, intended for use in the Work, and shall take all necessary precautions to prevent or minimize damage to same or detrimental effect upon his performance or that of his Subcontractors, caused by or due to rain, snow, ice, run-off, floods, temperature, wind, dust, sand and flying debris; for example, but not by way of limitation, Contractor shall, when necessary, utilize temporary dikes, channels or pumping to carry-off divert or drain water, and shall as necessary tie-down or otherwise secure the Work and employ appropriate covers and screens.

10.2.11 The Contractor shall designate a responsible member of his organization at the site whose duty shall be the prevention of accidents and the protection of material, equipment and property. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner.

10.2.12 The Contractor shall not load or permit any part of the Work to be loaded so as to endanger its safety.

10.2.13 Notification to the Contractor by the Owner or the Design Consultant of a safety violation will in no way relieve the Contractor of sole and complete responsibility for the correctness of said violation or of sole liability for the consequences of said violation.

10.2.14 Contractor acknowledges that if he will be performing the work on an actively operative, elementary or secondary school site, that a construction site might be an 'attractive nuisance' which might draw children to said site and contractor agrees that it will take reasonable precautions necessary to prevent children from entering the construction site or an area where materials are stored.

10.3 EMERGENCIES

10.3.1 In any emergency affecting the safety of persons or property, the Contractor shall act, at his discretion, to prevent threatened damage, injury or loss. The Contractor shall notify the Owner of the situation and all actions taken immediately thereafter. If, in the opinion of the Contractor,

immediate action is not required, the Contractor shall notify the Owner of the emergency situation and proceed in accordance with the Owner's instructions. Provided, however, if any loss, damage, injury or death occurs that could have been prevented by the Contractor's prompt and immediate action, the Contractor shall be fully liable for all costs, damages, claims, actions, suits, attorney's fees and all other expenses arising therefrom or relating thereto.

ARTICLE 11

INSURANCE

11.1 CONTRACTOR'S LIABILITY INSURANCE

11.1.1 The Contractor shall purchase and maintain in companies properly licensed by the Insurance Department of the State of North Carolina and acceptable to the Owner such insurance as will protect him, the Owner, and the Owner's agents, representatives, and employees from claims set forth below which may arise out of or result from the Contractor's operations under the Contract, whether such operations be by himself or by any Subcontractor or by anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable:

.1 Claims under workers' or workmen's compensation, disability benefit and other similar employee benefit acts (with Workmen's Compensation and Employer's Liability Insurance in amounts not less than those necessary to meet the statutory requirements of the state(s) having jurisdiction over any portion of the Work);

.2 Claims for damages because of bodily injury, sickness or disease, or death of his employees; the Contractor will require his Subcontractors to similarly provide Workmen's Compensation Insurance for all of the latter's employees;

.3 Claims for damages because of bodily injury, sickness or disease, or death of any person other than his employees;

.4 Claims for damages insured by usual personal injury liability coverage which are sustained (1) by any person as a result of an offense directly or indirectly related to the employment of such person by the Contractor, or (2) by any other person;

.5 Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property, including loss of use resulting therefrom; and

.6 Claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle.

11.1.2 The insurance required by Paragraph 11.1.1 shall be primary and non-contributing to any insurance possessed or procured by the Owner, and limits of liability shall be not less than those set forth in these General Conditions of the Contract or required by law, whichever is greater.

11.1.3 The insurance required by the Contract shall include contractual liability insurance applicable to the Contractor's obligations under the Contract

11.1.4 Without limiting the above during the term of the Contract, the Contractor and each Subcontractor shall, at their own expense, purchase and maintain the following insurance with companies properly licensed by the Insurance Department of the State of North Carolina and satisfactory to the Owner.

1. Worker's Compensation including Occupational Disease and Employer's Liability Insurance.

   a. Statutory - Amount and coverage as required by State of North Carolina Worker's Compensation laws.

   b. Employer's Liability
   $1,000,000 Each Accident
   $1,000,000 Policy Limit
   $1,000,000 Each Employee

2. Commercial General Liability (Occurrence Form) - The Contractor shall provide during the life of the Contract such Commercial General Liability (Occurrence Form) Insurance as shall protect him and any Subcontractor performing work under the Contract from claims for damages for Bodily Injury including accidental death, as well as from claims for Property Damage which may arise from operations under the Contract, whether such operations be by himself or by any Subcontractor or by anyone directly or indirectly employed by either of them. This insurance shall be on the Standard Insurance Services Office, Inc. (ISO) Commercial Liability Occurrence Form or other form reasonable acceptable to Owner. The Contractor shall procure insurance coverage for direct operations, sublet work, elevators, contractual liability and completed operations with limits not less than those stated below:

   a. A Combined Single Limit for Bodily Injury, Property Damage and Personal Injury of:
   Limits of Insurance
   $2,000,000 General Aggregate (except Products – Completed Operations) Limit
   $2,000,000 Products – Completed Operations Aggregate Limit
   $1,000,000 Personal and Advertising Injury Limit
   $1,000,000 Each Occurrence Limit

3. Property Damages, including Broad Form Property Damage and Explosion, Collapse, Underground property damage coverages, and blasting, where necessary;

4. Completed Operations Liability: Continuous coverage in force for one year after completion of the Work;

5. Commercial Automobile Insurance, including coverage for owned, non-owned and hired vehicles - with limits not less than those stated below:

   a. A Combined Single Limit for Bodily Injury
   and Property Damage of $1,000,000.

6. Umbrella Liability Insurance: Policy to "pay on behalf of the Insured"
   Limits of Liability:

   a. Contract Amount: $1,000,000-$2,000,000:
   Requires Umbrella Liability Insurance Limit of $1,000,000.

   b. Contract Amount: $2,000,000 and above:
   Requires Umbrella Liability Insurance Limit of $2,000,000.

11.1.5 The insurance required by Section 11.1 shall be written for not less than any limits of liability specified in the Contract Documents, or required by law, whichever is greater.

11.1.6 Certificates of Insurance acceptable to the Owner shall be filed with the Owner prior to commencement of the Work. These Certificates shall contain a provision that coverages afforded under the policies will not be canceled until at least thirty (30) days' prior written Notice has been given to the Owner. Failure to provide such Notice shall not limit the liability of the Insurer, its agents or representatives.

11.1.7 All insurance policies required in this Article, except Worker's Compensation and Commercial Automobile, shall name the Owner as additional named insured for the insurance.

11.1.8 The Contractor shall not commence the Work under the Contract until he has obtained all the insurance required hereunder and such insurance has been approved by the Owner, nor shall the Contractor allow any Subcontractor to commence work on his subcontract until all similar insurance required of the Subcontractor has been so obtained and approved. Approval of the insurance by the Owner shall not relieve or decrease the liability of the Contractor hereunder.

11.1.9 The Commercial General Liability and Workers Compensation Policies provided by the Contractor shall have endorsements waiving subrogation against the Owner.

11.2 PROPERTY INSURANCE

11.2.1 The Contractor shall purchase and at all times maintain such insurance as will protect the Contractor, the Owner, Subcontractors and Sub-subcontractors from loss or damage to the Work or property in the course of construction, including all machinery, materials and supplies on the premises or in transit thereto and intended to become a part of the finished Work until Final Completion. This insurance shall be in the form of "Builders Risk Covered Cause of Loss Form", or equivalent form, to include but not limited to theft, collapse, earth movement, flood, and portions of the Work stored on site, off site and in transit. Any deductible provision in such insurance shall not exceed ten thousand dollars ($10,000). Notwithstanding any such deductible provision, the Contractor shall remain solely liable for the full amount of any item covered by such insurance. Such insurance shall be in the initial Contract Sum and shall be increased at Contractor's expense in the amount of all additions to the Contract Sum. Such insurance shall include interests of the Owner, the Contractor, Subcontractors and Sub-subcontractors in the Project.

11.2.2 Any loss insured under Paragraph 11.2.1 is to be adjusted with the Owner and made payable to the Owner as trustee for the insureds, as their interests may appear, subject to the requirements of Paragraph 11.2.4. The Contractor shall pay each Subcontractor a just share of any insurance moneys received by the Contractor, and by appropriate agreement, written where legally required for validity, shall require each Subcontractor to make payments to his Sub-subcontractors in similar manner.

11.2.3 The Owner and Contractor waive all rights against each other for damages caused by fire or other perils to the extent their Claims are covered by insurance obtained pursuant to this Section 11.2, or any other property insurance applicable to the Work, except such rights as they may have to the proceeds of such insurance. The Contractor shall require, by appropriate agreement, written where legally required for validity, similar waivers in favor of the Owner and the Contractor by Subcontractors and Sub-subcontractors. With respect to the waiver of rights of recovery, the term Owner shall be deemed to include, to the extent covered by property insurance applicable thereto, his consultants, employees, and agents and representatives. The

Contractor waives as against any Separate Contractor described in Article 6, all rights for damages caused by fire or other perils in the same manner as is provided above as against the Owner. The Owner shall require, by appropriate agreement, written where legally required for validity, similar waivers in favor of the Contractor by any Separate Contractor and his subcontractors and sub-subcontractors.

11.2.4 The Owner as trustee shall have power to adjust and settle any loss with the insurers unless one of the parties in interest shall object in writing within five (5) days after the occurrence of loss to the Owner's exercise of this power, and if such objection is made, the matter shall be decided by a court of competent jurisdiction or as the parties in interest otherwise agree. The Owner as trustee shall, in that case, make settlement with the insurers in accordance with the orders of the court or as otherwise agreed by the parties in interest.

11.2.5 If the Owner finds it necessary to occupy or use a portion or portions of the Work prior to Substantial Completion thereof, such occupancy or use shall not commence prior to a time mutually agreed to by the Owner and Contractor and to which the insurance company or companies providing the property insurance have consented by endorsement to the policy or policies. This insurance shall not be canceled or lapsed on account of such partial occupancy or use. Consent of the Contractor and of the insurance company or companies to such occupancy or use shall not be unreasonably withheld.

11.2.6 The Contractor bears the risk of loss or damage to the Work, the Project, materials stored on site or off site, and Owner’s improvements and property under Contractor’s control, both during construction and prior to Substantial Completion.

11.3 EFFECT OF SUBMISSION OF CERTIFICATES

11.3.1 The Owner shall be under no obligation to review any Certificates of Insurance provided by the Contractor or to check or verify the Contractor's compliance with any and all requirements regarding insurance imposed by the Contract Documents. The Contractor is fully liable for the amounts and types of insurance required herein and is not excused should any policy or certificate of insurance provided by the Contractor not comply with any and all requirements regarding insurance imposed by the Contract Documents.

11.4 FAILURE OF COMPLIANCE

11.4.1 Should the Contractor fail to provide and maintain in force any and all insurance, or insurance coverage required by the Contract Documents or by law, or should a dispute arise between Owner and any insurance company of Contractor over policy coverage or limits of liability as required herein, the Owner shall be entitled to recover from the Contractor all amounts payable, as a matter of law, to Owner or any other parties, had the required insurance or insurance coverage been in force. Said recovery shall include, but is not limited to interest for the loss of use of such amounts of money, plus all attorney's fees, costs and expenses incurred in securing such determination and any other consequential damages arising out of the failure of the Contractor or insurance company to comply with the provisions of the Contract Documents, or any policy required hereby, or any other requirements regarding insurance imposed by law. Nothing herein shall limit any damages for which Contractor is responsible as a matter of law.

11.5 OWNER'S INSURANCE

11.5.1 Property Insurance: The Owner, at his option, may purchase and maintain such insurance as will insure him against loss of use of his property due to fire or other hazards, however caused.

11.5.2 Commercial Public Liability Insurance: The Owner, at his option, may purchase and maintain insurance which will insure and protect him against claims involving bodily injury and property damage to the public. The Owner does not request his insurer to waive any right of subrogation against the Contractor from claims under this coverage.

11.6 LICENSED INSURANCE COMPANIES

11.6.1 All insurance companies providing the above insurance shall be licensed by the Insurance Department of the State of North Carolina and have a minimum AM Best "A" rating or similar rating from another rating agency reasonably acceptable to Owner.

ARTICLE 12

CHANGES IN THE WORK

12.1 GENERAL PROVISIONS RELATED TO CHANGES

12.1.1 A Construction Change Directive is a document issued pursuant to this Paragraph 12.1.1. The Owner may, at any time, without the agreement of the Contractor, by written order signed by the Owner and Design Consultant designated or indicated to be a Construction Change Directive, make any Changes in the Work or add to or subtract from the Work within the general scope of the Contract. A Change in the Work is defined as changes within the general scope of the Contract, including, but not limited to changes:

1. In the Specifications or Drawings;

2. In the sequence, method or manner of performance of the Work;

3. In the Owner-furnished facilities, equipment, materials, services or site; or

4. Directing acceleration in the performance of the Work.

12.1.2 A Change Order is a document executed pursuant to this Paragraph 12.1.2. The Owner and Contractor may agree to Changes in the Work, the Contract Sum, the Contract Time and any other change in the Contract by written agreement signed by Owner, Contractor and Design Consultant designated or indicated to be a Change Order. If the Contractor, subsequent to the issuance of a Construction Change Directive, agrees to its terms including any applicable adjustment to the Contract Sum and Contract Time, Contractor shall sign it and it shall become a Change Order.

12.1.3 The Contractor shall not be entitled to any amount for indirect costs, damages or expenses of any nature, including, but not limited to, so-called "impact" costs, labor inefficiency, wage, material or other escalations beyond the prices upon which the Proposal is based and to which the parties have agreed pursuant to the provisions of Article 12, and which the Contractor, its Subcontractors or Sub-subcontractors or any other person may incur as a result of delays, interferences, suspensions, changes in sequence or the like, for whatever cause, whether reasonable or unreasonable, foreseeable or unforeseeable, or avoidable or unavoidable, arising from the performance of any and all Changes in the Work performed pursuant to this Article 12, unless the delay is caused solely by the Owner or its agent. It is understood and agreed that the Contractor's sole and exclusive remedy in the event the delay is caused solely by the Owner or its agent shall be recovery of his direct costs as compensable hereunder and an extension of the

Contract Time, but only in accordance with the provisions of the Contract Documents. The phrase "Owner or its agent" as used in the Contract, does not include the Prime Contractors or their Subcontractors.

12.1.4 No Claim by the Contractor shall be allowed if asserted after final payment under this Contract. No Claim relating to or flowing from a particular change shall be allowed after execution of the Change Order relating to that change or commencement of the change by the Contractor except as specifically provided in Paragraph 12.2.4.

12.1.5 If any dispute should arise between the parties with respect to an increase or decrease in the Contract Sum or an expansion or contraction in the Contract Time as a result of a Change in the Work, the Contractor shall not suspend performance of a Change in the Work or the Work itself unless otherwise so ordered by the Owner in writing. The Owner shall, however, pay to the Contractor up to the Owner's reasonable estimated value of the Change in the Work, regardless of the dispute, if said Change in the Work will result in an increase in the Contract Sum; and the Owner shall have the right to withhold payment from the Contractor in an amount up to the Owner's reasonable estimated value of the Change in the Work, regardless of the dispute, if said Change in the Work will result in a decrease in the Contract Sum.

12.1.6 No Change in the Work shall be performed without a fully executed Change Order to the Contract a fully executed Construction Change Directive or other Modification to the Contract.

12.1.7 If the Contractor intends to assert a Claim under this Article, he must, within ten (10) days after receipt of a Construction Change Directive, Notify the Owner by written statement setting forth the specific nature and cost of such Claim, unless this period is extended by the Owner. The statement of Claim shall include all direct, indirect and impact costs associated with the change, as well as the Contractor's estimate of the schedule impact of the change, if any. The Contractor and its Subcontractors shall not be entitled to reimbursement for any Claims that are not submitted in strict conformance with the Contract. The Contractor shall indemnify and hold the Owner harmless against any Claims by Subcontractors that are waived because they are not submitted in strict conformance with the Contract.

12.2 OWNER DIRECTED CHANGES REQUIRING AN INCREASE IN CONTRACT SUM. (For decreases in Contract Sum, refer to Section 12.6)

12.2.1 If the Change in the Work will result in an increase in the Contract Sum, the Owner shall have the right to require the performance thereof on a lump sum basis, a unit price basis or a time and material basis, all as hereinafter more particularly described (the right of the Owner as aforesaid shall apply with respect to each such Change in the Work).

If the Owner elects to have the Change in the Work performed on a lump sum basis, its election shall be based on a lump sum Proposal which shall be submitted by the Contractor to the Owner within ten (10) days of the Contractor's receipt of a request therefore (but the Owner's request for a lump sum Proposal shall not be deemed an election by the Owner to have the Change in the Work performed on a lump sum basis). The Contractor's Proposal shall be itemized and segregated by labor and materials for the various components of the Change in the Work (no aggregate labor total will be acceptable) and shall be accompanied by signed Proposals of any Subcontractors who will perform any portion of the Change in the Work and of any persons who will furnish materials or equipment for incorporation therein. The Proposal shall also include the Contractor's estimate of the time required to perform said changes. The Contractor shall provide any documentation that may be requested by the Owner or Design Consultant to support the change proposal, including but not limited to payroll records, insurance rates, material

quotes, and rental quotes.

The portion of the Proposal relating to labor, whether by the Contractor's forces or the forces of any of its Subcontractors, may include reasonably anticipated gross wages of job site labor, including foremen, who will be directly involved in the Change in the Work (for such time as they will be so involved), plus payroll costs (including premium costs of overtime time, if overtime is anticipated, Social Security, Federal or State unemployment insurance taxes and fringe benefits required by collective bargaining agreements entered into by the Contractor or any such Subcontractor in connection with such labor) and up to fifteen percent (15%) of such anticipated gross wages, but not payroll costs, as overhead and profit for the Contractor or any such Subcontractor, as applicable (said overhead and profit to include all supervision except foremen). Payroll costs are limited to 39% of the net pay of the worker.

The portion of the Proposal relating to materials may include the reasonably anticipated direct costs to the Contractor or to any of its Subcontractors of materials to be purchased for incorporation in the Change in the Work, plus transportation and applicable sales and use taxes and up to fifteen percent (15%) of said direct material costs as overhead and profit for the Contractor or any such Subcontractor (said overhead and profit to include all small tools), and may further include the Contractor's and any of its Subcontractor's reasonably anticipated rental costs in connection with the Change in the Work (either actual or discounted local published rates), plus up to eight percent (8%) thereof as overhead and profit for the Contractor or any such Subcontractors, as applicable. The Contractor shall provide an itemized breakdown of all transportation and shipping costs, including receipts documenting the expenses. Notwithstanding the above, overhead and profit shall not be applied to any sales tax paid for any purpose or to any transportation or shipping costs incurred by the Contractor or any subcontractor. If any of the items included in the lump sum Proposal are covered by unit prices contained in the Contract Documents, the Owner may, if it requires the Change in the Work to be performed on a lump sum basis, elect to use these unit prices in lieu of the similar items included in the lump sum Proposal, in which event an appropriate deduction will be made in the lump sum amount prior to the application of any allowed overhead and profit percentages. No overhead and profit shall be applied to any unit prices.

The lump sum Proposal may include up to eight percent (8%) of the amount which the Contractor will pay to any of its Subcontractors for Changes in the Work as overhead and profit for the Contractor. The Contractor shall not be reimbursed for the costs of the Subcontractors' Payment and Performance Bonds, as such bonding is not required by the Owner.

12.2.2 In the event that the Contractor fails to submit his Proposal within the designated period, the Owner may order the Contractor to proceed with the Change to the Work and the Contractor shall so proceed. The Owner shall unilaterally determine the reasonable cost and time to perform the Work in question, which determination shall be final and binding upon the Contractor. The Contractor may dispute such action in accordance with the Article 15.

12.2.3 In the event that the parties are unable to agree as to the reasonable cost and time to perform the Change in the Work based upon the Contractor's Proposal and the Owner does not elect to have the Change in the Work performed on a time and material basis, the Owner may choose to make a determination of the reasonable cost and time to perform the Change in the Work, based upon its own estimates, the Contractor's submission or a combination thereof. A Construction Change Directive shall be issued in this case for the amounts of cost and time determined by the Owner and shall become final and binding upon the Contractor, subject to Contractor's right to dispute such action in accordance with Article 15. Owner has the right to direct by Construction Change Directive a Change in the Work, which is the subject of such Change Order. Failure of the

parties to reach agreement regarding the cost and time of the performing the Construction Change Directive, shall not relieve the Contractor from performing the Change in the Work promptly and expeditiously.

12.2.3.1 The Owner reserves the right to reject the Contractor's Proposal for a Change in the Work and to elect to perform said Work using a Separate Contractor. Under such circumstances, all provisions of Article 6 shall be in force.

12.2.4 If the Owner elects to have the Change in the Work performed on a time and material basis, the same shall be performed, whether by the Contractor's forces or the forces of any of its Subcontractors or Sub-subcontractors, at actual cost to the entity performing the Change in the Work (without any charge for administration, clerical expense, supervision or superintendence of any nature whatsoever, including foremen, or the cost, use or rental of tools or plant), plus fifteen percent (15%) thereof as the total overhead and profit (except that said fifteen percent (15%) shall not be applied against any payroll costs, as set forth in Paragraph 12.2.1.) The Contractor shall submit to the Owner daily time and material tickets, on a daily basis to include the identification number assigned to the Change in the Work, the location and description of the Change in the Work, the classification of labor employed (and names and social security numbers), the materials used, the equipment rented (not tools) and such other evidence of cost as the Owner may require. The Owner may require authentication of all time and material tickets and invoices by persons designated by the Owner for such purpose. The failure of the Contractor to secure any required authentication shall, if the Owner elects to treat it as such, constitute a waiver by the Contractor of any Claim for the cost of that portion of the Change in the Work covered by a non-authenticated ticket or invoice; provided, however, that the authentication of any such ticket or invoice by the Owner shall not constitute an acknowledgment by the Owner that the items thereon were reasonably required for the Change in the Work.

12.2.5 No overhead and profit will be paid by the Owner on account of a Change in the Work except as specifically provided in Section 12.2. Overhead and profit, as allowed under Section 12.2, shall be deemed to include all costs and expenses which the Contractor or any of its Subcontractors may incur in the performance of a Change in the Work and which are not otherwise specifically recoverable by them pursuant to Section 12.2.

12.3 CONTRACTOR NOTICE OF CHANGE

12.3.1 If the Contractor or any of its Subcontractors asserts that any event or occurrence has caused a Change in the Work which change causes an increase or decrease in the Contractor's or its Subcontractors cost or the time required for the performance of any part of the Work under the Contract, including Work not affected directly by the change, the Contractor shall, within ten (10) days of such event, give the Owner written Notice as herein required. Said Notice shall include the instructions or circumstances that are the basis of the Claim and the Contractor's best estimate of the cost and time involved.

12.4 MINOR CHANGES IN THE WORK

12.4.1 The Owner shall have authority to order minor Changes in the Work not involving an adjustment in the Contract Sum or an extension of the Contract Time and not inconsistent with the intent of the Contract Documents. Such changes shall be effected by written order, and shall be binding on the Owner and the Contractor. The Contractor shall carry out such written orders promptly.

12.4.2 The Contractor shall not perform any Changes in the Work unless authorized in writing by the Design Consultant or Owner.

12.5 DIFFERING SITE CONDITIONS

12.5.1 Should the Contractor encounter subsurface and/or latent conditions at the site materially differing from those shown on the Drawings or indicated in the Specifications or differing materially from those ordinarily encountered and generally recognized as inherent in work of the character provided for in this Contract, or different from that shown on surveys or tests provided in the bid materials at the time the Owner solicited bids from the construction of the Project, he shall immediately give Notice to the Owner of such conditions before they are disturbed. The Owner and the Design Consultant shall thereupon promptly investigate the conditions and if they find that they materially differ from those shown on the Drawings or indicated in the Specifications, they shall at once make such changes in the Drawings and/or Specifications as they may find necessary. Any increase or decrease of cost resulting from such changes shall be adjusted in the manner provided herein for adjustments as to extra and/or additional work and changes. However, neither the Owner nor the Design Consultant shall be liable or responsible for additional work, costs or Changes to the Work due to material differences between actual conditions and any geotechnical, soils and other reports, surveys and analyses made available for the Contractor's review at the time the Owner solicited bids for the construction of the Project.

12.6 OWNER DIRECTED CHANGES REQUIRING A DECREASE IN CONTRACT SUM.

12.6.1 If the Change in the Work will result in a decrease in the Contract Sum, the Owner may request a quotation by the Contractor of the amount of such decrease. The following provisions shall apply:

The portion of the Proposal relating to labor, whether by the Contractor's forces or the forces of any of its Subcontractors, shall include reasonably anticipated gross wages of job site labor, including foremen, who would have been directly involved in the Work that has been deleted from the Contract, (for such time as they would have been so involved), plus payroll costs (including premium costs of overtime time, if overtime was anticipated, Social Security, Federal or State unemployment insurance taxes and fringe benefits required by collective bargaining agreements entered into by the Contractor or any such Subcontractor in connection with such labor) and seven percent (7%) of such anticipated gross wages, but not payroll costs, as overhead and profit not incurred or earned by the Contractor or any such Subcontractor, as applicable (said overhead and profit to include all supervision except foremen).

The portion of the Proposal relating to materials shall include the reasonably anticipated direct costs which would have been incurred by the Contractor or to any of its Subcontractors of materials which would have been purchased for incorporation in the Work but which has been deleted from the Contract, plus transportation and applicable sales and use taxes which will be avoided and seven percent (7%) of said direct material costs as overhead and profit not incurred or earned by the Contractor or any such Subcontractor (said overhead and profit to include all small tools), and shall further include the Contractor's and any of its Subcontractor's reasonably anticipated rental costs which will be avoided (either actual or discounted local published rates), plus five percent (5%) thereof as overhead and profit not incurred or earned by the Contractor or any such Subcontractors, as applicable. If any of the items included in the lump sum Proposal are covered by unit prices contained in the Contract Documents, the Owner may elect to use these unit prices in determining the amount of reduction to the Contract Sum as a result of a deletion of Work from the Contract. No overhead and profit shall be applied to any unit prices for purposes of calculation such reduction in the Contract Sum.

The lump sum Proposal for Work which would have been performed by any Subcontractors shall include four percent (4%) of that amount as an estimate of the Contractor's overhead and profit that will not be earned by Contractor due to the decrease in the Contract Sum.

The Contractor's quotation shall be forwarded to the Owner within ten (10) days of the Owner's request and, if acceptable to the Owner, shall be incorporated in the Change Order. If not acceptable, the parties shall make every reasonable effort to agree as to the amount of such decrease, which may be based on a lump sum properly itemized, on unit prices stated in the Contract Documents and/or on such other basis as the parties may mutually determine. If the parties are unable to so agree, the amount of such decrease shall be the total of the estimated reduction in actual cost of the Work, as determined by the Owner in its reasonable judgment, plus overhead and profits stated above. This shall become final and binding upon the Contractor, subject to Contractor's right to dispute such action in accordance with the Article 15.

ARTICLE 13

UNCOVERING AND CORRECTION OF WORK

13.1 UNCOVERING OF WORK

13.1.1 If any portion of the Work is covered contrary to the request of the Owner or the Design Consultant or to requirements specifically expressed in the Contract Documents or to requirements of applicable construction permits, it must, if required in writing by the Owner, be uncovered for his observation and shall be replaced at the Contractor's expense.

13.1.2 If any other portion of the Work has been covered which the Design Consultant or the Owner has not specifically requested to observe prior to being covered, either may request to see such portion of the Work and it shall be uncovered by the Contractor. If such Work be found in accordance with the Contract Documents, the cost of uncovering and replacement shall, by appropriate Change Order, be charged to the Owner. If such Work be found not in accordance with the Contract Documents, the Contractor shall pay such costs unless it is found that this condition was caused by the Owner, in which event the Owner shall be responsible for the payment of such costs. If such condition was caused by a Separate Contractor, Contractor may proceed against and only against, said Separate Contractor as provided in Article 6. Any costs to the Owner pursuant to this Paragraph shall be determined in accordance with the provisions of Article 12.

13.2 CORRECTION OF WORK

13.2.1 The Contractor shall promptly reconstruct, replace or correct portions of the Work rejected by the Design Consultant or Owner as defective or as failing to conform to the Contract Documents or as not in accordance with the guarantees and warranties specified in the Contract Documents whether observed before or after Substantial Completion and whether or not fabricated, installed or completed. The Contractor shall bear all costs of correcting such rejected portions of the Work, including compensation for the Design Consultant's and the Owner's additional construction management services made necessary thereby.

13.2.2 The Contractor, unless removal is waived by the Owner, shall remove from the site all portions of the Work which are defective or non-conforming, or if permitted or required, he shall correct such portions of the Work in place at his own expense promptly after receipt of Notice, and such rejected Work shall not thereafter be tendered for acceptance unless the former rejection or requirement for correction is disclosed.

13.2.3 If the Contractor does not proceed with the correction of such defective or non-conforming portions of the Work within a reasonable time fixed by written Notice from the Owner or Design Consultant, the Owner may either (1) by separate contract or otherwise replace or correct such portions of the Work and charge the Contractor the cost incurred by the Owner thereby and remove and store the materials or equipment at the expense of the Contractor, or (2) terminate this Contract for default as provided in Section 14.3, or both, or take any other measure allowed by law.

13.2.4 The Contractor shall bear the cost of making good all work of the Owner or Separate Contractors destroyed or damaged by such correction or removal.

13.2.5 Nothing contained in this Section 13.2 shall be construed to establish a period of limitation with respect to any other obligation which the Contractor might have under the Contract Documents, including Section 4.6 hereof. The establishment of the time period of one year after the date of Substantial Completion or such longer period of time as may be prescribed by law or by the terms of any warranty required by the Contract Documents relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which his obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to his obligations.

13.3 ACCEPTANCE OF DEFECTIVE OR NON-CONFORMING WORK

13.3.1 If the Owner prefers to accept defective or non-conforming Work, he may do so instead of requiring its removal and correction, in which case a Change Order will be issued to reflect a reduction in the Contract Sum where appropriate and equitable, or the Owner may elect to accept payment in materials or services, in lieu of a reduction in the Contract Sum. If the amount of a reduction is determined after final payment, it shall be paid to the Owner by the Contractor.

ARTICLE 14

TERMINATION OF THE CONTRACT

14.1 TERMINATION BY THE CONTRACTOR

14.1.1 If the Work is stopped for a period of one hundred twenty (120) days by the Owner or under an order of any court or other public authority having jurisdiction, or as a result of an act of government, such as a declaration of a national emergency making materials unavailable, and through no act or fault of the Contractor or a Subcontractor or their agents or employees or any other persons performing any of the Work under a contract with the Contractor, then the Contractor may, upon seven (7) additional days' written Notice to the Owner and the Design Consultant, terminate the Contract and recover from the Owner payment on a quantum merit basis, for all Work executed for which Contractor has not previously been paid, less any amounts Contractor may owe Owner under the Contract Documents and less any amounts Owner is entitled to withhold from Contractor or backcharge to the Contractor under the Contract Documents or pursuant to law. The Contractor shall not be entitled to collect and hereby expressly waives any overhead or profit on Work not performed and any damages related to that portion of the Contract which has been terminated.

14.2 TERMINATION FOR CONVENIENCE OF THE OWNER

14.2.1 The Owner may, at any time upon ten (10) days written Notice to the Contractor and to the Contractor's Surety, which Notice shall specify that portion of the Work to be terminated and the date said termination is to take effect, terminate (without prejudice to any right or remedy of the Owner) the whole or any portion of the Work for the convenience of the Owner. The Contractor's sole remedy, in the event of such termination, will be the allowable termination costs permitted by Section 14.4. Contractor shall include termination clauses identical to Article 14 in each of his subcontracts.

14.3 DEFAULT TERMINATION

14.3.1 Ten (10) days after written Notice is mailed to the Contractor and to the Contractor's Surety, the Owner may terminate (without prejudice to any right or remedy of the Owner or any subsequent buyer of any portion of the Work) the employment of the Contractor and his right to proceed either as to the whole or any portion of the Work required by the Contract Documents and may take possession of the Work and complete the Work by contract or otherwise in any one of the following circumstances:

1. If the Contractor or its Surety refuses or fails to prosecute the Work or any separable part thereof with such diligence as will ensure the Substantial and Final Completion of the Work by the dates specified in the Supplemental Conditions for Substantial and Final Completion or fails to complete the Work or remedy a default within said period;

2. If the Contractor is in material default in carrying out any provisions of the Contract;

3. If the Contractor fails to supply a sufficient number of properly skilled workers or proper equipment or materials;

4. If the Contractor fails to make prompt payment to Subcontractors or for materials or labor, unless he otherwise provides the Owner satisfactory evidence that payment is not legally due;

5. If the Contractor disregards laws, permits, ordinances, rules, regulations or orders of any public authority having jurisdiction, or fails to follow the instructions of the Owner;

6. If the Contractor substantially violates any provisions of the Contract Documents; or

7. If the Contractor refuses or fails to properly schedule, plan, coordinate and execute the Work, as specified herein, so as to perform the Work within the specified Completion Dates, or to provide scheduling or related information, revisions and updates as required by the Contract Documents.

14.3.2 The right of the Contractor to proceed shall not be so terminated under this Section 14.3 if the delays in the completion of the Work are due to unforeseeable causes beyond the control and without the fault or negligence of the Contractor or his Subcontractors as specifically set forth in Section 8.3 hereof.

14.3.3 If, after the Contractor has been terminated for default pursuant to Section 14.3, it is determined that none of the circumstances set forth in Paragraph 14.3.1 exist, then such termination shall be considered a termination for convenience pursuant to Section 14.2. In such case, the Contractor's sole remedy will be the costs permitted by Section 14.4.

14.3.4 If the Owner so terminates the employment of the Contractor due to the Contractor’s default,

the Contractor shall not be entitled to receive any further payment until the Work is finished. If the unpaid balance of the compensation to be paid to the Contractor hereunder shall exceed the expense of so completing the Work (including compensation for additional managerial, administrative, consultant and inspection services, attorney's fees and any damages for delay) such excess shall be paid to the Contractor.

14.3.5 If such expenses referenced in Paragraph 14.3.1, shall exceed the unpaid balance, the Contractor and his sureties shall be liable to the Owner for such excess. If the right of the Contractor to proceed with the Work is partially or fully terminated, the Owner may take possession of and utilize in completing the Work such materials, appliances, supplies, plant and equipment as may be on the site of the terminated portion of the Work and necessary for the completion of the Work. If the Owner does not fully terminate the right of the Contractor to proceed, the Contractor shall continue to perform the part of the Work that is not terminated.

14.3.6 If the Owner terminates the whole or any part of the Work pursuant to Section 14.3, the Owner may procure, upon such terms and in such manner as the Owner may deem appropriate, supplies or services similar to those so terminated, and the Contractor shall be liable to the Owner for any excess costs for such similar supplies or services. The Contractor shall continue the performance of the Contract to the extent not terminated hereunder.

14.4 ALLOWABLE TERMINATION COSTS

14.4.1 If the Owner terminates the whole or any portion of the Work pursuant to Section 14.2, then the Owner shall only be liable to the Contractor for those costs reimbursable to the Contractor in accordance with Paragraph 14.4.2, plus a markup of ten percent (10%) for profit and overhead on the actual fully accounted costs specified under Paragraph 14.4.2; provided however, that if there is evidence that the Contractor would have sustained a loss on the entire Contract had it been completed, no profit or overhead shall be included or allowed hereunder for the Work performed and an appropriate adjustment shall be made reducing the amount of the settlement to reflect the indicated rate of loss. Under no circumstances shall the Contractor be entitled to any loss profit on the Work terminated pursuant to Section 14.2.

14.4.1.1 After receipt of a Notice of Termination, the Contractor shall submit to the Owner his termination Claim, in the form and with certification prescribed by the Owner. Such Claim shall be submitted promptly but in no event later than three (3) months from the effective date of termination, unless one or more extensions in writing are granted by the Owner upon request of the Contractor made in writing within such three (3) month period or authorized extension thereof. However, if the Owner determines that the facts justify such action, he may receive and evaluate any such termination Claim at any time after such three (3) month period or any extension thereof. Upon failure of the Contractor to submit his termination Claim within the time allowed, the Owner may determine, on the basis of information available to him, the amount, if any, due to the Contractor by reason of the termination and such termination shall be final and binding on the Contractor.

14.4.2 If the Owner terminates the whole or any portion of the Work pursuant to Section 14.2, the Owner shall pay the Contractor an amount for supplies, services, or property accepted by the Owner, and which is in accordance with the Contract Documents, in an amount as if the Contract had not been terminated. In addition, in such event, the Owner shall pay to Contractor an amount representing Contractor's actual cost, excluding any overhead and profit for the items and things specified in Subparagraph 14.5.1.6 and not heretofore paid for, appropriately adjusted for any saving of freight or other charges. Under no circumstances shall the Contractor be entitled to any loss profit on the Work terminated pursuant to Section 14.2.

14.4.2.1 The Contractor agrees that neither the Owner nor the Design Consultant will be liable for payments to Contractors or Subcontractors pursuant to Section 14.4.2 unless each contract and subcontract contains termination provisions identical to those set forth in this Article 14. The Owner and the Design Consultant will not be liable to the Contractor or any of the Subcontractors for any costs associated with termination if the contract or subcontract of the party involved does not include the required termination language.

14.4.3 In arriving at any amount due the Contractor pursuant to Section 14.4, there shall be deducted the following:

1. All unliquidated advance or other payments on account theretofore made to the Contractor applicable to the terminated portion of the Contract;

2. Any Claim which the Owner may have against the Contractor;

3. Such amount as the Owner determines to be necessary to protect the Owner against loss because of outstanding or potential liens or claims; and

4. The agreed price for, or the proceeds of sale of, any materials, supplies or other things acquired by the Contractor sold, pursuant to the provisions of Subparagraph 14.5.1.7, and not otherwise recovered by or credited to the Owner, or returned for a refund by the Contractor.

5. All other amounts the Owner is entitled to withhold form the Contractor or charge to the Contractor pursuant to the Contract or as allowed by applicable law.

14.4.4 The total sum to be paid to the Contractor under Section 14.4 shall not exceed the Contract Sum as reduced by the amount of payments otherwise made or to be made for Work not terminated and as otherwise permitted by the Contract. Except for normal spoilage, and except to the extent that the Owner shall have otherwise expressly assumed the risk of loss, there shall be excluded from the amounts payable to the Contractor, as provided in Paragraph 14.4.2, the fair value, as determined by the Owner, of property which is destroyed, lost, stolen or damaged so as to become undeliverable to the Owner, or to a buyer pursuant to Subparagraph 14.5.1.7.

14.5 GENERAL TERMINATION PROVISIONS

14.5.1 After receipt of a Notice of termination from the Owner, pursuant to Section 14.2 or 14.3, and except as otherwise directed by the Owner, the Contractor shall:

1. Stop work under the Contract on the date and to the extent specified in the Notice of termination;

2. Place no further orders or subcontracts for materials, services or facilities, except as may be necessary for completion of such portion of the Work under the Contract as is not terminated;

3. Terminate all orders and subcontracts to the extent that they relate to the performance of the Work terminated by the Notice of termination;

4. At the option of the Owner, and in lieu of terminating such orders and subcontracts, assign to the Owner in the manner, at the times and to the extent directed by the Owner in writing,

all of the rights in the such orders and subcontracts,

5. Settle all outstanding liabilities and all Claims arising out of such termination or orders and subcontracts, with the approval or ratification of the Owner in writing, to the extent he may require, which approval or ratification shall be final for all the purposes of this Article;

6. Transfer title and deliver to the entity or entities designated by the Owner, in the manner, at the times and to the extent directed by the Owner to the extent specifically produced or specifically acquired by the Contractor for the performance of such portion of the Work as had been terminated, the following:

   (1) The fabricated or unfabricated parts, Work in process, partially completed supplies and equipment, materials, parts, tools, dies, jigs and other fixtures, completed Work, supplies and other material produced as part of, or acquired in connection with the performance of, the Work terminated by the Notice of termination; and

   (2) The completed or partially completed plans, drawings, information, releases, manuals and other property related to the Work and which, if the Contract had been completed, would have been required to be furnished to the Owner;

7. Use his best efforts to return for a refund or sell, in the manner, at the times, to the extent and at the price or prices directed or authorized by the Owner, any property of the types referred to in Subparagraph 14.5.1.6; provided, however, that the Contractor:

   (1) Shall not be required to extend credit to any buyer, and

   (2) May acquire any such property under the conditions prescribed by and at a price or prices approved by the Owner in writing; and provided further that the proceeds of any such transfer or disposition shall be applied in reduction of any payments to be made by the Owner to the Contractor under the Contract or shall otherwise be credited to the Contract Sum covered by the Contract or paid in such other manner as the Owner may direct;

8. Complete performance of such part of the Work as shall not have been terminated by the Notice of termination;

9. Take such action as may be necessary, or as the Owner may direct, for the protection and preservation of the property related to the Contract which is in the possession of the Contractor and in which the Owner has or may acquire an interest; and

10. Otherwise mitigate any damages Contractor claims to suffer as a result of a termination.

14.5.2 The Contractor shall, from the effective date of termination until the expiration of three (3) years after final settlement under the Contract, preserve and make available to the Owner, at all reasonable times at the office of the Contractor, but without direct charge to the Owner, all his books, records, documents and other evidence bearing on the costs and expenses of the Contractor under the Contract and relating to the Work terminated hereunder, or, to the extent approved by the Owner, photographs, micro-photographs or other authentic reproductions thereof.

14.5.3 If the termination, pursuant to Section 14.2, be partial, the Contractor may file with the Owner a Claim for an equitable adjustment of the price or prices specified in the Contract relating to

the continued portion of the Contract (the portion not terminated by the Notice of termination), and such equitable adjustment as may be agreed upon shall be made in such price or prices. Any Claim by the Contractor for an equitable adjustment under this Paragraph must be asserted within thirty (30) days from the effective date of the Notice of termination.

14.5.4 The Contractor shall refund to the Owner any amounts paid by the Owner to the Contractor in excess of costs reimbursable under Section 14.4.

14.5.5 The Contractor shall be entitled to only those damages and that relief from termination by the Owner as specifically provided in Article 14.

ARTICLE 15

DISPUTE RESOLUTION

15.1 INITIATING CLAIMS

15.1.1 Claims must be initiated by written Notice to the Owner and to the party against whom the Claim is made with a copy to the Design Consultant. The responsibility to substantiate Claims shall rest with the party making the Claim.

15.1.2 Nothing in the Contract shall be construed as meaning that the Owner's assessment of Liquidated Damages is a Claim as defined herein, or that the Owner has the burden of proof to assess Liquidated Damages. Should the Owner assess Liquidated Damages, the burden of proving that such damages should not have been assessed shall rest upon the Contractor.

15.2 RESOLUTION OF CLAIMS AND DISPUTES BETWEEN CONTRACTOR AND OWNER

15.2.1 Claims by Contractor against Owner and by Owner against Contractor, including those alleging an error or omission by the Design Consultant shall be subject to the process set forth in this Section 15.2. Such Claims shall be referred initially to the Design Consultant for a decision. A final decision by the Design Consultant, or the failure of the Design Consultant to issue a final decision shall be required as a condition precedent to mediation or litigation of all such Claims arising prior to the date final payment is due. The Design Consultant will initially decide disputes between Owner and Contractor.

15.2.2 The Design Consultant will review Claims by Contractor and Owner against each other and within twenty (20) days of the receipt of the written Claim and take one or more of the following actions:

1. Request additional supporting data from the claimant or a response with supporting data from the other party;

2. Reject the Claim in whole or in part;

3. Approve the Claim;

4. Suggest a compromise; or

5. Advise the parties that the Design Consultant is unable to resolve the Claim if the Design Consultant lacks sufficient information to evaluate the merits of the Claim or if the Design Consultant concludes that it would be inappropriate for the Design Consultant to resolve

the Claim.

15.2.3 In evaluating Claims made under this Section 15.2, the Design Consultant may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who assist the Design Consultant in rendering a decision.

15.2.4 If the Design Consultant requests a party to provide a response to a Claim under this Section 15.2, or to furnish additional supporting data, such party shall respond, within ten (10) days after receipt of such request, and shall within such time period, either provide a response to the requested supporting data, advise the Design Consultant when the response or supporting data will be furnished, or advise the Design Consultant that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Design Consultant will either reject or approve the Claim in whole or in part.

15.2.5 The Design Consultant will approve or reject Claims under this Section 15.2 by written decision, which shall state the reason thereof and which shall notify the parties of any change in the Contract Sum or Contract Time or both. The approval or rejection of a Claim by the Design Consultant under this Section 15.2 shall be final and binding on the parties but subject to mediation and litigation.

15.2.6 When a written decision of the Design Consultant under this Section 15.2 states that the decision is final but subject to mediation, then a demand for mediation of a Claim covered by such decision must be made within thirty (30) days after the date on which the party making the demand receives the final written decision. Any failure to demand mediation within said thirty (30) days' period shall result in the Design Consultant's decision becoming final and binding to all parties. Claims not resolved in mediation shall be subject to litigation if in accordance with the applicable statutes of limitation and repose.

15.2.7 Upon receipt of a Claim under Section 15.2 against the Contractor or at any time thereafter, the Design Consultant or the Owner may, but is not obligated to, notify the Surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Design Consultant or the Owner may, but are not obligated to, notify the Surety and request the Surety's assistance in resolving the controversy.

15.2.8 If the Design Consultant deems that a Claim under this Section 15.2 is valid, the Design Consultant shall require all parties to the dispute to share the cost of the Design Consultant's review equitably. If the Design Consultant deems that a Claim under this Section 15.2 is invalid, the Design Consultant shall require the complaining party to bear the cost of the Design Consultant's review. In any event, the Design Consultant may require the complaining party to submit a deposit equivalent to the Design Consultant's hourly rate multiplied by the amount of time the Design Consultant estimates, in the Design Consultant sole discretion, that will be necessary to review the Claim. The Design Consultant shall return any unused portion of this initial deposit to the complaining party following the Design Consultant's completion of the Design Consultant's review of the Claim. Nothing in these procedures shall entitle the Design Consultant to compensation for additional services from the Owner that is not authorized pursuant to the terms and conditions of the Agreement for Design Consultant Services.

15.3 TIME LIMITS ON CLAIMS

15.3.1 Unless a shorter time is provided in the Contract Documents, Claims by Contractor or any party except Owner must be initiated within twenty (20) days after occurrence of the event giving rise to such Claim or within twenty (20) days after the claimant first recognizes the condition

giving rise to the Claim, whichever is later. Claims against the Owner shall be initiated in strict conformance with the Contract Documents. Nothing in these procedures shall extend the period within or the manner in which Claims against the Owner must be submitted. Claims must be initiated by written Notice to the Owner and written notice to the other party and to the Design Consultant. Any Claim against the Owner that is not initiated within the applicable time period is waived. Claims by Owner may be made at any time within the applicable statute of limitations and repose.

15.4 CONTINUING CONTRACT PERFORMANCE

15.4.1 Pending final resolution of a Claim, the Contractor shall proceed diligently with the performance of the Contract, unless instructed otherwise in writing by the Owner.

15.5 MEDIATION

15.5.1 As required by N.C.G.S 143-128 (f1), any Claim as defined herein, which exceeds fifteen thousand dollars($15,000.00), and which concerns a party involved in the Project, including the Owner, Contractor, Design Consultant, any construction manager, Separate Contractors, or first and lower tier Subcontractors and which arise out of the Contract or the construction process, except those waived Claims shall, be subject to mediation as a condition precedent to the institution of legal proceedings by any party, except that any party may institute legal proceedings or perfect any mechanic's or materialmen's lien in order to meet any applicable statute of limitations or similar deadline prior to engaging in mediation.

15.5.2 The parties shall endeavor to resolve their Claims under this Section 15.5 by mediation which, unless the parties mutually agree otherwise, shall be in accordance with the rules established by the Owner.

15.5.3 The parties shall share cost of the mediation equally except that if the Owner is a party to the dispute, the Owner shall pay at least one third of the cost of the mediation.

15.5.4 The mediation shall be held in a place where the Project is located, unless another location is mutually agreed upon.

15.5.5 Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

END OF GENERAL CONDITIONS

SECTION SC

SUPPLEMENTAL CONDITIONS

GENERAL CONDITIONS

Document GC, GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION, constitutes the General Conditions of this Contract, and is hereinafter called "General Conditions." The General Conditions are further revised and supplemented by the provisions of these Supplemental Conditions. The General Conditions and the Supplemental Conditions are applicable to all of the Work under this contract and shall apply to the Contractor and all Subcontractors and Sub-subcontractors.

SUPPLEMENTS:

The following supplements modify, change, delete, or add to the General Conditions. Where any article of the General Conditions is modified or any paragraph deleted, subparagraph or clause thereof is modified, or deleted by these supplements, the unaltered provisions of such article, paragraph, subparagraph or clause shall remain in effect. If there is a discrepancy between the General Conditions and these Supplemental Conditions, the Supplemental Conditions shall control.

ARTICLE 1 - CONTRACT DOCUMENTS

ADD THE FOLLOWING TO 1.3.1:

1.3.1.1 The Contractor will be furnished with one set drawings and specifications for free.

ARTICLE 2 - ARCHITECT

ADD THE FOLLOWING TO PARAGRAPH 2.1:

Design Consultant:

CRA and Associates, Inc., 100 Europa Drive, Suite 565, Chapel Hill, NC 27517

ARTICLE 7 – MISCELLANEOUS PROVISIONS

ADD THE FOLLOWING TO THE END OF 7.1.1

The Contractor and Owner agree that Lee County, North Carolina shall be the proper venue for any litigation arising out of this Agreement.

ARTICLE 8 - TIME

ADD THE FOLLOWING TO PARAGRAPH 8.2:

8.2.4 The schedule below contains certain specific dates in addition to date of Notice to Proceed and Time for Completion. These dates shall be adhered to and are the last acceptable dates unless modified by mutual agreement between the Contractor and the Owner. All dates indicate midnight unless otherwise stipulated. The only exceptions to this schedule are defined in the General Conditions and Supplemental Conditions under Paragraph 8.3 DELAYS AND EXTENSIONS OF TIME. Adherence to the schedule below results in a Construction Duration of **427** calendar days until Substantial Completion and an additional **26** days until Final Completion.

Notice of Intent to Award – July 17, 2026

Return of Owner Contractor Agreement by Contractor – August 4, 2026

Notice to Proceed – (NTP) September 1, 2026

Substantial Completion – October 1, 2027

Complete Final Close-out – October 27, 2027

8.2.4.1 The Owner reserves the right to withhold the issuance of Notice to Proceed by up to forty-five (45) days. For each day that Notice to Proceed is withheld pursuant to this Subparagraph, the dates established for Substantial Completion and Final Completion shall be adjusted. The contractor shall not be entitled to additional compensation if the owner withholds the issuance of Notice to Proceed pursuant to this Subparagraph.

ADD THE FOLLOWING AS A NEW SECOND SENTENCE TO PARAGRAPH 8.3.1:

The Contractor acknowledges that the coronavirus (COVID-19) pandemic has impacted businesses across the country.

ADD THE FOLLOWING TO THE END OF THE FIRST PARAGRAPH IN 8.3.4.2.3:

The Parties agree that the weather station applicable to this Project shall be the one located at Greensboro, Piedmont Triad International Airport.

ADD THE FOLLOWING TO PARAGRAPH 8.5.1:

8.5.1.1 Substantial Completion Liquidated Damages shall be the sum of **two-hundred fifty dollars ($250)** per calendar day, and this amount shall be assessed in accordance with Subparagraph 8.5.1 of the General Conditions. The Liquidated Conditions shall apply for each indicated time period as noted in the Construction Schedule and Phasing.

8.5.1.2 Final Completion Liquidated Damages shall be the sum of **two-hundred fifty dollars ($250)** per calendar day, and this amount shall be assessed in accordance with Subparagraph 8.5.1 of the General Conditions.

ARTICLE 9 - PAYMENTS AND COMPLETION

ADD THE FOLLOWING TO PARAGRAPH 9.3:

9.3.1.2 Applications for progress payments shall be submitted to the Architect by the twenty-fifth day of the month. The period covered by each Application for Payment is one month, ending on the twentieth day of the month.

ADD THE FOLLOWING TO PARAGRAPH 9.6:

9.6.3 Additional services and dispute resolution services by the Design Consultant shall be paid by the Contractor at the rate of **one-hundred fifty dollars ($150) per hour**.

END OF SUPPLEMENTAL CONDITION

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Contractor's use of site and premises.
4. Work restrictions.
5. Specification and Drawing conventions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.
2. Section 017300 "Execution" for coordination of Owner-installed products.

1.3 PROJECT INFORMATION

A. Project Identification: Transportation Facility.

1. Project Location: 416 Cox Maddox Road, Sanford, North Carolina 27332.

B. Owner: Lee County Schools.

1. Owner's Representative: Chris Mc Neill, Director, Facilities and Maintenance.

C. Architect: CRA Associates, Inc.

1. Architect's Representative: Tedd Clippinger.

D. Architect's Consultants: Architect has retained the following design professionals, who have prepared designated portions of the Contract Documents:

1. Civil Engineer: Timmons Group.
2. Structural Engineer: Bennett & Pless, Inc.
3. Plumbing, Mechanical and Electrical Engineer: Reece, Noland and McElrath, Inc.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and includes, but is not limited to, the following:

1. Work will be performed on the site of the existing Bus Maintenance Garage which must remain operational during construction and is intended to remain for the Owner's future use. There is no work proposed to be done on the existing facility itself, work is limited to the surrounding site. New construction to include a new Transportation Facility, open-air Vehicle Storage building, and an add alternate for a Warehouse.
2. Transportation Facility: 20,727 square feet, slab on grade, S-1Moderate, Type II-B, Fully Sprinklered Transportation Facility consisting of an office suite with support spaces, maintenance bays and associated work areas.
3. Vehicle Storage Building: 5,000 square feet, slab on grade, pre-engineered metal, open-air structure.
4. Warehouse (add Alternate G-1): 6,000 square feet, slab on grade, pre-engineered metal building, shell space.
5. Work of Project includes:

    a. Site Features: New Utility Feeds, Concrete Pavement, Heavy-duty Asphalt Paving, Concrete Sidewalks, Storm drainage structures, Seeding.
    b. Structure: Poured-in-place concrete footings, foundation walls and floor slabs, Pre-engineered Metal Building components
    c. Building Envelope: insulated metal panel, metal building insulation system, concrete masonry, batt insulation, aluminum storefront, metal roofing, membrane roofing, pre-manufactured canopies.
    d. Interior Finishes: polished concrete, luxury vinyl tile, monolithic epoxy flooring with integral base, rubber base, acoustical tile ceilings, drywall ceilings, concrete sealer/hardener, paint, fiberglass reinforced panels.
    e. Mechanical, Plumbing, Fire Protection and Electrical Components

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.5 CONTRACTOR'S USE OF SITE AND PREMISES

A. Restricted Use of Site: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.

1.6 WORK RESTRICTIONS

A. Comply with restrictions on construction operations.

1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.

B. Smoking and Controlled Substance Restrictions: Use of tobacco products, alcoholic beverages, and other controlled substances on Project site is not permitted.

C. Employee Screening: Comply with Owner's requirements for drug and background screening of Contractor personnel working on Project site.

1. Maintain list of approved screened personnel with Owner's representative.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
2. Text Color: Text used in the Specifications, including units of measure, manufacturer and product names, and other text may appear in multiple colors or underlined as part of a hyperlink; no emphasis is implied by text with these characteristics.
3. Hypertext: Text used in the Specifications may contain hyperlinks. Hyperlinks may allow for access to linked information that is not residing in the Specifications. Unless otherwise indicated, linked information is not part of the Contract Documents.
4. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 00 Contracting Requirements: General provisions of the Contract, including General and Supplementary Conditions, apply to all Sections of the Specifications.

C. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 012300 - ALTERNATES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for alternates.

1.3 DEFINITIONS

A. Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined in the bidding requirements that may be added to or deducted from the base bid amount if the Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.

1. Alternates described in this Section are part of the Work only if enumerated in the Agreement.
2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternates into the Work. No other adjustments are made to the Contract Sum.

1.4 PROCEDURES

A. Coordination: Revise or adjust affected adjacent work as necessary to completely integrate work of the alternate into Project.

1. Include, as part of each alternate, miscellaneous devices, accessory objects, and similar items incidental to or required for a complete installation, whether or not indicated as part of alternate.

B. Execute accepted alternates under the same conditions as other Work of the Contract.

C. Schedule: A Part 3 "Schedule of Alternates" Article is included at the end of this Section. Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

A. Alternate No. G-1: Warehouse Building.

1. Base Bid: Provide lock cylinders/cores as indicated on Drawing A601-Door Schedule and as specified in Section 087100 "Door Hardware."
2. Alternate: Provide Warehouse Building as indicated on Drawing.

B. Alternate No. G-2: Preferred Brand: Best Key System.

1. Base Bid: Provide lock cylinders/cores as indicated on Drawing A601-Door Schedule and as specified in Section 087100 "Door Hardware."
2. Alternate: Provide Best key system.

C. Alternate No. G-3: Preferred Brands: Sherwin-Williams and Armorseal.

1. Base Bid: Provide any acceptable paint system as indicated on Drawing A701 Finish Schedule and as specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."
2. Alternate: Provide paints by Sherwin-Williams or Armorseal.

D. Alternate No. P-1: Preferred Brands: A. O. Smith and Zurn.

1. Base Bid: Provide hot water heaters and flush valves as indicated on Drawing P001 Plumbing Notes, Details and Specifications.
2. Alternate: Provide A. O. Smith hot water heaters and Zurn auto-flush valves.

E. Alternate No. M-1: Trane HVAC Equipment.

1. Base Bid: Provide HVAC equipment and controls as indicated on Drawing M001 Mechanical Summary and Schedules and as specified in Division 23.
2. Alternate: Provide Trane HVAC equipment and Trane Tracer Summit controls.

F. Alternate No. M-2: Preferred Brands: Pumps, Pump Controllers, Valves, and Boilers.

1. Base Bid: Provide pump controllers and drives, pumps, valves, and boilers as indicated on Drawing M001 Mechanical Summary and Schedules and as specified in Division 23.
2. Alternate: Provide ABB pump controllers and drives, Bell & Gosset pumps, Belimo valves, and Weil-McLain Slim-Fit boilers.

G. Alternate No. E-1: Site Lighting.

1. Base Bid: Provide no site lighting.
2. Alternate: Provide site lighting as scheduled on Drawing E001-Electrical Symbols, Notes & Specifications as indicated on Drawing E010-Site Lighting Alternate.

H. Alternate No. E-2: Preferred Brand: Square D.

1. Base Bid: Provide electrical equipment and devices as indicated on Electrical Drawings (E) and as specified in Division 26
2. Alternate: Provide equipment and devices from Square D, a Schneider Electric Company.

I. Alternate No. E-3: Preferred Brand: Notifier Fire Alarm.

1. Base Bid: Provide addressable fire-alarm system as indicated on Fire Protection (FP) Drawings and as specified in Section 284621.11 "Addressable Fire-Alarm Systems."
2. Alternate: Provide system from Notifier by Honeywell.

END OF SECTION 012300

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for substitutions.

B. Related Requirements:

1. Document 002600 "Procurement Substitution Procedures" for requirements for substitution requests prior to award of Contract.
2. Section 012100 "Allowances" for products selected under an allowance.
3. Section 012300 "Alternates" for products selected under an alternate.
4. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.3 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents.

1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required to meet other Project requirements but may offer advantage to Contractor or Owner.

1.4 ACTION SUBMITTALS

A. Substitution Requests: Submit documentation identifying product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Use form acceptable to Architect.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:

a. Statement indicating why specified product or fabrication or installation method cannot be provided, if applicable.

b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
c. Detailed comparison of significant qualities of proposed substitutions with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
e. Samples, where applicable or requested.
f. Certificates and qualification data, where applicable or requested.
g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
k. Cost information, including a proposal of change, if any, in the Contract Sum.
l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.5 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.7 SUBSTITUTIONS

A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
b. Substitution request is fully documented and properly submitted.
c. Requested substitution will not adversely affect Contractor's construction schedule.
d. Requested substitution has received necessary approvals of authorities having jurisdiction.
e. Requested substitution is compatible with other portions of the Work.
f. Requested substitution has been coordinated with other portions of the Work.
g. Requested substitution provides specified warranty.
h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

B. Substitutions for Convenience: Not allowed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section specifies administrative and procedural requirements for handling and processing Contract modifications.

B. Related Sections include the following:

1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.
2. Section 013100 "Project Management and Coordination" for requirements for forms for contract modifications provided as part of web-based Project management software.

1.3 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.4 PROPOSAL REQUESTS

A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.

1. Proposal Requests issued by Architect are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
2. Within seven days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

    a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    c. Include costs of labor and supervision directly attributable to the change.

d. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.

B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change to Architect.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Division 1 Section "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.

C. Proposal Request Form: Use AIA Document G709 for Proposal Requests.

1. Architect may approve Contractor’s use of other Proposal Request Form, if it provides all information included on the document indicated, and if form is submitted to Architect for approval prior to being used for Proposal Request.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on form included in “Project Forms” Section of this Project Manual.

1.6 CONSTRUCTION CHANGE DIRECTIVE

A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.

1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Sections include the following:

1. Section 012100 "Allowances" for procedural requirements governing the handling and processing of allowances.
2. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
3. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.3 SCHEDULE OF VALUES

A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.

1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:

a. Application for Payment forms with Continuation Sheets.
b. Submittals Schedule.
c. Contractor's Construction Schedule.

2. Submit the Schedule of Values to Architect at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

3. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.

4. Identification: Include the following Project identification on the Schedule of Values:

a. Project name and location.
b. Name of Architect.
c. Architect's project number.

d. Contractor's name and address.
e. Date of submittal.

5. Submit draft of AIA Document G703 Continuation Sheets.
6. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate. Include separate line items under required principal subcontracts for operation and maintenance manuals, punch list activities, Project Record Documents, and demonstration and training in the amount of 5 percent of the Contract Sum.
7. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
8. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.

    a. Differentiate between items stored on-site and items stored off-site. If specified, include evidence of insurance or bonded warehousing.

9. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
10. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.

    a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.

11. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.4 APPLICATIONS FOR PAYMENT

A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.

    1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

B. Payment Application Times: Progress payments shall be submitted to Architect by the twenty-fifth day of the month. The period covered by each Application for Payment is one month, ending on the twentieth day of the month.

C. Payment Application Forms: Use AIA Document G702 and AIA Document G703 Continuation Sheets as form for Applications for Payment.

D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

1. Entries shall match data on the Schedule of Values and Contractor's Construction Schedule. Use updated schedules if revisions were made.
2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
3. The Purchase Order Number issued by the Town shall appear on each application.

E. Transmittal: Submit 6 signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. Two copies shall include waivers of lien and similar attachments.

1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.

F. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's liens from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.

1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
2. When an application shows completion of an item, submit final or full waivers.
3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
4. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
5. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.

G. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

1. List of subcontractors.
2. Schedule of Values.
3. Contractor's Construction Schedule (preliminary if not final).
4. Products list.
5. Schedule of unit prices.
6. Submittals Schedule (preliminary if not final).
7. List of Contractor's staff assignments.
8. List of Contractor's principal consultants.
9. Copies of building permits.
10. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
11. Initial progress report.
12. Report of preconstruction conference.
13. Certificates of insurance and insurance policies.

H. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

I. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:

1. Evidence of completion of Project closeout requirements.
2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
3. Updated final statement, accounting for final changes to the Contract Sum.
4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
6. AIA Document G707, "Consent of Surety to Final Payment."
7. Evidence that claims have been settled.
8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
9. Final, liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012901

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

1. Preliminary Construction Schedule.
2. Contractor's Construction Schedule.
3. Submittals Schedule.
4. Daily construction reports.
5. Field condition reports.
6. Special reports.

B. Related Sections include the following:

1. Section 012900 "Payment Procedures" for schedule of values and requirements for use of cost-loaded schedule for Applications for Payment.

1.3 DEFINITIONS

A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.

1. Critical activities are activities on the critical path. They must start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. Cost Loading: The allocation of the Schedule of Values for the completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum, unless otherwise approved by Architect.

C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.

D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

E. Event: The starting or ending point of an activity.

F. Float: The measure of leeway in starting and completing an activity.

1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

G. Fragnet: A partial or fragmentary network that breaks down activities into smaller activities for greater detail.

H. Major Area: A story of construction, a separate building, or a similar significant construction element.

I. Milestone: A key or critical point in time for reference or measurement.

J. Network Diagram: A graphic diagram of a network schedule, showing activities and activity relationships.

K. Resource Loading: The allocation of manpower and equipment necessary for the completion of an activity as scheduled.

1.4 SUBMITTALS

A. Qualification Data: For scheduling consultant.

B. Submittals Schedule: Submit schedule. Arrange the following information in a tabular format:

1. Scheduled date for first submittal.
2. Specification Section number and title.
3. Submittal category (action or informational).
4. Name of subcontractor.
5. Description of the Work covered.
6. Scheduled date for Architect's final release or approval.

C. Preliminary Construction Schedule: Submit electronic copies.

1. Approval of cost-loaded preliminary construction schedule will not constitute approval of Schedule of Values for cost-loaded activities.

D. Contractor's Construction Schedule: Submit electronic copies of initial schedule.

E. Daily Construction Reports: Submit two copies at biweekly intervals.

F. Field Condition Reports: Submit two copies at time of discovery of differing conditions.

G. Special Reports: Submit two copies at time of unusual event.

1.5 QUALITY ASSURANCE

A. Scheduling Consultant Qualifications: An experienced specialist in CPM scheduling and reporting, with capability of producing CPM reports and diagrams within 24 hours of Architect's request.

1.6 COORDINATION

A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.

B. Coordinate Contractor's Construction Schedule with the Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.

1. Secure time commitments for performing critical elements of the Work from parties involved.
2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 SUBMITTALS SCHEDULE

A. Preparation: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, resubmittal, ordering, manufacturing, fabrication, and delivery when establishing dates.

1. Coordinate Submittals Schedule with list of subcontracts, the Schedule of Values, and Contractor's Construction Schedule.
2. Initial Submittal: Submit concurrently with preliminary bar-chart schedule. Include submittals required during the first 60 days of construction. List those required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's Construction Schedule.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

A. Procedures: Comply with procedures contained in AGC's "Construction Planning & Scheduling."

B. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Final Completion.

1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.

C. Activities: Comply with the following:

1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
2. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
3. Submittal Review Time: Include review and resubmittal times indicated in Division 1 Section "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
4. Startup and Testing Time: Include not less than 30 days for startup and testing.
5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.

D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
2. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Division 1 Section "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
3. Work Restrictions: Show the effect of the following items on the schedule:

    a. Coordination with existing construction.
    b. Partial occupancy before Substantial Completion.
    c. Use of premises restrictions.
    d. Provisions for future construction.
    e. Seasonal variations.
    f. Environmental control.

4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:

    a. Subcontract awards.
    b. Submittals.
    c. Purchases.
    d. Mockups.
    e. Fabrication.
    f. Sample testing.
    g. Deliveries.
    h. Installation.
    i. Tests and inspections.

j. Adjusting.
k. Curing.
l. Startup and placement into final use and operation.

E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion, and the following interim milestones:

1. Structural completion.
2. Permanent space enclosure.
3. Completion of equipment installation.
4. Completion of mechanical installation.
5. Completion of electrical installation.

F. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using fragnets to demonstrate the effect of the proposed change on the overall project schedule.

2.3 PRELIMINARY CONSTRUCTION SCHEDULE

A. Bar-Chart Schedule: Submit preliminary horizontal bar-chart-type construction schedule within seven days of date established for the Notice to Proceed.

B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line. Outline significant construction activities for first 60 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

2.4 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

A. General: Prepare network diagrams using AON (activity-on-node) format.

B. Preliminary Network Diagram: Submit diagram within 14 days of date established for the Notice to Proceed. Outline significant construction activities for the first 60 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

C. Initial Issue of Schedule: Prepare initial network diagram from a list of straight "early start-total float" sort. Identify critical activities. Prepare tabulated reports showing the following:

1. Contractor or subcontractor and the Work or activity.
2. Description of activity.
3. Principal events of activity.
4. Immediate preceding and succeeding activities.
5. Early and late start dates.
6. Early and late finish dates.
7. Activity duration in workdays.
8. Total float or slack time.
9. Average size of workforce.

10. Dollar value of activity (coordinated with the Schedule of Values).

D. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:

1. Identification of activities that have changed.
2. Changes in early and late start dates.
3. Changes in early and late finish dates.
4. Changes in activity durations in workdays.
5. Changes in the critical path.
6. Changes in total float or slack time.
7. Changes in the Contract Time.

E. Value Summaries: Prepare two cumulative value lists, sorted by finish dates.

1. In first list, tabulate activity number, early finish date, dollar value, and cumulative dollar value.
2. In second list, tabulate activity number, late finish date, dollar value, and cumulative dollar value.
3. In subsequent issues of both lists, substitute actual finish dates for activities completed as of list date.
4. Prepare list for ease of comparison with payment requests; coordinate timing with progress meetings.

a. In both value summary lists, tabulate "actual percent complete" and "cumulative value completed" with total at bottom.
b. Submit value summary printouts one week before each regularly scheduled progress meeting.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Contractor's Construction Schedule Updating: At biweekly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
3. As the Work progresses, indicate Actual Completion percentage for each activity.

END OF SECTION 013201

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Submittal schedule requirements.
2. Administrative and procedural requirements for submittals.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
2. Section 013100 "Project Management and Coordination" for submitting coordination drawings and subcontract list and for requirements for web-based Project software.
3. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
4. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
5. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
6. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
7. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
8. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.3 DEFINITIONS

A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."

B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.4 SUBMITTAL SCHEDULE

A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect] and additional time for handling and reviewing submittals required by those corrections.

1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
2. Final Submittal Schedule: Submit concurrently with the first complete submittal of Contractor's construction schedule.

    a. Submit revised submittal schedule as required to reflect changes in current status and timing for submittals.

3. Format: Arrange the following information in a tabular format:

    a. Scheduled date for first submittal.
    b. Specification Section number and title.
    c. Submittal Category: Action; informational.
    d. Name of subcontractor.
    e. Description of the Work covered.
    f. Scheduled date for Architect's final release or approval.

1.5 SUBMITTAL FORMATS

A. Submittal Information: Include the following information in each submittal:

1. Project name.
2. Date.
3. Name of Architect.
4. Name of Contractor.
5. Name of firm or entity that prepared submittal.
6. Names of subcontractor, manufacturer, and supplier.
7. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier and alphanumeric suffix for resubmittals.
8. Category and type of submittal.
9. Submittal purpose and description.
10. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.
11. Drawing number and detail references, as appropriate.
12. Indication of full or partial submittal.
13. Location(s) where product is to be installed, as appropriate.
14. Other necessary identification.
15. Remarks.
16. Signature of transmitter.

B. Options: Identify options requiring selection by Architect.

C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.

D. Electronic Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.

E. Submittals Utilizing Web-Based Project Software: Prepare submittals as PDF files or other format indicated by Project management software.

1.6 SUBMITTAL PROCEDURES

A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.

1. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project management software website. Enter required data in web-based software site to fully identify submittal.

B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections, so processing will not be delayed because of need to review submittals concurrently for coordination.

    a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.

1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
3. Resubmittal Review: Allow 15 days for review of each resubmittal.
4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.

5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow **15** days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.

    a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.

D. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in label or title block, and clearly indicate extent of revision.
3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.

E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.

F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

1.7 SUBMITTAL REQUIREMENTS

A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:

    a. Manufacturer's catalog cuts.
    b. Manufacturer's product specifications.
    c. Standard color charts.
    d. Statement of compliance with specified referenced standards.
    e. Testing by recognized testing agency.
    f. Application of testing agency labels and seals.
    g. Notation of coordination requirements.
    h. Availability and delivery time information.

4. For equipment, include the following in addition to the above, as applicable:

    a. Wiring diagrams that show factory-installed wiring.
    b. Printed performance curves.
    c. Operational range diagrams.
    d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before Shop Drawings, and before or concurrently with Samples.

B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:

a. Identification of products.
b. Schedules.
c. Compliance with specified standards.
d. Notation of coordination requirements.
e. Notation of dimensions established by field measurement.
f. Relationship and attachment to adjoining construction clearly indicated.
g. Seal and signature of professional engineer if specified.

C. Samples: Submit Samples for review of type, color, pattern, and texture for a check of these characteristics with other materials.

1. Transmit Samples that contain multiple, related components, such as accessories together in one submittal package.
2. Identification: Permanently attach label on unexposed side of Samples that includes the following:

a. Project name and submittal number.
b. Generic description of Sample.
c. Product name and name of manufacturer.
d. Sample source.
e. Number and title of applicable Specification Section.
f. Specification paragraph number and generic name of each item.

3. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project software website. Enter required data in web-based software site to fully identify submittal.
4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.

a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units, showing the full range of colors, textures, and patterns available.

a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.

6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.

    a. Number of Samples: Submit four sets of Samples. Architect will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record Sample.

        1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
        2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least four sets of paired units that show approximate limits of variations.

D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:

1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
2. Manufacturer and product name, and model number if applicable.
3. Number and name of room or space.
4. Location within room or space.

E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.

F. Design Data: Prepare and submit written and graphic information indicating compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.

G. Certificates:

1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
2. Installer Certificates: Submit written statements on manufacturer's letterhead, certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead, certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

4. Material Certificates: Submit written statements on manufacturer's letterhead, certifying that material complies with requirements in the Contract Documents.
5. Product Certificates: Submit written statements on manufacturer's letterhead, certifying that product complies with requirements in the Contract Documents.

H. Test and Research Reports:

1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for substrate preparation and primers required.
2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:

    a. Name of evaluation organization.
    b. Date of evaluation.
    c. Time period when report is in effect.
    d. Product and manufacturers' names.
    e. Description of product.
    f. Test procedures and results.
    g. Limitations of use.

1.8 DELEGATED-DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.

1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

1.9 CONTRACTOR'S REVIEW

A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.

B. Contractor's Approval: Indicate Contractor's approval for each submittal with indication in web-based Project management software. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

1. Architect will not review submittals received from Contractor that do not have Contractor's review and approval.

1.10 ARCHITECT'S REVIEW

A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required, and return.

1. Submittals by Web-Based Project Management Software: Architect will indicate, on Project management software website, the appropriate action.

a. Actions taken by indication on Project management software website have the following meanings:

1) Final Unrestricted Release: Where the submittal is marked "NO EXCEPTIONS TAKEN," the Work covered by the submittal may proceed provided that it complies with requirements of the Contract Documents. Final acceptance will depend on that compliance.
2) Final-but-Restricted Release: Where the submittal is marked "MAKE CORRECTIONS NOTED," the Work covered by the submittal may proceed provided it complies both with Architect’s notations and corrections on the submittal and with requirements of the Contract Documents. Final acceptance will depend on that compliance.
3) Resubmittal Required: Where the submittal is marked "REVISE AND RESUBMIT," do not proceed with the Work covered by the submittal, including purchasing, fabrication, delivery, or other activity for the product submitted. Revise or prepare new submittal based on Architect’s notations and corrections.

4) Rejected: Where the submittal is marked "REJECTED," co not proceed with the Work covered by the submittal, Prepare new submittal for product that complies with requirements of the Contract Documents.

B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.

C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.

D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

E. Architect will return without review submittals received from sources other than Contractor.

F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.

1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.

1.3 DEFINITIONS

A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.

C. Mockups: Full-size, physical assemblies that are constructed on-site. Mockups are used to verify selections made under sample submittals, to demonstrate aesthetic effects and, where indicated, qualities of materials and execution, and to review construction, coordination, testing, or operation; they are not Samples. Approved mockups establish the standard by which the Work will be judged.

D. Laboratory Mockups: Full-size, physical assemblies that are constructed at testing facility to verify performance characteristics.

E. Preconstruction Testing: Tests and inspections that are performed specifically for the Project before products and materials are incorporated into the Work to verify performance or compliance with specified criteria.

F. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with industry standards.

G. Source Quality-Control Testing: Tests and inspections that are performed at the source, i.e., plant, mill, factory, or shop.

H. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

I. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.

J. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.

1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.

K. Experienced: When used with an entity, "experienced" means having successfully completed a minimum of five previous projects similar in size and scope to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.4 CONFLICTING REQUIREMENTS

A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 SUBMITTALS

A. Qualification Data: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

B. Schedule of Tests and Inspections: Prepare in tabular form and include the following:

1. Specification Section number and title.
2. Description of test and inspection.
3. Identification of applicable standards.
4. Identification of test and inspection methods.
5. Number of tests and inspections required.
6. Time schedule or time span for tests and inspections.
7. Entity responsible for performing tests and inspections.
8. Requirements for obtaining samples.
9. Unique characteristics of each quality-control service.

C. Reports: Prepare and submit certified written reports that include the following:

1. Date of issue.
2. Project title and number.
3. Name, address, and telephone number of testing agency.
4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this Article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

C. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar to those indicated for this Project in material, design, and extent.

F. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 548; and with additional qualifications specified in individual Sections; and where required by authorities having jurisdiction, that is acceptable to authorities.

1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

G. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

H. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:

1. Contractor responsibilities include the following:

a. Provide test specimens representative of proposed products and construction.
b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.
f. When testing is complete, remove test specimens, assemblies, mockups, and laboratory mockups; do not reuse products on Project.

2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.

I. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:

1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
3. Demonstrate the proposed range of aesthetic effects and workmanship.
4. Obtain Architect's approval of mockups before starting work, fabrication, or construction.

    a. Allow seven days for initial review and each re-review of each mockup.

5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
6. Demolish and remove mockups when directed, unless otherwise indicated.

J. Laboratory Mockups: Comply with requirements of preconstruction testing and those specified in individual Sections in Divisions 2 through 16.

1.7 QUALITY CONTROL

A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.

1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.

B. Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.

1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.

    a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.

2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.

5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 1 Section "Submittal Procedures."

D. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.

E. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Preliminary design mix proposed for use for material mixes that require control by testing agency.
6. Security and protection for samples and for testing and inspecting equipment at Project site.

F. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

G. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents. Submit schedule concurrently with Contractor’s Construction Schedule.

1. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.

3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and modifications as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Comply with the Contract Document requirements for Division 1 Section "Cutting and Patching."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.3 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

1. For standards referenced by applicable building codes, comply with dates of standards as listed in building codes.

C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.4 ABBREVIATIONS AND ACRONYMS

A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

SECTION 014500 - INSPECTION REQUIREMENTS

PART 1 - GENERAL

Architect of Record: Tedd Clippinger, AIA – CRA Associates, Inc.
Structural Engineer of Record: Diane J Thompson, PE Bennett & Pless
Building Official: Sandford, NC

This Statement of Inspections is submitted as a condition for permit issuance in accordance with the Special Inspection requirements of the 2018 North Carolina State Building Code. It includes a Schedule of Special Inspection Services applicable to this project. The name of the Inspector(s) and the identity of other approved agencies intended to be retained for conducting these inspections will be released by the owner following the bid opening in accordance with SC Office of School Facilities requirements.

The Inspector(s) shall keep records of all inspections and shall furnish inspection reports to the Owner, Structural Engineer, and Architect of Record. A copy of all reports shall be kept on site at the contractor's trailer. Discovered discrepancies shall be brought to the immediate attention of the Contractor for correction. If such discrepancies are not corrected, the discrepancies shall be brought to the attention of the Owner, Structural Engineer and Architect of Record. The Inspections program does not relieve the Contractor of his or her supervision or inspection responsibilities.

The Contractor is responsible for notifications to Inspector and/or other agencies as required at least two days is advance. The Contractor is responsible for all additional costs incurred by failure to meet requirements or pass any/all inspections and/or testing as required in this section.

Interim reports shall be submitted to the Owner, Structural Engineer and Architect of Record.

Interim Report Frequency: Monthly

A Final Report of Inspections documenting completion of all required Special Inspections and correction of any discrepancies should be submitted prior to issuance of a Certificate of Use and Occupancy.

Job Site safety and means and methods of construction are solely the responsibility of the Contractor.

1.1 ITEMS REQUIRING IBC CHAPTER 1 INSPECTIONS/VERIFICATIONS

A. IBC Chapter 1 and NFPA required inspections include, but are not limited to, the following:
- 110.3.1 Footing or foundation inspection
- 110.3.2 Concrete slab or under-floor inspection
- 110.3.3 Lowest floor elevation
- 110.3.4 Frame Inspections
- 110.3.5 Lath or gypsum board inspection
- 110.3.6 Fire-resistant penetrations
- 110.3.7 Energy efficiency:

It is appropriate to take special note of the required energy efficiency compliance inspections. Ensuring compliance with ANSI/ASHRAE/IESNA Standard 90.1 – 2004 is a critical part of the inspection process and MUST be specifically addressed. The

American Society of Heating and Air Conditioning Engineers (ASHRAE) is the foremost technical society in the fields of heating, ventilation, air conditioning and refrigeration. ASHRAE Standard 90.1 is an ANSI approved national consensus standard co-sponsored by ASHRAE and the Illuminating Engineering Society of North America (IESNA). The Standard provides minimum energy efficiency requirements for the design and construction of new buildings and new construction in existing buildings. In particular, it applies to new buildings and their systems, building additions and their systems, and new systems and equipment in existing building.

The scope of the requirements of Standard 90.1 covers the design of the building envelope, the lighting systems, HVAC systems and other energy using equipment. For the OSF Approved Inspector, the 90.1 Users Manual is the best available source of information, worksheets and checklists for the purpose of ensuring compliance with Standard 90.1. These forms cannot be reproduced here due to the copyright restrictions. However, the 90.1 Users Manual can be obtained from the American Society of Heating and Air Conditioning Engineers, Incorporated, 1791 Tullie Circle, Atlanta, Georgia 30329. The telephone number is 404-636-8400. On the net they can be reached at ashrae.org.

Specifically, we refer you to the following in the Standard 90.1 User Manual:

1. Building Envelope Compliance Forms
2. HVAC Compliance Forms
3. Service Water Heating Compliance Forms
4. Power Distribution
5. Lighting Compliance Forms

These forms MUST be submitted to OSF at the final review stage. The Chapter 1 inspector shall request these forms be provided at the initial pre-construction meeting. The design professional shall have them available for that meeting.

909.3 Special inspection and test requirements (smoke control systems)

B. Mechanical Code: M107.1. Required inspections

1. Underground inspection shall be made after trenches or ditches are excavated and bedded, piping installed, and before backfill is put in place.

2. Rough-in inspection shall be made after the roof, framing, fireblocking and bracing are in place and all ducting and other components to be concealed are complete, and prior to the installation of wall or ceiling membranes.

C. Plumbing Code: P107.1 Required inspections and testing

1. Underground inspection shall be made after trenches or ditches are excavated and bedded, piping installed, and before any backfill is put in place.

2. Rough-in inspection shall be made after the roof, framing, fire blocking, firestopping, draft stopping and bracing is in place and all sanitary, storm and water distribution piping is roughed-in and prior to the installation of wall or ceiling membranes.

D. Electrical Code:

1. Underground inspection shall be made after trenches or ditches are excavated and bedded, conduit installed, and before backfill is placed.

2. Rough-in inspection shall be made after the roof, framing, fireblocking and bracing are in place and other components to be concealed are complete, and prior to the installation of concealing construction.

E. National Fire Alarm Code: Section 4.5:

1. The installing contractor shall furnish a written statement stating that the system has been installed in accordance with approved plans and tested in accordance with the manufacturer's published instructions and the appropriate NFPA requirements (Section 4.5.1.2).

2. This shall be accompanied by the record of completion form (Figure 4.5.2.1) Verification of compliance of the completed installation shall be included in the responsibilities of the Chapter 1 inspector (Section 4.5.2.4).

1.2 ITEMS REQUIRING IBC, CHAPTER 17 SPECIAL INSPECTIONS

A. IBC Chapter 17 requires special inspections including the following items as defined by their respective sections as noted:
IT-1 SPECIAL CASES (Refer to NCBC Section 1705.1.1)
IT-2 STEEL CONSTRUCTION (Refer to Section 1705.2 and the Exception; Table 1705.2.3)
IT-3 CONCRETE CONSTRUCTION (Refer to NCBC Section & Table1705.3; Ch. 19)
IT-4 MASONRY (Refer to NCBC Section 1705.4)
IT-5 WOOD (Refer to NCBC Section 1705.5)
IT-6 SOILS (Refer to NCBC Table 1705.6 & Section 1705.6)
IT-7 DRIVEN DEEP FOUNDATIONS (Refer to NCBC Section 1705.7)
IT 8 CAST-IN-PLACE DEEP FOUNDATIONS (Refer to NCBC Section 1705.8)
IT 9 HELICAL PILES (Refer to NCBC Sections 1705.9)
IT 10 FABRICATED ITEMS (Refer to NCBC Sections 1705.10 & 1704.2.5)
IT 11 WIND RESISTANCE (Refer to NCBC Sections 1705.11; 1705.11.1 – 1705.11.3; & 1609.3.1)
IT-12 SEISMIC RESISTANCE (Refer to NCBC Sections 1705.12)
IT 13 TESTING FOR SEISMIC RESISTANCE (Refer to Section 1705.13)
IT-14 SPRAYED FIRE-RESISTANT MATERIALS (Refer to NCBC Sections 1705.14)
IT 15 MASTIC AND INTUMESCENT FIRE-RESISTANT COATING 1705.15
IT-16 EXTERIOR INSULATION & FINISH SYSTEM (EIFS)
IT 17 FIRE-RESISTANT PENETRATIONS AND JOINTS (Refer to NCBC Sections 1705.17; 1705.17.1; & 1705.17.2)
IT-18 SMOKE CONTROL (Refer to NCBC Section 1705.18)

1.3 REPORTING SERVICES

A. It is the inspectors' responsibility to verify that the contractor conforms to this section of the code. Furthermore, it is vital to understand that mechanical, electrical and plumbing seismic and vibration analysis and inspections are required and must include the seismic protection for electrical raceways, and equipment; plumbing, piping and related equipment; and, seismic protection for mechanical systems.

B. Testing, inspections and source quality control may occur on or off project site. Perform off-

site testing as required by Architect or Owner.

C. Reports will be submitted by independent firm to Architect, Contractor, and authority having jurisdiction, in duplicate, indicating observations and results of tests and indicating compliance or non-compliance with Contract Documents.

1. Submit final report indicating correction of Work previously reported as non-compliant.

D. Cooperate with independent firm; furnish samples of materials, design mix, equipment, tools, storage, safe access, and assistance by incidental labor as requested.

1. Notify Architect and independent firm 48 hours prior to expected time for operations requiring services.

2. Make arrangements with independent firm and pay for additional samples and tests required for Contractor's use.

E. Testing and employment of testing agency or laboratory shall not relieve Contractor of obligation to perform Work in accordance with requirements of Contract Documents.

F. Re-testing or re-inspection required because of non-conformance to specified requirements shall be performed by same independent firm on instructions by Architect. Payment for re-testing or re-inspection will be charged to Contractor by deducting testing charges from Contract Sum/Price.

G. Agency Responsibilities:
1. Test samples of mixes submitted by Contractor.
2. Provide qualified personnel at site. Cooperate with Architect and Contractor in performance of services.
3. Perform specified sampling and testing of products in accordance with specified standards.
4. Ascertain compliance of materials and mixes with requirements of Contract Documents.
5. Promptly notify Architect and Contractor of observed irregularities or non-conformance of Work or products.
6. Perform additional tests required by Architect.
7. Attend preconstruction meetings and progress meetings.

H. Agency Reports: After each test, promptly submit two copies of report to Architect, Contractor, and authority having jurisdiction. When requested by Architect, provide interpretation of test results. Include the following:
1. Date issued.
2. Project title and number.
3. Name of inspector.
4. Date and time of sampling or inspection.
5. Identification of product and specifications section.
6. Location in Project.
7. Type of inspection or test.
8. Date of test.
9. Results of tests.
10. Conformance with Contract Documents.

I. Limits On Testing Authority:
1. Agency or laboratory may not release, revoke, alter, or enlarge on requirements of Contract Documents.
2. Agency or laboratory may not approve or accept any portion of the Work.

3. Agency or laboratory may not assume duties of Contractor.
4. Agency or laboratory has no authority to stop the Work.

1.4 MANUFACTURERS' FIELD SERVICES

A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust and balance of equipment as applicable, and to initiate instructions when necessary.

B. Submit qualifications of observer to Architect 30 days in advance of required observations.

C. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

D. Refer to Section 01 33 00 - Submittal Procedures, MANUFACTURERS' FIELD REPORTS article.

PART 2 - PRODUCTS

Not Used.

PART 3 - EXECUTION

Not Used.

STATEMENT OF SPECIAL INSPECTIONS

Project: *Transportation Facility*
Location: *Sandford, NC*

Owner: *Lee County Schools*

Design Professional in Responsible Charge: *Tedd Clippinger, AIA – CRA Associates*
Structural Engineer of Record: *Diane J Thompson, PE Bennett & Pless*

This *Statement of Special Inspections* is submitted as a condition for permit issuance in accordance with the Special Inspection and Structural Testing requirements of the Building Code. It includes a schedule of Special Inspection services applicable to this project as well as the name of the Special Inspection Coordinator and the identity of other approved agencies to be retained for conducting these inspections and tests. This *Statement of Special Inspections* encompass the following disciplines:

☒ Structural ☒ Mechanical/Electrical/Plumbing

☒ Architectural ☐ Other: _____

The Special Inspection Coordinator shall keep records of all inspections and shall furnish inspection reports to the Owner and the Registered Design Professional in Responsible Charge. Discovered discrepancies shall be brought to the immediate attention of the Contractor for correction. If such discrepancies are not corrected, the discrepancies shall be brought to the attention of the Owner and the Registered Design Professional in Responsible Charge. The Special Inspection program does not relieve the Contractor of his or her responsibilities.

Interim reports shall be submitted to the Owner and the Registered Design Professional in Responsible Charge.

Final Report of Special Inspections documenting completion of all required Special Inspections, testing and correction of any discrepancies noted in the inspections shall be submitted prior to issuance of a Certificate of Use and Occupancy.

Job site safety and means and methods of construction are solely the responsibility of the Contractor.

Interim Report Frequency: *WEEKLY* or ☐ per attached schedule.

Prepared by:

_____
(type or print name)

_____
Signature Date

Owner's Authorization:

_____
Signature Date

Building Official's Acceptance:

_____
Signature Date

SCHEDULE OF INSPECTION AND TESTING AGENCIES

This Statement of Special Inspections / Quality Assurance Plan includes the following building systems:

- ☒ Soils and Foundations
- ☒ Cast-in-Place Concrete
- ☐ Precast Concrete
- ☒ Masonry
- ☒ Structural Steel
- ☐ Cold-Formed Steel Framing
- ☐ Retaining Walls Taller than 5'
- ☐ Deep Foundations
- ☐ Spray Fire Resistant Material
- ☐ Wood Construction
- ☐ Exterior Insulation and Finish System
- ☒ Mechanical & Electrical Systems
- ☒ Architectural Systems
- ☐ Seismic Requirements
- ☐ Other

Special Inspection Agencies	**Firm**	**Address, Telephone, e-mail**
1. Special Inspections	*SI*	*OWNER TO PROVIDE*
2. Structural Engineer of Record	*Bennett & Pless*	*5340 Wade Park Blvd* *Suite 400* *Raleigh, NC 27607* *919.832.5587*
3. Testing Laboratory	*ITL*	*OWNER TO PROVIDE*
6. Other		

Note: The inspectors and testing agencies shall be engaged by the Owner or the Owner's Agent, and not by the Contractor or Subcontractor whose work is to be inspected or tested. Any conflict of interest must be disclosed to the Building Official, prior to commencing work.

QUALITY ASSURANCE PLAN

Quality Assurance for Seismic Resistance

Seismic Design Category	*C*

Quality Assurance for Wind Requirements

Basic Wind Speed (3 second gust)	*116 mph*
Wind Exposure Category	*C*

Statement of Responsibility

Each contractor responsible for the construction of a main wind- or seismic-force-resisting system, designated seismic system or a wind- or seismic-resisting component listed in the statement of special inspections shall submit a written statement of responsibility to the building official and the owner prior to the commencement of work on the system or component. The contractor's statement of responsibility shall contain the following:

a. Acknowledgment of awareness of the special requirements contained in the statement of special inspections;
b. Acknowledgment that control will be exercised to obtain conformance with the construction documents approved by the building official;
c. Procedures for exercising control within the contractor's organization, the method and frequency of reporting and the distribution of the reports; and
d. Identification and qualifications of the person(s) exercising such control and their position(s) in the organization.

SCHEDULE OF SPECIAL INSPECTIONS

Refer to the Structural Drawings for the Schedule of Special Inspections

FINAL REPORT OF SPECIAL INSPECTIONS

Project: *Transportation Facility*

Location: *Sandford, NC*

Owner: *Lee County Schools*

Design Professional in Responsible Charge: *Tedd Clippinger , AIA – CRA Associates*

To the best of my information, knowledge and belief, the Special Inspections required for this project, and itemized in the State of Special Inspections submitted for permit, have been performed and all discovered discrepancies have been reported and resolved other than the following:

Comments:

(Attach continuation sheets if required to complete the description of corrections).

Interim reports submitted prior to this final report form a basis for and are to be considered an integral part of this final report.

Respectfully submitted,
Special Inspector

Licensed Professional Seal

_____

Signature Date

FINAL REPORT OF SPECIAL INSPECTIONS

AGENTS FINAL REPORT

Project: *Transportation Facility*

Location: *Sandford, NC*

Owner: *Lee County Schools*

Design Professional in Responsible Charge: *Tedd Clippinger, AIA*

To the best of my information, knowledge and belief, the Special Inspections or testing required for this project, and designated for this Agent in the *Statement of Special Inspections* submitted for permit, have been performed and all discovered discrepancies have been reported and resolved other than the following:

Comments:

(Attach continuation sheets if required to complete the description of corrections).

Interim reports submitted prior to this final report form a basis for and are to be considered an integral part of this final report.

Respectfully submitted,

Agent of the Special Inspector

Licensed Professional Seal

Signature Date

END OF SECTION 01 45 00

S ECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.

1.3 USE CHARGES

A. Installation, removal, and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities engaged in the Project to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, testing agencies, and authorities having jurisdiction.

B. Sewer Service: Owner will pay sewer-service use charges for sewer usage by all entities for construction operations.

C. Water Service: Owner will pay water-service use charges for water used by all entities for construction operations.

D. Electric Power Service: Owner will pay electric-power-service use charges for electricity used by all entities for construction operations.

E. Provide connections and extensions of services as required for construction operations.

1.4 INFORMATIONAL SUBMITTALS

A. Site Utilization Plan: Show temporary facilities, temporary utility lines and connections, staging areas, construction site entrances, vehicle circulation, and parking areas for construction personnel.

B. Project Identification and Temporary Signs: Show fabrication and installation details, including plans, elevations, details, layouts, typestyles, graphic elements, and message content.

C. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.

D. Moisture- and Mold-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage and mold. Describe delivery, handling, storage, installation, and protection provisions for materials subject to water absorption or water damage.

1. Indicate procedures for discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and requirements for replacing water-damaged Work.
2. Indicate sequencing of work that requires water, such as sprayed fire-resistive materials, plastering, and terrazzo grinding, and describe plans for dealing with water from these operations. Show procedures for verifying that wet construction has dried sufficiently to permit installation of finish materials.
3. Indicate methods to be used to avoid trapping water in finished work.

E. Dust- and HVAC-Control Plan: Submit coordination drawing and narrative that indicates the dust- and HVAC-control measures proposed for use, proposed locations, and proposed time frame for their operation. Include the following:

1. HVAC system isolation schematic drawing.
2. Location of proposed air-filtration system discharge.
3. Waste-handling procedures.
4. Other dust-control measures.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Chain-Link Fencing: Minimum 2-inch (50-mm), 0.148-inch- (3.8-mm-) thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet (1.8 m) high with galvanized-steel pipe posts; minimum 2-3/8-inch- (60-mm-) OD line posts and 2-7/8-inch- (73-mm-) OD corner and pull posts, with 1-5/8-inch- (42-mm-) OD top rails.

B. Portable Chain-Link Fencing: Minimum 2-inch (50-mm), 0.148-inch- (3.8-mm-) thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet (1.8 m) high with galvanized-steel pipe posts; minimum 2-3/8-inch- (60-mm-) OD line posts and 2-7/8-inch- (73-mm-) OD corner and pull posts, with 1-5/8-inch- (42-mm-) OD top and bottom rails. Provide galvanized-steel bases for supporting posts.

C. Dust-Control Adhesive-Surface Walk-Off Mats: Provide mats, minimum 36 by 60 inches (914 by 1524 mm).

2.2 TEMPORARY FACILITIES

A. Field Offices: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.

B. Common-Use Field Office: Of sufficient size to accommodate needs of Owner, Architect, and construction personnel office activities and to accommodate Project meetings specified in other Division 01 Sections. Keep office clean and orderly. Furnish and equip offices as follows:

1. Furniture required for Project-site documents, including file cabinets, plan tables, plan racks, and bookcases.
2. Conference room of sufficient size to accommodate meetings of 12 individuals. Provide electrical power service and 120-V ac duplex receptacles, with no fewer than one receptacle on each wall. Furnish room with conference table, chairs, and 4-foot- (1.2-m-) square tack and marker boards.
3. Drinking water and private toilet.
4. Heating and cooling equipment necessary to maintain a uniform indoor temperature of 68 to 72 deg F (20 to 22 deg C).
5. Lighting fixtures capable of maintaining average illumination of 20 fc (215 lx) at desk height.

C. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.

1. Store combustible materials apart from building.

2.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.

1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
2. Heating, Cooling, and Dehumidifying Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

PART 3 - EXECUTION

3.1 TEMPORARY FACILITIES, GENERAL

A. Conservation: Coordinate construction and use of temporary facilities with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

3.2 INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

1. Locate facilities to limit site disturbance as specified in Section 011000 "Summary."

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.3 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.

B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

1. Connect temporary sewers to municipal system as directed by authorities having jurisdiction.

C. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction.

D. Sanitary Facilities: Provide temporary toilets, wash facilities, safety shower and eyewash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.

E. Temporary Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

1. Provide temporary dehumidification systems when required to reduce ambient and substrate moisture levels to level required to allow installation or application of finishes and their proper curing or drying.

F. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.

1. Install electric power service overhead unless otherwise indicated.

G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

H. Telephone Service: Provide temporary telephone service in common-use facilities for use by all construction personnel. Install WiFi cell phone access equipment for each field office.

1. At each telephone, post a list of important telephone numbers.

a. Police and fire departments.
b. Ambulance service.
c. Contractor's home office.
d. Contractor's emergency after-hours telephone number.
e. Architect's office.
f. Engineers' offices.
g. Owner's office.
h. Principal subcontractors' field and home offices.

I. Electronic Communication Service: Provide secure WiFi wireless connection to internet with provisions for access by Architect and Owner.

3.4 SUPPORT FACILITIES INSTALLATION

A. Comply with the following:

1. Utilize designated area within existing building for temporary field offices.
2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

B. Traffic Controls: Comply with requirements of authorities having jurisdiction.

1. Protect existing site improvements to remain, including curbs, pavement, and utilities.

2. Maintain access for fire-fighting equipment and access to fire hydrants.

C. Parking: Use designated areas of Owner's existing parking areas for construction personnel.

D. Storage and Staging: Use designated areas of Project site for storage and staging needs.

E. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.

1. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.

a. Provide temporary, directional signs for construction personnel and visitors.

2. Maintain and touch up signs, so they are legible at all times.

F. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."

3.5 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

1. Comply with work restrictions specified in Section 011000 "Summary."

C. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.

D. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.

E. Temporary Partitions: Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate areas occupied by Owner from fumes and noise.

F. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.

1. Prohibit smoking in construction areas. Comply with additional limits on smoking specified in other Sections.
2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition in accordance with requirements of authorities having jurisdiction.

3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign, stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

3.6 MOISTURE AND MOLD CONTROL

A. Moisture and Mold Protection: Protect stored materials and installed Work in accordance with Moisture and Mold Protection Plan.

B. Controlled Construction Period: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Use temporary or permanent HVAC system to control humidity within ranges specified for installed and stored materials.
3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.

    a. Hygroscopic materials that may support mold growth, including wood and gypsum-based products, that become wet during the course of construction and remain wet for 48 hours are considered defective and require replacing.
    b. Measure moisture content of materials that have been exposed to moisture during construction operations or after installation. Record readings beginning at time of exposure and continuing daily for 48 hours. Identify materials containing moisture levels higher than allowed. Report findings in writing to Architect.
    c. Remove and replace materials that cannot be completely restored to their manufactured moisture level within 48 hours.

3.7 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor.

2. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

1. Section 011000 "Summary" for Contractor requirements related to Owner-furnished products.
2. Section 012100 "Allowances" for products selected under an allowance.
3. Section 012300 "Alternates" for products selected under an alternate.
4. Section 012500 "Substitution Procedures" for requests for substitutions.
5. Section 014200 "References" for applicable industry standards for products specified.
6. Section 01770 "Closeout Procedures" for submitting warranties.

1.3 DEFINITIONS

A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
2. New Products: Items that have not previously been incorporated into another project or facility. Salvaged items or items reused from other projects are not considered new products. Items that are manufactured or fabricated to include recycled content materials are considered new products, unless indicated otherwise.
3. Comparable Product: Product by named manufacturer that is demonstrated and approved through the comparable product submittal process described in Part 2 "Comparable Products" Article, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model

number or other designation. Published attributes and characteristics of basis-of-design product establish salient characteristics of products.

1. Evaluation of Comparable Products: In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification. Manufacturer's published attributes and characteristics of basis-of-design product also establish salient characteristics of products for purposes of evaluating comparable products.

C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications; submit a comparable product request or substitution request, if applicable.

D. Comparable Product Request Submittal: An action submittal requesting consideration of a comparable product, including the following information:

1. Identification of basis-of-design product or fabrication or installation method to be replaced, including Specification Section number and title and Drawing numbers and titles.
2. Data indicating compliance with the requirements specified in Part 2 "Comparable Products" Article.

E. Basis-of-Design Product Specification Submittal: An action submittal complying with requirements in Section 013300 "Submittal Procedures."

F. Substitution: Refer to Section 012500 "Substitution Procedures" for definition and limitations on substitutions.

1.4 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1. Resolution of Compatibility Disputes between Multiple Contractors:

a. Contractors are responsible for providing products and construction methods compatible with products and construction methods of other contractors.
b. If a dispute arises between the multiple contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.

B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.

1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is not conspicuous.
2. Equipment Nameplates: Provide a permanent nameplate on each item of service- or power-operated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:

a. Name of product and manufacturer.
b. Model and serial number.
c. Capacity.
d. Speed.
e. Ratings.

3. See individual identification Sections in Divisions 21, 22, 23, and 26 for additional equipment identification requirements.

1.5 COORDINATION

A. Modify or adjust affected work as necessary to integrate work of approved comparable products and approved substitutions.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products, using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to determine compliance with the Contract Documents and that products are undamaged and properly protected.

C. Storage:

1. Provide a secure location and enclosure at Project site for storage of materials and equipment.
2. Store products to allow for inspection and measurement of quantity or counting of units.

3. Store materials in a manner that will not endanger Project structure.
4. Store products that are subject to damage by the elements under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation and with adequate protection from wind.
5. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
7. Protect stored products from damage and liquids from freezing.
8. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written standard warranty form furnished by individual manufacturer for a particular product and issued in the name of the Owner or endorsed by manufacturer to Owner.
2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner and issued in the name of the Owner or endorsed by manufacturer to Owner.

B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included in the Project Manual, prepare a written document, using indicated form properly executed.
3. See other Sections for specific content requirements and particular requirements for submitting special warranties.

C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.

2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
4. Where products are accompanied by the term "as selected," Architect will make selection.
5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.

B. Product Selection Procedures:

1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

    a. Sole product may be indicated by the phrase "Subject to compliance with requirements, provide the following."

2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

    a. Sole manufacturer/source may be indicated by the phrase "Subject to compliance with requirements, provide products by the following."

3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

    a. Limited list of products may be indicated by the phrase "Subject to compliance with requirements, provide one of the following."

4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed or an unnamed product that complies with requirements.

    a. Non-limited list of products is indicated by the phrase "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of an unnamed product is not considered a substitution, if the product complies with requirements.

5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

    a. Limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, provide products by one of the following."

6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed or a product by an unnamed manufacturer that complies with requirements.

    a. Non-limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of products of an unnamed manufacturer is not considered a substitution, if the product complies with requirements.

7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications may additionally indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

    a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.

C. Visual Matching Specification: Where Specifications require the phrase "match Architect's sample," provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.

    1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.

D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or a similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with the following requirements:

1. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work.
2. Detailed comparison of significant qualities of proposed product with those of the named basis-of-design product. Significant product qualities include attributes, such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects, with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

B. Architect's Action on Comparable Products Submittal: If necessary, Architect will request additional information or documentation for evaluation, as specified in Section 013300 "Submittal Procedures."

1. Form of Approval of Submittal: As specified in Section 013300 "Submittal Procedures."
2. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

C. Submittal Requirements, Two-Step Process: Approval by the Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

D. Submittal Requirements, Single-Step Process: When acceptable to Architect, incorporate specified submittal requirements of individual Specification Section in combined submittal for comparable products. Approval by the Architect of Contractor's request for use of comparable product and of individual submittal requirements will also satisfy other submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes general administrative and procedural requirements governing execution of the Work, including, but not limited to, the following:

1. Construction layout.
2. Installation of the Work.
3. Cutting and patching.
4. Coordination of Owner's portion of the Work.
5. Coordination of Owner-installed products.
6. Progress cleaning.
7. Starting and adjusting.
8. Protection of installed construction.

B. Related Requirements:

1. Section 011000 "Summary" for coordination of Owner-furnished products, Owner's separate contracts, and limits on use of Project site.
2. Section 013300 "Submittal Procedures" for submitting surveys.
3. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, replacing defective work, and final cleaning.

1.3 DEFINITIONS

A. Cutting: Removal of in-place construction necessary to permit installation or performance of subsequent work.

B. Patching: Fitting and repair work required to restore construction to original conditions after installation of subsequent work.

1.4 INFORMATIONAL SUBMITTALS

A. Cutting and Patching Plan: Submit plan describing procedures at least 10 days prior to the time cutting and patching will be performed. Include the following information:

1. Extent: Describe reason for and extent of each occurrence of cutting and patching.

2. Changes to In-Place Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building appearance and other significant visual elements.
3. Products: List products to be used for patching and firms or entities that will perform patching work.
4. Dates: Indicate when cutting and patching will be performed.
5. Utilities and Mechanical and Electrical Systems: List services and systems that cutting and patching procedures will disturb or affect. List services and systems that will be relocated and those that will be temporarily out of service. Indicate length of time permanent services and systems will be disrupted.

1.5 QUALITY ASSURANCE

A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.

1. Structural Elements: When cutting and patching structural elements, or when encountering the need for cutting and patching of elements whose structural function is not known, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include the following:

    a. Primary operational systems and equipment.
    b. Fire separation assemblies.
    c. Mechanical systems piping and ducts.
    d. Control systems.
    e. Communication systems.
    f. Fire-detection and -alarm systems.
    g. Electrical wiring systems.
    h. Operating systems of special construction.

3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Other construction elements include but are not limited to the following:

    a. Water, moisture, or vapor barriers.
    b. Membranes and flashings.
    c. Equipment supports.
    d. Piping, ductwork, vessels, and equipment.
    e. Noise- and vibration-control elements and systems.

4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner

that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of specified products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Comply with requirements specified in other Sections.

B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials. Use materials that are not considered hazardous.

C. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

B. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:

1. Description of the Work, including Specification Section number and paragraph, and Drawing sheet number and detail, where applicable.
2. List of detrimental conditions, including substrates.
3. List of unacceptable installation tolerances.
4. Recommended corrections.

C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect in accordance with requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks and existing conditions. If discrepancies are discovered, notify Architect promptly.

3.4 INSTALLATION

A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.

1. Make vertical work plumb, and make horizontal work level.
2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
4. Maintain minimum headroom clearance of 96 inches (2440 mm) in occupied spaces and 90 inches (2300 mm) in unoccupied spaces, unless otherwise indicated on Drawings.

B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

C. Install products at the time and under conditions that will ensure satisfactory results as judged by Architect. Maintain conditions required for product performance until Substantial Completion.

D. Conduct construction operations, so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy of type expected for Project.

E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on-site and placement in permanent locations.

F. Tools and Equipment: Select tools or equipment that minimize production of excessive noise levels.

G. Templates: Obtain and distribute to the parties involved templates for Work specified to be factory prepared and field installed. Check Shop Drawings of other portions of the Work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.

H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions with manufacturer.

1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
2. Allow for building movement, including thermal expansion and contraction.
3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

I. Joints: Make joints of uniform width. Where joint locations in exposed Work are not indicated, arrange joints for the best visual effect, as judged by Architect. Fit exposed connections together to form hairline joints.

J. Repair or remove and replace damaged, defective, or nonconforming Work.

1. Comply with Section 017700 "Closeout Procedures" for repairing or removing and replacing defective Work.

3.5 CUTTING AND PATCHING

A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.

C. Temporary Support: Provide temporary support of Work to be cut.

D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.

E. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching in accordance with requirements in Section 011000 "Summary."

F. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
6. Proceed with patching after construction operations requiring cutting are complete.

G. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as practicable, as judged by Architect. Provide materials and comply with installation requirements specified in other Sections, where applicable.

1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.

    a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
    b. Restore damaged pipe covering to its original condition.

3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall

coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch, corner to corner of wall and edge to edge of ceiling. Provide additional coats until patch blends with adjacent surfaces.

4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.

H. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.6 PROGRESS CLEANING

A. Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.

1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F (27 deg C).
3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

a. Use containers intended for holding waste materials of type to be stored.

B. Work Areas: Clean areas where Work is in progress to the level of cleanliness necessary for proper execution of the Work.

1. Remove liquid spills promptly.
2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

C. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.

D. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

E. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.

F. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.

G. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

H. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

I. Limiting Exposures: Supervise construction operations to ensure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.7 STARTING AND ADJUSTING

A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.

B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.

C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

D. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements."

3.8 PROTECTION AND REPAIR OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

B. Repair Work previously completed and subsequently damaged during construction period. Repair to like-new condition.

C. Protection of Existing Items: Provide protection and ensure that existing items to remain undisturbed by construction are maintained in condition that existed at commencement of the Work.

D. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 017300

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:

1. Inspection procedures.
2. Warranties.
3. Final cleaning.

B. Related Sections include the following:

1. Section 012900 "Payment Procedures" for requirements for Applications for Payment for Substantial Completion and Final Completion.
2. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
3. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.

1.3 SUBSTANTIAL COMPLETION

A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.

1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
2. Advise Owner of pending insurance changeover requirements.
3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
5. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
6. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
7. Complete startup testing of systems.
8. Submit test/adjust/balance records.

9. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
10. Advise Owner of changeover in heat and other utilities.
11. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
12. Complete final cleaning requirements, including touchup painting.
13. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for Final Completion.

1.4 FINAL COMPLETION

A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:

1. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."
2. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems, as specified in Division 1 Section “Demonstration and Training.”

B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
3. Include the following information at the top of each page:

    a. Project name.
    b. Date.
    c. Name of Architect.
    d. Name of Contractor.
    e. Page number.

1.6 WARRANTIES

A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.

B. Partial Occupancy: Submit properly executed warranties within 30 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.

C. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.

1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (215-by-280-mm) paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

B. Use the least toxic cleaning agents necessary to meet requirements.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:

a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
c. Remove tools, construction equipment, machinery, and surplus material from Project site.
d. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
e. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
f. Sweep concrete floors broom clean in unoccupied spaces.
g. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo with product recommended by carpet manufacturer if visible soil or stains remain.
h. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
i. Remove labels that are not permanent.
j. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.

1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.

k. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
l. Replace parts subject to unusual operating conditions.
m. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
n. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.

o. Clean ducts, blowers, and coils if units were operated without filters during construction.
p. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
q. Leave Project clean and ready for occupancy.

C. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.

END OF SECTION 017700

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:

1. Operation and maintenance documentation directory manuals.
2. Emergency manuals.
3. Systems and equipment operation manuals.
4. Systems and equipment maintenance manuals.
5. Product maintenance manuals.

B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.

1.3 DEFINITIONS

A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.

B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 CLOSEOUT SUBMITTALS

A. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.

1. Architect will comment on whether content of operation and maintenance submittals is acceptable.
2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.

B. Format: Submit operation and maintenance manuals in the following format:

1. Submit on digital media acceptable to Architect by uploading to web-based project software site or by email to Architect. Enable reviewer comments on draft submittals.

C. Initial Manual Submittal: Submit draft copy of each manual at least 30 days before commencing demonstration and training. Architect will comment on whether general scope and content of manual are acceptable.

D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.

1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.

E. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

1.5 FORMAT OF OPERATION AND MAINTENANCE MANUALS

A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.

1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

1.6 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:

1. Title page.
2. Table of contents.
3. Manual contents.

B. Title Page: Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.

3. Name and address of Owner.
4. Date of submittal.
5. Name and contact information for Contractor.
6. Name and contact information for Construction Manager.
7. Name and contact information for Architect.
8. Name and contact information for Commissioning Authority.
9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
10. Cross-reference to related systems in other operation and maintenance manuals.

C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.7 EMERGENCY MANUALS

A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.

B. Content: Organize manual into a separate section for each of the following:

1. Type of emergency.
2. Emergency instructions.
3. Emergency procedures.

C. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:

1. Fire.
2. Flood.
3. Gas leak.
4. Water leak.
5. Power failure.
6. Water outage.
7. System, subsystem, or equipment failure.

8. Chemical release or spill.

D. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.

E. Emergency Procedures: Include the following, as applicable:

1. Instructions on stopping.
2. Shutdown instructions for each type of emergency.
3. Operating instructions for conditions outside normal operating limits.
4. Required sequences for electric or electronic systems.
5. Special operating instructions and procedures.

1.8 SYSTEMS AND EQUIPMENT OPERATION MANUALS

A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:

1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
2. Performance and design criteria if Contractor has delegated design responsibility.
3. Operating standards.
4. Operating procedures.
5. Operating logs.
6. Wiring diagrams.
7. Control diagrams.
8. Piped system diagrams.
9. Precautions against improper use.
10. License requirements including inspection and renewal dates.

C. Descriptions: Include the following:

1. Product name and model number. Use designations for products indicated on Contract Documents.
2. Manufacturer's name.
3. Equipment identification with serial number of each component.
4. Equipment function.
5. Operating characteristics.
6. Limiting conditions.

7. Performance curves.
8. Engineering data and tests.
9. Complete nomenclature and number of replacement parts.

D. Operating Procedures: Include the following, as applicable:

1. Startup procedures.
2. Equipment or system break-in procedures.
3. Routine and normal operating instructions.
4. Regulation and control procedures.
5. Instructions on stopping.
6. Normal shutdown instructions.
7. Seasonal and weekend operating instructions.
8. Required sequences for electric or electronic systems.
9. Special operating instructions and procedures.

E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

F. Piped Systems: Diagram piping as installed, and identify color coding where required for identification.

1.9 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds as described below.

C. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:

1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component

incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.

a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.

2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
3. Identification and nomenclature of parts and components.
4. List of items recommended to be stocked as spare parts.

E. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:

1. Test and inspection instructions.
2. Troubleshooting guide.
3. Precautions against improper maintenance.
4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
5. Aligning, adjusting, and checking instructions.
6. Demonstration and training video recording, if available.

F. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.

1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.

G. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

H. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.

I. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

J. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.

1. Do not use original project record documents as part of maintenance manuals.

1.10 PRODUCT MAINTENANCE MANUALS

A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Product Information: Include the following, as applicable:

1. Product name and model number.
2. Manufacturer's name.
3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

E. Maintenance Procedures: Include manufacturer's written recommendations and the following:

1. Inspection procedures.
2. Types of cleaning agents to be used and methods of cleaning.
3. List of cleaning agents and methods of cleaning detrimental to product.
4. Schedule for routine cleaning and maintenance.
5. Repair instructions.

F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 017823

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for Project Record Documents, including the following:

1. Record Drawings.
2. Record specifications.
3. Record Product Data.
4. Miscellaneous record submittals.

B. Related Requirements:

1. Section 017700 "Closeout Procedures" for general closeout procedures.

1.3 CLOSEOUT SUBMITTALS

A. Record Drawings: Comply with the following:

1. Number of Copies: Submit copies of Record Drawings as follows:

a. Initial Submittal:

1) Submit PDF electronic files of scanned record prints and one set(s) of file prints.
2) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.

b. Final Submittal:

1) Submit PDF electronic files of scanned Record Prints and three set(s) of file prints.
2) Print each drawing, whether or not changes and additional information were recorded.

B. Record Specifications: Submit annotated PDF electronic files of Project's Specifications, including addenda and Contract modifications.

C. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.

1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.

1.4 RECORD DRAWINGS

A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation, where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

    a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    b. Accurately record information in an acceptable drawing technique.
    c. Record data as soon as possible after obtaining it.
    d. Record and check the markup before enclosing concealed installations.
    e. Cross-reference record prints to corresponding photographic documentation.

2. Content: Types of items requiring marking include, but are not limited to, the following:

    a. Dimensional changes to Drawings.
    b. Revisions to details shown on Drawings.
    c. Depths of foundations.
    d. Locations and depths of underground utilities.
    e. Revisions to routing of piping and conduits.
    f. Revisions to electrical circuitry.
    g. Actual equipment locations.
    h. Duct size and routing.
    i. Locations of concealed internal utilities.
    j. Changes made by Change Order or Construction Change Directive.
    k. Changes made following Architect's written orders.
    l. Details not on the original Contract Drawings.
    m. Field records for variable and concealed conditions.
    n. Record information on the Work that is shown only schematically.

3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
4. Mark record prints with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
5. Mark important additional information that was either shown schematically or omitted from original Drawings.
6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:

1. Format: Annotated PDF electronic file.
2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
3. Refer instances of uncertainty to Architect for resolution.
4. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.

    a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
    b. Architect will provide data file layer information. Record markups in separate layers.

C. Format: Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Format: Annotated PDF electronic file.
3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
4. Identification: As follows:

    a. Project name.
    b. Date.
    c. Designation "PROJECT RECORD DRAWINGS."
    d. Name of Architect.
    e. Name of Contractor.

1.5 RECORD SPECIFICATIONS

A. Preparation: Mark Specifications to indicate the actual product installation, where installation varies from that indicated in Specifications, addenda, and Contract modifications.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Note related Change Orders, Record Product Data, and Record Drawings where applicable.

B. Format: Submit record specifications as annotated PDF electronic file.

1.6 RECORD PRODUCT DATA

A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and revisions to Project Record Documents as they occur; do not wait until end of Project.

B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
3. Note related Change Orders, Record Specifications, and Record Drawings where applicable.

C. Format: Submit Record Product Data as annotated PDF electronic file.

1. Include Record Product Data directory organized by Specification Section number and title, electronically linked to each item of Record Product Data.

1.7 MAINTENANCE OF RECORD DOCUMENTS

A. Maintenance of Record Documents: Store Record Documents in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 017839

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:

1. Instruction in operation and maintenance of systems, subsystems, and equipment.

A. Related Requirements:

1. Section 117310 "Vertical Lifts" for estimate of instruction time required in operation of vertical lifts.
2. Section 117510 "Shop Equipment" for estimate of instruction time required in use of shop equipment.

1.3 INFORMATIONAL SUBMITTALS

A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.

1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.

B. Qualification Data: For instructor.

C. Attendance Record: For each training module, submit list of participants and length of instruction time.

D. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

1.4 QUALITY ASSURANCE

A. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.

B. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:

1. Inspect and discuss locations and other facilities required for instruction.
2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
3. Review required content of instruction.
4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

1.5 COORDINATION

A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.

B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.

C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

1.6 INSTRUCTION PROGRAM

A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.

B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:

1. Basis of System Design, Operational Requirements, and Criteria: Include the following:

a. System, subsystem, and equipment descriptions.
b. Performance and design criteria if Contractor is delegated design responsibility.
c. Operating standards.
d. Regulatory requirements.
e. Equipment function.
f. Operating characteristics.
g. Limiting conditions.

h. Performance curves.

2. Documentation: Review the following items in detail:

   a. Emergency manuals.
   b. Systems and equipment operation manuals.
   c. Systems and equipment maintenance manuals.
   d. Product maintenance manuals.
   e. Project Record Documents.
   f. Identification systems.
   g. Warranties and bonds.
   h. Maintenance service agreements and similar continuing commitments.

3. Emergencies: Include the following, as applicable:

   a. Instructions on meaning of warnings, trouble indications, and error messages.
   b. Instructions on stopping.
   c. Shutdown instructions for each type of emergency.
   d. Operating instructions for conditions outside of normal operating limits.
   e. Sequences for electric or electronic systems.
   f. Special operating instructions and procedures.

4. Operations: Include the following, as applicable:

   a. Startup procedures.
   b. Equipment or system break-in procedures.
   c. Routine and normal operating instructions.
   d. Regulation and control procedures.
   e. Control sequences.
   f. Safety procedures.
   g. Instructions on stopping.
   h. Normal shutdown instructions.
   i. Operating procedures for emergencies.
   j. Operating procedures for system, subsystem, or equipment failure.
   k. Seasonal and weekend operating instructions.
   l. Required sequences for electric or electronic systems.
   m. Special operating instructions and procedures.

5. Adjustments: Include the following:

   a. Alignments.
   b. Checking adjustments.
   c. Noise and vibration adjustments.
   d. Economy and efficiency adjustments.

6. Troubleshooting: Include the following:

   a. Diagnostic instructions.
   b. Test and inspection procedures.

7. Maintenance: Include the following:

    a. Inspection procedures.
    b. Types of cleaning agents to be used and methods of cleaning.
    c. List of cleaning agents and methods of cleaning detrimental to product.
    d. Procedures for routine cleaning.
    e. Procedures for preventive maintenance.
    f. Procedures for routine maintenance.
    g. Instruction on use of special tools.

8. Repairs: Include the following:

    a. Diagnosis instructions.
    b. Repair instructions.
    c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
    d. Instructions for identifying parts and components.
    e. Review of spare parts needed for operation and maintenance.

1.7 PREPARATION

A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."

B. Set up instructional equipment at instruction location.

1.8 INSTRUCTION

A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.

B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.

C. Scheduling: Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.

    1. Schedule training with Owner, through Architect with at least seven days' advance notice.

D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.

E. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of [**an oral**] [**a written**] [**a demonstration**] performance-based test.

F. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

PART 2 - PRODUCTS

PART 3 - EXECUTION

END OF SECTION 017900

SECTION 02 41 13 - SELECTIVE SITE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. The provisions of the Contract Documents apply to the work of this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Demolition and removal of existing asphalt and/or concrete pavement, concrete and/or asphalt walks, curbs and gutters, and other exterior site items indicated or not indicated which interfere with the Work.

2. Removal and/or relocation of existing underground utilities.

3. Removal and disposal of existing sanitary sewer pipe, water pipe, storm drainage pipe and appurtenances indicated. Filling of existing pipes to be abandoned in place.

4. Removal and replacement of fencing and playground equipment.

5. Removal and relocation of existing light poles.

6. Removal and disposal of material from dump areas.

1.3 DEFINITIONS

A. Remove: Remove and legally dispose of items except those indicated to be reinstalled, salvaged, or to remain the Owner's property.

B. Remove and Salvage: Items indicated to be removed and salvaged remain the Owner's property. Remove, clean, and pack or crate items to protect against damage. Identify contents of containers and deliver to Owner's designated storage area.

C. Remove and Reinstall: Remove items indicated; clean, service, and otherwise prepare them for reuse; store and protect against damage. Reinstall items in the same locations or in locations indicated.

D. Existing to Remain: Protect items indicated to remain against damage and soiling. When permitted by the Architect, items may be removed to a suitable, protected storage location and then cleaned and reinstalled in their original locations.

1.4 MATERIALS OWNERSHIP

A. Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain the Owner's property, remove demolished materials from the site with further disposition at the Contractor's option.

B. Storage or sale of removed items or materials on-site will not be permitted

C. Historical items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, antiques, and other items of interest or value to the Owner, which may be encountered, remain the Owner's property. Carefully remove and salvage each item or object in a manner to prevent damage and deliver promptly to the Owner.

1.5 SUBMITTALS

A. Photographs or videotape, sufficiently detailed, of existing conditions of adjoining construction and site improvements that might be misconstrued as damage caused by the Work.

B. Record drawings at Project closeout.

1. Identify and accurately locate capped utilities and other subsurface structural, electrical, or mechanical conditions.

C. Proposed dust-control measures.

D. Schedule of selective demolition activities indicating the following:

1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity.

2. Interruption of utility services.

3. Coordination for shutoff, capping, and continuation of utility services.

4. Detailed sequence of selective demolition and removal work to ensure uninterrupted progress of Owner's on-site operations.

5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.

6. Locations of temporary partitions and means of egress.

E. Inventory of items to be removed and salvaged or turned over to Owner.

F. Landfill records indicating receipt and acceptance of hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.6 QUALITY ASSURANCE

A. Regulatory Requirements: All work shall comply with Federal, State and Local laws and regulations concerning hauling and disposal of demolition debris.

B. Notify the proper agencies prior to the start of work and obtain all necessary permits for this work.

1.7 PROJECT CONDITIONS

A. Owner assumes no responsibility for actual condition of items or structures to be demolished. Conditions existing at the time of inspection for bidding purposes will be maintained by the Owner to the extent practical. However, minor variations may occur due to Owner's removal and salvage operations prior to the start of demolition work.

B. The location of existing underground utilities indicated is approximate only. Field locate all existing underground utilities in the area of work, regardless of whether or not they are indicated. Call NC one call at 1-800-632-4949 prior to the start of demolition work for assistance in the location of existing underground utilities.

C. Should charted, uncharted or incorrectly charted utilities be encountered during demolition, contact the Architect immediately for instructions. Cooperate with Owner and utility companies to keep services and facilities in operation.

D. Do not interrupt existing utilities serving facilities occupied and used by the Owner and others, except when permitted in writing by the Owner. Provide acceptable temporary utility service as required to maintain Owner's operations.

1.8 SCHEDULING

A. Owner will occupy portions of the building immediately adjacent to the Work. Conduct selective demolition so that the Owner's operations will not be disrupted. Provide not less than 72 hours notice to Owner of activities that will affect Owner's operations.

B. Arrange selective demolition schedule so as not to interfere with Owner's on-site operations.

C. Notify and coordinate any required relocation and/or removal of existing underground utilities, poles, meters or other above ground appurtenances with the appropriate utility company (i.e. power, telephone, cable and natural gas/propane) prior to the start of selective demolition work.

1.9 PAYMENT FOR UTILITY REMOVAL / RELOCATIONS

A. Electric Service

B. Phone Service

C. Cable Television

D. Gas

E. Fiber Optic Lines

F.Petroleum Pipelines

1.10 USE OF EXPLOSIVES

A. Do not use explosives to perform selective site demolition work.

PART 2 - PRODUCTS

PART 3 - EXECUTION

3.1 EXAMINATION

A. Call NC one call at 1-800-632-4949 prior to the start of demolition work for assistance in the location of existing underground utilities. Field locate all existing underground utilities in the area of work, regardless of whether or not they are indicated.

B. Should uncharted or incorrectly charted existing utilities be identified, contact the Architect immediately for instructions. Provide a scale drawing with the location of the uncharted or incorrectly charted utilities for use by the Architect in preparing additional direction.

C. Verify that utilities indicated as removed, abandoned and/or relocated have been disconnected and capped.

D. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.

E. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged and turned over to the Owner.

3.2 PROTECTION OF PERSONS AND PROPERTY

A. Drain, purge, or otherwise remove, collect, and dispose of chemicals, gases, explosives, acids, flammables, or other dangerous materials before proceeding with selective demolition operations.

B. Conduct demolition operations and remove debris to ensure minimum interference with roads, streets, walks and other adjacent occupied and used facilities.

1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by governing regulations.

C. Conduct demolition operations to prevent injury to people and damage to adjacent buildings and facilities to remain. Ensure safe passage of people around selective demolition area.

1. Erect temporary protection, such as walks, fences, railings, canopies, and covered passageways, where required by authorities having jurisdiction.

2. Protect existing site improvements, appurtenances, and landscaping to remain.

D. Barricade areas of demolition occurring as part of this work, and post with warning lights as required by authorities having jurisdiction.

E. Protect structures, buildings, utilities, walks, pavements, existing vegetation and other facilities to remain from damage caused by settlement, lateral movement, undermining, washout and other hazards created by demolition operations.

3.3 POLLUTION CONTROLS

A. Perform all work in accordance with the requirements of the latest edition of the North Carolina Erosion and Sediment Control Planning and Design Manual and those of the local Erosion Control official.

B. Clean adjacent structures and improvements of dust, dirt, and debris caused by the Work. Return adjacent areas to condition existing before start of selective demolition.

3.4 DEMOLITION OF EXISTING FACILITIES

A. Electric Service

1. Coordinate the removal and/or relocation of existing utilities with Power Company.

2. Contact Power Company Representative to arrange for required removal and/or relocation of existing service.

B. Phone Service

1. Coordinate the removal and/or relocation of existing utilities with Phone Company.

2. Contact Phone Company Representative to arrange for required removal and/or relocation of existing service.

C. Cable Television

1. Coordinate the removal and/or relocation of existing utilities with Cable Company.

2. Contact Cable Company Representative to arrange for required removal and/or relocation of existing service.

D. Gas

1. Coordinate the removal and/or relocation of existing utilities with Gas Company.

2. Contact Gas Company Representative to arrange for required removal and/or relocation of existing service.

E. Fiber Optic Lines

1. Coordinate the removal and/or relocation of existing utilities with Fiber Optic Company.

2. Contact Fiber Optic Company Representative to arrange for required removal and/or relocation of existing service.

F. Petroleum Pipelines

1. Coordinate the removal and/or relocation of existing utilities with Petroleum Pipeline Company.

2. Contact Petroleum Pipeline Company Representative to arrange for required removal and/or relocation of existing service.

G. Utilities

1. Coordinate the removal and/or relocation of existing utilities with the appropriate utility companies.

2. Remove existing utilities as indicated and terminate in a manner conforming to the nationally recognized code covering the specific utility and to local jurisdictional codes.

3. Provide adequate means of support and protection during demolition and other construction operations for existing utilities that are to remain in place. Repair utilities damaged by construction operations to the satisfaction of the utility owner.

H. Asphalt Pavement

1. Remove asphalt concrete pavement by sawcutting to the full depth of the pavement. Provide neat sawcuts at the limits of pavement removal indicated.

I. Concrete Pavement, Walks and Curbs

1. Remove concrete pavement and walks to the nearest joint. Sawcut concrete if joints are not present adjacent to the area of demolition.

2. Sawcut concrete along straight lines to a depth of not less than 2 inches. Break out remainder of concrete, provided that the broken area is concealed in the finished work, and the remaining concrete is sound. At locations where the broken face cannot be concealed, grind smooth or sawcut entirely through concrete.

J. Light Poles

1. Remove and relocate light poles as indicated. If light poles are owned by a public utility, coordinate the relocation with them.

K. Fencing

1. Remove existing chain-link fencing as indicated on the drawings.

2. Turn fencing materials removed over to the Owner.

L. Playground Equipment

1. Remove, store and protect existing playground equipment interfering with proposed construction.

2. Turn play equipment over to the Owner for reinstallation following the completion of construction in the area.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

A. Promptly dispose of demolished materials. Do not allow demolished materials to accumulate on-site.

B. Do not burn demolished materials or debris.

C. Transport and legally dispose of demolished materials off of Owner's property.

3.6 CLEANUP AND REPAIR

A. Upon completion of demolition work remove all tools, equipment and demolition materials from site. Remove demolition work area protection and leave areas clean.

B. Repair any demolition performed in excess of that required. Return elements of construction and surfaces to remain to the condition existing prior to the start of construction. Repair adjacent construction or surfaces soiled or damaged by demolition work.

END OF SECTION 02 41 13

SECTION 033000 – CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes cast-in-place concrete for the following:
1. Slabs on deck.
2. Slabs on grade.
3. Piers.
4. Footings.
5. Fill for metal pan stairs
6. Mechanical equipment pads and housekeeping pads.
7. Control, expansion and contraction joint devices.

1.2 REFERENCES

A. American Concrete Institute:
1. ACI 301 - Specifications for Structural Concrete.
2. ACI 305 - Hot Weather Concreting.
3. ACI 306.1 - Standard Specification for Cold Weather Concreting.
4. ACI 308.1 - Standard Specification for Curing Concrete.
5. ACI 318 - Building Code Requirements for Structural Concrete.

B. ASTM International:
1. ASTM B221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes.
2. ASTM C31/C31M - Standard Practice for Making and Curing Concrete Test Specimens in the Field.
3. ASTM C33 - Standard Specification for Concrete Aggregates.
4. ASTM C39 - Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.
5. ASTM C42/C42M - Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete.
6. ASTM C94/C94M - Standard Specification for Ready-Mixed Concrete.
7. ASTM C143/C143M - Standard Test Method for Slump of Hydraulic Cement Concrete.
8. ASTM C150 - Standard Specification for Portland Cement.
9. ASTM C172 - Standard Practice for Sampling Freshly Mixed Concrete.
10. ASTM C173/C173M - Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method.
11. ASTM C231 - Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method.
12. ASTM C260 - Standard Specification for Air-Entraining Admixtures for Concrete.
13. ASTM C330 - Standard Specification for Lightweight Aggregates for Structural Concrete.
14. ASTM C494/C494M - Standard Specification for Chemical Admixtures for Concrete.

15. ASTM C595 - Standard Specification for Blended Hydraulic Cements.
16. ASTM C618 - Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete.
17. ASTM C685/C685M - Standard Specification for Concrete Made By Volumetric Batching and Continuous Mixing.
18. ASTM C845 - Standard Specification for Expansive Hydraulic Cement.
19. ASTM C989 - Standard Specification for Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars.
20. ASTM C1017/C1017M - Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete.
21. ASTM C1064/C1064M - Standard Test Method for Temperature of Freshly Mixed Hydraulic-Cement Concrete.
22. ASTM C1107 - Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink).
23. ASTM C1116 - Standard Specification for Fiber-Reinforced Concrete and Shotcrete.
24. ASTM C1157 - Standard Performance Specification for Hydraulic Cement.
25. ASTM C1218 - Standard Test Method for Water-Soluble Chloride in Mortar and Concrete.
26. ASTM C1240 - Standard Specification for Silica Fume Used in Cementitious Mixtures.
27. ASTM D994 - Standard Specification for Preformed Expansion Joint Filler for Concrete (Bituminous Type).
28. ASTM D1751 - Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types).
29. ASTM D1752 - Standard Specification for Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction.
30. ASTM D6690 - Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements.
31. ASTM E96 - Standard Test Methods for Water Vapor Transmission of Materials.
32. ASTM E119 - Standard Test Methods for Fire Tests of Building Construction and Materials.
33. ASTM E1643 - Standard Practice for Installation of Water Vapor Retarders Used in Contact with Earth or Granular Fill under Concrete Slabs.
34. ASTM E1745 - Standard Specification for Plastic Water Vapor Retarders Used in Contact with Soil or Granular Fill under Concrete Slabs.

1.3 PERFORMANCE REQUIREMENTS

A. Vapor Barrier Permeance: testing results from ASTM F 1249 or ASTM E 96 must state a water vapor transmission rate (WVTR) of less than 0.01 perms (grains/[hour * ft2 * in. Hg])

1.4 SUBMITTALS

A. Section 013300 - Submittal Procedures: Submittal procedures.

B. Product Data: Submit data on joint devices, attachment accessories and admixtures.

C. Design Data:

1. Submit concrete mix design for each concrete strength. Submit separate mix designs when admixtures are required for the following:
   a. Hot and cold weather concrete work.
   b. Air entrained concrete work.
2. Identify mix ingredients and proportions, including admixtures.
3. Identify chloride content of admixtures and whether or not chloride was added during manufacture.

D. Manufacturer's Installation Instructions: Submit installation procedures and interface required with adjacent Work.

1.5 CLOSEOUT SUBMITTALS

A. Section 01770 - Execution and Closeout Requirements: Closeout procedures.

B. Project Record Documents: Accurately record actual locations of embedded utilities and components concealed from view in finished construction.

1.6 QUALITY ASSURANCE

A. Perform Work in accordance with ACI 301 and ACI 318.

B. Conform to ACI 305 when concreting during hot weather.

C. Conform to ACI 306.1 when concreting during cold weather.

D. Acquire cement and aggregate from one source for Work.

1.7 COORDINATION

A. Coordinate placement of joint devices with erection of concrete formwork and placement of form accessories.

B. Coordinate embedded items.

C. Coordinate openings and utility penetrations.

PART 2 PRODUCTS

2.1 CONCRETE MATERIALS

A. Portland Cement: ASTM C 150, and as follows:
   1. Type I, except where other type is specifically permitted or required.
      a. Type I may be replaced by Type III (high early strength) for concrete placed during cold weather.

B. Fly Ash: ASTM C 618, Type C or F.
   1. Maximum allowable loss on ignition: 4.0 percent.

C. Water: Potable.

D. Aggregates:
1. Normal weight concrete: ASTM C 33, uniformly graded as follows:
a. Class: Moderate weathering region, but not less than 3M
b. Nominal Maximum Aggregate Size:
1) Slabs on Grade: 1-inch.
2) Footings and Walls: 3/4-inch.

E. Admixtures - General: Admixtures which result in more than 0.1 percent of soluble chloride ions by weight of cement are prohibited.

F. Air-Entraining Admixture: ASTM C 260 and certified by manufacturer for compatibility with other mix components.

G. Water-Reducing Admixture: ASTM C 494, Type A.

H. Water-Reducing, Retarding Admixture: ASTM C 494, Type D.

I. Water-Reducing and Accelerating Admixtures: ASTM C 494, Type E.

2.2 REINFORCEMENT

A. Deformed Reinforcement: ASTM A615/A615M; 60 ksi yield strength, steel bars, unfinished.

2.3 REINFORCEMENT ACCESSORY MATERIALS

A. Chairs, Bolsters, Bar Supports, Spacers: Sized and shaped for strength and support of reinforcement during concrete placement conditions including load bearing pad on bottom to prevent vapor retarder puncture.

B. Special Chairs, Bolsters, Bar Supports, Spacers Adjacent to Weather Exposed Concrete Surfaces: Plastic tipped steel type; size and shape to meet Project conditions.

2.4 FORM-FACING MATERIALS

A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
1. Plywood, metal, or other approved panel materials.

B. Rough-Formed Finished Concrete: Plywood, lumber, metal, or another approved material. Provide lumber dressed on at least two edges and one side for tight fit.

2.5 MISCELLANEOUS MATERIALS AND ACCESSORIES

A. Vapor Barrier
1. Vapor barrier must have all of the following qualities:
a. Permeance of less than 0.01 Perms [grains/(ft^2 · hr · inHg)] as tested in accordance with ASTM E 1745 Section 7.1.
b. Other performance criteria:
1) Strength: ASTM E 1745 Class A.
2) Thickness: 15 mils
c. Manufactured from prime virgin resins.

2. Seam Tape: Manufacturer's recommended low permeance tape composed of a high-density polyethylene film and a rubber based, pressure-sensitive adhesive.

B. Nonshrink Grout: ASTM C 1107.
1. Type: Provide nonmetallic type only.
2. Products: The following products, provided they comply with requirements of the contract documents, will be among those considered acceptable:
a. Nonmetallic type:
1) "Masterflow 928"; Master Builders, Inc.
2) "Sonogrout 14k"; Sonneborn Building Products Division/ChemRex, Inc.
3) "Euco N-S Grout"; The Euclid Chemical Company.
4) "Supreme"; Cormix Construction Chemicals.
5) "Crystex"; L & M Construction Chemicals, Inc.
6) "Sure-Grip High Performance Grout"; Dayton Superior Corporation.
7) "Horn Non-Corrosive Non-Shrink Grout"; A. C. Horn, Inc.
8) "Five Star Grout"; Five Star Products, Inc.

C. Burlap: AASHTO M 182, Class 2 jute or kenaf cloth.

D. Moisture-Retaining Cover: ASTM C 171, and as follows:
1. Curing paper.
2. Polyethylene film.
3. White burlap-polyethylene sheeting.

E. Liquid Curing Compounds:
1. Manufacturers: Provide products complying with requirements of the contract documents and made by one of the following:
a. Master Builders, Inc.
b. Anti Hydro International, Inc.
c. The Euclid Chemical Company.
d. A. C. Horn, Inc.
e. Dayton Superior Corporation.
f. W. R. Meadows, Inc.
g. The Burke Company.
h. Sonneborn Building Products Division/ChemRex, Inc.
i. L & M Construction Chemicals, Inc.
j. Setcon Industries, Inc.
k. Cormix, Inc.
2. Material - curing compounds: Comply with ASTM C 309, Type 1.
a. Non-yellowing formulation where subject to ultraviolet light.
b. Where compounds are proposed for use on surfaces to which finishes, coatings, or coverings subsequently will be applied, compound shall possess demonstrated compatibility with finish, coating, or covering, and use shall be subject to approval of the architect.
c. Curing and sealing compound: Where indicated, provide curing and sealing formulation with long-lasting finish that is resistant to chemicals, oil, grease, deicing salts, and abrasion.
3. Solvents: Water-based products where used on interior surfaces.

F. Self-Expanding Strip Waterstops: Manufactured rectangular or trapezoidal strip, sodium bentonite or other hydrophylic material for adhesive bonding to concrete.
   1. Products: Subject to compliance with requirements, provide one of the following:
      a. Volclay Waterstop-RX;
      b. Colloid Environmental Technologies Co.
      c. Conseal CS-231; Concrete Sealants Inc.
      d. Swellseal Joint; De Neef Construction Chemicals (U.S.) Inc.
      e. Hydrotite; Greenstreak.
      f. Mirastop; Mirafi Moisture Protection, Div. of Royal Ten Cate (USA), Inc.
      g. Adeka Ultra Seal; Mitsubishi International Corporation.
      h. Superstop; Progress Unlimited Inc.

G. Underlayment Compound: Self-leveling cementitious compound designed for pumping.
   1. Products: Provide one of the following:
      a. "Flo-Top"; The Euclid Chemical Company.
      b. "Thoro Underlayment Self-Leveling"; Thoro System Products Division/ICI Americas.

H. Expansion Joint Filler:
   1. Interior - Nonextruding bituminous type: ASTM D 1751.
   2. Exterior - Sponge rubber type: ASTM D 1752, Type I.

2.6 CONCRETE MIX DESIGN - GENERAL

A. Review: Do not begin concrete operations until proposed mixes have been reviewed and approved by the architect.

B. Proportioning of Concrete: Comply with recommendations of ACI 211.1 for normal weight concrete and ACI 211.2 for structural lightweight concrete.

C. Required Average Strength: For each type and strength of concrete, establish the required average strength f(cr) of the design mix on the basis of either field experience or trial mixtures as specified in ACI 301, and proportion mixes accordingly. If trial mixtures method is used, employ an independent testing agency acceptable to the architect for preparing and reporting proposed mix designs.

D. Verify air-dry unit weight of lightweight concrete in accordance with ASTM C 567, and correlate with fresh unit weight for use in acceptance of fresh concrete during construction.

E. Fly Ash:
   1. The contractor may elect to replace a portion of the portland cement with fly ash up to a maximum of 25 percent by weight of cement plus fly ash.

F. Admixtures:
   1. Air-entraining admixture: Use in mixes for exterior exposed concrete unless otherwise specifically indicated. Add at rate to achieve total air content in

accordance with Table 1.4.3 of ACI 201.2. For concrete not exposed to exterior, add at rate to achieve total air content between 2 percent and 4 percent.

a. Do not use in slabs-on-grade scheduled to receive topping, unless manufacturer of topping recommends use over air-entrained concrete.

2. Water-reducing admixture: Add as required for placement and workability.
3. Water-reducing and retarding admixture: Add as required in concrete mixes to be placed at ambient temperatures above 90 degrees F.
4. Water-reducing and accelerating admixture: Add as required in concrete mixes to be placed at ambient temperatures below 50 degrees F.
5. Do not use admixtures not specified or approved.

G. Mix Adjustments: Provided that no additional expense to owner is involved, contractor may submit for architect's approval requests for adjustment to approved concrete mixes when circumstances such as changed project conditions, weather, or unfavorable test results occur. Include laboratory test data substantiating specified properties with mix adjustment requests.

2.7 CONCRETE MIXTURES FOR BUILDING ELEMENTS

A. Footings, Grade Beams: Proportion normal-weight concrete mixture as follows:

1. Minimum Compressive Strength: 3000 psi at 28 days.
2. Slump Limit: 4 inches, plus or minus 1 inch.
3. Exposure Class: ACI [F2] [S0] [W1] [C1]

B. Slabs-on-Grade, Piers, Turned Down Slabs, protected from weather: Proportion normal-weight concrete mixture as follows:

1. Minimum Compressive Strength: 4000 psi at 28 days.
2. Slump Limit: 4 inches, plus or minus 1 inch.
3. Air Content: Do not allow air content of troweled finished floors to exceed 3 percent.
4. Exposure Class: [F0] [S0] [W0] [C0]

C. Slabs-on-Grade, site ramps and stairs, exposed to weather: Proportion normal-weight concrete mixture as follows:

1. Minimum Compressive Strength: 4500 psi at 28 days.
2. Slump Limit: 4 inches, plus or minus 1 inch.
3. Exposure Class: [F2] [S0] [W1] [C1]

D. Suspended Slabs and Stair on Composite Steel Deck or Steel Plate: Proportion normal-weight concrete mixture as follows:

1. Minimum Compressive Strength: 4000 psi at 28 days.
2. Slump Limit: 4 inches, plus or minus 1 inch.
3. Exposure Class: [F0] [S0] [W0] [C0]

2.8 CONTROL OF MIX IN THE FIELD

A. Slump: A tolerance of up to 1 inch above approved design mix slump will be permitted for 1 batch in 5 consecutive batches tested. Concrete of lower slump than that specified may be used, provided proper placing and consolidation is obtained.

B. Total Air Content: A tolerance of plus or minus 1-1/2 percent of approved design mix air content will be allowed for field measurements.

C. Do not use batches that exceed tolerances.

2.9 CONCRETE MIXING

A. Transit Mixers: Mix concrete materials in transit mixers, complying with requirements of ASTM C 94.
1. At ambient temperatures of 85 to 90 degrees F, reduce mixing and delivery time to 75 minutes.
2. At ambient temperatures above 90 degrees F, reduce mixing and delivery time to 60 minutes.

PART 3 EXECUTION

3.1 EXAMINATION

A. Section 013100 - Administrative Requirements: Coordination and project conditions.

B. Verify requirements for concrete cover over reinforcement.

C. Verify anchors, seats, plates, reinforcement and other items to be cast into concrete are accurately placed, positioned securely, and will not interfere with placing concrete.

3.2 PREPARATION

A. Prepare previously placed concrete by cleaning with steel brush and applying bonding agent. Remove laitance, coatings, and unsound materials.

B. In locations where new concrete is doweled to existing work, drill holes in existing concrete, insert steel dowels and pack solid with non-shrink grout.

C. Remove debris and ice from formwork, reinforcement, and concrete substrates.

D. Remove water from areas receiving concrete before concrete is placed.

3.3 PLACING CONCRETE

A. Place concrete in accordance with ACI 301 and ACI 318.

B. Notify testing laboratory and Architect/Engineer minimum 24 hours prior to commencement of operations.

C. Ensure reinforcement, inserts, embedded parts, formed expansion and contraction joints are not disturbed during concrete placement.

D. Install vapor barrier under interior slabs on grade in accordance with ASTM E1643. Lap joints minimum 6 inches and seal watertight by taping edges and ends.

E. Repair vapor barrier damaged during placement of concrete reinforcing. Repair with vapor barrier material; lap over damaged areas minimum 6 inches and seal watertight.

F. Install construction joint devices in coordination with floor slab pattern placement sequence. Set top to required elevations. Secure to resist movement by wet concrete.

G. Install joint device anchors. Maintain correct position to allow joint cover to be flush with floor and wall finish.

H. Install joint covers in longest practical length, when adjacent construction activity is complete.

I. Apply sealants in joint devices in accordance with Section 07920.

J. Deposit concrete at final position. Prevent segregation of mix.

K. Place concrete in continuous operation for each panel or section determined by predetermined joints.

L. No free falls in excess of 3 feet shall be permitted. For falls in excess of 3 feet, chutes or elephant trunks shall be employed.

M. Concrete shall be thoroughly compacted during placing and thoroughly worked around reinforcing and embedded fixtures and into the corners of the form. Vibration shall be employed to aid the compaction of the concrete under experienced supervision. Forms shall be designed to withstand their action. Supplement vibration by spading. No forking and/or raking shall be permitted. At least one spare vibrator shall be on hand for emergency use.

N. Maintain records of concrete placement. Record date, location, quantity, air temperature, and test samples taken.

O. Place concrete continuously between predetermined expansion, control, and construction joints.

P. Do not interrupt successive placement; do not permit cold joints to occur.

Q. No concrete that has partially hardened, become contaminated by foreign materials, or has been re-tempered shall be deposited.

R. Place floor slabs in saw cut pattern indicated.

S. Saw cut joints within 12 hours after placing. Use 3/16 inch thick blade, cut into 1/4 depth of slab thickness.

T. Screed floors and slabs on grade level, maintaining surface flatness and levelness to F(F) 35 and F(L) 25. Elevated slabs shall be finished to F(F) 25.

3.4 FINISHING FORMED SURFACES

A. Repairs, General: Repair surface defects, including tie holes, immediately after removing formwork.
   1. Remove honeycombed areas and other defective concrete down to sound concrete, cutting perpendicular to surface or slightly undercutting. Dampen patch location and area immediately surrounding it prior to applying bonding compound or patching mortar.
   2. Before bonding compound has dried, apply patching mixture matching original concrete in materials and mix except for omission of coarse aggregate, and using a blend of white and normal portland cement as necessary to achieve color match. Consolidate thoroughly and strike off slightly higher than surrounding surface.

B. Unexposed Form Finish: Repair tie holes and patch defective areas. Rub down or chip off fins or other raised areas exceeding 1/4 inch height.

C. Exposed Form Finish: Repair and patch defective areas, with fins or other projections completely removed and smoothed.
   1. Smooth rubbed finish: Apply to surfaces indicated no later than 24 hours after form removal.
      a. Wet concrete surfaces to be finished and rub with Carborundum brick or other abrasive until uniform color and texture are achieved.
      b. Do not apply separate grout mixture.
   2. Contiguous unformed surfaces: Strike smooth and float to a similar texture tops of walls, horizontal offsets, and other unformed surfaces adjacent to or contiguous with formed surfaces. Continue final finish of formed surfaces across unformed surfaces, unless otherwise specifically indicated.

3.5 FINISHING SLABS

A. Finishing Operations - General:
   1. Do not directly apply water to slab surface or dust with cement.
   2. Use hand or powered equipment only as recommended in ACI 302.1R.
   3. Screeding: Strikeoff to required grade and within surface tolerances indicated. Verify conformance to surface tolerances. Correct deficiencies while concrete is still plastic.
   4. Bull Floating: Immediately following screeding, bull float or darby before bleed water appears to eliminate ridges, fill in voids, and embed coarse aggregate. Recheck and correct surface tolerances.
   5. Do not perform subsequent finishing until excess moisture or bleed water has disappeared and concrete will support either foot pressure with less than 1/4-inch indentation or weight of power floats without damaging flatness.
   6. Final floating: Float to embed coarse aggregate, to eliminate ridges, to compact concrete, to consolidate mortar at surface, and to achieve uniform, sandy texture. Recheck and correct surface tolerances.
   7. Troweling: Trowel immediately following final floating. Apply first troweling with power trowel except in confined areas, and apply subsequent trowelings

with hand trowels. Wait between trowelings to allow concrete to harden. Do not over trowel. Begin final troweling when surface produces a ringing sound as trowel is moved over it. Consolidate concrete surface by final troweling operation. Completed surface shall be free of trowel marks, uniform in texture and appearance, and within surface tolerance specified.

a. Grind smooth surface defects which would telegraph through final floor covering system.

B. Coordinate appearance and texture of required final finishes with the architect before application.

C. Float Finish: As specified above.

D. Broomed Float Finish: After floating and when water sheen has practically disappeared, apply uniform transverse corrugations approximately 1/16 inch deep, without tearing surface.

E. Trowel Finish: As specified above.

F. Trowel and Fine Broom Finish: Follow trowel finishing operation immediately with fine brooming to achieve slightly scarified surface.

G. Chemical Hardener Finish:

1. Trowel finish and allow complete curing and drying of concrete surface.
2. Apply chemical hardener finish following manufacturer's printed application instructions, applying in 3 coats diluted with water. Evenly apply each coat, allowing 24 hours for drying between coats.
3. Remove any surplus hardener according to manufacturer's instructions.

H. Slab Surface Tolerances:

1. Achieve flat, level planes except where grades are indicated. Slope uniformly to drains.
2. Floated finishes: Depressions between high spots shall not exceed 1/4 inch under a 10-foot straightedge.
3. Troweled finishes: Achieve level surface plane so that depressions between high spots do not exceed the following dimension, using a 10-foot straightedge:
   a. 1/8 inch non-cumulative in any direction and equivalent to F_F50 (floor flatness), F_L35 (floor levelness) at areas to receive wood flooring and special sports flooring as noted in Division 9.
   b. 3/16 inch all others receiving troweled finishes.
4. Refer to Section 033500 for flatness requirements at polished concrete slabs.

I. Slab Finish Schedule: Apply finishes in the following typical locations and as otherwise shown on the drawings:

1. Float finish:
   a. Surfaces to receive thickset stone flooring
2. Broomed float:
   a. Sidewalks.
   b. Exterior slabs not otherwise scheduled.
3. Trowel finish:
   a. Exposed interior floors not otherwise scheduled.

b. Surfaces to receive resilient tile.
c. Surfaces to receive carpet.

4. Trowel and fine broom:
   a. Surfaces to receive thinset tile.
5. Chemical hardener finish: In locations shown on the drawings.

J. Repair of Slab Surfaces: Test slab surfaces for smoothness and to verify surface plane to tolerance specified. Repair defects as follows:
1. High areas: Correct by grinding after concrete has cured for not less than 14 days.
2. Low areas: Immediately after completion of surface finishing operations, cut out low areas and replace with fresh concrete. Finish repaired areas to blend with adjacent concrete. Proprietary patching compounds may be used when approved by the architect.
3. Crazed or cracked areas: Cut out defective areas, except random cracks and single holes not exceeding 1 inch in diameter, by cutting out and replacing with fresh concrete. Remove defective areas with clean, square cuts. Dampen exposed concrete and apply bonding compound. Mix, place, compact, and finish patching concrete to match adjacent concrete.
4. Isolated cracks and holes: Groove top of cracks and cut out holes not over 1 inch in diameter. Dampen cleaned concrete surfaces and apply bonding compound; place dry pack or proprietary repair compound acceptable to architect while bonding compound is still active:
   a. Dry-pack mix: One part portland cement to 2-1/2 parts fine aggregate and enough water as required for handling and placing.
   b. Install patching mixture and consolidate thoroughly, striking off level with and matching surrounding surface. Do not allow patched areas to dry out prematurely.
5. Underlayment: Leveling of slabs for subsequent application of floor finishes may be achieved by use of specified underlayment material, at contractor's option.

K. Surface Sealer: Apply to all interior concrete slabs to remain exposed.
1. Allow concrete to cure for 30 days prior to application of sealer.
2. Use clear solvent base, 100% solid epoxy sealer similar to Tamms Duraltex 1705. Apply two coats. Follow manufacturer’s recommendation for surface preparation.

L. Polished Concrete:
1. Reference Specification Section 033543 Polished Concrete Finishing.

3.6 CONCRETE CURING AND PROTECTION

A. General:
1. Prevent premature drying of freshly placed concrete, and protect from excessively cold or hot temperatures until concrete has cured.
2. Provide curing of concrete by one of the methods listed and as appropriate to service conditions and type of applied finish in each case.

B. Normal Curing Period:

1. Not less than 7 days for standard cements and mixes.
2. Not less than 4 days for high early strength concrete using Type III cement.

C. Formed Surfaces: Cure formed concrete surfaces by moist curing with forms in place for full curing period or until forms are removed.
   1. Keep wooden or metal forms moist when exposed to heat of the sun.
   2. If forms are removed prior to completion of curing process, continue curing by one of the applicable methods specified.

D. Surfaces Not in Contact with Forms:
   1. Refer to Specification 033500 for curing requirements of polished concrete slabs.
   2. Start initial curing as soon as free water has disappeared, but before surface is dry.
   3. Keep continuously moist for not less than 7 days by uninterrupted use of any of the following:
      a. Water ponding.
      b. Water-saturated sand.
      c. Water-fog spray.
      d. Saturated burlap: Provide 4-inch minimum overlap at joints.
   4. Begin final curing procedures immediately following initial curing and before concrete has dried.
      a. Moisture-retaining cover: Lap not less than 3 inches at edges and ends, and seal with waterproof tape or adhesive. Repair holes or tears during curing period with same tape or adhesive. Maintain covering in intimate contact with concrete surface. Secure to avoid displacement.
         1) Extend covering past slab edges at least twice the thickness of slab.
         2) Do not use plastic sheeting on surfaces which will be exposed to view when in service.
      b. Curing compound: Apply at rate stated by manufacturer to conform with moisture-retention requirements specified, using second, immediate application at right angles to first, if necessary, and reapply if damaged by rain.
      c. Curing and sealing compound: Apply at rate stated by manufacturer to conform with moisture-retention requirements specified, using second, immediate application at right angles to first, if necessary, and reapply if damaged by rain. Apply additional coat near substantial completion to act as sealer.
      d. Use curing compounds only in locations permitted or required, and where use will not interfere with other finishes, coatings, or coverings to be applied.
   5. Continue final curing to end of curing period.

E. Avoid rapid drying at end of curing period.

F. During and following curing period, protect concrete from temperature changes of adjacent air in excess of 5 degrees F per hour and 50 degrees F per 24 hours. Progressively adjust protective measures to provide uniform temperature changes over entire concrete surface.

3.7 MISCELLANEOUS CONCRETE ITEMS

A. Fill-in: Fill in holes and openings left in concrete structures for passage of work by other trades after such work is in place. Place such fill-in concrete to blend with existing construction, using same mix and curing methods.

B. Equipment Bases and Foundations: Provide machine and equipment bases and foundations, as indicated on drawings. Set anchor bolts at correct elevations, complying with diagrams or templates of equipment manufacturer.
   1. Grout base plates and foundations as indicated with nonshrink grout.
   2. Use nonmetallic grout for exposed conditions, unless otherwise indicated.

C. Steel Pan Stairs: Provide concrete fill for steel pan stair treads, landings, and associated items. Screed, tamp, and finish concrete surfaces as scheduled.

D. Reinforced Masonry: Provide concrete grout for reinforced masonry where indicated on drawings and as scheduled.

3.8 CONCRETE REPAIRS

A. Perform cosmetic repairs of concrete surfaces as specified under concrete application.

B. Perform structural repairs with prior approval of the architect for method and procedure, using epoxy bonding systems. The architect's approval is required for repair methods using materials other than those specified.

3.9 QUALITY CONTROL TESTING DURING CONSTRUCTION

A. Composite Sampling, and Making and Curing of Specimens: ASTM C 172 and ASTM C 31.
   1. Take samples at point of discharge.
   2. For pumped concrete, perform sampling and testing at the frequencies specified herein at point of delivery to pump. Results obtained at discharge from line shall be used for acceptance of concrete.

B. Slump: ASTM C 143. One test per strength test and additional tests if concrete consistency changes.
   1. Modify sampling to comply with ASTM C 94.

C. Air Content of Normal Weight Concrete: ASTM C 173 or ASTM C 231. One test per strength test performed on air-entrained concrete.

D. Air Content of Lightweight Concrete: ASTM C 173. One test per strength test performed on air-entrained concrete.

E. Approximate Air-Dry Weight of Lightweight Concrete: ASTM C 567. Determine fresh unit weight once per strength test and report approximate air-dry weight of concrete represented.

F. Concrete Temperature:
   1. Test hourly when air temperature is 40 degrees F or below.

2. Test hourly when air temperature is 90 degrees F or above.
3. Test each time a set of strength test specimens is made.

G. Compressive Strength Tests: ASTM C 39.
1. Compression test specimens: Mold and cure one set of 5 standard cylinders for each compressive strength test required.
2. Testing for acceptance of potential strength of as-delivered concrete:
   a. Obtain samples on a statistically sound, random basis.
   b. Minimum frequency:
      1) One set per 100 cubic yards or fraction thereof for each day's pour of each concrete class.
      2) One set per 3500 square feet of slab or wall area or fraction thereof for each day's pour of each concrete class.
      3) When less than 5 cubic yards is placed in one day, the architect may, at architect's option, waive laboratory testing of specimens if adequate evidence of satisfactory strength is provided. (Molding and curing of these specimens is not waived.)
      4) When the above testing frequency would provide fewer than 5 strength tests for a given class of concrete during the project, conduct testing from not less than 5 randomly selected batches, or from each batch if fewer than 5.
   c. Test one specimen per set at 7 days for information unless an earlier age is required.
   d. Test 2 specimens per set for acceptance of strength potential; test at 28 days unless other age is specified. The test result shall be the average of the two specimens. If one specimen shows evidence of improper sampling, molding, or testing, the test result shall be the result of the remaining specimen; if both show such evidence, discard the test result and inform the architect.
   e. Retain one specimen from each set for later testing, if required.
   f. Strength potential of as-delivered concrete will be considered acceptable if all of the following criteria are met:
      1) No individual test result falls below specified compressive strength by more than 500 psi.
      2) Not more than 10 percent of individual test results fall below specified compressive strength f'(c).
      3) Average of any 3 consecutive strength test results equals or exceeds specified compressive strength f'(c).
3. Removal of forms or supports: Mold additional specimens and field-cure with concrete represented; test to determine strength of concrete at proposed time of form or support removal.

H. Test Results: Testing agency shall report test results in writing to architect and contractor within 24 hours of test.
1. Test reports shall contain the following data:
   a. Project name, number, and other identification.
   b. Name of concrete testing agency.
   c. Date and time of sampling.
   d. Concrete type and class.
   e. Location of concrete batch in the completed work.

f. All information required by respective ASTM test methods.

2. Nondestructive testing devices such as impact hammer or sonoscope may be used at architect's option for assistance in determining probable concrete strength at various locations or for selecting areas to be cored, but such tests shall not be the sole basis for acceptance or rejection.

3. The testing agency shall make additional tests of in-place concrete as directed by the architect when test results indicate that specified strength and other concrete characteristics have not been attained.
   a. Testing agency may conduct tests of cored cylinders complying with ASTM C 42, or tests as directed.
   b. Cost of additional testing shall be borne by the contractor when unacceptable concrete has been verified.

END OF SECTION 033000

SECTION 035300 - CONCRETE TOPPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Iron-aggregate concrete floor topping.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.5 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each concrete floor topping, for tests performed by a qualified testing agency.

1.6 QUALITY ASSURANCE

A. Mockups: Place concrete floor topping mockups to demonstrate typical joints, surface finish, bonding, texture, tolerances, and standard of workmanship.

1. Build mockups approximately 100 sq. ft. (9.3 sq. m) in the location indicated or, if not indicated, as directed by Architect.
2. If Architect determines that mockups do not meet requirements, demolish and remove them from the site and cast others until mockups are approved.
3. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in original packages and containers, with seals unbroken, bearing manufacturer's labels indicating brand name and directions for storage, mixing with other components, and application.

B. Store materials to comply with manufacturer's written instructions to prevent deterioration from moisture or other detrimental effects.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Comply with manufacturer's written instructions for substrate temperature and moisture content, ambient temperature and humidity, ventilation, and other conditions affecting concrete floor topping performance.

1. Place concrete floor topping only when ambient temperature and temperature of base slabs are between 50 and 86 deg F (10 and 30 deg C).

B. Close areas to traffic during topping application and, after application, for time period recommended in writing by manufacturer.

PART 2 - PRODUCTS

2.1 CONCRETE FLOOR TOPPINGS

A. Iron-Aggregate Concrete Floor Topping: Factory-prepared and dry-packaged mixture of graded iron aggregate, portland cement, plasticizers, and other admixtures to which only water needs to be added at Project site.

B. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:

1. Dayton Superior Corporation; Ferro Tuff Light Reflective.
2. Euclid Chemical Company (The); Euco-Plate HD Light Reflective.
3. Metalcrete Industries; Metalplate Plus, light reflective.

C. Compressive Strength (28 Days): 11,400 psi (78.6 MPa); ASTM C109/C109M.

2.2 CURING MATERIALS

A. Evaporation Retarder: Waterborne, monomolecular film forming; manufactured for application to fresh concrete.

B. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C309, Type 1, Class B, 25 percent solids content, minimum.

2.3 RELATED MATERIALS

A. Semirigid Joint Filler: Two-component, semirigid, 100 percent solids epoxy resin with a Type A Shore durometer hardness of 80 according to ASTM D2240.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for conditions affecting performance of the Work.

B. Proceed with application only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Install joint-filler strips where topping abuts vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.

1. Terminate full-width, joint-filler strips 1/2 inch (13 mm) below topping surface where joint sealants, specified in Section 079200 "Joint Sealants," are indicated.
2. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.

B. Ensure that enough dry shake hardener is on-site to complete the placement without interruption.

3.3 FLOOR TOPPING APPLICATION

A. Start floor topping application in presence of manufacturer's technical representative.

B. Monolithic Floor Topping: After textured-float finish is applied to fresh concrete of base slabs specified in Section 033000 "Cast-in-Place Concrete," place concrete floor topping while concrete is still plastic.

C. Dry-Shake Floor Hardener: After initial floating, apply dry-shake floor hardener to surfaces according to manufacturer's written instructions and as follows:

1. Uniformly apply dry-shake floor hardener at a rate of 100 lb/100 sq. ft. (49 kg/10 sq. m unless greater amount is recommended by manufacturer.
2. Uniformly distribute approximately two-thirds of dry-shake floor hardener over surface by hand or with mechanical spreader, and embed by power floating. Follow power floating with a second dry-shake floor hardener application, uniformly distributing remainder of material, and embed by power floating.
3. After final floating, apply a trowel finish. Cure concrete with curing compound recommended by dry-shake floor hardener manufacturer and apply immediately after final finishing.

D. Finishing: Consolidate surface with power-driven floats as soon as concrete floor topping can support equipment and operator. Restraighten, cut down high spots, and fill low spots. Repeat float passes and restraightening until concrete floor topping surface has a uniform, smooth, granular texture.

1. Hard Trowel Finish: After floating surface, apply first trowel finish and consolidate concrete floor topping by power-driven trowel without allowing blisters to develop. Continue troweling passes and restraighten until surface is smooth and uniform in texture.

E. Construction Joints: Construct joints true to line with faces perpendicular to surface plane of concrete floor topping, at locations indicated or as approved by Architect.

1. Coat face of construction joint with epoxy adhesive at locations where concrete floor topping is placed against hardened or partially hardened concrete floor topping.

F. Contraction Joints: Form weakened-plane contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- (3-mm-) wide joints into concrete floor topping when cutting action will not tear, abrade, or otherwise damage surface and before random contraction cracks develop.

1. Form joints in concrete floor topping over contraction joints in base slabs unless otherwise indicated.
2. Construct contraction joints for a combined depth equal to topping thickness and not less than one-fourth of base-slab thickness.

3.4 PROTECTING AND CURING

A. General: Protect freshly placed concrete floor topping from premature drying and excessive cold or hot temperatures.

B. Evaporation Retarder: Apply evaporation retarder to concrete floor topping surfaces in hot, dry, or windy conditions before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying floor topping, but before float finishing.

C. Begin curing immediately after finishing concrete floor topping. Cure by one or a combination of the following methods, according to concrete floor topping manufacturer's written instructions:

1. Curing Compound: Apply uniformly in two coats in continuous operations by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

3.5 JOINT FILLING

A. Prepare and clean contraction joints and install semirigid joint filler, according to manufacturer's written instructions, once topping has fully cured.

B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joints clean and dry.

C. Install semirigid joint filler full depth of contraction joints. Overfill joint and trim semirigid joint filler flush with top of joint after hardening.

3.6 REPAIR

A. Defective Topping: Repair and patch defective concrete floor topping areas, including areas that have not bonded to concrete substrate.

3.7 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.

B. Testing Services: Testing and inspecting of completed applications of concrete floor toppings shall take place in successive stages, in areas of extent and using methods as follows:

1. Sample Sets: At point of placement, a set of three molded-cube samples shall be taken from the topping mix for the first 1000 sq. ft. (93 sq. m), plus one set of samples for each subsequent 5000 sq. ft. (464 sq. m) of topping, or fraction thereof, but not less than six samples for each day's placement. Samples shall be tested according to ASTM C109/C109M for compliance with compressive-strength requirements.

C. Remove and replace applications of concrete floor topping where test results indicate that it does not comply with specified requirements.

D. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

END OF SECTION 035300

SECTION 042000 - UNIT MASONRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Concrete masonry units.
2. Clay face brick.
3. Building (common) brick.
4. Mortar and grout.
5. Steel reinforcing bars.
6. Masonry-joint reinforcement.
7. Ties and anchors.
8. Embedded flashing.
9. Miscellaneous masonry accessories.

B. Products Installed but not Furnished under This Section:

1. Steel lintels in unit masonry.
2. Steel shelf angles for supporting unit masonry.
3. Cavity wall insulation.

C. Related Requirements:

1. Section 072100 "Thermal Insulation" for cavity wall insulation.

1.3 DEFINITIONS

A. BIA: Brick Institute of America.

B. CMU(s): Concrete masonry unit(s).

C. Reinforced Masonry: Masonry containing reinforcing steel in grouted cells.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For the following:

1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes.
2. Reinforcing Steel: Detail bending, lap lengths, and placement of unit masonry reinforcing bars. Comply with ACI 315.
3. Fabricated Flashing: Detail corner units, end-dam units, and other special applications.

C. Samples for Initial Selection:

1. Clay face brick, in the form of straps of five or more bricks.
2. Colored mortar.
3. Weep holes/cavity vents.

D. Samples for Verification: For each type and color of the following:

1. Clay face brick, in the form of straps of five or more bricks.
2. Special brick shapes.
3. Pigmented mortar. Make Samples using same sand and mortar ingredients to be used on Project.
4. Weep holes and cavity vents.

1.6 INFORMATIONAL SUBMITTALS

A. List of Materials Used in Constructing Mockups: List generic product names together with manufacturers, manufacturers' product names, model numbers, lot numbers, batch numbers, source of supply, and other information as required to identify materials used. Include mix proportions for mortar and grout and source of aggregates.

1. Submittal is for information only. Receipt of list does not constitute approval of deviations from the Contract Documents unless such deviations are specifically brought to the attention of Architect and approved in writing.

B. Qualification Data: For Installer.

C. Material Certificates: For each type and size of the following:

1. Masonry units.

a. Include material test reports substantiating compliance with requirements.
b. For brick, include size-variation data verifying that actual range of sizes falls within specified tolerances.
c. For exposed brick, include test report for efflorescence according to ASTM C67.
d. For masonry units used in structural masonry, include data and calculations establishing average net-area compressive strength of units.

2. Cementitious materials. Include name of manufacturer, brand name, and type.
3. Preblended, dry mortar mixes. Include description of type and proportions of ingredients.

4. Grout mixes. Include description of type and proportions of ingredients.
5. Reinforcing bars.
6. Joint reinforcement.
7. Anchors, ties, and metal accessories.

D. Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients.

1. Include test reports for mortar mixes required to comply with property specification. Test according to ASTM C109/C109M for compressive strength, ASTM C1506 for water retention, and ASTM C91/C91M for air content.
2. Include test reports, according to ASTM C1019, for grout mixes required to comply with compressive strength requirement.

E. Statement of Compressive Strength of Masonry: For each combination of masonry unit type and mortar type, provide statement of average net-area compressive strength of masonry units, mortar type, and resulting net-area compressive strength of masonry determined according to TMS 602/ACI 530.1/ASCE 6.

F. Cold-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with requirements.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who have a minimum of 5 years of experience in installing products similar to those required for this Project.

B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.

1. Build mockup of typical wall area as shown on Drawings.
2. Clean one-half of exposed faces of mockups with masonry cleaner as indicated.
3. Protect accepted mockups from the elements with weather-resistant membrane.
4. Approval of mockups is for color, texture, and blending of masonry units; relationship of mortar and sealant colors to masonry unit colors; tooling of joints; and aesthetic qualities of workmanship.

    a. Approval of mockups is also for other material and construction qualities specifically approved by Architect in writing.
    b. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.

D. Deliver preblended, dry mortar mix in moisture-resistant containers. Store preblended, dry mortar mix in delivery containers on elevated platforms in a dry location or in covered weatherproof dispensing silos.

E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.9 FIELD CONDITIONS

A. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.

1. Extend cover a minimum of 24 inches (600 mm) down both sides of walls, and hold cover securely in place.
2. Where one wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches (600 mm) down face next to unconstructed wythe, and hold cover in place.

B. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least three days after building masonry walls or columns.

C. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed or painted. Immediately remove grout, mortar, and soil that come in contact with such masonry.

1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
2. Protect sills, ledges, and projections from mortar droppings.
3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.

D. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in TMS 602/ACI 530.1/ASCE 6.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F (4 deg C) and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.

E. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in TMS 602/ACI 530.1/ASCE 6.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, from single source from single manufacturer for each product required.

B. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from single manufacturer for each cementitious component and from single source or producer for each aggregate.

2.2 UNIT MASONRY, GENERAL

A. Masonry Standard: Comply with TMS 602/ACI 530.1/ASCE 6, except as modified by requirements in the Contract Documents.

B. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated. Do not use units where such defects are exposed in the completed Work and will be within 20 feet (6 m) vertically and horizontally of a walking surface.

2.3 CONCRETE MASONRY UNITS

A. Regional Materials: Location of manufacture shall be within 500 miles of the project site.

B. Shapes: Provide shapes indicated and as follows, with exposed surfaces matching exposed faces of adjacent units unless otherwise indicated.

1. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, and other special conditions.
2. Provide bullnose units for outside corners unless otherwise indicated.

C. CMUs: ASTM C90.

1. Density Classification: Lightweight unless otherwise indicated.
2. Size (Width): Manufactured to dimensions 3/8 inch (10 mm) less than nominal dimensions.
3. Exposed Faces: Provide color and texture matching the range represented by Architect's sample.

2.4 CONCRETE AND MASONRY LINTELS

A. General: Provide one of the following:

B. Concrete Lintels: ASTM C1623, matching CMUs in color, texture, and density classification; and with reinforcing bars indicated. Provide lintels with net-area compressive strength not less than that of CMUs.

C. Masonry Lintels: Prefabricated or built-in-place masonry lintels made from bond beam CMUs matching adjacent CMUs in color, texture, and density classification, with reinforcing bars placed as indicated and filled with coarse grout. Cure precast lintels before handling and installing. Temporarily support built-in-place lintels until cured.

2.5 BRICK

A. Regional Materials: Location of manufacture shall be within 500 miles of the project site.

B. General: Provide shapes indicated and as follows, with exposed surfaces matching finish and color of exposed faces of adjacent units:

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.
2. Provide special shapes for applications where stretcher units cannot accommodate special conditions, including those at corners, movement joints, bond beams, sashes, and lintels.
3. Provide special shapes for applications requiring brick of size, form, color, and texture on exposed surfaces that cannot be produced by sawing.
4. Provide special shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.

C. Clay Face Brick, Modular: Facing brick complying with ASTM C216.

1. Grade: SW.
2. Type: FBS.
3. Efflorescence: Provide brick that has been tested according to ASTM C67 and is rated "not effloresced."
4. Size (Actual Dimensions): 3-5/8 inches (92 mm) wide by 2-1/4 inches (57 mm) high by 7-5/8 inches (194 mm) long.
5. Application: Use where brick is exposed where indicated.
6. Color and Texture: As selected by Architect.

2.6 MORTAR AND GROUT MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.

1. Alkali content shall not be more than 0.1 percent when tested according to ASTM C114.

B. Hydrated Lime: ASTM C207, Type S.

C. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.

D. Aggregate for Mortar: ASTM C144.

1. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.
2. Colored-Mortar Aggregates: Natural sand or crushed stone of color necessary to produce required mortar color.

E. Aggregate for Grout: ASTM C404.

F. Cold-Weather Admixture: Nonchloride, noncorrosive, accelerating admixture complying with ASTM C494/C494M, Type C, and recommended by manufacturer for use in masonry mortar of composition indicated.

G. Water: Potable.

2.7 REINFORCEMENT

A. Uncoated-Steel Reinforcing Bars: ASTM A615/A615M or ASTM A996/A996M, Grade 60 (Grade 420).

B. Masonry-Joint Reinforcement, General: ASTM A951/A951M.

1. Exterior Walls: Hot-dip galvanized carbon steel.
2. Wire Size for Side Rods: 0.187-inch (4.76-mm) diameter.
3. Wire Size for Cross Rods: 0.187-inch (4.76-mm) diameter.
4. Wire Size for Veneer Ties: 0.187-inch (4.76-mm) diameter.
5. Spacing of Cross Rods, Tabs, and Cross Ties: Not more than 16 inches (407 mm) o.c.
6. Provide in lengths of not less than 10 feet (3 m), with prefabricated corner and tee units.

2.8 TIES AND ANCHORS

A. General: Ties and anchors shall extend at least 1-1/2 inches (38 mm) into veneer but with at least a 5/8-inch (16-mm) cover on outside face.

B. Materials: Provide ties and anchors specified in this article that are made from materials that comply with the following unless otherwise indicated:

1. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A82/A82M, with ASTM A153/A153M, Class B-2 coating.
2. Steel Sheet, Galvanized after Fabrication: ASTM A1008/A1008M, Commercial Steel, with ASTM A153/A153M, Class B coating.
3. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

C. Corrugated-Metal Ties: Metal strips not less than 7/8 inch (22 mm) wide with corrugations having a wavelength of 0.3 to 0.5 inch (7.6 to 12.7 mm) and an amplitude of 0.06 to 0.10 inch (1.5 to 2.5 mm) made from 0.060-inch- (1.52-mm-) thick steel sheet, galvanized after fabrication.

D. Individual Wire Ties: Rectangular units with closed ends and not less than 4 inches (100 mm) wide.

1. Z-shaped ties with ends bent 90 degrees to provide hooks not less than 2 inches (50 mm) long may be used for masonry constructed from solid units.
2. Where wythes are of different materials, use adjustable ties with pintle-and-eye connections having a maximum adjustment of 1-1/4 inches (32 mm).
3. Wire: Fabricate from 3/16-inch- (4.76-mm-) diameter, hot-dip galvanized steel wire.

E. Adjustable Anchors for Connecting to Structural Steel Framing: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Anchor Section for Welding to Steel Frame: Crimped 1/4-inch- (6.35-mm-) diameter, hot-dip galvanized steel wire
2. Tie Section: Triangular-shaped wire tie made from 0.187-inch- (4.76-mm-) diameter, hot-dip galvanized steel wire.

F. Adjustable Masonry-Veneer Anchors:

1. General: Provide anchors that allow vertical adjustment but resist a 100-lbf (445-N) load in both tension and compression perpendicular to plane of wall without deforming or developing play in excess of 1/16 inch (1.5 mm).
2. Fabricate sheet metal anchor sections and other sheet metal parts from 0.105-inch- (2.66-mm-) thick steel sheet, galvanized after fabrication.
3. Fabricate wire ties from 0.187-inch- (4.76-mm-) diameter, hot-dip galvanized-steel wire unless otherwise indicated.
4. Contractor's Option: Unless otherwise indicated, provide any of the adjustable masonry-veneer anchors specified.
5. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a rib-stiffened, sheet metal anchor section with screw holes top and bottom, with a projecting vertical tab having a slotted hole for inserting wire tie.
6. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a rib-stiffened, sheet metal anchor section with screw holes top and bottom, with projecting tabs having holes for inserting vertical legs of wire tie formed to fit anchor section.
7. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a sheet metal anchor section, 1-1/4 inches (32 mm) wide by 9 inches (229 mm) long, with screw holes top and bottom and with raised rib-stiffened strap, 5/8 inch (16 mm) wide by 5-1/2 inches (140 mm) long, stamped into center to provide a slot between strap and base for inserting wire tie.
8. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a sheet metal anchor section, 1-1/4 inches (32 mm) wide by 6 inches (152 mm) long, with screw holes top and bottom and with raised rib-stiffened strap, 5/8 inch (16 mm) wide by 3-5/8 inches (92 mm) long, stamped into center to provide a slot between strap and base for inserting wire tie.
9. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a gasketed sheet metal anchor section, 1-1/4 inches (32 mm) wide by 6 inches (152 mm) long, with screw holes top and bottom; top and bottom ends bent to form pronged legs of length to match thickness of insulation or sheathing; and raised rib-stiffened strap, 5/8 inch (16 mm) wide by 6 inches (152 mm) long, stamped into center to provide a slot between strap and base for inserting wire tie. Self-adhering, modified bituminous gasket fits behind anchor plate and extends beyond pronged legs.

10. Screw-Attached, Masonry-Veneer Anchors: Wire tie and a corrosion-resistant, self-drilling, eye-screw designed to receive wire tie. Eye-screw has spacer that seats directly against framing and is same thickness as sheathing and has gasketed washer head that covers hole in sheathing.
11. Seismic Masonry-Veneer Anchors: Connector section and rib-stiffened, sheet metal anchor section with screw holes top and bottom, with projecting tabs having slotted holes for inserting vertical leg of connector section. Connector section consists of a rib-stiffened, sheet metal bent plate with down-turned leg designed to fit in anchor section slot and with integral tabs designed to engage continuous wire.
12. Seismic Masonry-Veneer Anchors: Wire tie and a rib-stiffened, sheet metal anchor section with screw holes top and bottom, with projecting tabs having holes for inserting vertical legs of wire tie formed to fit anchor section. Wire tie has sheet metal clip welded to it with integral tabs designed to engage continuous wire.
13. Polymer-Coated, Steel Drill Screws for Steel Studs: ASTM C954 except manufactured with hex washer head and neoprene or EPDM washer, No. 10 (4.83-mm) diameter by length required to penetrate steel stud flange with not less than three exposed threads, and with organic polymer coating with salt-spray resistance to red rust of more than 800 hours according to ASTM B117.
14. Stainless Steel Drill Screws for Steel Studs: ASTM C954 except manufactured with hex washer head and neoprene or EPDM washer, No. 10 (4.83-mm) diameter by length required to penetrate steel stud flange with not less than three exposed threads; either made from Type 410 stainless steel or made with a carbon-steel drill point and 300 Series stainless steel shank.

2.9 EMBEDDED FLASHING MATERIALS

A. Metal Flashing: Provide metal flashing complying with SMACNA's "Architectural Sheet Metal Manual" and as follows:

1. Copper: ASTM B370, Temper H00, cold-rolled copper sheet, 16-oz./sq. ft. (4.9-kg/sq. m) weight or 0.0216 inch (0.55 mm) thick or ASTM B370, Temper H01, high-yield copper sheet, 12-oz./sq. ft. (3.7-kg/sq. m) weight or 0.0162 inch (0.41 mm) thick.
2. Fabricate continuous flashings in sections 96 inches (2400 mm) long minimum, but not exceeding 12 feet (3.7 m). Provide splice plates at joints of formed, smooth metal flashing.
3. Fabricate through-wall metal flashing embedded in masonry from copper, with ribs at 3-inch (76-mm) intervals along length of flashing to provide an integral mortar bond.
4. Fabricate through-wall flashing with snaplock receiver on exterior face where indicated to receive counterflashing.
5. Fabricate through-wall flashing with drip edge where indicated. Fabricate by extending flashing 1/2 inch (13 mm) out from wall, with outer edge bent down 30 degrees and hemmed.
6. Fabricate through-wall flashing with sealant stop unless otherwise indicated. Fabricate by bending metal back on itself 3/4 inch (19 mm) at exterior face of wall and down into joint 1/4 inch (6 mm) to form a stop for retaining sealant backer rod.
7. Fabricate metal drip edges and sealant stops for ribbed metal flashing from plain metal flashing of same metal as ribbed flashing and extending at least 3 inches (76 mm) into wall with hemmed inner edge to receive ribbed flashing and form a hooked seam. Form hem on upper surface of metal so that completed seam sheds water.
8. Fabricate metal expansion-joint strips from copper to shapes indicated.

9. Solder metal items at corners.

B. Flexible Flashing: Use the following unless otherwise indicated:

1. Copper-Laminated Flashing: 7-oz./sq. ft. (2-kg/sq. m) copper sheet bonded between two layers of glass-fiber cloth. Use only where flashing is fully concealed in masonry.

a. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

1) Advanced Building Products, Inc.; Copper Fabric Flashing.
2) AFCO Products, Inc.; Copper Fabric.
3) Hohmann & Barnard; H&B C-Fab Flashing.
4) Phoenix Building Products; Type FCC Fabric Covered Copper.
5) Polytite Manufacturing Corp.; Copper Fabric Flashing.
6) Sandell manufacturing Co., Inc.; Copper Fabric Flashing.
7) York Manufacturing, Inc.; Copper Fabric Flashing.

C. Application: Unless otherwise indicated, use the following:

1. Where flashing is indicated to receive counterflashing, use metal flashing.
2. Where flashing is indicated to be turned down at or beyond the wall face, use metal flashing.
3. Where flashing is partly exposed and is indicated to terminate at the wall face, use metal flashing with a sealant stop or flexible flashing with a metal sealant stop.
4. Where flashing is fully concealed, use metal flashing or flexible flashing.

D. Solder and Sealants for Sheet Metal Flashings: As specified in Section 076200 "Sheet Metal Flashing and Trim."

E. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer's standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates.

F. Termination Bars for Flexible Flashing: Stainless steel bars 0.075 inch by 1 inch (1.90 mm by 25 mm).

2.10 MISCELLANEOUS MASONRY ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene, urethane, or PVC.

B. Preformed Control-Joint Gaskets: Made from styrene-butadiene-rubber compound, complying with ASTM D2000, Designation M2AA-805 and designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.

C. Bond-Breaker Strips: Asphalt-saturated felt complying with ASTM D226/D226M, Type I (No. 15 asphalt felt).

D. Weep/Cavity Vent Products: Use the following unless otherwise indicated:

1. Cellular Plastic Weep/Vent: One-piece, flexible extrusion made from UV-resistant polypropylene copolymer, full height and width of head joint and depth 1/8 inch (3 mm) less than depth of outer wythe, in color selected from manufacturer's standard.

a. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

1) Advanced Building Products, Inc.; Mortar Maze Weep Vent.
2) Archovations, Inc.; CavClear Weep Vent.
3) Hohmann & Barnard; QV-Quadro-Vent.
4) Mortar Net USA, Ltd.; CellVent.

E. Cavity Drainage Material: Free-draining mesh, made from polymer strands that will not degrade within the wall cavity.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. Advanced Building Products, Inc.; Mortar Break II.
b. Archovations, Inc.; CavClear Masonry Mat.
c. Hohmann & Barnard; Mortar Web.
d. Mortar Net USA, Ltd.; Mortar Net.

2.11 MORTAR AND GROUT MIXES

A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.

1. Do not use calcium chloride in mortar or grout.
2. Use portland cement-lime mortar unless otherwise indicated.
3. For exterior masonry, use portland cement-lime mortar.
4. For reinforced masonry, use portland cement-lime mortar.
5. Add cold-weather admixture (if used) at same rate for all mortar that will be exposed to view, regardless of weather conditions, to ensure that mortar color is consistent.

B. Preblended, Dry Mortar Mix: Furnish dry mortar ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.

C. Mortar for Unit Masonry: Comply with ASTM C270, Proportion Specification. Provide the following types of mortar for applications stated unless another type is indicated or needed to provide required compressive strength of masonry.

1. For masonry below grade or in contact with earth, use Type M.
2. For reinforced masonry, use Type S.

3. For exterior, above-grade, load-bearing and nonload-bearing walls and parapet walls; for interior load-bearing walls; for interior nonload-bearing partitions; and for other applications where another type is not indicated, use Type N.
4. For interior nonload-bearing partitions, Type O may be used instead of Type N.

D. Grout for Unit Masonry: Comply with ASTM C476.

1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with TMS 602/ACI 530.1/ASCE 6 for dimensions of grout spaces and pour height.
2. Proportion grout in accordance with ASTM C476, Table 1.
3. Provide grout with a slump of 8 to 11 inches (200 to 280 mm) as measured according to ASTM C143/C143M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
2. Verify that foundations are within tolerances specified.
3. Verify that reinforcing dowels are properly placed.
4. Verify that substrates are free of substances that impair mortar bond.

B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping connections.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.

B. Build chases and recesses to accommodate items specified in this and other Sections.

C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match construction immediately adjacent to opening.

D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.

E. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures. Mix units from several pallets or cubes as they are placed.

F. Wetting of Brick: Wet brick before laying if initial rate of absorption exceeds 30 g/30 sq. in. (30 g/194 sq. cm) per minute when tested according to ASTM C67. Allow units to absorb water so they are damp but not wet at time of laying.

3.3 TOLERANCES

A. Dimensions and Locations of Elements:

1. For dimensions in cross section or elevation, do not vary by more than plus 1/2 inch (12 mm) or minus 1/4 inch (6 mm).
2. For location of elements in plan, do not vary from that indicated by more than plus or minus 1/2 inch (12 mm).
3. For location of elements in elevation, do not vary from that indicated by more than plus or minus 1/4 inch (6 mm) in a story height or 1/2 inch (12 mm) total.

B. Lines and Levels:

1. For bed joints and top surfaces of bearing walls, do not vary from level by more than 1/4 inch in 10 feet (6 mm in 3 m), or 1/2-inch (12-mm) maximum.
2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2-inch (12-mm) maximum.
3. For vertical lines and surfaces, do not vary from plumb by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2-inch (12-mm) maximum.
4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2-inch (12-mm) maximum.
5. For lines and surfaces, do not vary from straight by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2-inch (12-mm) maximum.
6. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet (6 mm in 3 m), or 1/2-inch (12-mm) maximum.

C. Joints:

1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm), with a maximum thickness limited to 1/2 inch (12 mm).
2. For exposed bed joints, do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch (3 mm).
3. For head and collar joints, do not vary from thickness indicated by more than plus 3/8 inch (9 mm) or minus 1/4 inch (6 mm).
4. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm). Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch (3 mm).
5. For exposed bed joints and head joints of stacked bond, do not vary from a straight line by more than 1/16 inch (1.5 mm) from one masonry unit to the next.

3.4 LAYING MASONRY WALLS

A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.

B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in running bond; do not use units with less-than-nominal 4-inch (100-mm) horizontal face dimensions at corners or jambs.

C. Stopping and Resuming Work: Stop work by stepping back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.

D. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

E. Where built-in items are to be embedded in cores of hollow masonry units, place a layer of metal lath, wire mesh, or plastic mesh in the joint below, and rod mortar or grout into core.

F. Fill cores in hollow CMUs with grout 24 inches (600 mm) under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.

3.5 MORTAR BEDDING AND JOINTING

A. Lay CMUs as follows:

1. Bed face shells in mortar and make head joints of depth equal to bed joints.
2. Bed webs in mortar in all courses of piers, columns, and pilasters.
3. Bed webs in mortar in grouted masonry, including starting course on footings.
4. Fully bed entire units, including areas under cells, at starting course on footings where cells are not grouted.
5. Fully bed units and fill cells with mortar at anchors and ties as needed to fully embed anchors and ties in mortar.

B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.

C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

D. Cut joints flush where indicated to receive cavity wall insulation unless otherwise indicated.

3.6 ANCHORED MASONRY VENEERS

A. Anchor masonry veneers to wall framing with masonry-veneer anchors to comply with the following requirements:

1. Fasten screw-attached anchors through sheathing to wall framing with metal fasteners of type indicated. Use two fasteners unless anchor design only uses one fastener.
2. Embed connector sections and continuous wire in masonry joints.
3. Locate anchor sections to allow maximum vertical differential movement of ties up and down.
4. Space anchors as indicated, but not more than 18 inches (458 mm) o.c. vertically and 24 inches (610 mm) o.c. horizontally, with not less than one anchor for each 2 sq. ft. (0.2 sq. m) of wall area. Install additional anchors within 12 inches (305 mm) of openings and at intervals, not exceeding 8 inches (203 mm), around perimeter.
5. Space anchors as indicated, but not more than 16 inches (406 mm) o.c. vertically and 25 inches (635 mm) o.c. horizontally, with not less than one anchor for each 2.67 sq. ft. (0.25 sq. m) of wall area. Install additional anchors within 12 inches (305 mm) of openings and at intervals, not exceeding 36 inches (914 mm), around perimeter.
6. Space anchors as indicated, but not more than 18 inches (458 mm) o.c. vertically and horizontally. Install additional anchors within 12 inches (305 mm) of openings and at intervals, not exceeding 24 inches (610 mm), around perimeter.

B. Provide not less than 2 inches (50 mm) of airspace between back of masonry veneer and face of insulation.

1. Keep airspace clean of mortar droppings and other materials during construction. Bevel beds away from airspace, to minimize mortar protrusions into airspace. Do not attempt to trowel or remove mortar fins protruding into airspace.

3.7 MASONRY-JOINT REINFORCEMENT

A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch (16 mm) on exterior side of walls, 1/2 inch (13 mm) elsewhere. Lap reinforcement a minimum of 6 inches (150 mm).

1. Space reinforcement not more than 16 inches (406 mm) o.c.
2. Space reinforcement not more than 8 inches (203 mm) o.c. in foundation walls and parapet walls.
3. Provide reinforcement not more than 8 inches (203 mm) above and below wall openings and extending 12 inches (305 mm) beyond openings in addition to continuous reinforcement.

B. Interrupt joint reinforcement at control and expansion joints unless otherwise indicated.

C. Provide continuity at wall intersections by using prefabricated T-shaped units.

D. Provide continuity at corners by using prefabricated L-shaped units.

E. Cut and bend reinforcing units as directed by manufacturer for continuity at corners, returns, offsets, column fireproofing, pipe enclosures, and other special conditions.

3.8 CONTROL AND EXPANSION JOINTS

A. General: Install control- and expansion-joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.

B. Form control joints in concrete masonry using one of the following methods:

1. Fit bond-breaker strips into hollow contour in ends of CMUs on one side of control joint. Fill resultant core with grout, and rake out joints in exposed faces for application of sealant.
2. Install preformed control-joint gaskets designed to fit standard sash block.
3. Install interlocking units designed for control joints. Install bond-breaker strips at joint. Keep head joints free and clear of mortar, or rake out joint for application of sealant.
4. Install temporary foam-plastic filler in head joints, and remove filler when unit masonry is complete for application of sealant.

C. Form expansion joints in brick as follows:

1. Build in compressible joint fillers where indicated.

D. Provide horizontal, pressure-relieving joints by either leaving an airspace or inserting a compressible filler of width required for installing sealant and backer rod specified in Section 079200 "Joint Sealants," but not less than 3/8 inch (10 mm).

1. Locate horizontal, pressure-relieving joints beneath shelf angles supporting masonry.

3.9 LINTELS

A. Install steel lintels where indicated.

B. Provide concrete or masonry lintels where shown and where openings of more than 12 inches (305 mm) for brick-size units and 24 inches (610 mm) for block-size units are shown without structural steel or other supporting lintels.

C. Provide minimum bearing of 8 inches (200 mm) at each jamb unless otherwise indicated.

3.10 FLASHING, WEEP HOLES, AND CAVITY VENTS

A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated. Install cavity vents at shelf angles, ledges, and other obstructions to upward flow of air in cavities, and where indicated.

B. Install flashing as follows unless otherwise indicated:

1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal

penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.

2. At masonry-veneer walls, extend flashing through veneer, across airspace behind veneer, and up face of sheathing at least 8 inches (200 mm); with upper edge tucked under water-resistive barrier, lapping at least 6 inches (150 mm). Fasten upper edge of flexible flashing to sheathing through termination bar.
3. At lintels and shelf angles, extend flashing a minimum of 6 inches (150 mm) into masonry at each end. At heads and sills, extend flashing 6 inches (150 mm) at ends and turn up not less than 2 inches (50 mm) to form end dams.
4. Cut flexible flashing off flush with face of wall after masonry wall construction is completed.

C. Install weep holes in exterior wythes and veneers in head joints of first course of masonry immediately above embedded flashing.

1. Use specified weep/cavity vent products to form weep holes.
2. Space weep holes 24 inches (600 mm) o.c. unless otherwise indicated.
3. Cover cavity side of weep holes with plastic insect screening at cavities insulated with loose-fill insulation.

D. Place cavity drainage material in airspace behind veneers to comply with configuration requirements for cavity drainage material in "Miscellaneous Masonry Accessories" Article.

E. Install cavity vents in head joints in exterior wythes at spacing indicated. Use specified weep/cavity vent products to form cavity vents.

1. Close cavities off vertically and horizontally with blocking in manner indicated. Install through-wall flashing and weep holes above horizontal blocking.

3.11 REINFORCED UNIT MASONRY

A. Placing Reinforcement: Comply with requirements in TMS 602/ACI 530.1/ASCE 6.

B. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure.

1. Comply with requirements in TMS 602/ACI 530.1/ASCE 6 for cleanouts and for grout placement, including minimum grout space and maximum pour height.
2. Limit height of vertical grout pours to not more than 60 inches (1520 mm).

3.12 REPAIRING, POINTING, AND CLEANING

A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.

B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent

construction, to provide a neat, uniform appearance. Prepare joints for sealant application, where indicated.

C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:

1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of masonry.
3. Clean brick by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.
4. Clean concrete masonry by applicable cleaning methods indicated in NCMA TEK 8-4A.

3.13 MASONRY WASTE DISPOSAL

A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

B. Waste Disposal as Fill Material: Dispose of clean masonry waste, including excess or soil-contaminated sand, waste mortar, and broken masonry units, by crushing and mixing with fill material as fill is placed.

1. Crush masonry waste to less than 4 inches (100 mm) in each dimension.
2. Mix masonry waste with at least two parts of specified fill material for each part of masonry waste. Fill material is specified in Section 312000 "Earth Moving."
3. Do not dispose of masonry waste as fill within 18 inches (450 mm) of finished grade.

C. Masonry Waste Recycling: Return broken CMUs not used as fill to manufacturer for recycling.

D. Excess Masonry Waste: Remove excess clean masonry waste that cannot be used as fill, as described above or recycled, and other masonry waste, and legally dispose of off Owner's property.

END OF SECTION 042000

TRANSPORTAION FACILITY
LEE COUNTY SCHOOLS

SECTION 051200 – STRUCTURAL STEEL

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:
1. Structural shapes.
2. Channels and angles.
3. Hollow structural sections.
4. Structural pipe.
5. Structural plates and bars.
6. Fasteners, connectors, and anchors.
7. Base plate grout

B. Related Sections:
1. Section 053100 - Steel Decking.

1.2 REFERENCES

A. American Institute of Steel Construction:
1. AISC Code of Standard Practice for Steel Buildings and Bridges.
2. AISC Load and Resistance Factor Design (LRFD) Specification for Structural Steel Buildings.
3. AISC Load and Resistance Factor Design Specification for Single-Angle Members.
4. AISC Seismic Provisions for Structural Steel Buildings.
5. AISC Specification for Allowable Stress Design of Single-Angle Members.
6. AISC Specification for the Design of Steel Hollow Structural Sections.
7. AISC Specification for Structural Steel Buildings Allowable Stress Design, and Plastic Design.

B. American Society of Civil Engineers:
1. ASCE 19 - Standard Applications of Steel Cables for Buildings.

C. ASTM International:
1. ASTM A36/A36M - Standard Specification for Carbon Structural Steel.
2. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless.
3. ASTM A108 - Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished.
4. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
5. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
6. ASTM A193/A193M - Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service.

7. ASTM A307 - Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength.
8. ASTM A325 - Standard Specification for Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength.
9. ASTM A354 - Standard Specification for Quenched and Tempered Alloy Steel Bolts, Studs, and Other Externally Threaded Fasteners.
10. ASTM A449 - Standard Specification for Quenched and Tempered Steel Bolts and Studs.
11. ASTM A490 - Standard Specification for Structural Bolts, Alloy Steel, Heat Treated, 150 ksi Minimum Tensile Strength.
12. ASTM A500 - Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes.
13. ASTM A501 - Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing.
14. ASTM A514/A514M - Standard Specification for High-Yield-Strength, Quenched and Tempered Alloy Steel Plate, Suitable for Welding.
15. ASTM A529/A529M - Standard Specification for High-Strength Carbon-Manganese Steel of Structural Quality.
16. ASTM A563 - Standard Specification for Carbon and Alloy Steel Nuts.
17. ASTM A572/A572M - Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Structural Steel.
18. ASTM A588/A588M - Standard Specification for High-Strength Low-Alloy Structural Steel with 50 ksi (345 MPa) Minimum Yield Point to 4-in. (100-mm) Thick.
19. ASTM A618 - Standard Specification for Hot-Formed Welded and Seamless High-Strength Low-Alloy Structural Tubing.
20. ASTM A786/A786M - Standard Specification for Hot-Rolled Carbon, Low-Alloy, High-Strength Low-Alloy, and Alloy Steel Floor Plates.
21. ASTM A847 - Standard Specification for Cold-Formed Welded and Seamless High Strength, Low Alloy Structural Tubing with Improved Atmospheric Corrosion Resistance.
22. ASTM A852/A852M - Standard Specification for Quenched and Tempered Low-Alloy Structural Steel Plate with 70 ksi (485 MPa) Minimum Yield Strength to 4 in. (100 mm) Thick.
23. ASTM A913/A913M - Standard Specification for High-Strength Low-Alloy Steel Shapes of Structural Quality, Produced by Quenching and Self-Tempering Process (QST).
24. ASTM A992/A992M - Standard Specification for Structural Steel Shapes.
25. ASTM B695 - Standard Specification for Coatings of Zinc Mechanically Deposited on Iron and Steel.
26. ASTM E94 - Standard Guide for Radiographic Examination.
27. ASTM E164 - Standard Practice for Ultrasonic Contact Examination of Weldments.
28. ASTM E165 - Standard Test Method for Liquid Penetrant Examination.
29. ASTM E709 - Standard Guide for Magnetic Particle Examination.
30. ASTM F436 - Standard Specification for Hardened Steel Washers.
31. ASTM F959 - Standard Specification for Compressible-Washer-Type Direct Tension Indicators for Use with Structural Fasteners.
32. ASTM F1554 - Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength.

33. ASTM F1852 - Standard Specification for Twist Off Type Tension Control Structural Bolt/Nut/Washer Assemblies, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength.

D. American Welding Society:
1. AWS A2.4 - Standard Symbols for Welding, Brazing, and Nondestructive Examination.
2. AWS D1.1 - Structural Welding Code - Steel.

E. Research Council on Structural Connections:
1. RCSC - Specification for Structural Joints Using ASTM A325 or A490 Bolts.

F. SSPC: The Society for Protective Coatings:
1. SSPC - Steel Structures Painting Manual.
2. SSPC Paint 15 - Steel Joist Shop Paint.
3. SSPC Paint 20 - Zinc-Rich Primers (Type I - Inorganic and Type II - Organic).
4. SSPC SP 3 - Power Tool Cleaning.
5. SSPC SP 6 - Commercial Blast Cleaning.

1.3 SUBMITTALS

A. Section 013300 - Submittal Procedures: Requirements for submittals.

B. Shop Drawings:
1. Indicate profiles, sizes, spacing, and location of structural members, openings, attachments and fasteners.
2. Connections. Engage a fabricator who utilizes a North Carolina registered Professional Engineer to prepare calculations, shop drawings and other structural data for structural steel connections. Calculations shall be submitted with the structural steel shop drawings affixed with the Professional Engineers seal.
3. Cambers.
4. Indicate welded connections with AWS A2.4 welding symbols. Indicate net weld lengths.

C. Mill Test Reports: Submit indicating structural strength, destructive and non-destructive test analysis.

D. Manufacturer’s Mill Certificate: Certify products meet or exceed specified requirements.

E. Welders Certificates: Certify welders employed on the Work, verifying AWS qualification within previous 12 months.

1.4 QUALITY ASSURANCE

A. Perform Work in accordance with the following:
1. AISC Code of Standard Practice for Steel Buildings and Bridges.
2. AISC Code of Standard Practice for Steel Buildings and Bridges. Section 10.
3. AISC Seismic Provisions for Structural Steel Buildings.
4. AISC Specification for Structural Steel Buildings Allowable Stress Design, and Plastic Design.

1.5 QUALIFICATIONS

A. Fabricator: Company specializing in performing Work of this section with minimum 5 years experience with the following current AISC Certification:
   1. Standard Steel Building Structures (STD).

B. Erector: Company specializing in performing Work of this section with minimum 5 years experience.

C. Welders and Welding Procedures: AWS D1.1 qualified within previous 12 months.

1.6 COORDINATION

A. Section 014000 - Quality Requirements.

B. Coordinate work with the following:
   1. Section 053100.
   2. Section 055000 for miscellaneous steel supports other than structural steel.

PART 2 PRODUCTS

2.1 STRUCTURAL STEEL

A. Structural W-Shapes: ASTM A992.

B. Structural M-Shapes: ASTM A572.

C. Structural T-Shapes: Cut from structural W-shapes.

D. Channels and Angles: ASTM A992.

E. Square and Rectangular Hollow Structural Sections: ASTM A500, Grade C.

F. Structural Pipe: ASTM A53, Grade B.

G. Structural Plates and Bars: ASTM A36 or ASTM A572, Grade 50.

2.2 FASTENERS, CONNECTORS, AND ANCHORS

A. High-Strength Bolts, Nuts, and Washers: ASTM A 325, Type 1, heavy hex steel structural bolts, heavy hex carbon-steel nuts, and hardened carbon-steel washers.
   1. Finish, Interior Framing: Plain, uncoated.
   2. Finish, Exterior Framing: Mechanically deposited zinc coating, ASTM B 695, Class 50.

B. Nuts: ASTM A563 heavy hex type.
   1. Finish: Unfinished.

C. Washers: ASTM F436; Type 1, circular
   1. Finish: Unfinished.

D. Shear Connectors: ASTM A108; Grade 1015 or 1020, headed, unfinished and in accordance with AWS D1.1; Type B.

E. Threaded Anchor Rods: ASTM F 1554, Grade 55, S1 weldable.
1. Configuration: Straight.
2. Nuts: ASTM A 563 (ASTM A 563M) heavy hex carbon steel.
3. Plate Washers: ASTM A 36/A 36M carbon steel.
4. Washers: ASTM F 436 (ASTM F 436M) hardened carbon steel.
5. Finish, Interior Framing: Plain.
6. Finish, Exterior Framing: Hot-dip zinc coating, ASTM A 153/A 153M, Class C or mechanically deposited zinc coating, ASTM B 695, Class 50.

F. Forged Structural Steel Hardware:
1. Clevises and Turnbuckles: ASTM A108; Grade 1085.
2. Eye Nuts and Eye Bolts: ASTM A108; Grade 1030.
3. Sleeve Nuts: ASTM A108; Grade 1018.
4. Rod Ends, Yoke Ends and Pins, Cotter Pins, and Coupling Nuts: Carbon steel.

2.3 WELDING MATERIALS

A. Welding Materials: AWS D1.1; type required for materials being welded.

2.4 ACCESSORIES

A. Grout: Non-shrink type, pre-mixed compound consisting of non-metallic aggregate, cement, water reducing and plasticizing additives, capable of developing minimum compressive strength of 7,000 psi at 28 days.

B. Shop and Touch-Up Primer:
1. Concealed Structural Steel: Fabricators dark color rust-inhibiting primer.
2. Exposed Structural Steel: Series 90-97 Tnemec-Zinc . DFT 2.5 to 3.n mils.

2.5 FABRICATION

A. Continuously seal joined members by continuous welds. Grind exposed welds smooth.

B. Fabricate connections for bolt, nut, and washer connectors.

C. Develop required camber for members.

2.6 FINISH

A. Prepare structural component surfaces in accordance with SSPC SP 3 "Power Tool Cleaning" for all concealed work and SSPC SP 6 "Commercial Blast Cleaning” for all work exposed to view.

B. Shop prime structural steel members. Do not prime surfaces that will be fireproofed, field welded or in contact with concrete.

C. Galvanizing for Structural Steel Members: ASTM A123; minimum 1.2 oz/sq ft coating thickness; galvanize after fabrication. Steel exposed to the weather shall be galvanized.

D. Galvanizing for Fasteners, Connectors, and Anchors:
1. Hot-Dipped Galvanizing: ASTM A153.

2.7 SOURCE QUALITY CONTROL AND TESTS

A. Section 014000 - Quality Requirements: Testing, inspection and analysis requirements.

B. Shop test bolted and welded connections as specified for field quality control tests.

C. When fabricator is approved by authority having jurisdiction, submit certificate of compliance indicating Work performed at fabricator's facility conforms to Contract Documents.
1. Specified shop tests are not required for Work performed by approved fabricator.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify bearing surfaces are at correct elevation.

B. Verify anchors rods are set in correct locations and arrangements with correct exposure for steel attachment.

3.2 PREPARATION

A. Furnish templates for installation of anchor rods and embedments in concrete and masonry work.

3.3 ERECTION

A. Allow for erection loads, and for sufficient temporary bracing to maintain structure safe, plumb, and in alignment until completion of erection and installation of permanent bracing.

B. Field weld components and shear connectors indicated on Drawings.

C. Field connect members with threaded fasteners; tighten to snug tight for bearing type connections.

D. Do not field cut or alter structural members without approval of Architect/Engineer.

E. After erection, touch up welds and abrasions to match shop finishes.

3.4 GROUT INSTALLATION

A. Shim bearing plates and equipment supports to proper elevation, snug tighten anchor bolts.

B. Fill void under bearing surface with grout. Install and pack grout to remove air pockets.

C. Moist cure grout.

D. Remove forms after grout is set. Trim grout edges to from smooth surface, splayed 45 degrees.

3.5 FIELD QUALITY CONTROL

A. Owner will engage an independent testing and inspecting agency to perform field inspections and tests and to prepare test reports.
   1. Testing agency will conduct and interpret tests and state in each report whether tested work complied with or deviates from requirements.

B. Correct deficiencies in or remove and replace structural steel that inspections and test reports indicate do not comply with specified requirements at no additional cost to the Owner.

C. Additional testing, at Contractor's expense, will be performed to determine compliance of corrected work with specified requirements.

D. Field-bolted connections will be tested and inspected according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts.
   1. Direct-tension indicator gaps will be verified to comply with ASTM F 592, Table 2.

E. In addition to visual inspection, field welded connections will be inspected and tested according to AWS D1.1 and the inspection procedures listed below, at testing agency's option.
   1. Liquid Penetrant Inspection: ASTM E165.
   2. Magnetic Particle Inspection: ASTM E 709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration will not be accepted.
   3. Radiographic Inspection: ASTM E 94 and ASTM E 142; minimum quality level "2-2T."
   4. Ultrasonic inspection: ASTM E 164.

F. In addition to visual inspection, field welded shear connectors will be inspected and tested according to requirements of AWS D1.1 for stud welding and as follows:
   1. Bend test will be performed when visual inspections reveal either less than a continuous 360 degree flash or welding repairs to any shear connector.
   2. Tests will be conducted on additional shear connectors when weld fracture occurs on shear connectors already tested, according to requirements of AWS D1.1

G. Contractor shall furnish all necessary staging, platforms, ladders, or other items necessary to facilitate the testing laboratory in testing and inspecting the work.

H. The testing laboratory shall inspect 15% of the field full penetration welds, except at truss splices where 100% shall be inspected. All tested welds shall pass.

I. The testing laboratory shall inspect 50% of the fillet welds and spot check gauge and length of all welds.

3.6 CLEANING

A. Touch-up Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas of shop paint. Apply paint to exposed areas using same material as used for shop painting.
   1. Apply by brush or spray to provide a minimum dry film thickness of 1.5 mils.

B. Touch up all hot dipped galvanized steel with high zinc dust content paint.
   1. For re-galvanizing welds and steel, comply with SSPC-Paint 20.

END OF SECTION 051200

SECTION 053100 – STEEL DECK

PART 1 - GENERAL

1.1 SCOPE

A. This work shall consist of furnishing all plant, labor, materials, equipment, and apparatus for the installation of all steel roof decking and floor decking with accessories indicated, specified, and/or reasonably implied for a complete, first-quality job.

1.2 RELATED WORK SPECIFIED ELSEWHERE

A. Section 033000 – Cast-in-Place Concrete

B. Section 051200 - Structural Steel

1.3 REFERENCE SPECIFICATIONS

A. "Specification for the Design of Light Gage Cold-Formed Steel Structure Members" of the American Institute of Steel Construction.

B. "Code of Recommended Standard Practice" of the Steel Deck Institute.

C. Specifications and commentary for composite steel floor deck of the Steel Deck Institute.

D. Specifications and commentary for steel roof deck of the Steel Deck Institute.

E. Structural Welding Code - Sheet steel of the American Welding Society.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: Engage an experienced installer who has completed steel deck similar in material, design, and extent to that indicated for this Project and with a record of successful in-service performance.

B. Qualifications of Welding: Use qualified processes and welding operators in conformance with AWS "Welder Qualification" procedures.

C. Testing Agency Qualifications: An independent agency qualified according to ASTM E 329 for testing indicated

D. Fire-Test-Response Characteristics: Where indicated, provide steel deck units identical to those tested for fire resistance per ASTM E 119 by a testing and inspecting agency acceptable to authorities having jurisdiction.
   1. Fire-Resistance Ratings: Indicated by design designations of applicable testing and inspecting agency.

2. Steel deck units shall be identified with appropriate markings of applicable testing and inspecting agency

E. AISI Specifications: Comply with calculated structural characteristics of steel deck according to AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members."

F. FMG Listing: Provide steel roof deck evaluated by FMG and listed in its "Approval Guide, Building Materials" for Class 1 fire rating and Class 1-90 windstorm ratings.

G. Welding Inspection: All decking welds shall be inspected by the Architect prior to covering. Notify the Architect in writing forty-eight (48) hours prior to completing welds for each major area.

1.5 SUBMITTALS

A. Shop and Erection Drawings shall be submitted for all metal decking to the Architect for approval. Drawings shall indicate layout, types of specified materials and accessories, gauges to be supplied, anchorage details, all conditions requiring closure panels, supplementary framing, sump pans, cant strips, cut openings, special jointing or other accessories. Drawings shall include layout for all shear studs to be applied through deck units. Manufacture or fabricating of any materials or the performing of any work prior to the approval of shop drawings will be entirely at the risk of the Contractor.

B. Product Data: For each type of deck, accessory, and product indicated

C. The Contractor shall submit the manufacturer's specifications, load tables, and installation instructions for each type specified.

D. Welding certificates.

E. Field quality-control test and inspection reports.

1.6 DELIVERY, STORAGE AND HANDLING

A. Steel deck units shall be protected against damage in transit to the jobsite.

B. If site storage is necessary, steel deck units shall be stacked on wood blocking clear of the ground and tilted slightly to insure against the entrapment of water.

C. The steel deck units shall be hoisted to each individual floor as required and rough spread.

PART 2 - PRODUCTS

2.1 ROOF DECK

2.2 COMPOSITE FLOOR DECK

A. Composite Steel Floor Deck: Fabricate panels, with integrally embossed or raised pattern ribs and interlocking side laps, to comply with "SDI Specifications and Commentary for Composite Steel Floor Deck," in SDI Publication No. 30, with the minimum section properties indicated, and with the following:
   1. Galvanized Steel Sheet: ASTM A653, Structural Steel (SS), Grade 50, G60 zinc coating.
   2. Profile Depth: 2”
   3. Design Uncoated-Steel Thickness: 20 gauge.
   4. Span Condition: Triple span or more.

2.3 ACCESSORIES

A. General: Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.

B. Weld Washers: Mild steel, uncoated, sized as recommended by manufacturer of steel deck units.

C. Mechanical Fasteners: Stainless steel, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.

D. Side-Lap Fasteners: Stainless steel, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 minimum diameter.

E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 33,000 psi, not less than 0.0359-inch design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.

F. Pour Stops and Girder Fillers: Steel sheet, minimum yield strength of 33,000 psi, of same material and finish as deck, and of thickness and profile indicated.

G. Column Closures, End Closures, Z-Closures, and Cover Plates: Steel sheet, of same material, finish, and thickness as deck, unless otherwise indicated.

H. Repair Paint: Manufacturer's standard rust-inhibitive primer of same color as primer.

I. Galvanizing Repair Paint: High zinc-dust content paint formulated specifically for repair of damaged galvanized surfaces. Prepare surfaces and repair in accordance with procedures specified in ASTM A 780.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance.

3.2 INSTALLATION, GENERAL

A. Install deck panels and accessories according to applicable specifications and commentary in SDI Publication No. 30, manufacturer's written instructions, and requirements in this Section.

B. Install temporary shoring before placing deck panels, if required to meet deflection limitations.

C. Locate deck bundles to prevent overloading of supporting members.

D. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.

E. Place deck panels flat and square and fasten to supporting frame without warp or deflection.

F. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.

G. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.

H. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.

I. Mechanical fasteners may be used in lieu of welding to fasten deck. Locate mechanical fasteners and install according to deck manufacturer's written instructions.

J. Holes for openings: Deck shall be cut by the Contractor to fit large framed openings which are located by dimension on the structural design drawings. Holes required by other trades shall be supplied at the expense of those trades. The trade involved shall notify the Architect/Engineer regarding the size, location and number of holes so that the structural adequacy of the steel deck units and/or composite slab can be checked. Holes shall be cut in floor deck units only after concrete has been placed and 75% of design strength attained. Refer to Typical Details for deck support steel framing.

3.3 FLOOR DECK INSTALLATION

A. Erect metal deck in accordance with SDI 29 Manual.

B. Bear deck on steel supports with 1-1/2 inch minimum bearing. Align and level.

C. Fasten deck to steel support members at ends and intermediate supports with 5/8" diameter fusion welds as indicated on the drawings.

D. Weld in accordance with AWS D1.1.

E. Mechanically clinch male/female side laps as indicated on the drawings..

F. Reinforce steel deck openings from 6 to 18 inches in size with 2 x 2 x ¼ inch steel angles. Place angles perpendicular to flutes; extend minimum two flutes beyond each side of opening and mechanically attach to deck at each flute. Unless other noted on the drawings. Refer to Typical Details.

G. Install 6 inch minimum wide sheet steel cover plates, of same thickness as deck, where deck changes direction. Mechanically attach 12 inches oc maximum.

H. Install wet concrete stops at floor edge upturned to top surface of slab, to contain wet concrete. Install stops of sufficient strength to remain stationary without distortion.

I. Install sheet steel closures and angle flashings to close openings between deck and walls, columns, and openings.

J. Position floor drain pans with flange bearing on top surface of deck. Fusion weld at each deck flute.

K. Welding washers shall be used on all deck units with metal thickness less than 0.028 inches (22 gage). Welding washers shall be a minimum thickness of 0.0598 inches and have a nominal 3/8 inch diameter hole.

L. Immediately after welding deck and other metal components in position, coat welds, burned areas, and damaged surface coating, with touch-up prime paint.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.

B. Field welds will be subject to inspection.

C. Additional testing will be performed to determine compliance of corrected work with specified requirements.

D. Testing agency will report inspection results promptly and in writing to Contractor and Architect.

E. Remove and replace work that does not comply with specified requirements.

F. Additional inspecting, at Contractor's expense, will be performed to determine compliance of corrected work with specified requirements.

3.5 REPAIRS AND PROTECTION

A. Repair Painting: Wire brushing, cleaning, and repair painting of rust spots, welds, and abraded areas of both deck surfaces are included in Division 9 Section “Interior Painting."

B. Provide final protection and maintain conditions to ensure that steel deck is without damage or deterioration at time of Substantial Completion.

END OF SECTION 053100

SECTION 055000 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Steel framing and supports for operable partitions.
2. Steel framing and supports for overhead doors.
3. Steel framing and supports for mechanical and electrical equipment.
4. Steel framing and supports for applications where framing and supports are not specified in other Sections.
5. Slotted channel framing.
6. Miscellaneous steel trim including steel angle corner guards and steel edgings.
7. Metal bollards.
8. Metal downspout boots.
9. Loose bearing and leveling plates for applications where they are not specified in other Sections.

B. Products furnished, but not installed, under this Section include the following:

1. Loose steel lintels.

C. Related Requirements:

1. Section 042000 "Unit Masonry" for installing loose lintels, anchor bolts, and other items built into unit masonry.

1.3 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written instructions to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of metal fabrications that are anchored to or that receive other work. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

1.4 ACTION SUBMITTALS

A. Product Data: For the following:

1. Nonslip aggregates and nonslip-aggregate surface finishes.
2. Fasteners.
3. Shop primers.
4. Shrinkage-resisting grout.
5. Slotted channel framing.
6. Metal downspout boots.

B. Shop Drawings: Show fabrication and installation details. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items. Provide Shop Drawings for the following:

1. Steel framing and supports for ceiling-hung toilet compartments.
2. Steel framing and supports for operable partitions.
3. Steel framing and supports for overhead doors.
4. Steel framing and supports for mechanical and electrical equipment.
5. Steel framing and supports for applications where framing and supports are not specified in other Sections.
6. Shelf angles.
7. Miscellaneous steel trim including steel angle corner guards and steel edgings.
8. Metal bollards.
9. Loose steel lintels.

1.5 INFORMATIONAL SUBMITTALS

A. Welding certificates.

B. Research Reports: For post-installed anchors.

1.6 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel in accordance with the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."
3. AWS D1.6/D1.6M, "Structural Welding Code - Stainless Steel."

1.7 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of walls, floor slabs, decks, and other construction contiguous with metal fabrications by field measurements before fabrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes acting on exterior metal fabrications by preventing buckling, opening of joints, overstressing of components, failure of connections, and other detrimental effects.

1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

2.2 METALS

A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.

B. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

C. Stainless Steel Sheet, Strip, and Plate: ASTM A240/A240M or ASTM A666, Type 304.

D. Stainless Steel Bars and Shapes: ASTM A276/A276M, Type 304.

E. Steel Tubing: ASTM A500/A500M, cold-formed steel tubing.

F. Steel Pipe: ASTM A53/A53M, Standard Weight (Schedule 40) unless otherwise indicated.

G. Slotted Channel Framing: Cold-formed metal box channels (struts) complying with MFMA-4.

1. Size of Channels: 1-5/8 by 1-5/8 inches (41 by 41 mm).
2. Material: Cold-rolled steel, ASTM A1008/A1008M, commercial steel, Type B; 0.0966-inch (2.5-mm) minimum thickness; coated with rust-inhibitive, baked-on, acrylic enamel.

H. Cast Iron: Either gray iron, ASTM A48/A48M, or malleable iron, ASTM A47/A47M, unless otherwise indicated.

I. Aluminum Plate and Sheet: ASTM B209 (ASTM B209M), Alloy 6061-T6.

J. Aluminum Extrusions: ASTM B221 (ASTM B221M), Alloy 6063-T6.

K. Aluminum Castings: ASTM B26/B26M, Alloy 443.0-F.

2.3 FASTENERS

A. General: Unless otherwise indicated, provide Type 304 stainless steel fasteners for exterior use and zinc-plated fasteners with coating complying with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, at exterior walls. Select fasteners for type, grade, and class required.

1. Provide stainless steel fasteners for fastening aluminum or stainless steel.

B. Steel Bolts and Nuts: Regular hexagon-head bolts, ASTM A307, Grade A (ASTM F568M, Property Class 4.6); with hex nuts, ASTM A563 (ASTM A563M); and, where indicated, flat washers.

C. High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A325 (Grade A325M), Type 3, heavy-hex steel structural bolts; ASTM A563, Grade DH3, (ASTM A563M, Class 10S3) heavy-hex carbon-steel nuts; and where indicated, flat washers.

D. Stainless Steel Bolts and Nuts: Regular hexagon-head annealed stainless steel bolts, ASTM F593 (ASTM F738M); with hex nuts, ASTM F594 (ASTM F836M); and, where indicated, flat washers; Alloy Group 1 (A1).

E. Anchor Bolts: ASTM F1554, Grade 36, of dimensions indicated; with nuts, ASTM A563 (ASTM A563M); and, where indicated, flat washers.

1. Hot-dip galvanize or provide mechanically deposited, zinc coating where item being fastened is indicated to be galvanized.

F. Anchors, General: Capable of sustaining, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing in accordance with ASTM E488/E488M, conducted by a qualified independent testing agency.

G. Cast-in-Place Anchors in Concrete: Either threaded or wedge type unless otherwise indicated; galvanized ferrous castings, either ASTM A47/A47M malleable iron or ASTM A27/A27M cast steel. Provide bolts, washers, and shims as needed, all hot-dip galvanized per ASTM F2329/F2329M.

H. Post-Installed Anchors: Torque-controlled expansion anchors or chemical anchors.

1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, unless otherwise indicated.
2. Material for Exterior Locations and Where Stainless Steel Is Indicated: Alloy Group 1 (A1) stainless steel bolts, ASTM F593 (ASTM F738M), and nuts, ASTM F594 (ASTM F836M).

2.4 MISCELLANEOUS MATERIALS

A. Shop Primers: Provide primers that comply with Section 099113 "Exterior Painting," Section 099123 "Interior Painting," and Section 099600 "High-Performance Coatings."

B. Galvanizing Repair Paint: High-zinc-dust-content paint complying with SSPC-Paint 20 and compatible with paints specified to be used over it.

C. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

D. Shrinkage-Resistant Grout: Factory-packaged, nonmetallic, nonstaining, noncorrosive, nongaseous grout complying with ASTM C1107/C1107M. Provide grout specifically recommended by manufacturer for interior and exterior applications.

E. Concrete: Comply with requirements in Section 033000 "Cast-in-Place Concrete" for normal-weight, air-entrained concrete with a minimum 28-day compressive strength of 3000 psi (20 MPa).

2.5 FABRICATION, GENERAL

A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.

B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch (1 mm) unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.

C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.

D. Form exposed work with accurate angles and surfaces and straight edges.

E. Weld corners and seams continuously to comply with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.

F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.

G. Fabricate seams and other connections that are exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.

H. Cut, reinforce, drill, and tap metal fabrications as indicated to receive finish hardware, screws, and similar items.

I. Provide for anchorage of type indicated; coordinate with supporting structure. Space anchoring devices to secure metal fabrications rigidly in place and to support indicated loads.

J. Where units are indicated to be cast into concrete or built into masonry, equip with integrally welded steel strap anchors, 1/8 by 1-1/2 inches (3.2 by 38 mm), with a minimum 6-inch (150-mm) embedment and 2-inch (50-mm) hook, not less than 8 inches (200 mm) from ends and corners of units and 24 inches (600 mm) o.c., unless otherwise indicated.

2.6 MISCELLANEOUS FRAMING AND SUPPORTS

A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.

B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction.

1. Fabricate units from slotted channel framing where indicated.
2. Furnish inserts for units installed after concrete is placed.

C. Fabricate supports for operable partitions from continuous steel beams of sizes indicated with attached bearing plates, anchors, and braces as recommended by partition manufacturer. Drill or punch bottom flanges of beams to receive partition track hanger rods; locate holes where indicated on operable partition Shop Drawings.

D. Galvanize miscellaneous framing and supports where indicated.

E. Prime miscellaneous framing and supports with primer specified in Section 099600 "High-Performance Coatings" where indicated.

2.7 SHELF ANGLES

A. Fabricate shelf angles from steel angles of sizes indicated and for attachment to concrete framing. Provide horizontally slotted holes to receive 3/4-inch (19-mm) bolts, spaced not more than 6 inches (150 mm) from ends and 24 inches (600 mm) o.c., unless otherwise indicated.

1. Provide mitered and welded units at corners.
2. Provide open joints in shelf angles at expansion and control joints. Make open joint approximately 2 inches (50 mm) larger than expansion or control joint.

B. For cavity walls, provide vertical channel brackets to support angles from backup masonry and concrete.

C. Galvanize and prime shelf angles located in exterior walls.

D. Prime shelf angles located in exterior walls with primer specified in Section 099600 "High-Performance Coatings."

E. Furnish wedge-type concrete inserts, complete with fasteners, to attach shelf angles to cast-in-place concrete.

2.8 MISCELLANEOUS STEEL TRIM

A. Unless otherwise indicated, fabricate units from steel shapes, plates, and bars of profiles shown with continuously welded joints and smooth exposed edges. Miter corners and use concealed field splices where possible.

B. Provide cutouts, fittings, and anchorages as needed to coordinate assembly and installation with other work.

1. Provide with integrally welded steel strap anchors for embedding in concrete or masonry construction.

C. Galvanize and prime exterior miscellaneous steel trim.

D. Prime exterior miscellaneous steel trim with primer specified in Section 099600 "High-Performance Coatings."

2.9 METAL BOLLARDS

A. Fabricate metal bollards from Schedule 80 stainless steel, No. 4/180-grit finish.

B. Prime steel bollards with primer specified in Section 099600 "High-Performance Coatings."

2.10 METAL DOWNSPOUT BOOTS

A. Manufacturers: Subject to compliance with requirements, provide products from one of the following:

1. J. R. Hoe.
2. J.R. Smith Manufacturing Company.
3. Mifab, Inc.
4. Neenah Foundry.
5. Zurn Industries, LLC.

B. Source Limitations: Obtain downspout boots from single source from single manufacturer.

C. Provide downspout boots made from cast iron in heights indicated with inlets of size and shape to suit downspouts. Provide units with flanges and holes for countersunk anchor bolts.

1. Outlet: Horizontal, to discharge into pipe.

D. Prime cast-iron downspout boots with primer specified in Section 099600 "High-Performance Coatings."

2.11 LOOSE BEARING AND LEVELING PLATES

A. Provide loose bearing and leveling plates for steel items bearing on masonry or concrete construction. Drill plates to receive anchor bolts and for grouting.

B. Galvanize bearing and leveling plates.

C. Prime plates with primer specified in Section 099600 "High-Performance Coatings."

2.12 LOOSE STEEL LINTELS

A. Fabricate loose steel lintels from steel angles and shapes of size indicated for openings and recesses in masonry walls and partitions at locations indicated. Fabricate in single lengths for each opening unless otherwise indicated. Weld adjoining members together to form a single unit where indicated.

B. Size loose lintels to provide bearing length at each side of openings equal to 1/12 of clear span, but not less than 8 inches (200 mm) unless otherwise indicated.

C. Galvanize and prime loose steel lintels located in exterior walls.

D. Prime loose steel lintels located in exterior walls with primer specified in Section 099600 "High-Performance Coatings."

2.13 STEEL WELD PLATES AND ANGLES

A. Provide steel weld plates and angles not specified in other Sections, for items supported from concrete construction as needed to complete the Work. Provide each unit with no fewer than two integrally welded steel strap anchors for embedding in concrete.

2.14 GENERAL FINISH REQUIREMENTS

A. Finish metal fabrications after assembly.

B. Finish exposed surfaces to remove tool and die marks and stretch lines, and to blend into surrounding surface.

2.15 STEEL AND IRON FINISHES

A. Galvanizing: Hot-dip galvanize items as indicated to comply with ASTM A153/A153M for steel and iron hardware and with ASTM A123/A123M for other steel and iron products.

1. Do not quench or apply post galvanizing treatments that might interfere with paint adhesion.

B. Preparation for Shop Priming Galvanized Items: After galvanizing, thoroughly clean galvanized surfaces of grease, dirt, oil, flux, and other foreign matter, and treat with metallic phosphate process.

C. Shop prime iron and steel items not indicated to be galvanized unless they are to be embedded in concrete, sprayed-on fireproofing, or masonry, or unless otherwise indicated.

D. Preparation for Shop Priming: Prepare surfaces to comply with requirements indicated below:

1. Exterior Items: SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
2. Items Indicated to Receive Primers Specified in Section 099600 "High-Performance Coatings": SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
3. Other Steel Items: SSPC-SP 3, "Power Tool Cleaning."

4. Galvanized-Steel Items: SSPC-SP 16, "Brush-off Blast Cleaning of Coated and Uncoated Galvanized Steel, Stainless Steels, and Non-Ferrous Metals."

E. Shop Priming: Apply shop primer to comply with SSPC-PA 1, "Paint Application Specification No. 1: Shop, Field, and Maintenance Painting of Steel," for shop painting.

1. Stripe paint corners, crevices, bolts, welds, and sharp edges.

2.16 ALUMINUM FINISHES

A. As-Fabricated Finish: AA-M12.

B. Clear Anodic Finish: AAMA 611, Class I, AA-M12C22A41.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.

B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.

C. Field Welding: Comply with the following requirements:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.

D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.

E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

F. Corrosion Protection: Coat concealed surfaces of aluminum that come into contact with grout, concrete, masonry, wood, or dissimilar metals with the following:

1. Cast Aluminum: Heavy coat of bituminous paint.
2. Extruded Aluminum: Two coats of clear lacquer.

3.2 INSTALLATION OF MISCELLANEOUS FRAMING AND SUPPORTS

A. General: Install framing and supports to comply with requirements of items being supported, including manufacturers' written instructions and requirements indicated on Shop Drawings.

B. Anchor supports for operable partitions and overhead doors securely to, and rigidly brace from, building structure.

C. Anchor shelf angles securely to existing construction with expansion anchors or anchor bolts.

D. Support steel girders on solid grouted masonry, concrete, or steel pipe columns. Secure girders with anchor bolts embedded in grouted masonry or concrete or with bolts through top plates of pipe columns.

1. Where grout space under bearing plates is indicated for girders supported on concrete or masonry, install as specified in "Installing Bearing and Leveling Plates" Article.

E. Install pipe columns on concrete footings with grouted baseplates. Position and grout column baseplates as specified in "Installation of Bearing and Leveling Plates" Article.

1. Grout baseplates of columns supporting steel girders after girders are installed and leveled.

3.3 INSTALLATION OF METAL BOLLARDS

A. Anchor bollards in place with concrete footings. Center and align bollards in holes 3 inches (75 mm) above bottom of excavation. Place concrete and vibrate or tamp for consolidation. Support and brace bollards in position until concrete has cured.

B. Fill bollards solidly with concrete, mounding top surface to shed water.

3.4 INSTALLATION OF BEARING AND LEVELING PLATES

A. Clean concrete and masonry bearing surfaces of bond-reducing materials, and roughen to improve bond to surfaces. Clean bottom surface of plates.

B. Set bearing and leveling plates on wedges, shims, or leveling nuts. After bearing members have been positioned and plumbed, tighten anchor bolts. Do not remove wedges or shims but, if protruding, cut off flush with edge of bearing plate before packing with shrinkage-resistant grout. Pack grout solidly between bearing surfaces and plates to ensure that no voids remain.

3.5 REPAIRS

A. Touchup Painting:

1. Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint are specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

B. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing to comply with ASTM A780/A780M.

END OF SECTION 055000

SECTION 055113 - METAL PAN STAIRS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Preassembled steel stairs with concrete-filled treads.
2. Steel tube railings and guards attached to metal stairs.
3. Steel tube handrails attached to walls adjacent to metal stairs.

1.3 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written instructions to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of anchorages for metal stairs, and railings.

1. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, blocking for attachment of wall-mounted handrails, and items with integral anchors, that are to be embedded in concrete or masonry.
2. Deliver such items to Project site in time for installation.

C. Schedule installation of railings and guards so wall attachments are made only to completed walls.

1. Do not support railings and guards temporarily by any means that do not satisfy structural performance requirements.

1.4 ACTION SUBMITTALS

A. Product Data: For metal pan stairs and the following:

1. Woven-wire mesh.
2. Abrasive nosings.
3. Grout.

B. Shop Drawings:

1. Include plans, elevations, sections, details, and attachments to other work.
2. Indicate sizes of metal sections, thickness of metals, profiles, holes, and field joints.
3. Include plan at each level.
4. Indicate locations of anchors, weld plates, and blocking for attachment of wall-mounted handrails.

C. Delegated-Design Submittal: For stairs, railings and guards, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For professional engineer's experience with providing delegated-design engineering services of the kind indicated, including documentation that engineer is licensed in the State in which Project is located.

B. Welding certificates.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

B. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
2. AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel."

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store materials to permit easy access for inspection and identification.

1. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers.
2. Protect steel members and packaged materials from corrosion and deterioration.
3. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures.

    a. Repair or replace damaged materials or structures as directed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design stairs, railings and guards, including attachment to building construction.

B. Structural Performance of Stairs: Metal stairs shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:

1. Uniform Load: 100 lbf/sq. ft. (4.79 kN/sq. m).
2. Concentrated Load: 300 lbf (1.33 kN) applied on an area of 4 sq. in. (2580 sq. mm).
3. Uniform and concentrated loads need not be assumed to act concurrently.
4. Stair Framing: Capable of withstanding stresses resulting from railing and guard loads in addition to loads specified above.
5. Limit deflection of treads, platforms, and framing members to L/360 or 1/4 inch (6.4 mm), whichever is less.

C. Structural Performance of Railings and Guards: Railings and guards, including attachment to building construction, shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:

1. Handrails and Top Rails of Guards:

a. Uniform load of 50 lbf/ft. (0.73 kN/m) applied in any direction.
b. Concentrated load of 200 lbf (0.89 kN) applied in any direction.
c. Uniform and concentrated loads need not be assumed to act concurrently.

2. Infill of Guards:

a. Concentrated load of 50 lbf (0.22 kN) applied horizontally on an area of 1 sq. ft. (0.093 sq. m).
b. Infill load and other loads need not be assumed to act concurrently.

3. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

2.2 METALS

A. Metal Surfaces: Provide materials with smooth, flat surfaces unless otherwise indicated. For components exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.

B. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

C. Steel Tubing for Railings and Guards: ASTM A513/A513M.

D. Steel Pipe for Railings and Guards: ASTM A53/A53M, Type F or Type S, Grade A, Standard Weight (Schedule 40), unless another grade and weight are required by structural loads.

E. Uncoated, Cold-Rolled Steel Sheet: ASTM A1008/A1008M, structural steel, Grade 25 (Grade 170), unless another grade is required by design loads; exposed.

F. Uncoated, Hot-Rolled Steel Sheet: ASTM A1011/A1011M, structural steel, Grade 30 (Grade 205), unless another grade is required by design loads.

G. Woven-Wire Mesh: Intermediate-crimp, diamond pattern, 2-inch (50-mm) woven-wire mesh, made from 0.135-inch (3.5-mm) nominal-diameter steel wire complying with ASTM A510/A510M.

H. Bronze Castings: ASTM B584, Alloy UNS No. C83600 (leaded red brass) or No. C84400 (leaded semired brass).

2.3 ABRASIVE NOSINGS

A. Cast-Metal Units: Cast bronze, with an integral abrasive, as-cast finish consisting of aluminum oxide, silicon carbide, or a combination of both. Fabricate units in lengths necessary to accurately fit openings or conditions.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. American Safety Tread Company, Inc.
b. Balco, Inc.
c. Barry Pattern & Foundry Company, Inc.
d. Granite State Casting Company.
e. Safe-T-Metal Company, Inc.
f. Wooster Products, Inc.

2. Configuration: Cross-hatched units, 4 inches (100 mm) wide without lip.

B. Provide anchors for embedding units in concrete, either integral or applied to units, as standard with manufacturer.

C. Apply bituminous paint to concealed surfaces of cast-metal units set into concrete.

2.4 FASTENERS

A. General: Provide zinc-plated fasteners with coating complying with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 12 for exterior use, and Class Fe/Zn 5 where built into exterior walls.

1. Select fasteners for type, grade, and class required.

B. Fasteners for Anchoring Railings and Guards to Other Construction: Select fasteners of type, grade, and class required to produce connections suitable for anchoring railings and guards to other types of construction indicated and capable of withstanding design loads.

C. Bolts and Nuts: Regular hexagon-head bolts, ASTM A307, Grade A; with hex nuts, ASTM A563 (ASTM A563M); and, where indicated, flat washers.

D. Anchor Bolts: ASTM F1554, Grade 36, of dimensions indicated; with nuts, ASTM A563 (ASTM A563M); and, where indicated, flat washers.

E. Post-Installed Anchors: Torque-controlled expansion anchors or chemical anchors capable of sustaining, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing according to ASTM E488/E488M, conducted by a qualified independent testing agency.

1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, unless otherwise indicated.

2.5 MISCELLANEOUS MATERIALS

A. Welding Electrodes: Comply with AWS requirements.

B. Shop Primers: Provide primers that comply with Section 099123 "Interior Painting."

C. Universal Shop Primer: Fast-curing, lead- and chromate-free, universal modified-alkyd primer complying with MPI#79 and compatible with topcoat.

1. Use primer containing pigments that make it easily distinguishable from zinc-rich primer.

D. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

E. Nonmetallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M, factory-packaged, nonmetallic aggregate grout; recommended by manufacturer for interior use; noncorrosive and nonstaining; mixed with water to consistency suitable for application and a 30-minute working time.

F. For galvanized reinforcement, use galvanized wire or dielectric-polymer-coated wire bar supports.

2.6 FABRICATION, GENERAL

A. Provide complete stair assemblies, including metal framing, hangers, struts, railings and guards, clips, brackets, bearing plates, and other components necessary to support and anchor stairs and platforms on supporting structure.

1. Join components by welding unless otherwise indicated.
2. Use connections that maintain structural value of joined pieces.

B. Assemble stairs, railings, and guards in shop to greatest extent possible.

1. Disassemble units only as necessary for shipping and handling limitations.
2. Clearly mark units for reassembly and coordinated installation.

C. Cut, drill, and punch metals cleanly and accurately.

1. Remove burrs and ease edges to a radius of approximately 1/32 inch (1 mm) unless otherwise indicated.
2. Remove sharp or rough areas on exposed surfaces.

D. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.

E. Form exposed work with accurate angles and surfaces and straight edges.

F. Weld connections to comply with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds to comply with NOMMA's "Voluntary Joint Finish Standards" for Finish #2 - Completely sanded joint with some undercutting and pinholes okay.

G. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners where possible.

1. Where exposed fasteners are required, use Phillips flat-head (countersunk) screws or bolts unless otherwise indicated.
2. Locate joints where least conspicuous.
3. Fabricate joints that will be exposed to weather in a manner to exclude water.
4. Provide weep holes where water may accumulate internally.

2.7 FABRICATION OF STEEL-FRAMED STAIRS

A. NAAMM Stair Standard: Comply with NAAMM AMP 510, "Metal Stairs Manual," for Commercial Class, unless more stringent requirements are indicated.

B. Stair Framing:

1. Fabricate stringers of steel channels.

a. Stringer Size: As required to comply with "Performance Requirements" Article.
b. Provide closures for exposed ends of channel and rectangular tube stringers.
c. Finish: Shop primed.

2. Construct platforms of steel channel headers and miscellaneous framing members as required to comply with "Performance Requirements" Article.

a. Provide closures for exposed ends of channel and rectangular tube framing.
b. Finish: Shop primed.

3. Weld stringers to headers; weld framing members to stringers and headers.
4. Where masonry walls support metal stairs, provide temporary supporting struts designed for erecting steel stair components before installing masonry.

C. Metal Pan Stairs: Form risers, subtread pans, and subplatforms to configurations shown from steel sheet of thickness needed to comply with performance requirements, but not less than 0.067 inch (1.7 mm).

1. Steel Sheet: Uncoated, cold-rolled steel sheet.
2. Directly weld metal pans to stringers; locate welds on top of subtreads where they will be concealed by concrete fill. Do not weld risers to stringers.
3. Attach risers and subtreads to stringers with brackets made of steel angles or bars. Weld brackets to stringers and attach metal pans to brackets by welding, riveting, or bolting.
4. Shape metal pans to include nosing integral with riser.
5. Attach abrasive nosings to risers.

2.8 FABRICATION OF STAIR RAILINGS AND GUARDS

A. Fabricate railings and guards to comply with requirements indicated for design, dimensions, details, finish, and member sizes, including wall thickness of member, post spacings, wall bracket spacing, and anchorage, but not less than that needed to withstand indicated loads.

1. Rails and Posts: 1-5/8-inch- (41-mm-) diameter top and bottom rails and 1-1/2-inch- (38-mm-) square posts.
2. Mesh Infill: Woven-wire mesh crimped into 1-by-1/2-by-1/8-inch (25-by-13-by-3-mm) steel channel frames. Orient wire mesh with diamonds vertical.

B. Welded Connections: Fabricate railings and guards with welded connections.

1. Fabricate connections that are exposed to weather in a manner that excludes water.

    a. Provide weep holes where water may accumulate internally.

2. Cope components at connections to provide close fit, or use fittings designed for this purpose.
3. Weld all around at connections, including at fittings.
4. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
5. Obtain fusion without undercut or overlap.
6. Remove flux immediately.
7. Finish welds to comply with NOMMA's "Voluntary Joint Finish Standards" for Finish #2 - Completely sanded joint, some undercutting and pinholes are okay as shown in NAAMM AMP 521.

C. Form changes in direction of railings and guards as follows:

1. By bending or by inserting prefabricated elbow fittings.

D. For changes in direction made by bending, use jigs to produce uniform curvature for each repetitive configuration required. Maintain cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of components.

E. Close exposed ends of railing and guard members with prefabricated end fittings.

F. Provide wall returns at ends of wall-mounted handrails unless otherwise indicated.

1. Close ends of returns unless clearance between end of rail and wall is 1/4 inch (6 mm) or less.

G. Connect posts to stair framing by direct welding unless otherwise indicated.

H. Brackets, Flanges, Fittings, and Anchors: Provide wall brackets, end closures, flanges, miscellaneous fittings, and anchors for interconnecting components and for attaching to other work.

1. Furnish inserts and other anchorage devices for connecting to concrete or masonry work.
2. For nongalvanized railings and guards, provide nongalvanized ferrous-metal fittings, brackets, fasteners, and sleeves, except galvanize anchors embedded in exterior masonry and concrete construction.
3. Provide type of bracket with flange tapped for concealed anchorage to threaded hanger bolt and that provides 1-1/2-inch (38-mm) clearance from inside face of handrail to finished wall surface.

I. Fillers: Provide fillers made from steel plate, or other suitably crush-resistant material, where needed to transfer wall bracket loads through wall finishes to structural supports.

1. Size fillers to suit wall finish thicknesses and to produce adequate bearing area to prevent bracket rotation and overstressing of substrate.

2.9 FINISHES

A. Finish metal stairs after assembly.

B. Preparation for Shop Priming: Prepare uncoated, ferrous-metal surfaces to comply with SSPC-SP 3, "Power Tool Cleaning."

C. Apply shop primer to uncoated surfaces of metal stair components, except those with galvanized finishes and those to be embedded in concrete or masonry unless otherwise indicated. Comply with SSPC-PA 1, "Paint Application Specification No. 1: Shop, Field, and Maintenance Painting of Steel," for shop painting.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify elevations of floors, bearing surfaces and locations of bearing plates, and other embedments for compliance with requirements.

1. For wall-mounted railings, verify locations of concealed reinforcement within gypsum board and plaster assemblies.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF METAL PAN STAIRS

A. Fastening to In-Place Construction: Provide anchorage devices and fasteners where necessary for securing metal stairs to in-place construction.

1. Include threaded fasteners for concrete and masonry inserts, through-bolts, lag bolts, and other connectors.

B. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal stairs. Set units accurately in location, alignment, and elevation, measured from established lines and levels and free of rack.

C. Install metal stairs by welding stair framing to steel structure or to weld plates cast into concrete unless otherwise indicated.

1. Grouted Baseplates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates.

a. Clean bottom surface of plates.
b. Set plates for structural members on wedges, shims, or setting nuts.
c. Tighten anchor bolts after supported members have been positioned and plumbed.
d. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
e. Promptly pack grout solidly between bearing surfaces and plates so no voids remain.

1) Neatly finish exposed surfaces; protect grout and allow to cure.
2) Comply with manufacturer's written installation instructions for shrinkage-resistant grouts.

D. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

E. Fit exposed connections accurately together to form hairline joints.

1. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations.
2. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.
3. Comply with requirements for welding in "Fabrication, General" Article.

F. Place and finish concrete fill for treads and platforms to comply with Section 033000 "Cast-in-Place Concrete."

1. Install abrasive nosings with anchors fully embedded in concrete.
2. Center nosings on tread width.

3.3 INSTALLATION OF RAILINGS AND GUARDS

A. Adjust railing and guard systems before anchoring to ensure matching alignment at abutting joints with tight, hairline joints.

1. Space posts at spacing indicated or, if not indicated, as required by design loads.
2. Plumb posts in each direction, within a tolerance of 1/16 inch in 3 feet (2 mm in 1 m).

3. Align rails and guards so variations from level for horizontal members and variations from parallel with rake of stairs for sloping members do not exceed 1/4 inch in 12 feet (6 mm in 3.5 m).
4. Secure posts, rail ends, and guard ends to building construction as follows:

    a. Anchor posts to steel by welding to steel supporting members.
    b. Anchor handrail and guard ends to concrete and masonry with steel round flanges welded to rail and guard ends and anchored with post-installed anchors and bolts.

B. Install railing gates level, plumb, and secure for full opening without interference.

1. Attach hardware using tamper-resistant or concealed means.
2. Adjust hardware for smooth operation.

C. Attach handrails to wall with wall brackets.

1. Locate brackets as indicated or, if not indicated, at spacing required to support structural loads.
2. Secure wall brackets to building construction as required to comply with performance requirements.

END OF SECTION 055113

SECTION 061053 - MISCELLANEOUS ROUGH CARPENTRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Wood blocking and nailers.
2. Wood furring.
3. Plywood backing panels.

1.3 DEFINITIONS

A. Boards or Strips: Lumber of less than 2 inches nominal (38 mm actual) size in least dimension.

B. Dimension Lumber: Lumber of 2 inches nominal (38 mm actual) or greater size but less than 5 inches nominal (114 mm actual) size in least dimension.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials based on testing by a qualified independent testing agency.
3. For fire-retardant treatments, include physical properties of treated lumber both before and after exposure to elevated temperatures, based on testing by a qualified independent testing agency according to ASTM D5664.
4. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.

1.5 INFORMATIONAL SUBMITTALS

A. Evaluation Reports: For the following, from ICC-ES:

1. Preservative-treated wood.
2. Fire-retardant-treated wood.
3. Power-driven fasteners.
4. Post-installed anchors.
5. Metal framing anchors.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant-treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.

B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal (38-mm actual) thickness or less, 19 percent for more than 2-inch nominal (38-mm actual) thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with ground, Use Category UC3b for exterior construction not in contact with ground, and Use Category UC4a for items in contact with ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat items indicated on Drawings, and the following:

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
2. Wood sills, sleepers, blocking, furring, and similar concealed members in contact with masonry or concrete.

2.3 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, materials shall comply with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested according to ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet (3.2 m) beyond the centerline of the burners at any time during the test.

1. Treatment shall not promote corrosion of metal fasteners.
2. Exterior Type: Treated materials shall comply with requirements specified above for fire-retardant-treated lumber and plywood by pressure process after being subjected to accelerated weathering according to ASTM D2898. Use for exterior locations and where indicated.
3. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D3201 at 92 percent relative humidity. Use where exterior type is not indicated.

C. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Kiln-dry plywood after treatment to a maximum moisture content of 15 percent.

D. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency.

E. Application: Treat items indicated on Drawings, and the following:

1. Concealed blocking.
2. Plywood backing panels.

2.4 MISCELLANEOUS LUMBER

A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.
3. Furring.
4. Grounds.

B. Dimension Lumber Items: Construction or No. 2 grade lumber of any species.

C. Concealed Boards: 15 percent maximum moisture content of any of the following species and grades:

1. Mixed southern pine or southern pine, No. 2 grade; SPIB.
2. Hem-fir or hem-fir (north), Construction or No. 2 Common grade; NLGA, WCLIB, or WWPA.
3. Spruce-pine-fir (south) or spruce-pine-fir, Construction or No. 2 Common grade; NeLMA, NLGA, WCLIB, or WWPA.

D. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.

E. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.

F. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.5 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: Plywood, DOC PS 1, Exterior, A-C, fire-retardant treated, in thickness indicated or, if not indicated, not less than 3/4-inch (19-mm) nominal thickness.

2.6 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. Where carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M or of Type 304 stainless steel.

B. Nails, Brads, and Staples: ASTM F1667.

C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry accurately to other construction. Locate furring, nailers, blocking, and similar supports to comply with requirements for attaching other construction.

B. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels. Install fire-retardant-treated plywood backing panels with classification marking of testing agency exposed to view.

C. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.

1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches (406 mm) o.c.

D. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

E. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

1. Use inorganic boron for items that are continuously protected from liquid water.
2. Use copper naphthenate for items not continuously protected from liquid water.

F. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.

G. Securely attach carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
2. ICC-ES evaluation report for fastener.

H. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF WOOD BLOCKING AND NAILERS

A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

3.3 INSTALLATION OF WOOD FURRING

A. Install level and plumb with closure strips at edges and openings. Shim with wood as required for tolerance of finish work.

B. Furring to Receive Plywood or Hardboard Paneling: Install 1-by-3-inch nominal- (19-by-63-mm actual-) size furring horizontally at 24 inches (610 mm) o.c.

3.4 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

B. Protect miscellaneous rough carpentry from weather. If, despite protection, miscellaneous rough carpentry becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 061053

SECTION 064116 - PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Plastic-laminate-clad architectural cabinets.
2. Cabinet hardware and accessories.

B. Related Requirements:

1. Section 061053 "Miscellaneous Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing cabinets that are concealed within other construction before cabinet installation.
2. Section 123623.13 "Plastic-Laminate-Clad Countertops."

1.3 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to support loads imposed by installed and fully loaded cabinets.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include data for fire-retardant treatment from chemical-treatment manufacturer and certification by treating plant that treated materials comply with requirements.

B. Shop Drawings:

1. Include plans, elevations, sections, and attachment details.
2. Show large-scale details.

3. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
4. Show locations and sizes of cutouts and holes for items installed in plastic-laminate architectural cabinets.

C. Samples for Initial Selection: For each type of exposed finish.

D. Samples for Verification: For the following:

1. Plastic Laminates: 12 by 12 inches (300 by 300 mm), for each type, color, pattern, and surface finish required.

a. Provide one sample applied to core material with specified edge material applied to one edge.

2. Thermoset Decorative Panels: 12 by 12 inches (300 by 300 mm), for each color, pattern, and surface finish.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer and Installer.

B. Product Certificates: For the following:

1. Composite wood products.
2. Thermoset decorative panels.
3. High-pressure decorative laminate.
4. Adhesives.

1.7 QUALITY ASSURANCE

A. Manufacturer's Qualifications: Employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

B. Installer Qualifications: Manufacturer of products.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver cabinets until painting and similar finish operations that might damage architectural cabinets have been completed in installation areas. Store cabinets in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.9 FIELD CONDITIONS

A. Environmental Limitations with Humidity Control: Do not deliver or install cabinets until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining

temperature between 60 and 90 deg F (16 and 32 deg C) and relative humidity between 43 and 70 percent during the remainder of the construction period.

B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed/concealed by construction, and indicate measurements on Shop Drawings.

PART 2 - PRODUCTS

2.1 ARCHITECTURAL CABINET MANUFACTURERS

2.2 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS

A. Architectural Woodwork Standards Grade: Custom.

B. Type of Construction: Frameless.

C. Door and Drawer-Front Style: Flush overlay.

D. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or if not indicated, as required by quality standard.

1. Manufacturers: Subject to compliance with requirements, provide high-pressure decorative laminates by one of the following:

a. Formica Corporation.
b. Nevamar Company, LLC; Decorative Products Division.
c. Wilsonart International; Division of Premark international, Inc.

E. Laminate Cladding for Exposed Surfaces:

1. Horizontal Surfaces: Grade HGS.
2. Postformed Surfaces: Grade HGP.
3. Vertical Surfaces: Grade HGS.
4. Edges: PVC edge banding, 1/8-inch (3.0 mm) thick, matching laminate in color, pattern, and finish.

F. Materials for Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: Thermoset decorative panels.

a. Edges of Thermoset Decorative Panel Shelves: PVC or polyester edge banding.

2. Drawer Sides and Backs: Thermoset decorative panels with PVC or polyester edge banding.
3. Drawer Bottoms: Thermoset decorative panels.

G. Dust Panels: 1/4-inch (6.4-mm) plywood or tempered hardboard above compartments and drawers unless located directly under tops.

H. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate, NEMA LD 3, Grade BKL.

I. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.

1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners or glued dovetail joints.

J. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As selected by Architect from laminate manufacturer's full range.

2.3 WOOD MATERIALS

A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Wood Moisture Content: 8 to 13 percent.

B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Medium-Density Fiberboard (MDF): ANSI A208.2, Grade 130.
2. Softwood Plywood: DOC PS 1, medium-density overlay.
3. Thermoset Decorative Panels: Particleboard or MDF finished with thermally fused, melamine-impregnated decorative paper and complying with requirements of NEMA LD 3, Grade VGL, for Test Methods 3.3, 3.4, 3.6, 3.8, and 3.10.

2.4 CABINET HARDWARE AND ACCESSORIES

A. Butt Hinges: 2-3/4-inch (70-mm), five-knuckle steel hinges made from 0.095-inch- (2.4-mm-) thick metal, and as follows:

1. Semiconcealed Hinges for Flush Doors: ANSI/BHMA A156.9, B01361.
2. Semiconcealed Hinges for Overlay Doors: ANSI/BHMA A156.9, B01521.

B. Wire Pulls: Back mounted, solid metal, 4 inches (100 mm) long, 5/16 inch (8 mm) in diameter.

C. Catches: Push-in magnetic catches, ANSI/BHMA A156.9, B03131.

D. Adjustable Shelf Standards and Supports: ANSI/BHMA A156.9, B04102; with shelf brackets, B04112.

E. Shelf Rests: ANSI/BHMA A156.9, B04013; metal.

F. Drawer Slides: ANSI/BHMA A156.9.

1. Grade 1 and Grade 2: Side mounted.

a. Type: Full extension.
b. Material: Zinc-plated steel with polymer rollers.

2. Grade 1HD-100 and Grade 1HD-200: Side mounted; full-extension type; zinc-plated-steel ball-bearing slides.
3. For drawers not more than 3 inches (75 mm) high and not more than 24 inches (600 mm) wide, provide Grade 1.
4. For drawers more than 3 inches (75 mm) high, but not more than 6 inches (150 mm) high and not more than 24 inches (600 mm) wide, provide Grade 1HD-100.
5. For drawers more than 6 inches (150 mm) high or more than 24 inches (600 mm) wide, provide Grade 1HD-200.
6. For computer keyboard shelves, provide Grade 1HD-100.
7. For trash bins not more than 20 inches (500 mm) high and 16 inches (400 mm) wide, provide Grade 1HD-100.

G. Door Locks: ANSI/BHMA A156.11, E07121.

H. Drawer Locks: ANSI/BHMA A156.11, E07041.

I. Grommets for Cable Passage: 2-inch (51-mm) OD, molded-plastic grommets and matching plastic caps with slot for wire passage.

1. Color: Black.

J. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with ANSI/BHMA A156.18 for ANSI/BHMA finish number indicated.

1. Satin Chromium Plated: ANSI/BHMA 626 for brass or bronze base; ANSI/BHMA 652 for steel base.

K. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in ANSI/BHMA A156.9.

2.5 MISCELLANEOUS MATERIALS

A. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.

B. Adhesive for Bonding Plastic Laminate: Unpigmented contact cement.

1. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.6 FABRICATION

A. Fabricate architectural cabinets to dimensions, profiles, and details indicated.

B. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

1. Notify Architect seven days in advance of the dates and times architectural cabinet fabrication will be complete.
2. Trial fit assemblies at manufacturer's shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements before disassembling for shipment.

C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition cabinets to humidity conditions in installation areas for not less than 72 hours.

3.2 INSTALLATION

A. Architectural Woodwork Standards Grade: Install cabinets to comply with quality standard grade of item to be installed.

B. Assemble cabinets and complete fabrication at Project site to extent that it was not completed in the shop.

C. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with wafer-head cabinet installation screws.

D. Install cabinets level, plumb, and true in line to a tolerance of 1/8 inch in 96 inches (3 mm in 2400 mm) using concealed shims.

1. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

2. Install cabinets without distortion so doors and drawers fit openings and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
3. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches (400 mm) o.c. with No. 10 wafer-head sheet metal screws through metal backing or metal framing behind wall finish or toggle bolts through metal backing or metal framing behind wall finish.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective cabinets, where possible, to eliminate functional and visual defects. Where not possible to repair, replace architectural cabinets. Adjust joinery for uniform appearance.

B. Clean, lubricate, and adjust hardware.

C. Clean cabinets on exposed and semiexposed surfaces.

END OF SECTION 064116

SECTION 072100 - THERMAL INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Extruded polystyrene foam-plastic board insulation.
2. Polyisocyanurate foam-plastic board insulation.
3. Glass-fiber blanket insulation.
4. Glass-fiber board insulation.
5. Mineral-wool blanket insulation.
6. Mineral-wool board insulation.

B. Related Requirements:

1. Section 071416 "Cold Fluid-Applied Waterproofing" for insulated drainage panels installed with foundation walls retaining backfill.
2. Section 072119 "Foamed-in-Place Insulation" for spray-applied polyurethane foam insulation.
3. Section 075216 "Styrene-Butadiene-Styrene (SBS) Modified Bituminous Membrane Roofing for insulation specified as part of roofing construction.
4. Section 092900 "Gypsum Board" for sound attenuation blanket used as acoustic insulation.
5. Section 098100 "Acoustical Insulation" for glass-fiber board and glass-fiber blanket used as acoustic insulation.

1.3 ACTION SUBMITTALS

A. Product Data: For the following:

1. Extruded polystyrene foam-plastic board insulation.
2. Polyisocyanurate foam-plastic board insulation.
3. Glass-fiber blanket insulation.
4. Glass-fiber board insulation.
5. Mineral-wool blanket insulation.
6. Mineral-wool board insulation.

1.4 INFORMATIONAL SUBMITTALS

A. Installer's Certification: Listing type, manufacturer, and R-value of insulation installed in each element of the building thermal envelope.

1. Sign, date, and post the certification in a conspicuous location on Project site.

B. Product Test Reports: For each product, for tests performed by a qualified testing agency.

C. Research Reports: For foam-plastic insulation, from ICC-ES.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.

B. Protect foam-plastic board insulation as follows:

1. Do not expose to sunlight except to necessary extent for period of installation and concealment.
2. Protect against ignition at all times. Do not deliver foam-plastic board materials to Project site until just before installation time.
3. Quickly complete installation and concealment of foam-plastic board insulation in each area of construction.

PART 2 - PRODUCTS

2.1 EXTRUDED POLYSTYRENE FOAM-PLASTIC BOARD INSULATION

A. Extruded Polystyrene Board Insulation, Type IV: ASTM C578, Type IV, 25-psi (173-kPa) minimum compressive strength; unfaced.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. DiversiFoam Products.
b. Dow Chemical Company (The).
c. MBCI.
d. Owens Corning.

2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
3. Smoke-Developed Index: Not more than 450 when tested in accordance with ASTM E84.
4. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

B. Extruded Polystyrene Board Insulation, Type VI: ASTM C578, Type VI, 40-psi (276-kPa) minimum compressive strength.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. DiversiFoam Products.
b. Dow Chemical Company (The).
c. Kingspan Insulation Limited.
d. Owens Corning.

2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
3. Smoke-Developed Index: Not more than 450 when tested in accordance with ASTM E84.
4. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.2 POLYISOCYANURATE FOAM-PLASTIC BOARD INSULATION

A. Polyisocyanurate Board Insulation, Glass-Fiber-Mat Faced: ASTM C1289, glass-fiber-mat faced, Type II, Class 2.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Atlas EPS; a Division of Atlas Roofing Corporation.
b. Atlas Roofing Corporation.
c. Carlisle Coatings & Waterproofing Inc.
d. Dow Chemical Company (The).
e. Firestone Building Products.
f. Hunter Panels.
g. Johns Manville; a Berkshire Hathaway company.
h. Rmax, Inc.

2. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.3 GLASS-FIBER BLANKET INSULATION

A. Insulation shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

B. Glass-Fiber Blanket Insulation, Unfaced: ASTM C665, Type I; passing ASTM E136 for combustion characteristics.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. CertainTeed Corporation.

b. Johns Manville; a Berkshire Hathaway Company.
c. Knauf Insulation.
d. Owens Corning.

2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
3. Smoke-Developed Index: Not more than 50 when tested in accordance with ASTM E84.
4. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.4 GLASS-FIBER BOARD INSULATION

A. Insulation shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

B. Glass-Fiber Board Insulation, Unfaced: ASTM C612, Type IA; unfaced, passing ASTM E136 for combustion characteristics.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. CertainTeed Corporation.
b. Johns Manville; a Berkshire Hathaway Company.
c. Knauf Insulation.
d. Owens Corning.

2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
3. Smoke-Developed Index: Not more than 50 when tested in accordance with ASTM E84.
4. Nominal Density: 3 lb/cu. ft. (48 kg/cu. m) or 4.25 lb/cu. ft. (68 kg/cu. m).
5. Thermal Resistivity: 4.3 deg F x h x sq. ft./Btu x in. at 75 deg F (29.8 K x m/W at 24 deg C).
6. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.5 MINERAL-WOOL BLANKET INSULATION

A. Insulation shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

B. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 40 percent.

C. Mineral-Wool Blanket Insulation, Unfaced: ASTM C665, Type I (blankets without membrane facing); consisting of fibers; passing ASTM E136 for combustion characteristics.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Johns Manville; a Berkshire Hathaway company.
b. Rockwool International.
c. Thermafiber, Inc.; an Owens Corning company.

2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
3. Smoke-Developed Index: Not more than 50 when tested in accordance with ASTM E84.
4. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.6 MINERAL-WOOL BOARD INSULATION

A. Mineral-Wool Board Insulation, Types IA and IB, Unfaced: ASTM C612, Types IA and IB; passing ASTM E136 for combustion characteristics.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Johns Manville; a Berkshire Hathaway company.
b. Rockwool International.
c. Thermafiber, Inc.; an Owens Corning company.

2. Nominal Density: 4 lb/cu. ft. (64 kg/cu. m).
3. Flame-Spread Index: Not more than 15 when tested in accordance with ASTM E84.
4. Smoke-Developed Index: Not more than zero when tested in accordance with ASTM E84.
5. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches (305 mm) and wider in width.

2.7 ACCESSORIES

A. Insulation for Miscellaneous Voids:

1. Glass-Fiber Insulation: ASTM C764, Type II, loose fill; with maximum flame-spread and smoke-developed indexes of 5, per ASTM E84.
2. Spray Polyurethane Foam Insulation: ASTM C1029, Type II, closed cell, with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, per ASTM E84.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean substrates of substances that are harmful to insulation, including removing projections capable of puncturing insulation or vapor retarders, or that interfere with insulation attachment.

3.2 INSTALLATION, GENERAL

A. Comply with insulation manufacturer's written instructions applicable to products and applications.

B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.

C. Install insulation with manufacturer's R-value label exposed after insulation is installed.

D. Extend insulation to envelop entire area to be insulated. Fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

E. Provide sizes to fit applications and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units unless multiple layers are otherwise shown or required to make up total thickness or to achieve R-value.

3.3 INSTALLATION OF SLAB INSULATION

A. On vertical slab edge and foundation surfaces, set insulation units using manufacturer's recommended adhesive according to manufacturer's written instructions.

1. If not otherwise indicated, extend insulation a minimum of 24 inches (610 mm) below exterior grade line.

B. On horizontal surfaces, loosely lay insulation units according to manufacturer's written instructions. Stagger end joints and tightly abut insulation units.

1. If not otherwise indicated, extend insulation a minimum of 24 inches (610 mm) in from exterior walls.

3.4 INSTALLATION OF INSULATION IN FRAMED CONSTRUCTION

A. Blanket Insulation: Install in cavities formed by framing members according to the following requirements:

1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill the cavities, provide lengths that will produce a snug fit between ends.
2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.

3. Maintain 3-inch (76-mm) clearance of insulation around recessed lighting fixtures not rated for or protected from contact with insulation.
4. For metal-framed wall cavities where cavity heights exceed 96 inches (2438 mm), support unfaced blankets mechanically and support faced blankets by taping flanges of insulation to flanges of metal studs.

B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:

1. Glass-Fiber Insulation: Compact to approximately 40 percent of normal maximum volume equaling a density of approximately 2.5 lb/cu. ft. (40 kg/cu. m).
2. Spray Polyurethane Insulation: Apply according to manufacturer's written instructions.

3.5 PROTECTION

A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes.

B. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

END OF SECTION 072100

SECTION 075419 - POLYVINYL-CHLORIDE (PVC) ROOFING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Adhered polyvinyl-chloride (PVC) roofing system.
2. Roof insulation.
3. Walkways.

B. Related Requirements:

1. Section 061053 "Miscellaneous Rough Carpentry" for wood nailers, curbs, and blocking; and for wood-based, structural-use roof deck panels.
2. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.
3. Section 221423 "Storm Drainage Piping Specialties" for roof drains.

1.3 DEFINITIONS

A. Roofing Terminology: Definitions in ASTM D 1079 and glossary in NRCA's "The NRCA Roofing and Waterproofing Manual" apply to work of this Section.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Roofing Conference: Conduct conference at Project site.

1. Meet with Owner, Architect, Owner's insurer if applicable, testing and inspecting agency representative, roofing Installer, roofing system manufacturer's representative, deck Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
3. Review and finalize construction schedule, and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
4. Examine deck substrate conditions and finishes for compliance with requirements, including flatness and fastening.
5. Review structural loading limitations of roof deck during and after roofing.
6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that affects roofing system.

7. Review governing regulations and requirements for insurance and certificates if applicable.
8. Review temporary protection requirements for roofing system during and after installation.
9. Review roof observation and repair procedures after roofing installation.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other work, including:

1. Base flashings and membrane terminations.
2. Tapered insulation, including slopes.
3. Roof plan showing orientation of steel roof deck and orientation of roofing, fastening spacings, and patterns for mechanically fastened roofing.
4. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.

C. Samples for Verification: For the following products:

1. Sheet roofing, of color required.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and manufacturer.

B. Manufacturer Certificates: Signed by roofing manufacturer certifying that roofing system complies with requirements specified in "Performance Requirements" Article.

1. Submit evidence of compliance with performance requirements.

C. Product Test Reports: For components of roofing system, for tests performed by manufacturer and witnessed by a qualified testing agency.

D. Research/Evaluation Reports: For components of roofing system, from ICC-ES.

E. Sample Warranties: For manufacturer's special warranties.

1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For roofing system to include in maintenance manuals.

1.8 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer that is UL listed for roofing system identical to that used for this Project.

B. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.

B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.

1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.

C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.

D. Handle and store roofing materials, and place equipment in a manner to avoid permanent deflection of deck.

1.10 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

1.11 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within specified warranty period.

1. Special warranty includes membrane roofing, base flashings, roof insulation, fasteners, cover boards, substrate board, and other components of roofing system.
2. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain components including roof insulation for roofing system from same manufacturer as membrane roofing or manufacturer approved by membrane roofing manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General Performance: Installed roofing and base flashings shall withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Roofing and base flashings shall remain watertight.

1. Accelerated Weathering: Roofing system shall withstand 2000 hours of exposure when tested according to ASTM G 152, ASTM G 154, or ASTM G 155.
2. Impact Resistance: Roofing system shall resist impact damage when tested according to ASTM D 3746 or ASTM D 4272.

B. Material Compatibility: Roofing materials shall be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roofing manufacturer based on testing and field experience.

C. Roofing System Design: Tested by a qualified testing agency to resist the following uplift pressures:

1. Corner Uplift Pressure: As indicated.
2. Perimeter Uplift Pressure: As indicated.
3. Field-of-Roof Uplift Pressure: As indicated.
4. Hail-Resistance Rating: MH.

D. Exterior Fire-Test Exposure: ASTM E 108 or UL 790, Class A; for application and roof slopes indicated; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

2.3 PVC ROOFING

A. PVC Sheet: ASTM D4434/D4434M, Type III, fabric reinforced and fabric backed.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Duro-Last Roofing; Duro-Fleece 60-mil Membrane or comparable product by one of the following:

a. Carlisle SynTec Incorporated.
b. Cooley Engineered Membranes.
c. Elevate (formerly Firestone Building Products).
d. Mule-Hide Products Co., Inc.

2. Thickness: 60 mils (1.5 mm), nominal.
3. Exposed Face Color: White.

2.4 AUXILIARY ROOFING MATERIALS

A. General: Auxiliary materials recommended by roofing system manufacturer for intended use and compatible with roofing.

1. Liquid-type auxiliary materials shall comply with VOC limits of authorities having jurisdiction.

B. Sheet Flashing: Manufacturer's standard sheet flashing of same material, type, reinforcement, thickness, and color as PVC sheet.

C. Prefabricated Pipe Flashings: As recommended by roof membrane manufacturer.

D. Bonding Adhesive: Manufacturer's standard, water based.

E. Water-Based, Fabric-Backed Membrane Adhesive: Roofing system manufacturer's standard water-based, cold-applied adhesive formulated for compatibility and use with fabric-backed membrane roofing.

F. Low-Rise, Urethane, Fabric-Backed Membrane Adhesive: Roof system manufacturer's standard spray-applied, low-rise, two-component urethane adhesive formulated for compatibility and use with fabric-backed membrane roofing.

G. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch (25 by 3 mm) thick; with anchors.

H. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, lap sealants, termination reglets, and other accessories.

2.5 SUBSTRATE BOARDS

A. Substrate Board: ASTM C 1177/C 1177M, glass-mat, water-resistant gypsum substrate, 1/4 inch (6 mm) thick.

1. Products: Subject to compliance with requirements, provide one of the following:

a. CertainTeed Corporation; GlasRoc Sheathing.
b. Georgia-Pacific Corporation; Dens Deck.
c. National Gypsum Company; Gold Bond eXP Extended Exposure Sheathing.
d. Temple-Inland, Inc; GreenGlass Exterior Sheathing.
e. USG Corporation; Securock Glass Mat Roof Board.

B. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Global 4470, designed for fastening substrate board to roof deck.

2.6 ROOF INSULATION

A. General: Preformed roof insulation boards manufactured or approved by PVC roofing manufacturer, selected from manufacturer's standard sizes suitable for application, of thicknesses indicated.

B. Polyisocyanurate Board Insulation: ASTM C 1289, Type II, Class 1, Grade 3, felt or glass-fiber mat facer on both major surfaces.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Atlas Roofing Corporation.
b. Carlisle SynTec Incorporated.
c. Dyplast Products.
d. Firestone Building Products.
e. GAF Materials Corporation.
f. Hunter Panels.
g. Insulfoam LLC; a Carlisle company.
h. Johns Manville.
i. Rmax, Inc.

C. Tapered Insulation: Provide factory-tapered insulation boards fabricated to slope of 1/4 inch per 12 inches (1:48) unless otherwise indicated.

D. Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated.

2.7 INSULATION ACCESSORIES

A. General: Roof insulation accessories recommended by insulation manufacturer for intended use and compatibility with roofing.

B. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Global 4470, designed for fastening roof insulation and cover boards to substrate, and acceptable to roofing system manufacturer.

C. Insulation Adhesive: Insulation manufacturer's recommended adhesive formulated to attach roof insulation to substrate or to another insulation layer as follows:

1. Modified asphaltic, asbestos-free, cold-applied adhesive.
2. Bead-applied, low-rise, one-component or multicomponent urethane adhesive.
3. Full-spread spray-applied, low-rise, two-component urethane adhesive.

D. Cover Board: ASTM C 1177/C 1177M, glass-mat, water-resistant gypsum substrate, 1/4 inch (6 mm) thick.

1. Products: Subject to compliance with requirements, provide one of the following:

a. CertainTeed Corporation; GlasRoc Sheathing.

b. Georgia-Pacific Corporation; Dens Deck or Dens Deck Primed.
c. National Gypsum Company; Gold Bond eXP Extended Exposure Sheathing.
d. Temple-Inland, Inc; GreenGlass Exterior Sheathing.
e. USG Corporation; Securock Glass Mat Roof Board.

2.8 ASPHALT MATERIALS

A. Roofing Asphalt: ASTM D 312, Type III or Type IV.

2.9 WALKWAYS

A. Flexible Walkways: Factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads, approximately 3/16 inch (5 mm) thick and acceptable to roofing system manufacturer.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Duro-Last Roofing; Duro-Last Roof Trak III Walkway Pad, or comparable product by one of the following:

a. Carlisle SynTec Incorporated.
b. Cooley Engineered Membranes.
c. Elevate (formerly Firestone Building Products).
d. Mule-Hide Products Co., Inc.

2. Size: Approximately 36 by 60 inches (914 by 1524 mm).
3. Color: Contrasting with roof membrane.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work:

1. Verify that roof openings and penetrations are in place, curbs are set and braced, and roof-drain bodies are securely clamped in place.
2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
3. Verify that surface plane flatness and fastening of steel roof deck complies with requirements in Section 053100 "Steel Decking."

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.

B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

3.3 ROOFING INSTALLATION, GENERAL

A. Install roofing system according to roofing system manufacturer's written instructions.

B. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at end of workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

3.4 SUBSTRATE BOARD INSTALLATION

A. Install substrate board with long joints in continuous straight lines, perpendicular to roof slopes with end joints staggered between rows. Tightly butt substrate boards together.

1. Fasten substrate board to top flanges of steel deck to resist uplift pressure at corners, perimeter, and field of roof according to roofing system manufacturers' written instructions.

3.5 INSULATION INSTALLATION

A. Coordinate installing roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.

B. Comply with roofing system and insulation manufacturer's written instructions for installing roof insulation.

C. Install tapered insulation under area of roofing to conform to slopes indicated.

D. Install insulation under area of roofing to achieve required thickness. Where overall insulation thickness is 2.7 inches (68 mm) or greater, install two or more layers with joints of each succeeding layer staggered from joints of previous layer a minimum of 6 inches (150 mm) in each direction.

E. Trim surface of insulation where necessary at roof drains so completed surface is flush and does not restrict flow of water.

F. Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows, abutting edges and ends between boards. Fill gaps exceeding 1/4 inch (6 mm) with insulation.

1. Cut and fit insulation within 1/4 inch (6 mm) of nailers, projections, and penetrations.

G. Mechanically Fastened Insulation: Install each layer of insulation and secure to deck using mechanical fasteners specifically designed and sized for fastening specified board-type roof insulation to deck type.

1. Fasten insulation to resist uplift pressure at corners, perimeter, and field of roof.

H. Install cover boards over insulation with long joints in continuous straight lines with end joints staggered between rows. Offset joints of insulation below a minimum of 6 inches (150 mm) in each direction. Loosely butt cover boards together and fasten to roof deck.

1. Fasten cover boards to resist uplift pressure at corners, perimeter, and field of roof.

3.6 ADHERED ROOFING INSTALLATION

A. Adhere roofing over area to receive roofing according to roofing system manufacturer's written instructions. Unroll roofing and allow to relax before retaining.

1. Install sheet according to ASTM D 5036.

B. Accurately align roofing, and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.

C. Bonding Adhesive: Apply to substrate and underside of roofing at rate required by manufacturer, and allow to partially dry before installing roofing. Do not apply to splice area of roofing.

D. In addition to adhering, mechanically fasten roofing securely at terminations, penetrations, and perimeter of roofing.

E. Apply roofing with side laps shingled with slope of roof deck where possible.

F. Seams: Clean seam areas, overlap roofing, and hot-air weld side and end laps of roofing and sheet flashings according to manufacturer's written instructions, to ensure a watertight seam installation.

1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of sheet.
2. Verify field strength of seams a minimum of twice daily, and repair seam sample areas.
3. Repair tears, voids, and lapped seams in roofing that do not comply with requirements.

G. Spread sealant bed over deck-drain flange at roof drains, and securely seal roofing in place with clamping ring.

3.7 BASE FLASHING INSTALLATION

A. Install sheet flashings and preformed flashing accessories, and adhere to substrates according to roofing system manufacturer's written instructions.

B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate, and allow to partially dry. Do not apply to seam area of flashing.

C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.

D. Clean seam areas, overlap, and firmly roll sheet flashings into the adhesive. Hot-air weld side and end laps to ensure a watertight seam installation.

E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

3.8 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components, and to furnish reports to Architect.

B. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.

C. Repair or remove and replace components of roofing system where inspections indicate that they do not comply with specified requirements.

D. Additional testing and inspecting, at Contractor's expense, will be performed to determine if replaced or additional work complies with specified requirements.

3.9 PROTECTING AND CLEANING

A. Protect roofing system from damage and wear during remainder of construction period. When remaining construction does not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.

B. Correct deficiencies in or remove roofing system that does not comply with requirements, repair substrates, and repair or reinstall roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.

END OF SECTION 075419

SECTION 077253 - SNOW GUARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Rail-type, seam-mounted snow guards.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product, include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

B. Shop Drawings: Include roof plans showing layouts and attachment details of snow guards.

1. Include details of rail-type snow guards.

C. Samples:

1. Rail-Type Snow Guards: Bracket, 12-inch- (300-mm-) long rail, and installation hardware.

D. Delegated-Design Submittal: For snow guards, include analysis reports signed and sealed by the qualified professional engineer responsible for their preparation.

1. Include calculation of number and location of snow guards.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For professional engineer's experience with providing delegated design engineering services of the kind indicated, including documentation that the engineer is licensed in the state in which the Project is located.

B. Product Test Reports: For each type of snow guard, for tests performed by a qualified testing agency, indicating load at failure of attachment to roof system identical to roof system used on this Project.

1.5 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit adhesive-mounted snow guards to be installed, and adhesive cured, according to adhesive manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design snow guards, including attachment to roofing material and roof deck, as applicable for attachment method, based on the following:

1. Roof snow load.
2. Snow drifting
3. Roof slope.
4. Roof type.
5. Roof dimensions.
6. Roofing substrate type and thickness.
7. Snow guard type.
8. Snow guard fastening method and strength.
9. Snow guard spacing.
10. Coefficient of Friction Between Snow and Roof Surface: 0.
11. Factor of Safety**:** 2.

B. Performance Requirements: Provide snow guards that withstand exposure to weather and resist thermally induced movement without failure, rattling, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.

1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

C. Structural Performance: Snow guards shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated.

1. Snow Loads: As indicated on Drawings.

2.2 RAIL-TYPE SNOW GUARDS

A. Rail-Type, Seam-Mounted Snow Guards:

1. Products: Subject to compliance with requirements, provide one of the following:

a. Alpine SnowGuards, a division of Vermont Slate & Copper Services, Inc.; SnowMax.
b. LMCurbs; ColorGard.
c. S-5! Metal Roof Innovations, Ltd.; ColorGard.
d. Snow Gem; 2” iClad-S.

2. Description: Snow guard rails fabricated from metal pipes, bars, or extrusions, anchored to brackets and equipped with one rail with integral track to accept color-matching inserts of material and finish used for metal roof.
3. Brackets and Baseplate: ASTM B221 (ASTM B221M) aluminum; mill finish.
4. Bars: ASTM B221 (ASTM B221M) aluminum.

    a. Profile: Fence-style with integral track to accept color-matching inserts of material and finish used for metal roof.

5. Seam clamps: ASTM B221 (ASTM B221M) aluminum extrusion or ASTM B85/B85M aluminum casting with stainless steel set screws incorporating round nonpenetrating point; designed for use with applicable roofing system to which clamp is attached.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, snow guard attachment, and other conditions affecting performance of the Work.

1. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install snow guards according to manufacturer's written instructions.

1. Space rows as indicated on Shop Drawings.

B. Attachment for Standing-Seam Metal Roofing:

1. Do not use fasteners that will penetrate metal roofing or fastening methods that void metal roofing finish warranty.
2. Rail-Type, Seam-Mounted Snow Guards:

    a. Install brackets to vertical ribs in straight rows.
    b. Secure with stainless steel set screws, incorporating round nonpenetrating point, on same side of standing seam.
    c. Torque set screw according to manufacturer's instructions.
    d. Install cross members to brackets.

END OF SECTION 077253

SECTION 079100 - PREFORMED JOINT SEALS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Preformed, foam joint seals.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for liquid sealants applied over preformed seals in dual seal systems.

1.3 ACTION SUBMITTALS

A. Product Data: For each preformed joint seal product.

B. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available for each product exposed to view.

C. Samples for Verification: For each type and color of preformed joint seal required, provide Samples with joint seals in 1/2-inch- (13-mm-) wide joints formed between two 6-inch- (150-mm-) long strips of material matching the appearance of exposed surfaces adjacent to joint seals.

D. Preformed Joint Seal Schedule: Include the following information:

1. Joint seal location and designation.
2. Joint width and movement capability.
3. Joint seal manufacturer and product name.
4. Joint seal color.

1.4 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each preformed joint seal for tests performed by a qualified testing agency.

B. Warranties: For special warranties.

1.5 QUALITY ASSURANCE

A. Mockups: Install mockups of assemblies specified in other Sections that are indicated to receive preformed joint seals specified in this Section. Use materials and installation methods specified in this Section.

1.6 WARRANTY

A. Special Warranty: Installer agrees to repair or replace preformed joint seals that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish preformed joint seals to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PREFORMED, FOAM JOINT SEALS

A. Preformed, Foam Joint Seals PJS: Manufacturer's standard joint seal manufactured from urethane or EVA (ethylene vinyl acetate) foam with minimum density of 10 lb/cu. ft. (160 kg/cu. m) and impregnated with a nondrying, water-repellent agent. Factory produce in precompressed sizes in roll or stick form to fit joint widths based on design criteria indicated, with factory- or field-applied adhesive for bonding to substrates.

1. Available Products: Subject to compliance with requirements, provide one of the following:

a. BASF; Wabo Weatherseal II.
b. Emseal Joint Systems, Ltd., a Sika Company; Colorseal.
c. Lym Tal International, Inc.; Iso-Flex Hydoseal-P.
d. Willseal, a Tremco Affiliate Brand; Willseal 150.

2. Design Criteria:

a. Nominal Joint Width: As indicated on Drawings.
b. Movement Capability: -25 percent/+25 percent.

3. Joint Seal Color: As selected by Architect from full range of industry colors.

2.2 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by preformed-joint-seal manufacturer for joint substrates indicated.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to preformed joint seal manufacturer, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces, and formulated to promote best adhesion to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with preformed joint seals and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive preformed joint seals, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting preformed-joint seal performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing preformed joint seals to comply with preformed joint seal manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of preformed joint seal, including dust, paints (except for permanent protective coatings tested and approved for seal adhesion and compatibility by seal manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimal bond with preformed joint seals. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Masonry.

3. Remove laitance and form-release agents from concrete.

B. Joint Priming: Prime joint substrates where recommended by preformed joint seal manufacturer or as indicated by tests or prior experience. Apply primer to comply with joint seal manufacturer's written instructions. Confine primers to areas of joint seal bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of adhesive or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION

A. General: Comply with preformed joint seal manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.

B. Installation of Preformed, Foam Joint Seals:

1. Install each length of seal immediately after removing protective wrapping.
2. Firmly secure compressed joint seals to joint gap side to obtain full bond using exposed pressure-sensitive adhesive or field-applied adhesive as recommended by manufacturer.
3. Do not pull or stretch material. Produce seal continuity at splices, ends, turns, and intersections of joints.
4. For applications at low ambient temperatures, heat foam joint seal material in compliance with manufacturer's written instructions.

3.4 PROTECTION

A. Protect preformed joint seals from damage resulting from construction operations or other causes so seals are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated seals immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 079100

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Nonstaining silicone joint sealants.
3. Mildew-resistant joint sealants.
4. Polysulfide joint sealants.
5. Butyl joint sealants.
6. Latex joint sealants.

B. Related Requirements:

1. Section 079100 "Preformed Joint Seals" for preformed compressible foam and precured joint seals.
2. Section 079219 "Acoustical Joint Sealants" for sealing joints in sound-rated construction.
3. Section 321373 "Concrete Paving Joint Sealants" for sealing joints in paved roads, parking lots, walkways, and curbing.

1.3 ACTION SUBMITTALS

A. Product Data: For each joint-sealant product.

B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.

C. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- (13-mm-) wide joints formed between two 6-inch- (150-mm-) long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

D. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified testing agency.

B. Product Test Reports: For each kind of joint sealant, for tests performed by manufacturer and witnessed by a qualified testing agency.

C. Preconstruction Laboratory Test Schedule: Include the following information for each joint sealant and substrate material to be tested:

1. Joint-sealant location and designation.
2. Manufacturer and product name.
3. Type of substrate material.
4. Proposed test.
5. Number of samples required.

D. Preconstruction Laboratory Test Reports: From sealant manufacturer, indicating the following:

1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
2. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion.

E. Preconstruction Field-Adhesion-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Preconstruction Testing" Article.

F. Field-Adhesion-Test Reports: For each sealant application tested.

G. Sample Warranties: For special warranties.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

B. Product Testing: Test joint sealants using a qualified testing agency.

1. Testing Agency Qualifications: Qualified according to ASTM C1021 to conduct the testing indicated.

1.6 PRECONSTRUCTION TESTING

A. Preconstruction Laboratory Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.

1. Adhesion Testing: Use ASTM C794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.

2. Compatibility Testing: Use ASTM C1087 to determine sealant compatibility when in contact with glazing and gasket materials.
3. Stain Testing: Use ASTM C1248 to determine stain potential of sealant when in contact with masonry substrates.
4. Submit manufacturer's recommended number of pieces of each type of material, including joint substrates, joint-sealant backings, and miscellaneous materials.
5. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
6. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures, including use of specially formulated primers.
7. Testing will not be required if joint-sealant manufacturers submit data that are based on previous testing, not older than 24 months, of sealant products for adhesion to, staining of, and compatibility with joint substrates and other materials matching those submitted.

B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates as follows:

1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
2. Conduct field tests for each kind of sealant and joint substrate.
3. Notify Architect seven days in advance of dates and times when test joints will be erected.
4. Arrange for tests to take place with joint-sealant manufacturer's technical representative present.

    a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1.1 in ASTM C1193 or Method A, Tail Procedure, in ASTM C1521.

        1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

5. Report whether sealant failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
6. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

1.7 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F (5 deg C).
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.8 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

B. VOC Content of Interior Sealants: provide interior sealants and sealant primers that comply with the following limits for VOC content when calculated according to 40 CFR 5, Subpart D (EPA Method 24).

1. Sealants: 250g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.

C. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 SILICONE JOINT SEALANTS

A. Silicone, S, P, 100/50, T, NT: Single-component, pourable, plus 100 percent and minus 50 percent movement capability traffic- and nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade P, Class 100/50, Uses T and NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

    a. Dow Corning Corporation; 890-SL.
    b. Pecora Corporation; 300 Pavement Sealant (Self-Leveling).

2.3 NONSTAINING SILICONE JOINT SEALANTS

A. Nonstaining Joint Sealants: No staining of substrates when tested according to ASTM C1248.

B. Silicone, Nonstaining, S, NS, 100/50, NT: Nonstaining, single-component, nonsag, plus 100 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 100/50, Use NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

    a. GE Silicones; SilPruf SCS9000 NB.
    b. GE Silicone; UltraPruf II SCS2900.
    c. Pecora Corporation; 865
    d. Pecora Corporation; 895
    e. Pecora Corporation; 898

C. Silicone, Nonstaining, S, NS, 50, NT: Nonstaining, single-component, nonsag, plus 50 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 50, Use NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

    a. GE Silicones; SilPruf SCS2000.
    b. Pecora Corporation; 864.
    c. Pecora Corporation; 890
    d. Polymeric Systems, Inc.; PSI-641.
    e. Sonneborn, Division of ChemRex, Inc.; Omniseal.
    f. Tremco; Spectrum 3.

2.4 MILDEW-RESISTANT JOINT SEALANTS

A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.

B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

a. Dow Corning Corporation; 786 Mildew Resistant.
b. GE Silicones; Sanitary SCS1700.
c. Tremco; Tremsil 200 White.

2.5 POLYSULFIDE JOINT SEALANTS

A. Polysulfide, S, NS, 25, NT: Single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, polysulfide joint sealant; ASTM C920, Type S, Grade NS, Class 25, Use NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

a. Pacific Polymers, Inc.; Elasto-Seal 230 Type I (Gun Grade).
b. Polymeric Systems, Inc.; PSI-7000.

B. Polysulfide, M, NS, 25, T, NT: Multicomponent, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, polysulfide joint sealant; ASTM C920, Type M, Grade NS, Class 25, Use NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

a. Pacific Polymers, Inc.; Elasto-Seal 227 Type II (Gun Grade).
b. Pecora Corporation; Synthacalk GC-2+.
c. Polymeric Systems, Inc.; PSI-350.
d. PolySpec Corp.; T-2235-SL.
e. Sonneborn, Division of ChemRex, Inc.; Sonolastic Polysulfide Sealant.

C. Polysulfide, M, P, 25, T, NT: Multicomponent, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, polysulfide joint sealant; ASTM C920, Type M, Grade P, Class 25, Uses T and NT.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

a. Meadows, W. R., Inc.; Deck-O-Seal.
b. Pacific Polymers, Inc.; Elasto-Seal 227 Type II (Gun Grade).

2.6 BUTYL JOINT SEALANTS

A. Butyl-Rubber-Based Joint Sealants: ASTM C1311.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Bostik, Inc; Chem-Calk 300.
b. H.B. Fuller Construction Products, Inc.; ElastiSeal 95-88.
c. Pecora Corporation; BC-158.

2.7 LATEX JOINT SEALANTS

A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C834, Type OP, Grade NF.

1. Available Products: Subject to compliance with requirements, products that may be included in the Work include, but are not limited to, the following:

a. Bostik Findley.; 600
b. Pecora Corporation; AC-20+.
c. Schnee-Morehead, Inc.; SM 8200.
d. Sonneborn, Division of ChemRex, Inc.; Sonolac.
e. Tremco; Tremflex 834.

2.8 JOINT-SEALANT BACKING

A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin), Type O (open-cell material), Type B (bicellular material with a surface skin) or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.9 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Concrete.
    b. Masonry.
    c. Unglazed surfaces of ceramic tile.

3. Remove laitance and form-release agents from concrete.
4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

    a. Metal.
    b. Glass.
    c. Porcelain enamel.
    d. Glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile per Figure 8A in ASTM C1193 unless otherwise indicated.
4. Provide flush joint profile at locations indicated on Drawings according to Figure 8B in ASTM C1193.
5. Provide recessed joint configuration of recess depth and at locations indicated on Drawings according to Figure 8C in ASTM C1193.

    a. Use masking tape to protect surfaces adjacent to recessed tooled joints.

3.4 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed and cured sealant joints as follows:

a. Perform 10 tests for the first 1000 feet (300 m) of joint length for each kind of sealant and joint substrate.
b. Perform one test for each 500 feet (150 m) of joint length thereafter or one test per each floor per elevation.

2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C1193 or Method A, Tail Procedure, in ASTM C1521.

a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

3. Inspect tested joints and report on the following:

a. Whether sealants filled joint cavities and are free of voids.
b. Whether sealant dimensions and configurations comply with specified requirements.
c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.

4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.
5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage

or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.7 JOINT-SEALANT SCHEDULE

A. Joint-Sealant Application: Exterior joints in horizontal traffic surfaces JS-#1.

1. Joint Locations:

   a. Isolation and contraction joints in cast-in-place concrete slabs.
   b. Tile control and expansion joints.
   c. Joints between different materials listed above.
   d. Other joints as indicated on Drawings.

2. Joint Sealant: [**Urethane, M, P, 50, T, NT**] <**Insert joint sealant**>.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

B. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces JS-#2.

1. Joint Locations:

   a. Control and expansion joints in unit masonry.
   b. Joints between metal panels.
   c. Joints between different materials listed above.
   d. Perimeter joints between materials listed above and frames of doors, windows and louvers.
   e. Control and expansion joints in ceilings and other overhead surfaces.
   f. Other joints as indicated on Drawings.

2. Joint Sealant: Silicone, nonstaining, S, NS, 50, NT.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

C. Joint-Sealant Application: Interior joints in horizontal traffic surfaces JS-#3.

1. Joint Locations:

   a. Isolation joints in cast-in-place concrete slabs.
   b. Control and expansion joints in tile flooring.
   c. Other joints as indicated on Drawings.

2. Joint Sealant: [**Urethane, S, P, 25, T, NT**] <**Insert joint sealant**>.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

D. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces JS-#4.

1. Joint Locations:

   a. Control and expansion joints on exposed interior surfaces of exterior walls.
   b. Tile control and expansion joints.

c. Vertical joints on exposed surfaces of unit masonry walls and partitions.
d. Other joints as indicated on Drawings.

2. Joint Sealant: [**Urethane, S, NS, 25, NT**] <**Insert joint sealant**>.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

E. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces not subject to significant movement JS-#5.

1. Joint Locations:

a. Control joints on exposed interior surfaces of exterior walls.
b. Perimeter joints between interior wall surfaces and frames of interior doors and windows.
c. Other joints as indicated on Drawings.

2. Joint Sealant: Acrylic latex.
3. Joint-Sealant Color: White.

F. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal nontraffic surfaces JS-#6.

1. Joint Locations:

a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
b. Tile control and expansion joints where indicated.
c. Other joints as indicated on Drawings.

2. Joint Sealant: Silicone, mildew resistant, acid curing, S, NS, 25, NT.
3. Joint-Sealant Color: White.

G. Joint-Sealant Application: Concealed mastics JS-#7.

1. Joint Locations:

a. Aluminum thresholds.
b. Sill plates.
c. Other joints as indicated on Drawings.

2. Joint Sealant: Butyl-rubber based.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

END OF SECTION 079200

SECTION 079219 - ACOUSTICAL JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes acoustical joint sealants.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for elastomeric, latex, and butyl-rubber-based joint sealants for nonacoustical applications.

1.3 ACTION SUBMITTALS

A. Product Data: For each acoustical joint sealant.

B. Sustainable Design Submittals:

1. Product Data: For sealants, indicating VOC content.
2. Laboratory Test Reports: For sealants, indicating compliance with requirements for low-emitting materials.

C. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.

D. Samples for Verification: For each kind and color of acoustical joint sealant required, provide Samples with joint sealants in 1/2-inch- (13-mm-) wide joints formed between two 6-inch- (150-mm-) long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

E. Acoustical-Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.4 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each kind of acoustical joint sealant, for tests performed by a qualified testing agency.

B. Sample Warranties: For special warranties.

1.5 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace acoustical joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish acoustical joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Provide acoustical joint-sealant products that effectively reduce airborne sound transmission through perimeter joints and openings in building construction, as demonstrated by testing representative assemblies according to ASTM E90.

1. Sealant shall have a VOC content of 250 g/L or less.
2. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.2 ACOUSTICAL JOINT SEALANTS

A. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex acoustical sealant complying with ASTM C834.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Accumetric LLC.
b. Franklin International.
c. GE Construction Sealants; Momentive Performance Materials Inc.
d. Grabber Construction Products.
e. Hilti, Inc.

f. OSI Sealants; Henkel Corporation.
g. Pecora Corporation.
h. Serious Energy Inc.
i. Tremco Incorporated.
j. United States Gypsum Company.

2. Colors of Exposed Acoustical Joint Sealants: White.

2.3 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by acoustical-joint-sealant manufacturer where required for adhesion of sealant to joint substrates.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive acoustical joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing acoustical joint sealants to comply with joint-sealant manufacturer's written instructions.

B. Joint Priming: Prime joint substrates where recommended by acoustical-joint-sealant manufacturer. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF ACOUSTICAL JOINT SEALANTS

A. Comply with acoustical joint-sealant manufacturer's written installation instructions unless more stringent requirements apply.

B. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical joint sealant. Install acoustical joint sealants at both faces of partitions, at perimeters, and through penetrations. Comply with ASTM C919, ASTM C1193, and manufacturer's written recommendations for closing off sound-flanking paths around or through assemblies, including sealing partitions to underside of floor slabs above acoustical ceilings.

C. Acoustical Ceiling Areas: Apply acoustical joint sealant at perimeter edge moldings of acoustical ceiling areas in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.

3.4 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of acoustical joint sealants and of products in which joints occur.

3.5 PROTECTION

A. Protect acoustical joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated acoustical joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 079219

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes:

1. Interior standard steel doors and frames.
2. Exterior standard steel doors and frames.

B. Related Requirements:

1. Section 081416 "Flush Wood Doors" for wood doors be mounted in hollow-metal frames.
2. Section 087100 "Door Hardware" for door hardware for hollow-metal doors.

1.3 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or ANSI/SDI A250.8.

1.4 COORDINATION

A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

1.5 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.6 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, and finishes.

B. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
7. Details of anchorages, joints, field splices, and connections.
8. Details of accessories.
9. Details of moldings, removable stops, and glazing.

C. Samples for Verification:

1. Finishes: For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches (75 by 127 mm).

D. Product Schedule: For hollow-metal doors and frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

1.7 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each type of fire-rated hollow-metal door and frame assembly] [fire-rated borrowed-lite assembly for tests performed by a qualified testing agency indicating compliance with performance requirements.

1.8 CLOSEOUT SUBMITTALS

A. Record Documents: For fire-rated doors, list of door numbers and applicable room name and number to which door accesses.

1.9 QUALITY ASSURANCE

A. Deliver hollow-metal doors and frames palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

1. Provide additional protection to prevent damage to factory-finished units.

B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

C. Store hollow-metal doors and frames vertically under cover at Project site with head up. Place on minimum 4-inch- (102-mm-) high wood blocking. Provide minimum 1/4-inch (6-mm) space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products of one of the following:

1. Ceco Doors, an ASSA ABLOY Group company.
2. Curries Company, an ASSA ABLOY Group company.
3. Deansteel Manufacturing Co., Inc.
4. Fleming Door Products Ltd., an ASSA ABLOY Group company.
5. Kewanee Corporation (The).
6. Mesker Door, Inc.
7. Pioneer Industries, an ASSA ABLOY Group company.
8. Republic and Frames, an Alegion brand.
9. Steelcraft, an Allegion brand.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Rated Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated on Drawings, based on testing at positive pressure according to NFPA 252 or UL 10C.

1. Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing according to UL 1784 and installed in compliance with NFPA 105.

B. Thermally Rated Door Assemblies: Provide door assemblies with U-factor of not more than 0.50 deg Btu/F x h x sq. ft. (2.84 W/K x sq. m) when tested according to ASTM C518.

2.3 INTERIOR STANDARD STEEL DOORS AND FRAMES

A. Construct hollow-metal doors and frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Heavy-Duty Doors and Frames: ANSI/SDI A250.8, Level 2; ANSI/SDI A250.4, Level B.

1. Doors:

a. Type: As indicated in the Door and Frame Schedule.
b. Thickness: 1-3/4 inches (44.5 mm).
c. Face: Uncoated steel sheet, minimum thickness of 0.042 inch (1.0 mm).
d. Edge Construction: Model 2, Seamless.
e. Edge Bevel: Provide manufacturer's standard beveled or square edges.
f. Core: Manufacturer's standard.
g. Fire-Rated Core: Manufacturer's standard core for fire-rated doors.

2. Frames:

a. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch (1.3 mm).
b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.
c. Construction: Full profile welded.

3. Exposed Finish: Prime.

2.4 EXTERIOR STANDARD STEEL DOORS AND FRAMES

A. Construct hollow-metal doors and frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Heavy-Duty Doors and Frames: ANSI/SDI A250.8, Level 2; ANSI/SDI A250.4, Level B.

1. Doors:

a. Type: As indicated in the Door and Frame Schedule.
b. Thickness: 1-3/4 inches (44.5 mm).
c. Face: Metallic-coated steel sheet, minimum thickness of 0.042 inch (1.0 mm), with minimum A40 (ZF120) coating.
d. Edge Construction: Model 2, Seamless.
e. Edge Bevel: Provide manufacturer's standard beveled or square edges.
f. Top Edge Closures: Close top edges of doors with flush closures of same material as face sheets. Seal joints against water penetration.
g. Bottom Edges: Close bottom edges of doors where required for attachment of weather stripping with end closures or channels of same material as face sheets. Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape.
h. Core: Manufacturer's standard.

2. Frames:

a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch (1.3 mm), with minimum A40 (ZF120) coating.
b. Construction: Thermally broken.

3. Exposed Finish: Prime.

2.5 BORROWED LITES

A. Fabricate of metallic-coated steel sheet, minimum thickness of 0.042 inch (1.0 mm).

B. Construction: Full profile welded.

C. Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as metal as frames.

D. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.

2.6 FRAME ANCHORS

A. Jamb Anchors:

1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.
2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches (610 mm) of frame height above 7 feet (2.1 m).
3. Postinstalled Expansion Anchor: Minimum 3/8-inch- (9.5-mm-) diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.

B. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.

C. Floor Anchors for Concrete Slabs with Underlayment: Adjustable-type anchors with extension clips, allowing not less than 2-inch (51-mm) height adjustment. Terminate bottom of frames at top of underlayment.

D. Material: ASTM A879/A879M, Commercial Steel (CS), 04Z (12G) coating designation; mill phosphatized.

1. For anchors built into exterior walls, steel sheet complying with ASTM A1008/A1008M or ASTM A1011/A1011M; hot-dip galvanized according to ASTM A153/A153M, Class B.

2.7 MATERIALS

A. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

B. Hot-Rolled Steel Sheet: ASTM A1011/A1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

C. Metallic-Coated Steel Sheet: ASTM A653/A653M, Commercial Steel (CS), Type B.

D. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A153/A153M.

E. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

F. Mineral-Fiber Insulation: ASTM C665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E136 for combustion characteristics.

G. Glazing: Comply with requirements in Section 088000 "Glazing."

2.8 FABRICATION

A. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.

1. Sidelite and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by welding, or by rigid mechanical anchors.
2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
3. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.

    a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

B. Hardware Preparation: Factory prepare hollow-metal doors and frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping according to ANSI/SDI A250.6, the Door Hardware Schedule, and templates.

1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
2. Comply with BHMA A156.115 for preparing hollow-metal doors and frames for hardware.

C. Glazed Lites: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with mitered hairline joints.

1. Provide stops and moldings flush with face of door, and with [**beveled**] [**square**] stops unless otherwise indicated.
2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.

3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames. Provide loose stops and moldings on inside of hollow-metal doors and frames.
4. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.
5. Provide stops for installation with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches (230 mm) o.c. and not more than 2 inches (51 mm) o.c. from each corner.

2.9 STEEL FINISHES

A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

2.10 PREPARATION

A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.

B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

2.11 INSTALLATION

A. Install hollow-metal doors and frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions.

B. Hollow-Metal Frames: Comply with ANSI/SDI A250.11.

1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.

    a. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
    b. Install frames with removable stops located on secure side of opening.

2. Fire-Rated Openings: Install frames according to NFPA 80.
3. Floor Anchors: Secure with postinstalled expansion anchors.

    a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.

4. Solidly pack mineral-fiber insulation inside frames.
5. In-Place Concrete or Masonry Construction: Secure frames in place with postinstalled expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces**.**
6. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:

    a. Squareness: Plus or minus 1/16 inch (1.6 mm), measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
    b. Alignment: Plus or minus 1/16 inch (1.6 mm), measured at jambs on a horizontal line parallel to plane of wall.
    c. Twist: Plus or minus 1/16 inch (1.6 mm), measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
    d. Plumbness: Plus or minus 1/16 inch (1.6 mm), measured at jambs at floor.

C. Hollow-Metal Doors: Fit and adjust hollow-metal doors accurately in frames, within clearances specified below.

1. Non-Fire-Rated Steel Doors: Comply with ANSI/SDI A250.8.
2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.

D. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow-metal manufacturer's written instructions.

2.12 FIELD QUALITY CONTROL

A. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

B. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

C. Prepare and submit separate inspection report for each fire-rated door assembly indicating compliance with each item listed in NFPA 80 and NFPA 101.

2.13 REPAIR

A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

B. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.

END OF SECTION 081113

SECTION 081416 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Five-ply flush wood veneer-faced doors for transparent finish.
2. Factory finishing flush wood doors.
3. Factory fitting flush wood doors to frames and factory machining for hardware.

B. Related Requirements:

1. Section 088000 "Glazing" for glass view panels in flush wood doors.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product, including the following:

1. Door core materials and construction.
2. Door edge construction
3. Door face type and characteristics.
4. Door trim for openings.
5. Factory-machining criteria.
6. Factory finishing specifications.

B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in Product Data; and the following:

1. Door schedule indicating door location, type, size, fire protection rating, and swing.
2. Door elevations, dimension and locations of hardware, lite and louver cutouts, and glazing thicknesses.
3. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
4. Dimensions and locations of blocking for hardware attachment.
5. Dimensions and locations of mortises and holes for hardware.
6. Clearances and undercuts.
7. Requirements for veneer matching.
8. Doors to be factory finished and application requirements.

C. Samples for Initial Selection: For factory-finished doors.

D. Samples for Verification:

1. Corner sections of doors, approximately 8 by 10 inches (200 by 250 mm), with door faces and edges representing actual materials to be used.
2. Frames for light openings, 6 inches (150 mm) long, for each material, type, and finish required.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For door inspector.

1. Fire-Rated Door Inspector: Submit documentation of compliance with NFPA 80, Section 5.2.3.1.
2. Egress Door Inspector: Submit documentation of compliance with NFPA 101, Section 7.2.1.15.4.
3. Submit copy of DHI's Fire and Egress Door Assembly Inspector (FDAI) certificate.

B. Field quality-control reports.

C. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Special warranties.

B. Record Documents: For fire-rated doors, list of door numbers and applicable room name and number to which door accesses.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Comply with requirements of referenced standard and manufacturer's written instructions.

B. Package doors individually in cardboard cartons, and wrap bundles of doors in plastic sheeting.

C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and HVAC system is operating and maintaining temperature and relative humidity at levels designed for building occupants for the remainder of construction period.

B. Environmental Limitations: Do not deliver or install doors until building is enclosed and weathertight, wet work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F (16 and 32 deg C) and relative humidity between 43 and 70 percent during remainder of construction period.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Delamination of veneer.
b. Warping (bow, cup, or twist) more than 1/4 inch (6.4 mm) in a 42-by-84-inch (1067-by-2134-mm) section.
c. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch (0.25 mm in a 76.2-mm) span.

2. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
3. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain flush wood doors from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Rated Wood Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated on Drawings, based on testing at positive pressure in accordance with UL 10C or NFPA 252.

2.3 FLUSH WOOD DOORS, GENERAL

A. Quality Standard: In addition to requirements specified, comply with ANSI/WDMA I.S. 1A.

2.4 SOLID-CORE FIVE-PLY FLUSH WOOD VENEER-FACED DOORS FOR TRANSPARENT FINISH

A. Interior Doors:

1. Manufacturers: Subject to compliance with requirements, provide products from one of the following:

a. Forte Opening Solutions.
b. Lambton Doors.
c. Lyndon Door, Inc.
d. Oregon Door.
e. Oshkosh Door Company.

f. VT Industries, Inc.

2. Performance Grade: ANSI/WDMA I.S. 1A Heavy Duty.
3. ANSI/WDMA I.S. 1A Grade: Custom.
4. Faces: Single-ply wood veneer not less than 1/50 inch (0.508 mm) thick.

   a. Species: Red oak.
   b. Cut: Plain sliced (flat sliced).
   c. Match between Veneer Leaves: Slip match.
   d. Assembly of Veneer Leaves on Door Faces: Running match.
   e. Pair and Set Match: Provide for doors hung in same opening or separated only by mullions.

5. Exposed Vertical and Top Edges: Same species as faces - Architectural Woodwork Standards edge Type A.

   a. Fire-Rated Single Doors: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed vertical edges.
   b. Mineral-Core Doors: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.

      1) Screw-Holding Capability: 475 lbf (2110 N) in accordance with WDMA T.M. 10.

6. Core for Non-Fire-Rated Doors:

   a. ANSI A208.1, Grade LD-1 particleboard.
   b. Glued wood stave.
   c. WDMA I.S. 10 structural composite lumber.

      1) Screw Withdrawal, Door Face: 475 lbf (2110 N).
      2) Screw Withdrawal, Vertical Door Edge: 475 lbf (2110 N).

   d. Either glued wood stave or WDMA I.S. 10 structural composite lumber.

7. Core for Fire-Rated Doors: As required to achieve fire-protection rating indicated on Drawings.
8. Construction: Five plies, hot-pressed bonded (vertical and horizontal edging is bonded to core), with entire unit abrasive planed before veneering.

   a. 2-1/2-inch (64-mm) midrail blocking.

2.5 FABRICATION

A. Factory fit doors to suit frame-opening sizes indicated.

   1. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.

2. Comply with NFPA 80 requirements for fire-rated doors.

B. Factory machine doors for hardware that is not surface applied.

1. Locate hardware to comply with DHI-WDHS-3.
2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.
3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
4. For doors scheduled to receive electrified locksets, provide factory-installed raceway and wiring to accommodate specified hardware.

C. Openings: Factory cut and trim openings through doors.

1. Light Openings: Trim openings with moldings of material and profile indicated.
2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 088000 "Glazing."

2.6 FACTORY FINISHING

A. Comply with referenced quality standard for factory finishing.

1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
2. Finish faces, all four edges, edges of cutouts, and mortises.
3. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.

B. Factory finish doors.

C. Transparent Finish:

1. ANSI/WDMA I.S. 1A Grade: Custom.
2. Finish: ANSI/WDMA I.S. 1A TR-6 Catalyzed Polyurethane.
3. Effect**:** Open-grain finish.
4. Sheen: Satin.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine doors and installed door frames, with Installer present, before hanging doors.

1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
2. Reject doors with defects.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Hardware: For installation, see Section 087100 "Door Hardware."

B. Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.

1. Install fire-rated doors and frames in accordance with NFPA 80.

C. Job-Fitted Doors:

1. Align and fit doors in frames with uniform clearances and bevels as indicated below.

a. Do not trim stiles and rails in excess of limits set by manufacturer or permitted for fire-rated doors.

2. Machine doors for hardware.
3. Seal edges of doors, edges of cutouts, and mortises after fitting and machining.
4. Clearances:

a. Provide 1/8 inch (3.2 mm) at heads, jambs, and between pairs of doors.
b. Provide 1/8 inch (3.2 mm) from bottom of door to top of decorative floor finish or covering unless otherwise indicated on Drawings.
c. Where threshold is shown or scheduled, provide1/4 inch (6.4 mm) from bottom of door to top of threshold unless otherwise indicated.
d. Comply with NFPA 80 for fire-rated doors.

5. Bevel fire-rated doors 1/8 inch in 2 inches (3-1/2 degrees) at lock edge; trim stiles and rails only to extent permitted by labeling agency.

D. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.

E. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 FIELD QUALITY CONTROL

A. Inspection Agency: Engage a qualified inspector to perform inspections and to furnish reports to Architect.

B. Inspections:

1. Fire-Rated Door Inspections: Inspect each fire-rated door in accordance with NFPA 80, Section 5.2.
2. Egress Door Inspections: Inspect each door equipped with panic hardware, each door equipped with fire exit hardware, each door located in an exit enclosure, each electrically controlled egress door, and each door equipped with special locking arrangements in accordance with NFPA 101, Section 7.2.1.15.

C. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

E. Prepare and submit separate inspection report for each fire-rated door assembly indicating compliance with each item listed in NFPA 80 and NFPA 101.

3.4 ADJUSTING

A. Operation: Rehang or replace doors that do not swing or operate freely.

B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 081416

SECTION 083323 - OVERHEAD COILING DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Insulated service doors.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for miscellaneous steel supports, door-opening framing, corner guards, and bollards.

1.3 ACTION SUBMITTALS

A. Product Data: For each type and size of overhead coiling door and accessory.

1. Include construction details, material descriptions, dimensions of individual components, profiles for slats, and finishes.

B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies, and indicate dimensions, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
4. For exterior components, include details of provisions for assembly expansion and contraction and for excluding and draining moisture to the exterior.
5. Show locations of controls, locking devices and other accessories.

C. Samples for Initial Selection: Manufacturer's finish charts showing full range of colors and textures available for units with factory-applied finishes.

1. Include similar Samples of accessories involving color selection.

D. Samples for Verification: For each type of exposed finish on the following components, in manufacturer's standard sizes:

1. Curtain slats.
2. Include similar Samples of accessories involving color selection.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For overhead coiling doors to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer for both installation and maintenance of units required for this Project.

1. Maintenance Proximity: Not more than two hours' normal travel time from Installer's place of business to Project site.

B. Regulatory Requirements: Comply with applicable provisions in ICC A117.1.

PART 2 - PRODUCTS

2.1 MANUFACTURERS, GENERAL

A. Source Limitations: Obtain overhead coiling doors from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Structural Performance, Exterior Doors: Capable of withstanding the design wind loads.

1. Design Wind Load: As indicated on Drawings.
2. Testing: According to ASTM E 330.
3. Deflection Limits: Design overhead coiling doors to withstand design wind load without evidencing permanent deformation or disengagement of door components.

B. Seismic Performance: Overhead coiling doors shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

Component Importance Factor: 1.0.

2.3 INSULATED SERVICE DOORS

A. Insulated Service Door: Overhead coiling door formed with curtain of interlocking metal slats.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Alpine Overhead Doors, Inc.
b. Cookson Company.
c. Cornell Iron Works, Inc.
d. Overhead Door Corporation.
e. Wayne-Dalton Corp.

B. Operation Cycles: Door components and operators capable of operating for not less than 20,000. One operation cycle is complete when a door is opened from the closed position to the fully open position and returned to the closed position.

C. Air Infiltration: Maximum rate of 0.08 cfm/sq. ft. (0.406 L/s per sq. m) at 15 and 25 mph (24.1 and 40.2 km/h) when tested according to ASTM E 283.

D. Curtain R-Value: 8.0 deg F x h x sq. ft./Btu (1.409 K x sq. m/W).

E. Door Curtain Material: Galvanized steel.

F. Door Curtain Slats: Flat profile slats of between 1-7/8-inch (48-mm) and 3-1/4-inch (83-mm) center-to-center height.

1. Insulated-Slat Interior Facing: Metal.

G. Bottom Bar: Two angles, each not less than 1-1/2 by 1-1/2 by 1/8 inch (38 by 38 by 3 mm) thick; fabricated from hot-dip galvanized steel and finished to match door.

H. Curtain Jamb Guides: Galvanized steel with exposed finish matching curtain slats.

I. Hood: Galvanized steel.

1. Shape: Round.
2. Mounting: Face of wall.

J. Locking Devices: Equip door with locking device assembly.

1. Locking Device Assembly: Single-jamb side locking bars, operable from inside with thumb turn and outside with cylinder.

K. Electric Door Operator:

1. Usage Classification: Medium duty, up to 12 cycles per hour and up to 50 cycles per day.
2. Operator Location: Top of hood.
3. Safety: Listed according to UL 325 by a qualified testing agency for commercial or industrial use.
4. Motor Exposure: Interior.

5. Emergency Manual Operation: Chain type.
6. Obstruction-Detection Device: Automatic electric sensor edge on bottom bar.

    a. Sensor Edge Bulb Color: Black.

7. Control Station(s): Interior mounted.

L. Curtain Accessories: Equip door with **w**eatherseals.

M. Door Finish:

1. Powder-Coated Finish: Color as selected by Architect from manufacturer's full range.
2. Interior Curtain-Slat Facing: Match finish of exterior curtain-slat face.

2.4 MATERIALS, GENERAL

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.5 DOOR CURTAIN MATERIALS AND CONSTRUCTION

A. Door Curtains: Fabricate overhead coiling-door curtain of interlocking metal slats, designed to withstand wind loading indicated, in a continuous length for width of door without splices. Unless otherwise indicated, provide slats of thickness and mechanical properties recommended by door manufacturer for performance, size, and type of door indicated, and as follows:

1. Steel Door Curtain Slats: Zinc-coated (galvanized), cold-rolled structural steel sheet; complying with ASTM A 653/A 653M, with G90 (Z275) zinc coating; nominal sheet thickness (coated) of 0.028 inch (0.71 mm); and as required.
2. Insulation: Fill slats for insulated doors with manufacturer's standard thermal insulation complying with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, according to ASTM E 84 or UL 723. Enclose insulation completely within slat faces.
3. Metal Interior Curtain-Slat Facing: Match metal of exterior curtain-slat face, with minimum steel thickness of 0.010 inch (0.25 mm).

B. Curtain Jamb Guides: Manufacturer's standard angles or channels and angles of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for guide adjustment. Provide removable stops on guides to prevent overtravel of curtain, and a continuous bar for holding windlocks.

2.6 HOODS

A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any

portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

1. Galvanized Steel: Nominal 0.028-inch- (0.71-mm-) thick, hot-dip galvanized steel sheet with G90 (Z275) zinc coating, complying with ASTM A 653/A 653M.

2.7 LOCKING DEVICES

A. Slide Bolt: Fabricate with side-locking bolts to engage through slots in tracks for locking by padlock, located on both left and right jamb sides, operable from coil side.

B. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

2.8 CURTAIN ACCESSORIES

A. Weatherseals for Exterior Doors: Equip each exterior door with weather-stripping gaskets fitted to entire exterior perimeter of door for a weather-resistant installation unless otherwise indicated.

1. At door head, use 1/8-inch- (3-mm-) thick, replaceable, continuous-sheet baffle secured to inside of hood or field- installed on the header.
2. At door jambs, use replaceable, adjustable, continuous, flexible, 1/8-inch- (3-mm-) thick seals of flexible vinyl, rubber, or neoprene.

2.9 COUNTERBALANCING MECHANISM

A. General: Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed bearings or self-lubricating graphite bearings for rotating members.

B. Counterbalance Barrel: Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, seamless or welded carbon-steel pipe, of sufficient diameter and wall thickness to support rolled-up curtain without distortion of slats and to limit barrel deflection to not more than 0.03 in./ft. (2.5 mm/m) of span under full load.

C. Counterbalance Spring: One or more oil-tempered, heat-treated steel helical torsion springs. Size springs to counterbalance weight of curtain, with uniform adjustment accessible from outside barrel. Secure ends of springs to barrel and shaft with cast-steel barrel plugs.

D. Torsion Rod for Counterbalance Shaft: Fabricate of manufacturer's standard cold-rolled steel, sized to hold fixed spring ends and carry torsional load.

E. Brackets: Manufacturer's standard mounting brackets of either cast iron or cold-rolled steel plate.

2.10 ELECTRIC DOOR OPERATORS

A. General: Electric door operator assembly of size and capacity recommended and provided by door manufacturer for door and operation-cycles requirement specified, with electric motor and factory-prewired motor controls, starter, gear-reduction unit, solenoid-operated brake, clutch, control stations, control devices, integral gearing for locking door, and accessories required for proper operation.

1. Comply with NFPA 70.
2. Control equipment complying with NEMA ICS 1, NEMA ICS 2, and NEMA ICS 6, with NFPA 70 Class 2 control circuit, maximum 24-V ac or dc.

B. Usage Classification: Electric operator and components capable of operating for not less than number of cycles per hour indicated for each door.

C. Door Operator Location(s): Operator location indicated for each door.

1. Top-of-Hood Mounted: Operator is mounted to the right or left door head plate with the operator on top of the door-hood assembly and connected to the door drive shaft with drive chain and sprockets. Headroom is required for this type of mounting.

D. Motors: Reversible-type motor with controller (disconnect switch) for motor exposure indicated.

1. Electrical Characteristics:

a. Phase: Single phase.
b. Volts: 208V.
c. Hertz: 60.

2. Motor Size: Manufacturer’s standard motor size, large enough to start, accelerate, and operate door in either direction from any position, at a speed not less than 8 in./sec. (203 mm/s) and not more than 12 in./sec. (305 mm/s), without exceeding nameplate ratings or service factor.
3. Operating Controls, Controllers, Disconnect Switches, Wiring Devices, and Wiring: Manufacturer's standard unless otherwise indicated.
4. Coordinate wiring requirements and electrical characteristics of motors and other electrical devices with building electrical system and each location where installed.

E. Limit Switches: Equip each motorized door with adjustable switches interlocked with motor controls and set to automatically stop door at fully opened and fully closed positions.

F. Obstruction Detection Devices: External entrapment protection consisting of indicated automatic safety sensor capable of protecting full width of door opening. For non-fire-rated doors, activation of device immediately stops and reverses downward door travel.

1. Electric Sensor Edge: Automatic safety sensor edge, located within astragal or weather stripping mounted to bottom bar. Contact with sensor activates device. Connect to control circuit using manufacturer's standard take-up reel or self-coiling cable.

G. Control Station: Three-button control station in fixed location with momentary-contact push-button controls labeled "Open" and "Stop" and sustained- or constant-pressure push-button control labeled "Close."

1. Interior-Mounted Units: Full-guarded, surface-mounted, heavy-duty type, with general-purpose NEMA ICS 6, Type 1 enclosure.

H. Emergency Manual Operation: Equip each electrically powered door with capability for emergency manual operation. Design manual mechanism so required force for door operation does not exceed 25 lbf.

I. Emergency Operation Disconnect Device: Equip operator with hand-operated disconnect mechanism for automatically engaging manual operator and releasing brake for emergency manual operation while disconnecting motor without affecting timing of limit switch. Mount mechanism so it is accessible from floor level. Include interlock device to automatically prevent motor from operating when emergency operator is engaged.

J. Motor Removal: Design operator so motor may be removed without disturbing limit-switch adjustment and without affecting emergency manual operation.

K. Portable Radio-Control System: Consisting of one of the following per door operator:

1. Three-channel universal coaxial receiver to open, close, and stop door.

2.11 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM/NOMMA's "Metal Finishes Manual for Architectural and Metal Products (AMP 500-06)" for recommendations for applying and designating finishes.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.12 STEEL AND GALVANIZED-STEEL FINISHES

A. Factory Prime Finish: Manufacturer's standard primer, compatible with field-applied finish. Comply with coating manufacturer's written instructions for cleaning, pretreatment, application, and minimum dry film thickness.

B. Baked-Enamel or Powder-Coat Finish: Manufacturer's standard baked-on finish consisting of prime coat and thermosetting topcoat. Comply with coating manufacturer's written instructions for cleaning, pretreatment, application, and minimum dry film thickness.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates areas and conditions, with Installer present, for compliance with requirements for substrate construction and other conditions affecting performance of the Work.

B. Examine locations of electrical connections.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install overhead coiling doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.

B. Install overhead coiling doors, hoods, controls, and operators at the mounting locations indicated for each door.

C. Accessibility: Install overhead coiling doors, switches, and controls along accessible routes in compliance with regulatory requirements for accessibility.

3.3 ADJUSTING

A. Adjust hardware and moving parts to function smoothly so that doors operate easily, free of warp, twist, or distortion.

1. Adjust exterior doors and components to be weather-resistant.

B. Lubricate bearings and sliding parts as recommended by manufacturer.

C. Adjust seals to provide tight fit around entire perimeter.

3.4 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain overhead coiling doors.

END OF SECTION 083323

SECTION 084113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Aluminum-framed storefront systems.
2. Aluminum-framed entrance door systems.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

B. Sustainable Design Submittals:

1. Product Data: For adhesives and sealants indicating compliance with General Emissions evaluation and VOC content requirements.
2. Submit documentation of recycled content, documentation indicating percentages by weight of post-consumer and pre-consumer content and location of manufacture as well as the location of extraction and harvest. Extraction and Harvest as well as location of manufacture shall be within 500 miles of the project site.
3. Building Product Disclosure Documents: Provide the following information when available:

a. Environmental Product Declarations.
b. Material Ingredients Documentation demonstrating the chemical inventory of the product to at least 0.1 percent (1000 ppm).

C. Shop Drawings: For aluminum-framed entrances and storefronts. Include plans, elevations, sections, full-size details, and attachments to other work.

1. Include details of provisions for assembly expansion and contraction and for draining moisture occurring within the assembly to the exterior.
2. Include full-size isometric details of each type of vertical-to-horizontal intersection of aluminum-framed entrances and storefronts, showing the following:

a. Joinery, including concealed welds.
b. Anchorage.
c. Expansion provisions.
d. Glazing.
e. Flashing and drainage.

3. Show connection to and continuity with adjacent thermal, weather, air, and vapor barriers.
4. Include point-to-point wiring diagrams showing the following:

a. Power requirements for each electrically operated door hardware.
b. Location and types of switches, signal device, conduit sizes, and number and size of wires.

D. Samples for Verification: For each type of exposed finish required, in manufacturer's standard sizes.

E. Fabrication Sample: Of each vertical-to-horizontal intersection of assemblies, made from 12-inch (300-mm) lengths of full-size components and showing details of the following:

1. Joinery, including concealed welds.
2. Anchorage.
3. Expansion provisions.
4. Glazing.
5. Flashing and drainage.

F. Entrance Door Hardware Schedule: Prepared by or under supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams. Coordinate final entrance door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of entrance door hardware.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data:

1. For Installer.
2. For professional engineer's experience with providing delegated-design engineering services of the kind indicated, including documentation that engineer is licensed in the state in which Project is located.

B. Energy Performance Certificates: For aluminum-framed entrances and storefronts, accessories, and components, from manufacturer.

1. Basis for Certification: NFRC-certified energy performance values for each aluminum-framed entrance and storefront.

C. Product Test Reports: For aluminum-framed entrances and storefronts, for tests performed by a qualified testing agency.

D. Source quality-control reports.

E. Sample Warranties: For special warranties.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For aluminum-framed entrances and storefronts to include in maintenance manuals.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer, and who have no fewer than five years of experience installing products similar to those required for this Project.

B. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.

1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

1.8 MOCKUPS

A. Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.

1. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.

1.9 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of aluminum-framed entrances and storefronts that do not comply with requirements or that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures, including, but not limited to, excessive deflection.
b. Noise or vibration created by wind and thermal and structural movements.
c. Deterioration of metals and other materials beyond normal weathering.
d. Water penetration through fixed glazing and framing areas.
e. Failure of operating components.

2. Warranty Period: Two years from date of Substantial Completion.

B. Special Finish Warranty, Factory-Applied Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of factory-applied finishes within specified warranty period.

1. Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested according to ASTM D2244.
b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain all components of aluminum-framed entrance and storefront system, including framing and accessories, from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrances and storefronts representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

1. Aluminum-framed entrances and storefronts shall withstand movements of supporting structure, including, but not limited to, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
2. Failure also includes the following:

a. Thermal stresses transferring to building structure.

b. Glass breakage.
c. Noise or vibration created by wind and thermal and structural movements.
d. Loosening or weakening of fasteners, attachments, and other components.
e. Failure of operating units.

B. Structural Loads:

1. Wind Loads: As indicated on Drawings.
2. Other Design Loads: As indicated on Drawings.

C. Deflection of Framing Members: At design wind pressure, as follows:

1. Deflection Normal to Wall Plane: Limited to edge of glass in a direction perpendicular to glass plane not exceeding 1/175 of the glass edge length for each individual glazing lite or an amount that restricts edge deflection of individual glazing lites to 3/4 inch (19.1 mm), whichever is less.
2. Deflection Parallel to Glazing Plane: Limited to amount not exceeding that which reduces glazing bite to less than 75 percent of design dimension and that which reduces edge clearance between framing members and glazing or other fixed components to less than 1/8 inch (3.2 mm).

D. Structural: Test according to ASTM E330/E330M as follows:

1. When tested at positive and negative wind-load design pressures, storefront assemblies, including entrance doors, do not evidence deflection exceeding specified limits.
2. When tested at 150 percent of positive and negative wind-load design pressures, storefront assemblies, including entrance doors and anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
3. Test Durations: As required by design wind velocity, but not less than 10 seconds.

E. Water Penetration under Static Pressure: Test according to ASTM E331 as follows:

1. No evidence of water penetration through fixed glazing and framing areas, including entrance doors, when tested according to a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 6.24 lbf/sq. ft. (300 Pa).
2. Maximum Water Leakage: No uncontrolled water penetrating assemblies or water appearing on assemblies' normally exposed interior surfaces from sources other than condensation. Water leakage does not include water controlled by flashing and gutters, or water that is drained to exterior.

F. Energy Performance: Certified and labeled by manufacturer for energy performance as follows:

1. Thermal Transmittance (U-factor):

a. Fixed Glazing and Framing Areas: U-factor for the system of not more than 0.41 Btu/sq. ft. x h x deg F (2.33 W/sq. m x K) as determined according to NFRC 100.
b. Entrance Doors: U-factor of not more than 0.77 Btu/sq. ft. x h x deg F (4.37 W/sq. m x K) as determined according to NFRC 100.

2. Solar Heat-Gain Coefficient (SHGC):

   a. Fixed Glazing and Framing Areas: SHGC for the system of not more than 0.40 as determined according to NFRC 200.
   b. Entrance Doors: SHGC of not more than 0.40 as determined according to NFRC 200.

3. Air Leakage:

   a. Fixed Glazing and Framing Areas: Air leakage for the system of not more than 0.06 cfm/sq. ft. (0.30 L/s per sq. m) at a static-air-pressure differential of 6.24 lbf/sq. ft. (300 Pa) when tested according to ASTM E283.
   b. Entrance Doors: Air leakage of not more than 1.0 cfm/sq. ft. (5.08 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).

4. Condensation Resistance Factor (CRF):

   a. Fixed Glazing and Framing Areas: CRF for the system of not less than 68 as determined according to AAMA 1503.
   b. Entrance Doors: CRF of not less than 57 as determined according to AAMA 1503.

A. Noise Reduction: Test according to ASTM E90, with ratings determined by ASTM E1332, as follows.

   1. Outdoor-Indoor Transmission Class: Minimum 30.

B. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes.

   1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

2.3 STOREFRONT SYSTEMS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Kawneer Company, Inc.; Trifab 451 UT, or comparable product by one of the following:

   1. EFCO, an Apogee Architectural Metals brand.
   2. Oldcastle Building Envelope.
   3. Tubelite, an Apogee Architectural Metals brand.
   4. YKK AP America, Inc.

B. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.

   1. Exterior Framing Construction: Thermally broken.
   2. Interior Vestibule Framing Construction: Nonthermal.
   3. Glazing System: Retained mechanically with gaskets on four sides.
   4. Glazing Plane: Center.
   5. Finish: High-performance organic finish.

6. Fabrication Method: Field-fabricated stick system.
7. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
8. Steel Reinforcement: As required by manufacturer.

C. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.

D. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

2.4 ENTRANCE DOOR SYSTEMS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Kawneer Company, Inc.; 500 Standard Entrance Door, or comparable product by one of the following:

1. EFCO Corporation.
2. Oldcastle Building Envelope.
3. Tubelite, an Apogee Architectural Metal brand.
4. YKK AP America, Inc.

B. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing or automatic operation.

1. Door Construction: 1-3/4-inch (44.5-mm) overall thickness, with minimum 0.125-inch-(3.2-mm) thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.
2. Door Design: Wide stile; 5-inch (127-mm) nominal width.
3. Glazing Stops and Gaskets: Beveled, snap-on, extruded-aluminum stops and preformed gaskets.

    a. Provide nonremovable glazing stops on outside of door.

4. Finish: Match adjacent storefront framing finish.

2.5 ENTRANCE DOOR HARDWARE

A. Entrance Door Hardware: Hardware not specified in this Section is specified in Section 087100 "Door Hardware."

2.6 GLAZING

A. Glazing: Comply with Section 088000 "Glazing."

B. Glazing Gaskets: Manufacturer's standard sealed-corner pressure-glazing system of black, resilient elastomeric glazing gaskets, setting blocks, and shims or spacers.

C. Glazing Sealants: As recommended by manufacturer.

1. VOC Content Requirements for Wet Applied Products: All sealants wet-applied on site must meet the applicable chemical content requirements of SCAQMD Rule 1168, amended October 26, 2017, Adhesive and Sealant Applications, as analyzed by the methods specified in Rule 1168. The provisions of SCAQMD Rule 1168 do not apply to adhesives and sealants subject to state or federal consumer product VOC regulations.
2. Do not use adhesives that contain urea formaldehyde.

2.7 MATERIALS

A. Sheet and Plate: ASTM B209 (ASTM B209M).

B. Extruded Bars, Rods, Profiles, and Tubes: ASTM B221 (ASTM B221M).

C. Extruded Structural Pipe and Tubes: ASTM B429/B429M.

D. Structural Profiles: ASTM B308/B308M.

E. Steel Reinforcement:

1. Structural Shapes, Plates, and Bars: ASTM A36/A36M.
2. Cold-Rolled Sheet and Strip: ASTM A1008/A1008M.
3. Hot-Rolled Sheet and Strip: ASTM A1011/A1011M.

F. Steel Reinforcement Primer: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods according to recommendations in SSPC-SP COM, and prepare surfaces according to applicable SSPC standard.

2.8 ACCESSORIES

A. Automatic Door Operators: Section 087113 "Automatic Door Operators."

B. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
2. Reinforce members as required to receive fastener threads.

C. Anchors: Three-way adjustable anchors with minimum adjustment of 1 inch (25.4 mm) that accommodate fabrication and installation tolerances in material and finish compatible with adjoining materials and recommended by manufacturer.

1. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A123/A123M or ASTM A153/A153M requirements.

D. Concealed Flashing: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials.

E. Bituminous Paint: Cold-applied asphalt-mastic paint containing no asbestos, formulated for 30-mil (0.762-mm) thickness per coat.

F. Rigid PVC Filler.

2.9 FABRICATION

A. Form or extrude aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
5. Provisions for field replacement of glazing from exterior.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.

E. Storefront Framing: Fabricate components for assembly using screw-spline system.

F. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.

1. At interior and exterior doors, provide compression weather stripping at fixed stops.

G. Entrance Doors: Reinforce doors as required for installing entrance door hardware.

1. At pairs of exterior doors, provide sliding-type weather stripping retained in adjustable strip and mortised into door edge.
2. At exterior doors, provide weather sweeps applied to door bottoms.

H. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.

I. After fabrication, clearly mark components to identify their locations in Project according to Shop Drawings.

2.10 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Comply with manufacturer's written instructions.

B. Do not install damaged components.

C. Fit joints to produce hairline joints free of burrs and distortion.

D. Rigidly secure nonmovement joints.

E. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.

F. Seal perimeter and other joints watertight unless otherwise indicated.

G. Metal Protection:

1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or by installing nonconductive spacers.
2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

H. Set continuous sill members and flashing in full sealant bed, as specified in Section 079200 "Joint Sealants," to produce weathertight installation.

I. Install joint filler behind sealant as recommended by sealant manufacturer.

J. Install components plumb and true in alignment with established lines and grades.

3.3 INSTALLATION OF GLAZING

A. Install glazing as specified in Section 088000 "Glazing."

3.4 INSTALLATION OF ALUMINUM-FRAMED ENTRANCE DOORS

A. Install entrance doors to produce smooth operation and tight fit at contact points.

1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.
2. Field-Installed Entrance Door Hardware: Install surface-mounted entrance door hardware according to entrance door hardware manufacturers' written instructions using concealed fasteners to greatest extent possible.

3.5 ERECTION TOLERANCES

A. Install aluminum-framed entrances and storefronts to comply with the following maximum tolerances:

1. Plumb: 1/8 inch in 10 feet (3.2 mm in 3 m); 1/4 inch in 40 feet (6.35 mm in 12.2 m).
2. Level: 1/8 inch in 20 feet (3.2 mm in 6 m); 1/4 inch in 40 feet (6.35 mm in 12.2 m).
3. Alignment:

    a. Where surfaces abut in line or are separated by reveal or protruding element up to 1/2 inch (12.7 mm) wide, limit offset from true alignment to 1/16 inch (1.6 mm).
    b. Where surfaces are separated by reveal or protruding element from 1/2 to 1 inch (12.7 to 25.4 mm) wide, limit offset from true alignment to 1/8 inch (3.2 mm).
    c. Where surfaces are separated by reveal or protruding element of 1 inch (25.4 mm) wide or more, limit offset from true alignment to 1/4 inch (6 mm).

4. Location: Limit variation from plane to 1/8 inch in 12 feet (3.2 mm in 3.6 m); 1/2 inch (12.7 mm) over total length.

3.6 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

B. Field Quality-Control Testing: Perform the following test on representative areas of aluminum-framed entrances and storefronts.

1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect shall be tested according to AAMA 501.2 and shall not evidence water penetration.

    a. Perform a minimum of three tests in areas as directed by Architect.

2. Air Leakage: ASTM E783 at 1.5 times the rate specified for laboratory testing in "Performance Requirements" Article but not more than 0.09 cfm/sq. ft. (0.45 L/s per sq. m) at a static-air-pressure differential of 1.57 lbf/sq. ft. (75 Pa).

    a. Perform a minimum of three tests in areas as directed by Architect.

3. Water Penetration: ASTM E1105 at a minimum uniform static-air-pressure differential of 0.67 times the static-air-pressure differential specified for laboratory testing in "Performance Requirements" Article, but not less than 6.24 lbf/sq. ft. (300 Pa), and shall not evidence water penetration.

C. Aluminum-framed entrances and storefronts will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports.

END OF SECTION 084113

SECTION 085113 - ALUMINUM WINDOWS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes aluminum windows for exterior locations.

B. Related Requirements:

1. Section 084113 "Aluminum-Framed Entrances and Storefronts" for coordinating finish among aluminum fenestration units.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
2. Review and discuss the finishing of aluminum windows that is required to be coordinated with the finishing of other aluminum work for color and finish matching.
3. Review, discuss, and coordinate the interrelationship of aluminum windows with other exterior wall components. Include provisions for anchoring, flashing, weeping, sealing perimeters, and protecting finishes.
4. Review and discuss the sequence of work required to construct a watertight and weathertight exterior building envelope.
5. Inspect and discuss the condition of substrate and other preparatory work performed by other trades.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, glazing and fabrication methods, dimensions of individual components and profiles, hardware, and finishes for aluminum windows.

B. Shop Drawings: For aluminum windows.

1. Include plans, elevations, sections, hardware, accessories, insect screens, operational clearances, and details of installation, including anchor, flashing, and sealant installation.

C. Samples for Verification: For aluminum windows and components required, showing full range of color variations for finishes, and prepared on Samples of size indicated below:

1. Exposed Finishes: 2 by 4 inches (50 by 100 mm).
2. Exposed Hardware: Full-size units.

D. Product Schedule: For aluminum windows. Use same designations indicated on Drawings.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer and Installer.

B. Product Test Reports: For each type of aluminum window, for tests performed by a qualified testing agency.

C. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. Manufacturer Qualifications: A manufacturer capable of fabricating aluminum windows that meet or exceed performance requirements indicated and of documenting this performance by test reports and calculations.

B. Installer Qualifications: An installer acceptable to aluminum window manufacturer for installation of units required for this Project.

1.7 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace aluminum windows that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure to meet performance requirements.
b. Structural failures including excessive deflection, water leakage, condensation, and air infiltration.
c. Faulty operation of movable sash and hardware.
d. Deterioration of materials and finishes beyond normal weathering.
e. Failure of insulating glass.

2. Warranty Period:

a. Window: 10 years from date of Substantial Completion.

b. Glazing Units: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain aluminum windows from single source from single manufacturer.

2.2 WINDOW PERFORMANCE REQUIREMENTS

A. Product Standard: Comply with AAMA/WDMA/CSA 101/I.S.2/A440 for definitions and minimum standards of performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.

1. Window Certification: AAMA certified with label attached to each window.

B. Performance Class and Grade: AAMA/WDMA/CSA 101/I.S.2/A440 as follows:

1. Minimum Performance Class: AW.
2. Minimum Performance Grade: 80.

C. Thermal Transmittance: NFRC 100 maximum whole-window U-factor of 0.44 Btu/sq. ft. x h x deg F (2.27 W/sq. m x K).

D. Solar Heat-Gain Coefficient (SHGC): NFRC 200 maximum whole-window SHGC of 0.30.

E. Condensation-Resistance Factor (CRF): Provide aluminum windows tested for thermal performance according to AAMA 1503, showing a CRF of not less than 63.

F. Thermal Movements: Provide aluminum windows, including anchorage, that allow for thermal movements resulting from the following maximum change (range) in ambient and surface temperatures by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base engineering calculation on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change: 120 deg F (67 deg C) ambient; 180 deg F (100 deg C) material surfaces.

G. Sound Transmission Class (STC): Rated for not less than 30 STC when tested for laboratory sound transmission loss according to ASTM E90 and determined by ASTM E413.

H. Outside-Inside Transmission Class (OITC): Rated for not less than 26 OITC when tested for laboratory sound transmission loss according to ASTM E90 and determined by ASTM E1332.

I. Windborne-Debris Impact Resistance: Passes ASTM E1886 missile-impact and cyclic-pressure tests in accordance with ASTM E1996 for Wind Zone 4 for basic protection.

1. Large-Missile Test: For glazing located within 30 feet (9.1 m) of grade.

2.3 ALUMINUM WINDOWS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Kawneer; Series AA®4325 Ultra Thermal Window – Outswing Casement Window, or comparable product by one of the following:

1. EFCO, an Apogee Architectural Metals brand.
2. Oldcastle Building Envelope.
3. Tubelite, an Apogee Architectural Metals brand.
4. YKK AP America, Inc.

B. Types: Provide the following types in locations indicated on Drawings:

1. Lower Panels: Outswing casement next to outswing casement
2. Upper Panel: Fixed.

C. Frames and Sashes: Aluminum extrusions complying with AAMA/WDMA/CSA 101/I.S.2/A440.

1. Thermally Improved Construction: Fabricate frames, sashes, and muntins with an integral, concealed, low-conductance thermal barrier located between exterior materials and window members exposed on interior side in a manner that eliminates direct metal-to-metal contact.

D. Windborne-Debris-Impact-Resistant Insulating-Glass Units: ASTM E2190 with two lites and complying with impact-resistance requirements in "Window Performance Requirements" Article.

1. Exterior Lite: ASTM C1036, Type 1, Class 1, q3.

a. Tint: Clear.
b. Kind: Fully tempered.

2. Interior Lite: ASTM C1172 clear laminated glass with two plies of float glass.

a. Float Glass: Fully tempered.
b. Interlayer Thickness: 0.090 inch (2.29 mm).

3. Filling: Fill space between glass lites with air.
4. Low-E Coating: Sputtered on second surface.

E. Glazing System: Manufacturer's standard factory-glazing system that produces weathertight seal.

F. Hardware, General: Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with adjacent materials; designed to smoothly operate, tightly close, and securely lock windows, and sized to accommodate sash weight and dimensions.

1. Exposed Hardware Color and Finish: As selected by Architect from manufacturer's full range.

G. Casement Window Hardware:

1. Gear-Type Rotary Operators: Complying with AAMA 901 when tested according to ASTM E405, Method A. Provide operators that function without requiring the removal of interior screens or using screen wickets.

a. Type and Style: As selected by Architect from manufacturer's full range of types and styles.

2. Hinges: Non-friction type, not less than two per sash.
3. Lock: Dual lever handles, tie rod, and cam-action lock with keepers.
4. Limit Devices: Concealed friction adjustor, adjustable stay bar limit devices designed to restrict sash opening.

H. Weather Stripping: Provide full-perimeter weather stripping for each operable sash unless otherwise indicated.

I. Fasteners: Noncorrosive and compatible with window members, trim, hardware, anchors, and other components.

1. Exposed Fasteners: Do not use exposed fasteners to greatest extent possible. For application of hardware, use fasteners that match finish hardware being fastened.

2.4 ACCESSORIES

A. Subsills: Thermally broken, extruded-aluminum subsills in configurations indicated on Drawings.

B. Column Covers: Extruded-aluminum profiles in sizes and configurations indicated on Drawings.

C. Interior Trim: Extruded-aluminum profiles in sizes and configurations indicated on Drawings.

D. Panning Trim: Extruded-aluminum profiles in sizes and configurations indicated on Drawings.

E. Receptor System: Two-piece, snap-together, thermally broken, extruded-aluminum receptor system that anchors windows in place.

2.5 INSECT SCREENS

A. General: Fabricate insect screens to integrate with window frame. Provide screen for each operable exterior sash. Screen wickets are not permitted.

1. Type and Location: Full, inside for outswing sashes.

B. Aluminum Frames: Manufacturer's standard aluminum alloy complying with SMA 1004 or SMA 1201. Fabricate frames with mitered or coped joints or corner extrusions, concealed fasteners, and removable PVC spline/anchor concealing edge of frame.

1. Tubular Framing Sections and Cross Braces: Roll formed from aluminum sheet.

C. Glass-Fiber Mesh Fabric: 18-by-14 (1.1-by-1.4-mm) or 18-by-16 (1.0-by-1.1-mm) mesh of PVC-coated, glass-fiber threads; woven and fused to form a fabric mesh resistant to corrosion, shrinkage, stretch, impact damage, and weather deterioration. Comply with ASTM D3656/D3656M.

1. Mesh Color: Manufacturer's standard.

D. Aluminum Wire Fabric: 18-by-16 (1.1-by-1.3-mm) mesh of 0.011-inch- (0.28-mm-) diameter, coated aluminum wire.

1. Wire-Fabric Finish: Manufacturer's standard.

2.6 FABRICATION

A. Fabricate aluminum windows in sizes indicated. Include a complete system for assembling components and anchoring windows.

B. Glaze aluminum windows in the factory.

C. Weather strip each operable sash to provide weathertight installation.

D. Weep Holes: Provide weep holes and internal passages to conduct infiltrating water to exterior.

E. Complete fabrication, assembly, finishing, hardware application, and other work in the factory to greatest extent possible. Disassemble components only as necessary for shipment and installation.

2.7 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM's "Metal Finishes Manual" for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.8 ALUMINUM FINISHES

A. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

B. Class I, Clear Anodic Finish: AA-M12C22A41 (Mechanical Finish: nonspecular as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class I, clear coating 0.018 mm or thicker) complying with AAMA 611.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine openings, substrates, structural support, anchorage, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Verify rough opening dimensions, levelness of sill plate, and operational clearances.

C. Examine wall flashings, vapor retarders, water and weather barriers, and other built-in components to ensure weathertight window installation.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Comply with manufacturer's written instructions for installing windows, hardware, accessories, and other components. For installation procedures and requirements not addressed in manufacturer's written instructions, comply with installation requirements in ASTM E2112.

B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction to produce weathertight construction.

C. Install windows and components to drain condensation, water penetrating joints, and moisture migrating within windows to the exterior.

D. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

1. Testing and inspecting agency will interpret tests and state in each report whether tested work complies with or deviates from requirements.

B. Testing Services: Testing and inspecting of installed windows shall take place as follows:

1. Testing Methodology: Testing of windows for air infiltration and water resistance shall be performed according to AAMA 502.
2. Air-Infiltration Testing:

    a. Test Pressure: That required to determine compliance with AAMA/WDMA/CSA 101/I.S.2/A440 performance class indicated.
    b. Allowable Air-Leakage Rate: 1.5 times the applicable AAMA/WDMA/CSA 101/I.S.2/A440 rate for product type and performance class rounded down to one decimal place.

3. Water-Resistance Testing:

    a. Test Pressure: Two-thirds times test pressure required to determine compliance with AAMA/WDMA/CSA 101/I.S.2/A440 performance grade indicated.
    b. Allowable Water Infiltration: No water penetration.

4. Testing Extent: Three windows of each type as selected by Architect and a qualified independent testing and inspecting agency. Windows shall be tested after perimeter sealants have cured.
5. Test Reports: Prepared according to AAMA 502.

C. Windows will be considered defective if they do not pass tests and inspections.

D. Prepare test and inspection reports.

3.4 ADJUSTING, CLEANING, AND PROTECTION

A. Adjust operating sashes and hardware for a tight fit at contact points and weather stripping for smooth operation and weathertight closure.

B. Clean exposed surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.

1. Keep protective films and coverings in place until final cleaning.

C. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

D. Protect window surfaces from contact with contaminating substances resulting from construction operations. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written instructions.

END OF SECTION 085113

SECTION 085619 - PASS WINDOWS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply top this Section.

1.2 DESCRIPTION

A. This section specifies counter-mounted horizontal-sliding glass pass windows.

B. Related Requirements:

1. Section 084113 "Aluminum-Framed Entrances and Storefronts" for coordinating finish among interior aluminum frames.

1.3 ACTION SUBMITTALS

A. Product Data: For each type and size of pass window and accessory. Include the following:

1. Construction details, material descriptions, dimensions of individual components, profiles for slats, and finishes.

B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data. Include plans, elevations, sections, details, and attachments to other work.

C. Samples for Initial Selection: Manufacturer's finish charts showing full range of colors and textures available for units with factory-applied finishes.

D. Samples for Verification: For each type of exposed finish required.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For sliding glass pass windows to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide CRL Satin Anodized Horizontal Sliding Daisy Model Pass-Thru Assembly With D6 Overhead Track and Jambs or comparable product by one of the following:

1. Arcadia, Inc.
2. Creative Industries, Inc.
3. Nissen & Company, Inc.

2.2 COMPONENTS

A. Aluminum Framing: ASTM B 221 (ASTM B 221M), Alloy 6063-T5 or alloy and temper required to suit structural and finish requirements, not less than 0.062 inch (1.6 mm) thick.

B. Glazing Gaskets: ASTM C 509.

2.3 FABRICATION

A. Fabricate sliding glass sash and frames of extruded aluminum with corners mitered.

B. Fabricate sash to receive 1/4 inch (6 mm) thick glass.

C. Fabricate sliding sash of "H" channel molding at bottom edges including concealed nylon rollers at bottom set on track and guides at top set into track.

D. Provide sash with pin tumbler lock and two keys.

E. Provide sash with finger slot on vertical edge.

F. Fabricate frame with channel sash slot, bottom roller track, and top guides.

G. Sash may be factory or field glazed using glazing gaskets.

H. Use concealed screws in assembly.

2.4 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.5 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine wall opening with Installer present, for conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install interior aluminum frames plumb, rigid, properly aligned, and securely fastened in place; comply with manufacturer's written instructions.

B. Set frames accurately in position and plumbed, aligned, and securely anchored to substrates.

1. Secure with screws to opening; ASME B18.6.4.

a. Screw within 4 inches (100 mm) of ends.
b. Space screws not over 24 inches (600 mm) between end screws.

C. Coat aluminum in contact with steel with one coat of MPI No. 18.

3.3 CLEANING

A. Clean exposed frame surfaces promptly after installation, using cleaning methods recommended by frame manufacturer and according to AAMA 609 & 610.

3.4 OPERATION

A. Adjust pass window to roll smoothly and stay in position where stopped.

END OF SECTION 085619

SECTION 087100 - DOOR HARDWARE

PART 1 - GENERAL

1.01 SUMMARY

A. Section includes:

1. Mechanical and electrified door hardware
2. Electronic access control system components

B. Section excludes:

1. Windows
2. Cabinets (casework), including locks in cabinets
3. Signage
4. Toilet accessories
5. Overhead doors

C. Related Sections:

1. Division 01 "General Requirements" sections for Allowances, Alternates, Owner Furnished Contractor Installed, Project Management and Coordination.
2. Division 06 Section "Rough Carpentry"
3. Division 06 Section "Finish Carpentry"
4. Division 07 Section "Joint Sealants" for sealant requirements applicable to threshold installation specified in this section.
5. Division 08 Sections:
   a. "Metal Doors and Frames"
   b. "Flush Wood Doors"
   c. "Stile and Rail Wood Doors"
   d. "Interior Aluminum Doors and Frames"
   e. "Aluminum-Framed Entrances and Storefronts"
   f. "Stainless Steel Doors and Frames"
   g. "Special Function Doors"
   h. "Entrances"
6. Division 26 "Electrical" sections for connections to electrical power system and for low-voltage wiring.
7. Division 28 "Electronic Safety and Security" sections for coordination with other components of electronic access control system and fire alarm system.

1.02 REFERENCES

A. UL LLC

1. UL 10B - Fire Test of Door Assemblies
2. UL 10C - Positive Pressure Test of Fire Door Assemblies
3. UL 1784 - Air Leakage Tests of Door Assemblies
4. UL 305 - Panic Hardware

B. DHI - Door and Hardware Institute

1. Sequence and Format for the Hardware Schedule
2. Recommended Locations for Builders Hardware
3. Keying Systems and Nomenclature
4. Installation Guide for Doors and Hardware

C. NFPA – National Fire Protection Association

1. NFPA 70 – National Electric Code
2. NFPA 80 – Standard for Fire Doors and Other Opening Protectives
3. NFPA 101 – Life Safety Code
4. NFPA 105 – Smoke and Draft Control Door Assemblies
5. NFPA 252 – Fire Tests of Door Assemblies

D. ANSI - American National Standards Institute

1. ANSI A117.1 – 2017 Edition – Accessible and Usable Buildings and Facilities
2. ANSI/BHMA A156.1 - A156.29, and ANSI/BHMA A156.31 - Standards for Hardware and Specialties
3. ANSI/BHMA A156.28 - Recommended Practices for Keying Systems
4. ANSI/WDMA I.S. 1A - Interior Architectural Wood Flush Doors
5. ANSI/SDI A250.8 - Standard Steel Doors and Frames

1.03 SUBMITTALS

A. General:

1. Submit in accordance with Conditions of Contract and Division 01 Submittal Procedures.
2. Prior to forwarding submittal:
   a. Review drawings and Sections from related trades to verify compatibility with specified hardware.
   b. Highlight, encircle, or otherwise specifically identify on submittals: deviations from Contract Documents, issues of incompatibility or other issues which may detrimentally affect the Work.

B. Action Submittals:

1. Product Data: Submit technical product data for each item of door hardware, installation instructions, maintenance of operating parts and finish, and other information necessary to show compliance with requirements.
2. Riser and Wiring Diagrams: After final approval of hardware schedule, submit details of electrified door hardware, indicating:
   a. Wiring Diagrams: For power, signal, and control wiring and including:
      1) Details of interface of electrified door hardware and building safety and security systems.
      2) Schematic diagram of systems that interface with electrified door hardware.
      3) Point-to-point wiring.
      4) Risers.

3. Samples for Verification: If requested by Architect, submit production sample of requested door hardware unit in finish indicated and tagged with full description for coordination with schedule.
   a. Samples will be returned to supplier. Units that are acceptable to Architect may, after final check of operations, be incorporated into Work, within limitations of key coordination requirements.

4. Door Hardware Schedule:
   a. Submit concurrent with submissions of Product Data, Samples, and Shop Drawings. Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate fabrication of other work critical in Project construction schedule.
   b. Submit under direct supervision of a Door Hardware Institute (DHI) certified Architectural Hardware Consultant (AHC) or Door Hardware Consultant (DHC) with hardware sets in vertical format as illustrated by Sequence of Format for the Hardware Schedule published by DHI.
   c. Indicate complete designations of each item required for each opening, include:
      1) Door Index: door number, heading number, and Architect's hardware set number.
      2) Quantity, type, style, function, size, and finish of each hardware item.
      3) Name and manufacturer of each item.
      4) Fastenings and other pertinent information.
      5) Location of each hardware set cross-referenced to indications on Drawings.
      6) Explanation of all abbreviations, symbols, and codes contained in schedule.
      7) Mounting locations for hardware.
      8) Door and frame sizes and materials.
      9) Degree of door swing and handing.
      10) Operational Description of openings with electrified hardware covering egress, ingress (access), and fire/smoke alarm connections.

5. Key Schedule:
   a. After Keying Conference, provide keying schedule that includes levels of keying, explanations of key system's function, key symbols used, and door numbers controlled.
   b. Use ANSI/BHMA A156.28 "Recommended Practices for Keying Systems" as guideline for nomenclature, definitions, and approach for selecting optimal keying system.
   c. Provide 3 copies of keying schedule for review prepared and detailed in accordance with referenced DHI publication. Include schematic keying diagram and index each key to unique door designations.
   d. Index keying schedule by door number, keyset, hardware heading number, cross keying instructions, and special key stamping instructions.
   e. Provide one complete bitting list of key cuts and one key system schematic illustrating system usage and expansion. Forward bitting list, key cuts and key system schematic directly to Owner, by means as directed by Owner.
   f. Prepare key schedule by or under supervision of supplier, detailing Owner's final keying instructions for locks.

C. Informational Submittals:

1. Provide Qualification Data for Supplier, Installer and Architectural Hardware Consultant.
2. Provide Product Data:
   a. Certify that door hardware approved for use on types and sizes of labeled fire-rated doors complies with listed fire-rated door assemblies.
   b. Include warranties for specified door hardware.

D. Closeout Submittals:

1. Operations and Maintenance Data: Provide in accordance with Division 01 and include:
   a. Complete information on care, maintenance, and adjustment; data on repair and replacement parts, and information on preservation of finishes.
   b. Catalog pages for each product.
   c. Final approved hardware schedule edited to reflect conditions as installed.
   d. Final keying schedule
   e. Copy of warranties including appropriate reference numbers for manufacturers to identify project.
   f. As-installed wiring diagrams for each opening connected to power, both low voltage and 110 volts.

E. Inspection and Testing:

1. Submit written reports to the Owner and Authority Having Jurisdiction (AHJ) of the results of functional testing and inspection for:
   a. Fire door assemblies, in compliance with NFPA 80.
   b. Required egress door assemblies, in compliance with NFPA 101.

1.04 QUALITY ASSURANCE

A. Qualifications and Responsibilities:

1. Supplier: Recognized architectural hardware supplier with a minimum of 5 years documented experience supplying both mechanical and electromechanical door hardware similar in quantity, type, and quality to that indicated for this Project. Supplier to be recognized as a factory direct distributor by the manufacturer of the primary materials with a warehousing facility in the Project's vicinity. Supplier to have on staff, a certified Architectural Hardware Consultant (AHC) or Door Hardware Consultant (DHC) available to Owner, Architect, and Contractor, at reasonable times during the Work for consultation.
2. Installer: Qualified tradesperson skilled in the application of commercial grade hardware with experience installing door hardware similar in quantity, type, and quality as indicated for this Project.
3. Architectural Hardware Consultant: Person who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project and meets these requirements:
   a. For door hardware: DHI certified AHC or DHC.
   b. Can provide installation and technical data to Architect and other related subcontractors.
   c. Can inspect and verify components are in working order upon completion of installation.
   d. Capable of producing wiring diagram and coordinating installation of electrified hardware with Architect and electrical engineers.

4. Single Source Responsibility: Obtain each type of door hardware from single manufacturer.

B. Certifications:

1. Fire-Rated Door Openings:
   a. Provide door hardware for fire-rated openings that complies with NFPA 80 and requirements of authorities having jurisdiction.

b. Provide only items of door hardware that are listed products tested by UL LLC, Intertek Testing Services, or other testing and inspecting organizations acceptable to authorities having jurisdiction for use on types and sizes of doors indicated, based on testing at positive pressure and according to NFPA 252 or UL 10C and in compliance with requirements of fire-rated door and door frame labels.

2. Smoke and Draft Control Door Assemblies:
   a. Provide door hardware that meets requirements of assemblies tested according to UL 1784 and installed in compliance with NFPA 105
   b. Comply with the maximum air leakage of 0.3 cfm/sq. ft. (3 cu. m per minute/sq. m) at tested pressure differential of 0.3-inch wg (75 Pa) of water.

3. Electrified Door Hardware
   a. Listed and labeled as defined in NFPA 70, Article 100, by testing agency acceptable to authorities having jurisdiction.

4. Accessibility Requirements:
   a. Comply with governing accessibility regulations cited in "REFERENCES" article 087100, 1.02.D3 herein for door hardware on doors in an accessible route. This project must comply with all Federal Americans with Disability Act regulations and all Local Accessibility Regulations.

C. Pre-Installation Meetings

1. Keying Conference
   a. Incorporate keying conference decisions into final keying schedule after reviewing door hardware keying system including:
      1) Function of building, flow of traffic, purpose of each area, degree of security required, and plans for future expansion.
      2) Preliminary key system schematic diagram.
      3) Requirements for key control system.
      4) Requirements for access control.
      5) Address for delivery of keys.

2. Pre-installation Conference
   a. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
   b. Inspect and discuss preparatory work performed by other trades.
   c. Inspect and discuss electrical roughing-in for electrified door hardware.
   d. Review sequence of operation for each type of electrified door hardware.
   e. Review required testing, inspecting, and certifying procedures.
   f. Review questions or concerns related to proper installation and adjustment of door hardware.

3. Electrified Hardware Coordination Conference:
   a. Prior to ordering electrified hardware, schedule and hold meeting to coordinate door hardware with security, electrical, doors and frames, and other related suppliers.

1.05 DELIVERY, STORAGE, AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up for hardware delivered to Project site. Promptly replace products damaged during shipping

B. Tag each item or package separately with identification coordinated with final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package. Deliver each article of hardware in manufacturer's original packaging.

C. Maintain manufacturer-recommended environmental conditions throughout storage and installation periods.

D. Provide secure lock-up for door hardware delivered to Project. Control handling and installation of hardware items so that completion of Work will not be delayed by hardware losses both before and after installation.

E. Handle hardware in manner to avoid damage, marring, or scratching. Correct, replace or repair products damaged during Work. Protect products against malfunction due to paint, solvent, cleanser, or any chemical agent.

F. Deliver keys to manufacturer of key control system for subsequent delivery to Owner.

1.06 COORDINATION

A. Coordinate layout and installation of floor-recessed door hardware with floor construction. Cast anchoring inserts into concrete.

B. Installation Templates: Distribute for doors, frames, and other work specified to be factory or shop prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.

C. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.

D. Electrical System Roughing-In: Coordinate layout and installation of electrified door hardware with connections to power supplies and building safety and security systems.

1.07 WARRANTY

A. Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within published warranty period.

1. Warranty does not cover damage or faulty operation due to improper installation, improper use or abuse.
2. Warranty Period: Beginning from date of Substantial Completion, for durations indicated in manufacturer's published listings.
    a. Mechanical Warranty
        1) Exit Devices
            a) Von Duprin: 10 years
        2) Closers
            a) LCN 4000 Series: 30 years
    b. Electrical Warranty
        1) Exit Devices
            a) Von Duprin: 3 years

1.08 MAINTENANCE

A. Furnish complete set of special tools required for maintenance and adjustment of hardware, including changing of cylinders.

B. Turn over unused materials to Owner for maintenance purposes.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

A. Approval of alternate manufacturers and/or products other than those listed as ''Scheduled Manufacturer'' or ''Acceptable Manufacturers'' in the individual article for the product category are only to be considered by official substitution request in accordance with section 01 25 00.

B. Approval of products from manufacturers indicated in ''Acceptable Manufacturers'' is contingent upon those products providing all functions and features and meeting all requirements of scheduled manufacturer's product.

C. Where specified hardware is not adaptable to finished shape or size of members requiring hardware, furnish suitable types having same operation and quality as type specified, subject to Architect's approval.

2.02 MATERIALS

A. Fabrication

1. Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. provide screws according to manufacturer’s recognized installation standards for application intended.
2. Finish exposed screws to match hardware finish, or, if exposed in surfaces of other work, to match finish of this other work including prepared for paint surfaces to receive painted finish.
3. Provide concealed fasteners wherever possible for hardware units exposed when door is closed. Coordinate with “Metal Doors and Frames”, “Flush Wood Doors”, “Stile and Rail Wood Doors” to ensure proper reinforcements. Advise the Architect where visible fasteners, such as thru bolts, are required.

B. Provide screws, bolts, expansion shields, drop plates and other devices necessary for hardware installation.

1. Where fasteners are exposed to view: Finish to match adjacent door hardware material.

C. Cable and Connectors:

1. Where scheduled in the hardware sets, provide each item of electrified hardware and wire harnesses with number and gage of wires enough to accommodate electric function of specified hardware.
2. Provide Molex connectors that plug directly into connectors from harnesses, electric locking and power transfer devices.

3. Provide through-door wire harness for each electrified locking device installed in a door and wire harness for each electrified hinge, electrified continuous hinge, electrified pivot, and electric power transfer for connection to power supplies.

2.03 HINGES

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product:
   a. Ives 5BB series

2. Acceptable Manufacturers and Products:
   a. Hager BB1191/1279 series
   b. Best FBB series

B. Requirements:

1. Provide hinges conforming to ANSI/BHMA A156.1.
2. Provide five knuckle, ball bearing hinges.
3. 1-3/4 inch (44 mm) thick doors, up to and including 36 inches (914 mm) wide:
   a. Exterior: Standard weight, bronze or stainless steel, 4-1/2 inches (114 mm) high
   b. Interior: Standard weight, steel, 4-1/2 inches (114 mm) high

4. 1-3/4 inch (44 mm) thick doors over 36 inches (914 mm) wide:
   a. Exterior: Heavy weight, bronze/stainless steel, 5 inches (127 mm) high
   b. Interior: Heavy weight, steel, 5 inches (127 mm) high

5. 2 inches or thicker doors:
   a. Exterior: Heavy weight, bronze or stainless steel, 5 inches (127 mm) high
   b. Interior: Heavy weight, steel, 5 inches (127 mm) high

6. Adjust hinge width for door, frame, and wall conditions to allow proper degree of opening.
7. Provide three hinges per door leaf for doors 90 inches (2286 mm) or less in height, and one additional hinge for each 30 inches (762 mm) of additional door height.
8. Hinge Pins: Except as otherwise indicated, provide hinge pins as follows:
   a. Steel Hinges: Steel pins
   b. Non-Ferrous Hinges: Stainless steel pins
   c. Out-Swinging Exterior Doors: Non-removable pins
   d. Out-Swinging Interior Lockable Doors: Non-removable pins
   e. Interior Non-lockable Doors: Non-rising pins

9. Provide hinges with electrified options as scheduled in the hardware sets. Provide with number and gage of wires enough to accommodate electric function of specified hardware. Locate electric hinge at second hinge from bottom or nearest to electrified locking component. Provide mortar guard for each electrified hinge specified.

2.04 CONTINUOUS HINGES

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Select
   b. Roton

B. Requirements:

1. Provide aluminum geared continuous hinges conforming to ANSI/BHMA A156.26, Grade 1.
2. Provide aluminum geared continuous hinges, where specified in the hardware sets, fabricated from 6063-T6 aluminum.
3. Provide split nylon bearings at each hinge knuckle for quiet, smooth, self-lubricating operation.
4. Provide hinges capable of supporting door weights up to 450 pounds, and successfully tested for 1,500,000 cycles.
5. On fire-rated doors, provide aluminum geared continuous hinges classified for use on rated doors by testing agency acceptable to authority having jurisdiction.
6. Provide aluminum geared continuous hinges with electrified option scheduled in the hardware sets. Provide with number and gage of wires enough to accommodate electric function of specified hardware.
7. Provide hinges 1 inch (25 mm) shorter in length than nominal height of door, unless otherwise noted or door details require shorter length and with symmetrical hole pattern.

2.05 ELECTRIC POWER TRANSFER

A. Manufacturers:

1. Scheduled Manufacturer and Product:
   a. Von Duprin EPT-10

2. Acceptable Manufacturers and Products:
   a. Securitron CEPT-10
   b. Security Door Controls PTM

B. Requirements:

1. Provide power transfer with electrified options as scheduled in the hardware sets. Provide with number and gage of wires enough to accommodate electric function of specified hardware.
2. Locate electric power transfer per manufacturer's template and UL requirements, unless interference with operation of door or other hardware items.

2.06 FLUSH BOLTS

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Rockwood
   b. Hager

B. Requirements:

1. Provide automatic, constant latching, and manual flush bolts with forged bronze or stainless-steel face plates, extruded brass levers, and with wrought brass guides and strikes. Provide 12 inch (305 mm) steel or brass rods at doors up to 90 inches (2286 mm) in height. For doors over 90 inches (2286 mm) in height increase top rods by 6 inches (152 mm) for each additional 6 inches (152 mm) of door height. Provide dust-proof strikes at each bottom flush bolt.

2.07 CYLINDRICAL LOCKS – GRADE 1

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product:
   a. Best 9k series

2. Acceptable Manufacturers and Products:
   a. Schlage ND series
   b. Corbin-Russwin CL3100 series

B. Requirements:

1. Provide cylindrical locks conforming to ANSI/BHMA A156.2 Series 4000, Grade 1, and UL Listed for 3-hour fire doors.
2. Indicators: Where specified, provide escutcheon with lock status indicator window on top of lockset rose:
   a. Escutcheon height (including rose) 6.05 inches high by 3.68 inches wide.
   b. Indicator window measuring a minimum 3.52-inch by .60 inch with 1.92 square-inches of front facing viewing area and 180-degree visibility with a total of .236 square-inches of total viewable area.
   c. Provide snap-in serviceable window to prevent tampering. Lock must function if indicator is compromised.
   d. Provide messages color-coded with full text and symbol, as scheduled, for easy visibility.
   e. Unlocked and Unoccupied message will display on white background, and Locked and Occupied message will display on red background.
3. Cylinders: Refer to "KEYING" article, herein.
4. Provide locks with standard 2-3/4 inches (70 mm) backset, unless noted otherwise, with 1/2-inch latch throw. Provide proper latch throw for UL listing at pairs.
5. Provide locksets with separate anti-rotation thru-bolts, and no exposed screws.
6. Provide independently operating levers with two external return spring cassettes mounted under roses to prevent lever sag.
7. Provide standard ASA strikes unless extended lip strikes are necessary to protect trim.
8. Provide electrified options as scheduled in the hardware sets.
9. Lever Trim: Solid cast levers without plastic inserts and wrought roses on both sides.
   a. Provide levers that return to within 1/2 inch (13 mm) of door face.
   b. Vandlgard: Provide levers with vandal resistant technology for use at heavy traffic or abusive applications.
   c. Lever Design: 16L

2.08 EXIT DEVICES

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product:
   a. Von Duprin 98/35A series

2. Acceptable Manufacturers and Products:
   a. Detex Advantex series
   b. Precision APEX 2000 series

B. Requirements:

1. Provide exit devices tested to ANSI/BHMA A156.3 Grade 1 and UL listed for Panic Exit or Fire Exit Hardware.
2. Cylinders: Refer to "KEYING" article, herein.
3. Provide smooth touchpad type exit devices, fabricated of brass, bronze, stainless steel, or aluminum, plated to standard architectural finishes to match balance of door hardware.
4. Touchpad must extend a minimum of one half of door width. No plastic inserts are allowed in touchpads.
5. Provide exit devices with deadlatching feature for security and for future addition of alarm kits and/or other electrified requirements.
6. Provide exit devices at pool gates with weather resistant components that can withstand harsh conditions of various climates and corrosive cleaners used in outdoor pool environments.
7. Provide flush end caps for exit devices.
8. Install exit devices at height recommended by exit device manufacturer, allowable by governing building codes, and approved by Architect.
9. Provide exit devices with manufacturers' approved strikes.
10. Mount mechanism case flush on face of doors or provide spacers to fill gaps behind devices. Where glass trim or molding projects off face of door, provide glass bead kits.
11. Provide cylinder or hex-key dogging as specified at non fire-rated openings.
12. Removable Mullions: 2 inches (51 mm) x 3 inches (76 mm) steel tube. Where scheduled as keyed removable mullion, provide type that can be removed by use of a keyed cylinder, which is self-locking when re-installed.
13. Provide factory drilled weep holes for exit devices used in full exterior application, highly corrosive areas, and where noted in hardware sets.
14. Provide electrified options as scheduled.
15. Top latch mounting: double- or single-tab mount for steel doors, face mount for aluminum doors eliminating requirement of tabs, and double tab mount for wood doors.
16. Provide exit devices with optional trim designs to match other lever and pull designs used on the project.
17. Special Options:
    a. SI
       1) Provide dogging indicators for visible indication of dogging status.
    b. XP
       1) Rim Exit Devices: provide devices with non-tapered smart latchbolt with 90° latchbolt to strike engagement under stress and Static Load Resistance of 2000 pounds.
    c. QM
       1) Rim Exit Devices: provide devices with damper-controlled re-latching to reduce operational noise. Where lever trim is specified, provide damper controlled lever return.
    d. HH
       1) Provide wind and impact rated hurricane exit devices and mullions certified to comply with Florida Building Code (FBC) TAS 201, 202, 203.

e. HW
   1) Provide wind rated hurricane exit devices and mullions certified to comply with ANSI-ASTM E330.
f. CX
   1) Provide delayed egress devices, where scheduled, that are UL 294 listed, meet National Fire Protection Association (NFPA) and International Building Code (IBC) governing delayed egress, and/or other local and national fire codes acceptable to authority having jurisdiction as required.
      a) Provide non-handed and field sizable device with 3/4 (19mm) throw deadlocking latch bolt. Device incorporates an internal RX switch that detects attempt to exit from applying less than 15lbs to the push pad, which causes this switch to start an irreversible alarm cycle. Key switch in device is capable of arming, disarming, or resetting the device; and indicator lamp determines status of the device.
      b) Provide devices capable of standard 15 second release delay and indefinite release delay as required by code, when tied into fire alarm system will release immediately when an alarm condition exists.
      c) Provide devices with all control inputs – door position input, external inhibit input, fire alarm input; auxiliary locking; nuisance alarm and internal horn; and, remote signaling output self-contained in the device assembly.
g. CVC
   1) Provide cable-actuated concealed vertical latch system in two-point for non-rated or fire rated wood doors up to a 90 minute rating and less bottom latch (LBL) configuration for non-rated or fire rated wood doors up to 20 minute rating. Vertical rods are not permitted.
      a) Cable: Stainless steel with abrasive resistant coating. Conduit and core wire ends snap into latch and center slides without use of tools.
      b) Wood Door Prep: Maximum 1 inch x 1.1875 inch x 3.875 inches top latch pocket and 1 inch x 1.1875 inch x 5 inches bottom latch pocket which does not require the use of a metal wrap or edge for non-rated or fire rated wood doors up to a 45 minute rating.
      c) Latchbolts and Blocking Cams: Manufactured from sintered metal low carbon copper- infiltrated steel, with molybdenum disulfide low friction coating.
      d) Top Latchbolt: Minimum 0.38 inch (10 mm) and greater than 90-degree engagement with strike to prevent door and frame separation under high static load.
      e) Bottom Latchbolt: Minimum of 0.44-inch (11 mm) engagement with strike.
      f) Product Cycle Life: 1,000,000 cycles.
      g) Latch Operation: Top and bottom latch operate independently of each other. Top latch fully engages top strike even when bottom latch is compromised. Separate trigger mechanisms not permitted.
      h) Latch release does not require separate trigger mechanism.
      i) Cable and latching system characteristics:
         i. Installed independently of exit device installation, and capable of functioning on door prior to device and trim installation.
         ii. Connected to exit device at single point in steel and aluminum doors, and two points for top and bottom latches in wood doors.
         iii. Bottom latch height adjusted, from single point for steel and aluminum doors and two points for wood doors, after system is installed and connected to exit device, while door is hanging
         iv. Bottom latch position altered up and down minimum of 2 inches (51 mm) in steel and aluminum doors without additional adjustment. Bottom latch deadlocks in every adjustment position in wood doors.
         v. Top and bottom latches in steel and aluminum doors and top latch in wood doors may be removed while door is hanging.

2.09 ELECTRIC STRIKES

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product:
   a. Von Duprin 6000 Series

2. Acceptable Manufacturers and Products:
   a. Folger Adam 300 Series
   b. HES 1006 Series

B. Requirements:

1. Provide electric strikes designed for use with type of locks shown at each opening.
2. Provide electric strikes UL Listed as burglary resistant that are tested to a minimum endurance test of 1,000,000 cycles.
3. Where required, provide electric strikes UL Listed for fire doors and frames.
4. Provide transformers and rectifiers for each strike as required. Verify voltage with electrical contractor.

2.10 CYLINDERS

A. Manufacturers:

1. Scheduled Manufacturer and Product:
   a. BEST 7-pin

2. Acceptable Manufacturers and Products:

B. Requirements:

1. Provide cylinders/cores to match Owner’s existing key system, compliant with ANSI/BHMA A156.5; latest revision; cylinder face finished to match lockset, manufacturer’s series as indicated. Refer to “KEYING” article, herein.

2.11 KEYING

A. Scheduled System:

1. Existing factory registered system:
   a. Provide cylinders/cores keyed into Owner’s existing factory registered keying system. Comply with guidelines in ANSI/BHMA A156.28, incorporating decisions made at keying conference.

B. Requirements:

1. Construction Keying:
   a. Replaceable Construction Cores.
      1) Provide temporary construction cores replaceable by permanent cores, furnished in accordance with the following requirements.
         a) 3 construction control keys
         b) 12 construction change (day) keys.
      2) Owner or Owner’s Representative will replace temporary construction cores with permanent cores.

2. Permanent Keying:
   a. Provide permanent cylinders/cores keyed by the manufacturer according to the following key system.
      1) Master Keying system as directed by the Owner.
   b. Forward bitting list and keys separately from cylinders, by means as directed by Owner. Failure to comply with forwarding requirements will be cause for replacement of cylinders/cores involved at no additional cost to Owner.
   c. Provide keys with the following features:
      1) Material: Nickel silver; minimum thickness of .107-inch (2.3mm)
      2) Patent Protection: Keys and blanks protected by one or more utility patent(s).
   d. Identification:
      1) Mark permanent cylinders/cores and keys with applicable blind code for identification. Do not provide blind code marks with actual key cuts.
      2) Identification stamping provisions must be approved by the Architect and Owner.
      3) Stamp cylinders/cores and keys with Owner's unique key system facility code as established by the manufacturer; key symbol and embossed or stamped with "DO NOT DUPLICATE" along with the "PATENTED" or patent number to enforce the patent protection.
      4) Failure to comply with stamping requirements will be cause for replacement of keys involved at no additional cost to Owner.
      5) Forward permanent cylinders/cores to Owner, separately from keys, by means as directed by Owner.
   e. Quantity: Furnish in the following quantities.
      1) Permanent Control Keys: 3.
      2) Master Keys: 6.
      3) Change (Day) Keys: 3 per cylinder/core that is keyed differently
      4) Key Blanks: Quantity as determined in the keying meeting.

2.12 KEY CONTROL SYSTEM

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Lund

2. Acceptable Manufacturers:
   a. HPC
   b. Telkee

B. Requirements:

1. Provide key control system, including envelopes, labels, tags with self-locking key clips, receipt forms, 3-way visible card index, temporary markers, permanent markers, and standard metal cabinet, all as recommended by system manufacturer, with capacity for 150% of number of locks required for Project.
   a. Provide complete cross index system set up by hardware supplier, and place keys on markers and hooks in cabinet as determined by final key schedule.
   b. Provide hinged-panel type cabinet for wall mounting.

2.13 DOOR CLOSERS

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product:
   a. LCN 4010/4110/4020 series

2. Acceptable Manufacturers and Products:
   a. Corbin-Russwin DC8000 series
   b. Sargent 281 series

B. Requirements:

1. Provide door closers conforming to ANSI/BHMA A156.4 Grade 1 requirements by BHMA certified independent testing laboratory. Certify surface mounted mechanical closers to meet fifteen million (15,000,000) full load cycles. ISO 9000 certify closers. Stamp units with date of manufacture code.
2. Provide door closers with fully hydraulic, full rack and pinion action with high strength cast iron cylinder, and full complement bearings at shaft.
3. Cylinder Body: 1-1/2-inch (38 mm) diameter with 11/16-inch (17 mm) diameter double heat-treated pinion journal.
4. Hydraulic Fluid: Fireproof, passing requirements of UL10C, and requiring no seasonal closer adjustment for temperatures ranging from 120 degrees F to -30 degrees F.
5. Spring Power: Continuously adjustable over full range of closer sizes, and providing reduced opening force as required by accessibility codes and standards.
6. Hydraulic Regulation: By tamper-proof, non-critical valves, with separate adjustment for latch speed, general speed, and backcheck.
7. Provide closers with solid forged steel main arms and factory assembled heavy-duty forged forearms for parallel arm closers. When closers are parallel arm mounted, provide closers which mount within 6-inch (152 mm) top rail without use of mounting plate so that closer is not visible through vision panel from pull side.
8. Pressure Relief Valve (PRV) Technology: Not permitted.
9. Finish for Closer Cylinders, Arms, Adapter Plates, and Metal Covers: Powder coating finish which has been certified to exceed 100 hours salt spray testing as described in ANSI/BHMA Standard A156.4 and ASTM B117, or has special rust inhibitor (SRI).
10. Provide special templates, drop plates, mounting brackets, or adapters for arms as required for details, overhead stops, and other door hardware items interfering with closer mounting.

2.14 DOOR TRIM

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Hager
   b. Rockwood

B. Requirements:

1. Provide push plates, push bars, pull plates, pulls, and hands-free reversible door pulls with diameter and length as scheduled.

2.15 PROTECTION PLATES

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Hager
   b. Rockwood

B. Requirements:

1. Provide protection plates with a minimum of 0.050 inch (1 mm) thick, beveled four edges as scheduled. Furnish with sheet metal or wood screws, finished to match plates.
2. Sizes plates 2 inches (51 mm) less width of door on single doors, pairs of doors with a mullion, and doors with edge guards. Size plates 1 inch (25 mm) less width of door on pairs without a mullion or edge guards.
3. At fire rated doors, provide protection plates over 16 inches high with UL label.

2.16 OVERHEAD STOPS AND OVERHEAD STOP/HOLDERS

A. Manufacturers:

1. Scheduled Manufacturers:
   a. Glynn-Johnson

2. Acceptable Manufacturers:
   a. Rixson
   b. ABH

B. Requirements:

1. Provide overhead stop at any door where conditions do not allow for a wall stop or floor stop presents tripping hazard.

2.17 DOOR STOPS AND HOLDERS

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Hager
   b. Rockwood

B. Provide door stops at each door leaf:

1. Provide wall stops wherever possible. Provide concave type where lockset has a push button of thumbturn.
2. Where a wall stop cannot be used, provide universal floor stops.
3. Where wall or floor stop cannot be used, provide overhead stop.

4. Provide roller bumper where doors open into each other and overhead stop cannot be used.

2.18 SILENCERS

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Rockwood
   b. Hager

B. Requirements:

1. Provide "push-in" type silencers for hollow metal or wood frames.
2. Provide one silencer per 30 inches (762 mm) of height on each single frame, and two for each pair frame.
3. Omit where gasketing is specified.

2.19 THRESHOLDS, SEALS, DOOR SWEEPS, AUTOMATIC DOOR BOTTOMS, AND GASKETING

A. Scheduled Manufacturer:

1. Zero International

B. Acceptable Manufacturers:

1. National Guard
2. Pemko

C. Seals and Gasketing: Provide continuous gasketing on exterior openings, to the head and jambs, forming a continuous seal between the door and the frame. Provide smoke, light, or sound gasketing on interior doors where indicated.

1. Provide self-tapping fasteners for aluminum extruded gasketing being applied to hollow metal frames.
   a. Provide non-corrosive fasteners for all exterior applications.
   b. Provide security fasteners where indicated.

2. Provide neoprene, EPDM, silicone, or nylon brush inserts as specified in hardware sets. Provide non brush inserts of solid or sponge cell, as specified in hardware sets. Vinyl inserts are not allowed except where specified in hardware sets.

D. Smoke Labeled Gasketing: At all smoke labeled openings, provide smoke listed perimeter gasketing assemblies complying with NFPA 105 listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction for smoke control ratings indicated based on testing according to UL 1784.

E. Fire Listed Gasketing: Assemblies complying with NFPA 80 that are listed by a testing and inspecting agency acceptable to authorities having jurisdiction for fire ratings indicated based on testing according to UL-10C.

1. Where frame-applied intumescent seals are required by the manufacturer, provide gaskets that comply with UL10C Standard for Positive Pressure Fire Tests of Door Assemblies and UBC 7-2, Fire Tests of Door Assemblies.

F. Sound-Rated Gasketing: Provide acoustic gasketing to meet Sound Transmission Class (STC) rating required.

G. Meeting-Stile Gasketing: Provide meeting-stile gasketing that fastens to the meeting stiles forming a continuous seal when doors are closed.

H. Door Sweeps or Shoes: Apply to the bottom of the door to close the gap between the door bottom and finished floor or saddle threshold.

1. Provide solid neoprene, EPDM, silicone, or nylon brush type of seal as specified in hardware sets. Vinyl inserts are not allowed except where specified in hardware sets.

I. Automatic Door Bottoms:

1. Provide closed cell sponge, bulb neoprene. or EPDM type of seal as specified in hardware sets.
2. Door bottom to be mortised, semi mortised, or surface mount as with a minimum thickness as specified in hardware sets.

J. Rain Drips:

1. Provide overhead rain drips for out-swinging hollow metal doors that are not covered against 45 degree blowing rain. Aluminum extrusion to be a minimum of .088 inches thick and extend 2.50 inches from the face of the frame, in anodized finish to match door.
2. Door sweeps or shoes with integral rain drip must meet ADA requirements

K. Thresholds: Provide threshold units not less than 4 inches wide, formed to accommodate change in floor elevation where indicated, and fabricated to accommodate door hardware and fit door frames.

1. Threshold extrusion to be a minimum thickness as specified in hardware sets.

2.20 COAT HOOKS

A. Manufacturers:

1. Scheduled Manufacturer:
   a. Ives

2. Acceptable Manufacturers:
   a. Burns
   b. Rockwood

B. Provide coat hooks as specified.

2.21 FINISHES

A. FINISH: BHMA 626/652 (US26D); EXCEPT:

1. Hinges at Exterior Doors: BHMA 630 (US32D)
2. Aluminum Geared Continuous Hinges: BHMA 628 (US28)
3. Push Plates, Pulls, and Push Bars: BHMA 630 (US32D)
4. Protection Plates: BHMA 630 (US32D)
5. Overhead Stops and Holders: BHMA 630 (US32D)
6. Door Closers: Powder Coat to Match
7. Wall Stops: BHMA 630 (US32D)
8. Latch Protectors: BHMA 630 (US32D)
9. Weatherstripping: Clear Anodized Aluminum
10. Thresholds: Mill Finish Aluminum

PART 3 - EXECUTION

3.01 EXAMINATION

A. Prior to installation of hardware, examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance. Verify doors, frames, and walls have been properly reinforced for hardware installation.

B. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.

C. Submit a list of deficiencies in writing and proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION

A. Mount door hardware units at heights to comply with the following, unless otherwise indicated or required to comply with governing regulations.

1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
2. Custom Steel Doors and Frames: HMMA 831.
3. Interior Architectural Wood Flush Doors: ANSI/WDMA I.S. 1A
4. Installation Guide for Doors and Hardware: DHI TDH-007-20

B. Install door hardware in accordance with NFPA 80, NFPA 101 and provide post-install inspection, testing as specified in section 1.03.E unless otherwise required to comply with governing regulations.

C. Install each hardware item in compliance with manufacturer's instructions and recommendations, using only fasteners provided by manufacturer.

D. Do not install surface mounted items until finishes have been completed on substrate. Protect all installed hardware during painting.

E. Set units level, plumb and true to line and location. Adjust and reinforce attachment substrate as necessary for proper installation and operation.

F. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.

G. Install operating parts so they move freely and smoothly without binding, sticking, or excessive clearance.

H. Hinges: Install types and in quantities indicated in door hardware schedule but not fewer than quantity recommended by manufacturer for application indicated.

I. Lock Cylinders:

1. Install construction cores to secure building and areas during construction period.
2. Replace construction cores with permanent cores as indicated in keying section.
3. Furnish permanent cores to Owner for installation.

J. Wiring: Coordinate with Division 26, ELECTRICAL and Division 28 ELECTRONIC SAFETY AND SECURITY sections for:

1. Conduit, junction boxes and wire pulls.
2. Connections to and from power supplies to electrified hardware.
3. Connections to fire/smoke alarm system and smoke evacuation system.
4. Connection of wire to door position switches and wire runs to central room or area, as directed by Architect.
5. Connections to panel interface modules, controllers, and gateways.
6. Testing and labeling wires with Architect's opening number.

K. Key Control System: Tag keys and place them on markers and hooks in key control system cabinet, as determined by final keying schedule.

L. Continuous Hinges: Re-locate the door and frame fire rating labels where they will remain visible so that the hinge does not cover the label once installed.

M. Door Closers & Auto Operators: Mount closers/operators on room side of corridor doors, inside of exterior doors, and stair side of stairway doors from corridors. Mount closers/operators so they are not visible in corridors, lobbies and other public spaces unless approved by Architect.

N. Overhead Stops/Holders: Mount overhead stops/holders on room side of corridor doors, inside of exterior doors, and stair side of stairway doors.

O. Power Supplies: Locate power supplies as indicated or, if not indicated, above accessible ceilings or in equipment room, or alternate location as directed by Architect.

P. Thresholds:

1. Set thresholds in full bed of sealant complying with requirements specified in Division 07 Section "Joint Sealants."
2. Aluminum thresholds to be cut-in, and scribed around mullions, frame members, and stops. Do not butt to thresholds. Provide a continuous surface across full width of opening from jamb to jamb.
3. Where aluminum panic-type (rabbeted) thresholds with neoprene inserts are specified, undercut doors as required to properly mate with seal in threshold.

Q. Stops: Provide floor stops for doors unless wall or other type stops are indicated in door hardware schedule. Do not mount floor stops where they may impede traffic or present tripping hazard.

R. Perimeter Gasketing:

1. Apply to head and jamb, forming seal between door and frame.
2. Install gasketing in a manner eliminating need to cut any seal to install surface mounted hardware. Install compatible mounting bracket for surface mounted hardware unless minimum 1/4 inch thick solid aluminum seals are provided for mounting of surface applied hardware.

S. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.

T. Door Bottoms and Sweeps: Apply to bottom of door, forming seal with threshold when door is closed.

3.03 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

1. Spring Hinges: Adjust to achieve positive latching when door can close freely from an open position of 30 degrees.
2. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.
3. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.

B. Occupancy Adjustment: Approximately three to six months after date of Substantial Completion, examine and readjust each item of door hardware, including adjusting operating forces, as necessary to ensure function of doors and door hardware.

3.04 CLEANING AND PROTECTION

A. Clean adjacent surfaces soiled by door hardware installation.

B. Clean operating items per manufacturer's instructions to restore proper function and finish.

C. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of Substantial Completion.

3.05 DOOR HARDWARE SCHEDULE

A. The intent of the hardware specification is to specify the hardware for interior and exterior doors, and to establish a type, continuity, and standard of quality. However, it is the door hardware supplier's responsibility to thoroughly review existing conditions, schedules, specifications, drawings, and other Contract Documents to verify the suitability of the hardware specified.

B. Discrepancies, conflicting hardware, and missing items are to be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application.

C. Hardware items are referenced in the following hardware schedule. Refer to the above specifications for special features, options, cylinders/keying, and other requirements.

D. Hardware Sets:

3.06 HAEDWARE SCHEDULE

Legend:

Link to catalog cut sheet
Electrified Opening

Hardware Group No. 01

For use on Door #(s):
101 101A 102

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
2	EA	CONT. HINGE	112HD EPT			628	IVE
2	EA	POWER TRANSFER	EPT10			689	VON
1	EA	REMOVABLE MULLION	4954			689	VON
1	EA	ELEC PANIC HARDWARE	RX-LC-QEL-98-EO 24 VDC			626	VON
1	EA	ELEC PANIC HARDWARE	RX-LC-QEL-98-NL-OP-110MD 24 VDC			626	VON
1	EA	CYLINDER	AS REQUIRED			626	BES
1	EA	CYLINDER	AS REQUIRED			626	BES
2	EA	SFIC CORE	AS REQUIRED			626	BES
2	EA	90 DEG OFFSET PULL	8190EZHD 10" O			630-316	IVE
2	EA	SURFACE CLOSER	4111 SCUSH MC			689	LCN
2	EA	DOOR CONTACT	BY SECURITY CONTRACTOR				
1	EA	THRESHOLD	65A-223			A	ZER
1	EA	POWER SUPPLY	BY SECURITY CONTRACTOR			LGR	SCE
			WEATHERSTRIP BY DOOR/FRAME MANUFACTURER				

COORDINATE WITH ELECTRICAL AND SECURITY SYSTEMS.

DOORS CAN BE ELECTRONICALLY LOCKED BY SIGNAL FROM SECURITY SYSTEM.

KEY SWITCH USED TO TURN ON AND TURN OFF AUTOMATIC DOOR OPERATOR AND ACTUATORS FOR OPERATOR. ACTUATORS WILL ONLY OPEN DOORS WHEN DOORS ARE UNLOCKED.

FREE EGRESS ALWAYS ALLOWED.

Hardware Group No. 02

For use on Door #(s):
103 105 114 117

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5			652	IVE
1	EA	OFFICE LOCK	9K7 AB 16L			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	WALL STOP	WS406/407CCV			626	IVE
3	EA	SILENCER	SR64			GRY	IVE

Hardware Group No. 03

For use on Door #(s):
104 113

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
1	EA	CONT. HINGE	112HD EPT			628	IVE
1	EA	POWER TRANSFER	EPT10			689	VON
1	EA	ELEC PANIC HARDWARE	RX-LC-QEL-98-NL-OP-110MD 24 VDC			626	VON
1	EA	CYLINDER	AS REQUIRED			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	90 DEG OFFSET PULL	8190EZHD 10" O			630-316	IVE
1	EA	SURFACE CLOSER	4111 SCUSH MC			689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS			630	IVE
1	EA	DOOR CONTACT	BY SECURITY CONTRACTOR				
1	EA	PERIMETER GASKETING	BY ALUMINUM DOOR MANUFACTURER				
1	EA	THRESHOLD	65A-223			A	ZER
1	EA	POWER SUPPLY	BY SECURITY CONTRACTOR CARD READER - WORK OF DIVISION 28			LGR	SCE

COORDINATE WITH ELECTRICAL AND SECURITY SYSTEMS.

DOOR NORMALLY CLOSED AND LOCKED. ACCESS BY VALID CARD READ, WHICH SHUNTS DOOR POSITION SWITCH AND ALLOWS DOOR TO BE OPENED.

FREE EGRESS ALWAYS ALLOWED.

Hardware Group No. 04

For use on Door #(s):

104A	106	120	121	121A	122
124	126A				

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5			652	IVE
1	EA	CLASSROOM LOCK	9K7 R 16L			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	WALL STOP	WS406/407CCV			626	IVE
3	EA	SILENCER	SR64			GRY	IVE

Hardware Group No. 05

For use on Door #(s):

106A

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5			652	IVE
1	EA	STOREROOM LOCK	9K7 D 16L			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	ELECTRIC STRIKE	6211 FS 12/16/24/28 VAC/VDC			630	VON
1	EA	SURFACE CLOSER	4111 EDA MC			689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS			630	IVE
1	EA	DOOR CONTACT	BY SECURITY CONTRACTOR				
1	EA	WALL STOP	WS406/407CCV			626	IVE
3	EA	SILENCER	SR64			GRY	IVE
1	EA	POWER SUPPLY	BY SECURITY CONTRACTOR CARD READER - WORK OF DIVISION 28			LGR	SCE

COORDINATE WITH ELECTRICAL AND SECURITY SYSTEMS.

DOOR NORMALLY CLOSED AND LOCKED. WHEN VALID CREDENTIAL IS PRESENTED TO CARD READER, LEVER ON LOCK WILL BECOME ACTIVE ALLOWING ENTRY.

FREE EGRESS ALWAYS ALLOWED.

Hardware Group No. 06

For use on Door #(s):
107 109

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1HW 4.5 X 4.5		652	IVE
1	EA	PUSH PLATE	8200 6" X 16"		630	IVE
1	EA	PULL PLATE	8303 10" 4" X 16"		630	IVE
1	EA	SURFACE CLOSER	4111 EDA MC		689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS		630	IVE
1	EA	WALL STOP	WS406/407CCV		626	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 07

For use on Door #(s):
110

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	PRIVACY LOCK	9K0 L 16L		626	BES
1	EA	MOP PLATE	8400 4" X 1" LDW B-CS		630	IVE
1	EA	WALL STOP	WS406/407CCV		626	IVE
1	SET	GASKETING	429AA-S		AA	ZER
1	EA	DOOR BOTTOM	365AA		AA	ZER
1	EA	COAT AND HAT HOOK	582		626	IVE

Hardware Group No. 08

For use on Door #(s):
111

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	OFFICE LOCK	9K7 AB 16L		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	OH STOP	90S		630	GLY
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 09

For use on Door #(s):
112

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	PASSAGE SET	9KO N 16L		626	BES
1	EA	WALL STOP	WS406/407CCV		626	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 10

For use on Door #(s):
115

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	STOREROOM LOCK	9K7 D 16L		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	WALL STOP	WS406/407CCV		626	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 11

For use on Door #(s):
116

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	STOREROOM LOCK	9K7 D 16L		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SURFACE CLOSER	4011 MC		689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS		630	IVE
1	EA	WALL STOP	WS406/407CCV		626	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 12

For use on Door #(s):

118	123.AG	201

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5 NRP		652	IVE
1	EA	STOREROOM LOCK	9K7 D 16L		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SURFACE CLOSER	4111 SCUSH MC		689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS		630	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 13

For use on Door #(s):

119	W101	W101A

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
1	EA	CONT. HINGE	112HD		628	IVE
1	EA	STOREROOM LOCK	9K7 D 16L		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SURFACE CLOSER	4111 SHCUSH MC		689	LCN
1	EA	RAIN DRIP	142AA		AA	ZER
1	SET	GASKETING	429AA-S		AA	ZER
1	EA	DOOR SWEEP	39A		A	ZER
1	EA	THRESHOLD	65A-223		A	ZER

Hardware Group No. 14

For use on Door #(s):

120.1	123.1	123.2	123.3	123.4	123.5
123.6	123.7	123.8	123.9	124.1	127.1
W101.1	W101.2				

Provide each RU door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ALL HARDWARE	BY ROLL-UP DOOR MANUFACTURER		

Hardware Group No. 15

For use on Door #(s):
123

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
1	EA	CONT. HINGE	112HD		628	IVE
1	EA	PANIC HARDWARE	98-NL		626	VON
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SURFACE CLOSER	4111 SCUSH MC		689	LCN
1	EA	RAIN DRIP	142AA		AA	ZER
1	SET	GASKETING	429AA-S		AA	ZER
1	EA	DOOR SWEEP	39A		A	ZER
1	EA	THRESHOLD	65A-223		A	ZER

Hardware Group No. 16

For use on Door #(s):
123A

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5		652	IVE
1	EA	PANIC HARDWARE	98-L-07		626	VON
1	EA	CYLINDER	AS REQUIRED		626	BES
1	EA	SFIC CORE	AS REQUIRED		626	BES
1	EA	SURFACE CLOSER	4111 EDA MC		689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS		630	IVE
1	EA	WALL STOP	WS406/407CCV		626	IVE
3	EA	SILENCER	SR64		GRY	IVE

Hardware Group No. 17

For use on Door #(s):
125

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
1	EA	CONT. HINGE	112HD EPT			628	IVE
1	EA	POWER TRANSFER	EPT10			689	VON
1	EA	ELEC PANIC HARDWARE	RX-LC-QEL-98-NL 24 VDC			626	VON
1	EA	CYLINDER	AS REQUIRED			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	SURFACE CLOSER	4111 SCUSH MC			689	LCN
1	EA	KICK PLATE	8400 8" X 2" LDW B-CS			630	IVE
1	EA	DOOR CONTACT	BY SECURITY CONTRACTOR				
1	EA	RAIN DRIP	142AA			AA	ZER
1	SET	GASKETING	429AA-S			AA	ZER
1	EA	DOOR SWEEP	39A			A	ZER
1	EA	THRESHOLD	65A-223			A	ZER
1	EA	POWER SUPPLY	BY SECURITY CONTRACTOR CARD READER - WORK OF DIVISION 28			LGR	SCE

COORDINATE WITH ELECTRICAL AND SECURITY SYSTEMS.

DOOR NORMALLY CLOSED AND LOCKED. ACCESS BY VALID CARD READ, WHICH SHUNTS DOOR POSITION SWITCH AND ALLOWS DOOR TO BE OPENED.

FREE EGRESS ALWAYS ALLOWED.

Hardware Group No. 18

For use on Door #(s):
126

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
1	EA	CONT. HINGE	112HD			628	IVE
1	EA	CONT. HINGE	112HD EPT			628	IVE
1	EA	POWER TRANSFER	EPT10		✓	689	VON
1	EA	MANUAL FLUSH BOLT	FB458			626	IVE
1	EA	DUST PROOF STRIKE	DP2			626	IVE
1	EA	STOREROOM LOCK	9K7 D 16L			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
1	EA	ELECTRIC STRIKE	6221 FS 12/16/24/28 VAC/VDC		✓	630	VON
2	EA	SURFACE CLOSER	4111 SHCUSH MC			689	LCN
2	EA	KICK PLATE	8400 8" X 1" LDW B-CS			630	IVE
1	EA	DOOR CONTACT	BY SECURITY CONTRACTOR		✓		
1	EA	RAIN DRIP	142AA			AA	ZER
1	SET	GASKETING	429AA-S			AA	ZER
1	EA	MEETING STILE	8042SBK PSA			BK	ZER
2	EA	DOOR SWEEP	39A			A	ZER
1	EA	THRESHOLD	65A-223			A	ZER
1	EA	POWER SUPPLY	BY SECURITY CONTRACTOR CARD READER - WORK OF DIVISION 28		✓	LGR	SCE

COORDINATE WITH ELECTRICAL AND SECURITY SYSTEMS.

DOORS NORMALLY CLOSED AND LOCKED. WHEN VALID CREDENTIAL IS PRESENTED TO CARD READER, LEVER ON LOCK WILL BECOME ACTIVE ALLOWING ENTRY.

FREE EGRESS ALWAYS ALLOWED.

Hardware Group No. 19

For use on Door #(s):
127

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER			FINISH	MFR
6	EA	HINGE	5BB1 4.5 X 4.5 NRP			652	IVE
2	EA	MANUAL FLUSH BOLT	FB458			626	IVE
1	EA	DUST PROOF STRIKE	DP2			626	IVE
1	EA	CLASSROOM LOCK	9K7 R 16L			626	BES
1	EA	SFIC CORE	AS REQUIRED			626	BES
2	EA	OH STOP	90S			630	GLY
2	EA	KICK PLATE	8400 8" X 1" LDW B-CS			630	IVE
2	EA	SILENCER	SR64			GRY	IVE

END OF SECTION 087100

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Glass products.
2. Insulating glass.
3. Glazing sealants.
4. Glazing tapes.
5. Miscellaneous glazing materials.

1.3 DEFINITIONS

A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

B. Glass Thicknesses: Indicated by thickness designations in millimeters in accordance with ASTM C1036.

C. IBC: International Building Code.

D. Interspace: Space between lites of an insulating-glass unit.

1.4 COORDINATION

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Product Certificates: For glass.

C. Product Test Reports: For fabricated glass and glazing sealants, for tests performed by a qualified testing agency.

1. For glazing sealants, provide test reports based on testing current sealant formulations within previous 36-month period.

D. Sample Warranties: For special warranties.

1.7 QUALITY ASSURANCE

A. Fabricated-Glass Manufacturer Qualifications: A qualified manufacturer of fabricated glass units who is approved and certified by primary glass manufacturer.

B. Installer Qualifications: A qualified glazing contractor for this Project who is certified under the North American Contractor Certification Program (NACC) for Architectural Glass & Metal (AG&M) contractors and who employs glazing technicians certified under the Architectural Glass and Metal Technician (AGMT) certification program.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials in accordance with manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

B. Comply with insulating-glass manufacturer's written instructions for venting and sealing units to avoid hermetic seal ruptures due to altitude change.

1.9 FIELD CONDITIONS

A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below 40 deg F (4.4 deg C).

1.10 WARRANTY

A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or

to maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.

1. Warranty Period: 10 years from date of Substantial Completion.

B. Manufacturer's Special Warranty for Insulating Glass: Manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is obstruction of vision by dust, moisture, or film on interior surfaces of glass.

1. Warranty Period: 10 years from date of Substantial Completion.

C. Manufacturer's Special Warranty for Heat-Soaked Tempered Glass: Manufacturer agrees to replace heat-soaked tempered glass units that spontaneously break due to nickel sulfide (NiS) inclusions at a rate exceeding 0.3 percent (3/1000) within specified warranty period. Coverage for any other cause is excluded.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations for Glass: Obtain coated glass from single source from single manufacturer.

B. Source Limitations for Glazing Accessories: For each product and installation method, obtain from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.

B. Structural Performance: Glazing shall withstand the following design loads within limits and under conditions indicated determined in accordance with the IBC and ASTM E1300:

1. Design Wind Pressures: As indicated on Drawings.

a. Wind Design Data: As indicated on Drawings.

2. Maximum Lateral Deflection: For glass supported on all four edges, limit center-of-glass deflection at design wind pressure to not more than 1/50 times the short-side length or 1 inch (25 mm), whichever is less.

C. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

D. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:

1. For monolithic-glass lites, properties are based on units with lites of thickness indicated.
2. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.
3. U-Factors: Center-of-glazing values, in accordance with NFRC 100 and based on LBL's WINDOW 7 computer program, expressed as Btu/sq. ft. x h x deg F (W/sq. m x K).
4. SHGC and Visible Transmittance: Center-of-glazing values, in accordance with NFRC 200 and based on LBL's WINDOW 7 computer program.
5. Visible Reflectance: Center-of-glazing values, in accordance with NFRC 300.

2.3 GLASS PRODUCTS, GENERAL

A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. NGA Publications: "Glazing Manual."
2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."

B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.

C. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of the IGCC.

D. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than thickness indicated.

E. Strength: Where annealed float glass is indicated, provide annealed float glass, heat-strengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heat-strengthened float glass or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

2.4 GLASS PRODUCTS

A. Clear Annealed Float Glass: ASTM C1036, Type I, Class 1 (clear), Quality-Q3.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Cardinal Glass Industries.
    b. Guardian Glass, LLC.
    c. Oldcastle Building Envelope.
    d. Viracon.
    e. Vitro Architectural Glass.

B. Fully Tempered Float Glass: ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.

2.5 INSULATING GLASS

A. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified in accordance with ASTM E2190.

1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.
2. Perimeter Spacer: Manufacturer's standard spacer material and construction.
3. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Cardinal Glass Industries.
    b. Guardian Glass, LLC.
    c. Oldcastle Building Envelope.
    d. Viracon.
    e. Vitro Architectural Glass.

4. Desiccant: Molecular sieve or silica gel, or a blend of both.

2.6 GLAZING SEALANTS

A. General:

1. Compatibility: Compatible with one another and with other materials they contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.

3. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range of industry colors.

B. Neutral-Curing Silicone Glazing Sealant, Class 50: Complying with ASTM C920, Type S, Grade NS, Use NT.

2.7 GLAZING TAPES

A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281 and AAMA 800 for products indicated below:

1. AAMA 804.3 tape, where indicated.
2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

1. AAMA 810.1, Type 1, for glazing applications in which tape acts as primary sealant.
2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.8 MISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, recommended in writing by manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

C. Setting Blocks:

1. Type recommended in writing by sealant or glass manufacturer.

D. Spacers:

1. Type recommended in writing by sealant or glass manufacturer.

E. Edge Blocks:

1. Type recommended in writing by sealant or glass manufacturer.

F. Cylindrical Glazing Sealant Backing: ASTM C1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

2.9 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.

a. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:

1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
2. Presence and functioning of weep systems.
3. Minimum required face and edge clearances.
4. Effective sealing between joints of glass-framing members.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

3.3 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.

C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

F. Provide spacers for glass lites where length plus width is larger than 50 inches (1270 mm).

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
2. Provide 1/8-inch- (3-mm-) minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and in accordance with requirements in referenced glazing publications.

H. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

I. Set glass lites with proper orientation so that coatings face exterior or interior as specified.

J. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.

K. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended in writing by gasket manufacturer.

3.4 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first, then to jambs. Cover horizontal framing joints by applying tapes to jambs, then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Do not remove release paper from tape until right before each glazing unit is installed.

F. Center glass lites in openings on setting blocks, and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

G. Apply cap bead of elastomeric sealant over exposed edge of tape.

3.5 GASKET GLAZING (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.

C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

E. Install gaskets so they protrude past face of glazing stops.

3.6 SEALANT GLAZING (WET)

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.7 CLEANING AND PROTECTION

A. Immediately after installation, remove nonpermanent labels and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.

1. If, despite such protection, contaminating substances do contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.

C. Remove and replace glass that is damaged during construction period.

3.8 MONOLITHIC GLASS SCHEDULE

A. Clear Glass Type MG-1: Annealed float glass.

1. Minimum Thickness: 6 mm.

B. Clear Glass Type MG-2: Fully tempered float glass.

1. Minimum Thickness: 6 mm.
2. Safety glazing required.

3.9 INSULATING GLASS SCHEDULE

A. Low-E-Coated, Clear Insulating Glass Type IG-1:

1. Basis-of-Design Product: Guardian Glass, LLC; SunGuard SNR 43 on Clear.
2. Overall Unit Thickness: 1 inch (25 mm).
3. Minimum Thickness of Each Glass Lite: 6 mm.
4. Outdoor Lite: Fully tempered float glass.
5. Interspace Content: Air.
6. Indoor Lite: Fully tempered float glass.
7. Low-E Coating: Sputtered on second surface.
8. Winter Nighttime U-Factor: 0.29 maximum.
9. Summer Daytime U-Factor: 0.27 maximum.
10. Visible Light Transmittance: 43 percent minimum.
11. SGHC: 0.23 maximum.
12. Safety glazing required.

END OF SECTION 088000

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior partitions.
2. Suspension systems for interior ceilings and soffits.
3. Grid suspension systems for gypsum board ceilings.

B. Related Requirements:

1. Section 054000 "Cold-Formed Metal Framing" for exterior and interior load-bearing and exterior non-load-bearing wall studs; floor joists; and roof rafters and ceiling joists.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

A. Product Certificates: For each type of code-compliance certification for studs and tracks.

1.5 QUALITY ASSURANCE

A. Code-Compliance Certification of Studs and Tracks: Provide documentation that framing members are certified according to the product-certification program of the Certified Steel Stud Association, the Steel Framing Industry Association, or the Steel Stud Manufacturers Association.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, according to ASTM E90 and classified according to ASTM E413 by an independent testing agency.

B. Horizontal Deflection: For composite wall assemblies, limited to 1/360 of the wall height based on horizontal loading of 10 lbf/sq. ft. (480 Pa).

2.2 FRAMING SYSTEMS

A. Framing Members, General: Comply with ASTM C754 for conditions indicated.

1. Steel Sheet Components: Comply with ASTM C645 requirements for steel unless otherwise indicated.
2. Protective Coating: ASTM A653/A653M, G40 (Z120), hot-dip galvanized unless otherwise indicated.

B. Studs and Tracks: ASTM C645.

1. Steel Studs and Tracks:

a. Minimum Base-Steel Thickness: As required by performance requirements for horizontal deflection.
b. Depth: As indicated on Drawings.

C. Slip-Type Head Joints: Where indicated, provide one of the following:

1. Single Long-Leg Track System: ASTM C645 top track with 2-inch- (51-mm-) deep flanges in thickness not less than indicated for studs, installed with studs friction fit into top track and with continuous bridging located within 12 inches (305 mm) of the top of studs to provide lateral bracing.
2. Double-Track System: ASTM C645 top outer tracks, inside track with 2-inch- (51-mm-) deep flanges in thickness not less than indicated for studs and fastened to studs, and outer track sized to friction-fit over inner track.
3. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.

a. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:

1) Steel Network, Inc. (The); VertiTrack VTD Series.
2) Superior Metal Trim; Superior Flex Track System (SFT).

D. Cold-Rolled Channel Bridging: Steel, 0.0538-inch (1.367-mm) minimum base-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges.

1. Depth: 1-1/2 inches (38 mm).
2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches (38 by 38 mm), 0.068-inch- (1.72-mm-) thick, galvanized steel.

E. Hat-Shaped, Rigid Furring Channels: ASTM C645.

1. Minimum Base-Steel Thickness: 0.0179 inch (0.455 mm).
2. Depth: 7/8 inch (22.2 mm).

F. Resilient Furring Channels: 1/2-inch- (13-mm-) deep, steel sheet members designed to reduce sound transmission.

1. Configuration: Asymmetrical or hat shaped.

G. Cold-Rolled Furring Channels: 0.053-inch (1.34-mm) uncoated-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges.

1. Depth: 3/4 inch (19 mm).
2. Furring Brackets: Adjustable, corrugated-edge-type steel sheet with minimum uncoated-steel thickness of 0.0329 inch (0.8 mm).
3. Tie Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.

2.3 SUSPENSION SYSTEMS

A. Tie Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.

B. Wire Hangers: ASTM A641/A641M, Class 1 zinc coating, soft temper, 0.16 inch (4.12 mm) in diameter.

C. Carrying Channels (Main Runners): Cold-rolled, commercial-steel sheet with a base-steel thickness of 0.0538 inch (1.367 mm) and minimum 1/2-inch- (13-mm-) wide flanges.

1. Depth: As indicated on Drawings.

D. Furring Channels (Furring Members):

1. Cold-Rolled Channels: 0.0538-inch (1.367-mm) uncoated-steel thickness, with minimum 1/2-inch- (13-mm-) wide flanges, 3/4 inch (19 mm) deep
2. Steel Studs and Tracks: ASTM C645.

a. Minimum Base-Steel Thickness: 0.0329 inch (0.836 mm).
b. Depth: As indicated on Drawings.

3. Hat-Shaped, Rigid Furring Channels: ASTM C645, 7/8 inch (22 mm) deep.

    a. Minimum Base-Steel Thickness: 0.0179 inch (0.455 mm).

4. Resilient Furring Channels: 1/2-inch- (13-mm-) deep members designed to reduce sound transmission.

    a. Configuration: Asymmetrical or hat shaped.

E. Grid Suspension System for Gypsum Board Ceilings: ASTM C645, direct-hung system composed of main beams and cross-furring members that interlock.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:

    a. Armstrong World Industries, Inc.; Drywall Grid System.
    b. Chicago Metallic Corporation; 660-C Drywall Furring System.
    c. USG Corporation; Drywall Suspension System.

2.4 AUXILIARY MATERIALS

A. General: Provide auxiliary materials that comply with referenced installation standards.

1. Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

B. Isolation Strip at Exterior Walls: Provide one of the following:

1. Asphalt-Saturated Organic Felt: ASTM D226/D226M, Type I (No. 15 asphalt felt), nonperforated.
2. Foam Gasket: Adhesive-backed, closed-cell vinyl foam strips that allow fastener penetration without foam displacement, 1/8 inch (3.2 mm) thick, in width to suit steel stud size.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure to ensure that inserts and other provisions for anchorages to building

structure have been installed to receive hangers at spacing required to support the Work and that hangers will develop their full strength.

1. Furnish concrete inserts and other devices indicated to other trades for installation in advance of time needed for coordination and construction.

3.3 INSTALLATION, GENERAL

A. Installation Standard: ASTM C754.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C840 that apply to framing installation.

B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.

C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.

D. Install bracing at terminations in assemblies.

E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.4 INSTALLING FRAMED ASSEMBLIES

A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.

1. Single-Layer Application: 16 inches (406 mm) o.c. unless otherwise indicated.
2. Multilayer Application: 16 inches (406 mm) o.c. unless otherwise indicated.
3. Tile Backing Panels: 16 inches (406 mm) o.c. unless otherwise indicated.

B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.

C. Install studs so flanges within framing system point in same direction.

D. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.

1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install track section (for cripple studs) at head and secure to jamb studs.

    a. Install two studs at each jamb unless otherwise indicated.

b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch (13-mm) clearance from jamb stud to allow for installation of control joint in finished assembly.
c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.

3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
4. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.

E. Direct Furring:

1. Screw to wood framing.
2. Attach to concrete or masonry with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches (610 mm) o.c.

F. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch (3 mm) from the plane formed by faces of adjacent framing.

3.5 INSTALLING CEILING SUSPENSION SYSTEMS

A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.

1. Hangers: 48 inches (1219 mm) o.c.
2. Carrying Channels (Main Runners): 48 inches (1219 mm) o.c.
3. Furring Channels (Furring Members): 16 inches (406 mm) o.c.

B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.

C. Suspend hangers from building structure as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.

a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.

2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.

a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards.

3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
4. Flat Hangers: Secure to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices and fasteners that are secure and appropriate for structure and hanger, and in a manner that will not cause hangers to deteriorate or otherwise fail.
5. Do not attach hangers to steel roof deck.
6. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
7. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
8. Do not connect or suspend steel framing from ducts, pipes, or conduit.

D. Grid Suspension Systems: Attach perimeter wall track or angle where grid suspension systems meet vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track.

E. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet (3 mm in 3.6 m) measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION 092216

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Tile backing panels.

B. Related Requirements:

1. Section 061600 "Sheathing" for gypsum sheathing for exterior walls.
2. Section 079219 "Acoustical Joint Sealants" for acoustical joint sealants installed in gypsum board assemblies.
3. Section 092216 "Non-Structural Metal Framing" for non-structural steel framing and suspension systems that support gypsum board panels.

1.3 ACTION SUBMITTALS

A. Product Data: For the following:

1. Gypsum wallboard.
2. Gypsum ceiling board.
3. Abuse-resistant gypsum board.
4. Mold-resistant gypsum board.
5. Gypsum board, Type C.
6. Glass-mat interior gypsum board.
7. Glass-mat, water-resistant backing board.
8. Interior trim.
9. Aluminum trim.
10. Joint treatment materials.
11. Sound-attenuation blankets.
12. Acoustical sealant.

B. Samples: For the following products:

1. Trim Accessories: Full-size Sample in 12-inch- (300-mm-) long length for each trim accessory indicated.

1.4 DELIVERY, STORAGE AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Comply with ASTM C840 requirements or gypsum board manufacturer's written instructions, whichever are more stringent.

B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.

C. Do not install panels that are wet, moisture damaged, and mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E90 and classified according to ASTM E413 by an independent testing agency.

2.2 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.3 INTERIOR GYPSUM BOARD

A. General: Complying with ASTM C 36/C 36M or ASTM C 1396/C 1396M, as applicable to type of gypsum board indicated and whichever is more stringent.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. American Gypsum Company.
b. CertainTeed Corporation.
c. Georgia-Pacific Gypsum, LLC.
d. National Gypsum Company.
e. PABCO Gypsum.
f. USG Corporation.

B. Regular Type:

1. Thickness: 5/8 inch (15.9 mm).
2. Long Edges: Tapered and featured (rounded or beveled) for prefilling.

C. Abuse-Resistant Gypsum Board: ASTM C 1629/C 1629M, Level 1.

1. Core: 5/8 inch (15.9 mm), Type X.
2. Long Edges: Tapered.
3. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

D. Ceiling Type: Manufactured to have more sag resistance than regular-type gypsum board.

1. Thickness: 1/2 inch (12.7 mm).
2. Long Edges: Tapered.

2.4 TILE BACKING PANELS

A. Glass-Mat, Water-Resistant Backing Board:

1. Complying with ASTM C 1178/C 1178M.

a. Product: Subject to compliance with requirements, provide Georgia-Pacific Gypsum, LLC; DensShield Tile Guard.

2.5 TRIM ACCESSORIES

A. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.
2. Shapes:

a. Cornerbead.
b. Bullnose bead.
c. L-Bead: L-shaped; exposed long flange receives joint compound.
d. U-Bead: J-shaped; exposed short flange does not receive joint compound.
e. Expansion (control) joint.
f. Curved-Edge Cornerbead: With notched or flexible flanges.

B. Aluminum Trim: Extruded accessories of profiles and dimensions indicated.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Fry Reglet Corp.
b. Gordon, Inc.
c. Pittcon Industries.

2. Aluminum: Alloy and temper with not less than the strength and durability properties of ASTM B 221 (ASTM B 221M), Alloy 6063-T5.
3. Finish**:** Corrosion-resistant primer compatible with joint compound and finish materials specified.

2.6 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:

1. Interior Gypsum Wallboard: Paper.
2. Glass-Mat Gypsum Sheathing Board: 10-by-10 glass mesh.
3. Tile Backing Panels: As recommended by panel manufacturer.

C. Joint Compound for Interior Gypsum Wallboard: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.

1. Prefilling: At open joints**,** rounded or beveled panel edges, and damaged surface areas, use setting-type taping compound.
2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.

    a. Use setting-type compound for installing paper-faced metal trim accessories.

3. Fill Coat: For second coat, use setting-type, sandable topping compound.
4. Finish Coat: For third coat, use setting-type, sandable topping compound.
5. Skim Coat: For final coat of Level 5 finish, use high-build interior coating product designed for application by airless sprayer and to be used instead of skim coat to produce Level 5 finish.

D. Joint Compound for Tile Backing Panels:

1. Glass-Mat, Water-Resistant Backing Panel: As recommended by backing panel manufacturer.
2. Water-Resistant Gypsum Backing Board: Use setting-type taping compound and setting-type, sandable topping compound.

2.7 AUXILIARY MATERIALS

A. Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.

B. Steel Drill Screws: ASTM C1002 unless otherwise indicated.

1. Use screws complying with ASTM C954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.

C. Sound-Attenuation Blankets: ASTM C665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

D. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

E. Thermal Insulation: As specified in Section 072100 "Thermal Insulation."

F. Vapor Retarder: As specified in Section 072600 "Vapor Retarders."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates including welded hollow-metal frames and support framing, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION AND FINISHING OF PANELS, GENERAL

A. Comply with ASTM C840.

B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.

C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch (1.5 mm) of open space between panels. Do not force into place.

D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.

E. Form control and expansion joints with space between edges of adjoining gypsum panels.

F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.

1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. (0.7 sq. m) in area.
2. Fit gypsum panels around ducts, pipes, and conduits.

3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch- (6.4- to 9.5-mm-) wide joints to install sealant.

G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.

I. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C919 and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.

J. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

3.3 INSTALLATION OF INTERIOR GYPSUM BOARD

A. Install interior gypsum board in the following locations:

1. Wallboard Type: Vertical surfaces unless otherwise indicated.
2. Ceiling Type: Ceiling surfaces.
3. Abuse-Resistant Type: As indicated on Drawings.
4. Mold-Resistant Type: As indicated on Drawings.
5. Glass-Mat Interior Type: As indicated on Drawings.

B. Single-Layer Application:

1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
2. On partitions/walls, apply gypsum panels horizontally (perpendicular to framing) unless otherwise indicated or required by fire-resistance-rated assembly, and minimize end joints.

    a. Stagger abutting end joints not less than one framing member in alternate courses of panels.

3. On Z-shaped furring members, apply gypsum panels vertically (parallel to framing) with no end joints. Locate edge joints over furring members.
4. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

C. Multilayer Application:

1. On ceilings, apply gypsum board indicated for base layers before applying base layers on walls/partitions; apply face layers in same sequence. Apply base layers at right angles to

framing members and offset face-layer joints one framing member, 16 inches (400 mm) minimum, from parallel base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly.

2. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over stud or furring member and face-layer joints offset at least one stud or furring member with base-layer joints unless otherwise indicated or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.
3. On Z-shaped furring members, apply base layer vertically (parallel to framing) and face layer either vertically (parallel to framing) or horizontally (perpendicular to framing) with vertical joints offset at least one furring member. Locate edge joints of base layer over furring members.
4. Fastening Methods: Fasten base layers and face layers separately to supports with screws.

D. Laminating to Substrate: Where gypsum panels are indicated as directly adhered to a substrate (other than studs, joists, furring members, or base layer of gypsum board), comply with gypsum board manufacturer's written instructions and temporarily brace or fasten gypsum panels until fastening adhesive has set.

3.4 INSTALLATION OF TILE BACKING PANELS

A. Glass-Mat, Water-Resistant Backing Panels: Comply with manufacturer's written installation instructions and install at locations indicated to receive tile. Install with 1/4-inch (6.4-mm) gap where panels abut other construction or penetrations.

B. Water-Resistant Backing Board: Install where indicated with 1/4-inch (6.4-mm) gap where panels abut other construction or penetrations.

C. Where tile backing panels abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.

3.5 INSTALLATION OF TRIM ACCESSORIES

A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.

B. Control Joints: Install control joints at locations indicated on Drawings.

C. Interior Trim: Install in the following locations:

1. Cornerbead: Use at outside corners unless otherwise indicated.
2. Bullnose Bead: Use where indicated.
3. L-Bead: Use where indicated.
4. U-Bead: Use at exposed panel edges.
5. Curved-Edge Cornerbead: Use at curved openings.

D. Aluminum Trim: Install in locations indicated on Drawings.

3.6 FINISHING GYPSUM BOARD

A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.

B. Prefill open joints**,** rounded or beveled edges, and damaged surface areas.

C. Apply joint tape over gypsum board joints, except those with trim having flanges not intended for tape.

D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:

1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
2. Level 2: Panels that are substrate for tile.
3. Level 3: In Shell Spaces.
4. Level 4: At panel surfaces that will be exposed to view, unless otherwise indicated.

    a. Primer and its application to surfaces are specified in other Division 9 Sections.

5. Level 5: At panel surfaces that will be exposed to direct daylight, unless otherwise indicated, and at panels to receive glosss and semigloss enamels.

    a. Primer and its application to surfaces are specified in other Division 9 Sections.

E. Glass-Mat Gypsum Sheathing Board: Finish according to manufacturer's written instructions for use as exposed soffit board.

F. Glass-Mat, Water-Resistant Backing Panels: Finish according to manufacturer's written instructions.

3.7 PROTECTION

A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.

B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.

C. Remove and replace panels that are wet, moisture damaged, and mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 092900

SECTION 093013 - CERAMIC TILING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Ceramic mosaic tile.
2. Porcelain tile.
3. Solid polymer thresholds installed as part of tile installations.
4. Waterproof membrane.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for sealing of expansion, contraction, control, and isolation joints in tile surfaces.
2. Section 092900 "Gypsum Board" for glass-mat, water-resistant backer board.

1.3 DEFINITIONS

A. General: Definitions in the ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.

B. ANSI A108 Series: ANSI A108.01, ANSI A108.02, ANSI A108.1A, ANSI A108.1B, ANSI A108.1C, ANSI A108.4, ANSI A108.5, ANSI A108.6, ANSI A108.8, ANSI A108.9, ANSI A108.10, ANSI A108.11, ANSI A108.12, ANSI A108.13, ANSI A108.14, ANSI A108.15, ANSI A108.16, and ANSI A108.17, which are contained in its "Specifications for Installation of Ceramic Tile."

C. Face Size: Actual tile size, excluding spacer lugs.

D. Module Size: Actual tile size plus joint width indicated.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review requirements in ANSI A108.01 for substrates and for preparation by other trades.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For adhesives indicating compliance with General Emissions evaluation and VOC content requirements.
2. Product Data: For sealants indicating compliance with General Emissions evaluation and VOC content requirements.

C. Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.

D. Samples for Initial Selection: For tile, grout, and accessories involving color selection.

E. Samples for Verification:

1. Full-size units of each type and composition of tile and for each color and finish required. For ceramic mosaic tile in color blend patterns, provide full sheets of each color blend.
2. Full-size units of each type of trim and accessory for each color and finish required.
3. Thresholds in 6-inch (150-mm) lengths.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Master Grade Certificates: For each shipment, type, and composition of tile, signed by tile manufacturer and Installer.

C. Product Certificates: For each type of product.

D. Product Test Reports: For tile-setting and -grouting products and certified porcelain tile.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.
2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Installer is a Five-Star member of the National Tile Contractors Association or a Trowel of Excellence member of the Tile Contractors' Association of America.
2. Installer employs only Ceramic Tile Education Foundation Certified Installers or installers recognized by the U.S. Department of Labor as Journeyman Tile Layers for Project.
3. Installer employs at least one installer for Project that has completed the Advanced Certification for Tile Installers (ACT) certification for installation of mud floors, membranes, and large format tile.

B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup of floor tile installation.
2. Build mockup of wall tile installation.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.

B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.

C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.

D. Store liquid materials in unopened containers and protected from freezing.

1.10 FIELD CONDITIONS

A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations for Tile: Obtain tile of each type and color or finish from single source or producer.

1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each contiguous area.

B. Source Limitations for Setting and Grouting Materials: Obtain ingredients of a uniform quality for each mortar, adhesive, and grout component from single manufacturer and each aggregate from single source or producer.

1. Obtain setting and grouting materials, except for unmodified Portland cement and aggregate, from single manufacturer.
2. Obtain waterproof membrane, except for sheet products, from manufacturer of setting and grouting materials.

C. Source Limitations for Other Products: Obtain each of the following products specified in this Section from a single manufacturer:

1. Thresholds.
2. Waterproof membrane.

2.2 PRODUCTS, GENERAL

A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.

1. Provide tile complying with Standard grade requirements.

B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.

C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.

2.3 TILE PRODUCTS

A. Ceramic Tile Type CT-1: Unglazed porcelain tile.

1. Basis-of-Design Product: Dal-Tile Corporation; Portfolio ColorBody Porcelain Porcealto Series, or a comparable product from one of the following:

a. American Marazzi Tile, Inc.
b. American Olean Corporation.
c. Crossville.
d. Fiandre, part of Iris Ceramica Group.

2. Certification: Tile certified by the Porcelain Tile Certification Agency.
3. Face Size: 12 by 12 inches (200 by 200 mm) nominal.
4. Thickness: 3/8 inch (9.5 mm).
5. Face: Plain with square or cushion edges.
6. Tile Color, Glaze, and Pattern: As selected by Architect from manufacturer's full range.
7. Grout Color: As selected by Architect from manufacturer's full range.

B. Ceramic Tile Type CT-2: Unglazed porcelain tile.

1. Basis-of-Design Product: Dal-Tile; Portfolio Colorbody Porcelain, or a comparable product from one of the following:

a. American Marazzi Tile, Inc.
b. American Olean Corporation.
c. Crossville.
d. Fiandre, part of Iris Ceramica Group.

2. Certification: Tile certified by the Porcelain Tile Certification Agency.
3. Face Size: 6 by 6 inches (100 by 100 mm) nominal.
4. Thickness: 3/8 inch (9.5 mm).
5. Face: Plain with square or cushion edges.
6. Tile Color, Glaze, and Pattern: As selected by Architect from manufacturer's full range.
7. Grout Color: As selected by Architect from manufacturer's full range.

2.4 THRESHOLDS

A. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.

1. Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch (1.5 mm) above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch (12.7 mm) or less above adjacent floor surface.

B. Solid Polymer Thresholds.

2.5 WATERPROOF MEMBRANE

A. General: Manufacturer's standard product, selected from the following, that complies with ANSI A118.10 and is recommended by the manufacturer for the application indicated. Include reinforcement and accessories recommended by manufacturer.

B. Chlorinated Polyethylene Sheet: Nonplasticized, chlorinated polyethylene faced on both sides with nonwoven polyester fabric; 0.030 inch (0.76 mm) nominal thickness.

1. Product: Subject to compliance with requirements, provide the following:

a. Noble Company (The); Nobleseal CIS.

C. PVC Sheet: PVC heat-fused on both sides to facings of nonwoven polyester; 0.040 inch (1 mm) nominal thickness.

1. Product: Subject to compliance with requirements, provide the following:

a. Compotite Corporation; Composeal Gold.

D. Polyethylene Sheet: Polyethylene faced on both sides with fleece webbing; 0.008-inch (0.2-mm) nominal thickness.

1. Product: Subject to compliance with requirements, provide the following:

a. Schluter Systems, L. P.; KERDI.

E. Fabric-Reinforced, Modified-Bituminous Sheet: Self-adhering, SBS-modified-bituminous sheet with fabric reinforcement facing; 0.040-inch (1 -mm) nominal thickness.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Boiardi Products Corporation, a QEP Company; Elastiment 340 Sound Control Sheet Membrane Waterproofing and Anti-Fracture/Crack Suppression System.
b. Custom Building Products; Crack Buster Pro Crack Prevention Mat Underlayment.
c. National Applied Construction Products, Inc.; ECB Anti-Fracture Membrane.
d. MAPEI Corporation; Mapeguard 2.

F. Fabric-Reinforced, Fluid-Applied Membrane: System consisting of liquid-latex rubber or elastomeric polymer and continuous fabric reinforcement.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Boiardi Products Corporation, a QEP Company; Elastimant 344 Reinforced Waterproofing and Anti-Fracture/Crack Suppression Membrane.
b. Bonsal American, an Oldcastle Company; B 6000 Waterproof-Crack Isolation Membrane with B 6000 Mesh.
c. Bostik, Inc.; Hydroment Blacktop 90210.
d. Custom Building Products; 9240 Waterproofing and Anti-Fracture Membrane.
e. Laticrete International, Inc.; Laticrete 9235 Waterproof Membrane.
f. MAPEI Corporation; Mapelastic HPG with MAPEI Fiberglass Mesh.
g. Merkrete Systems, Parex USA, Inc.; Hydro-Guard 2000.
h. Southern Grouts & Mortars, Inc.; Southcrete 1100 Crack suppression.
i. Summitville Tiles, Inc.; S-9000.

G. Fluid-Applied Membrane: Liquid-latex rubber or elastomeric polymer.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Bostik, Inc.; Hydroment GoldPlus.
b. C-Cure; Pro-Red Waterproofing Membrane 963.
c. Custom Building Products; RedGard Waterproofing and Crack Prevention Membrane.
d. Jamo, Inc.; Waterproof.
e. Laticrete International, Inc.; Laticrete Hydro ban.
f. MAPEI Corporation; Mapelastic AquaDefense.
g. Merkrete Systems, Parex USA, Inc.; Hydro-Guard SP1.
h. Southern Grouts & Mortars, Inc.; Southcrete 1132.
i. TEC, H. B. Fuller Construction Products, Inc.; HydraFlex – Waterproofing Crack Isolation Membrane.

H. Latex-Portland Cement Waterproof Mortar: Flexible, waterproof mortar consisting of cement-based mix and latex additive.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Ardex Americas; Ardex 8+9 Waterproofing Compound.
b. Boiardi Products Corporation, a QEP Company; Elastiment 323 Cement Based Waterproofing, Anti-Fracture/Crack Suppression Membrane.
c. C-Cure; UltraCure 971.
d. MAPEI Corporation; Mapelastic 315.
e. TEC, H. B. Fuller Construction Products, Inc.; Triple Flex Waterproofing, Crack Isolation Membrane & Mortar.

I. Waterproofing and Tile-Setting Adhesive: One-part, fluid-applied product intended for use as both waterproofing and tile-setting adhesive in a two-step process.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Boiardi Products Corporation, a QEP Company; Elastiment 324 Waterproofing, Anti-Fracture/Crack Suppressant and Tile Setting Adhesive.
b. Bostik, Inc.; Hydroment Ultra-Set Advanced.

2. Adhesives shall have a VOC content of 65 g/L or less.
3. Adhesives shall comply with the testing and product requirements of the California Department of Public Health's (formerly the California Department of Health Service's) "Standard Method of Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Small-Scale Environmental Chambers."

2.6 SETTING MATERIALS

A. Portland Cement Mortar (Thickset) Installation Materials: ANSI A108.02.

1. Cleavage Membrane: Asphalt felt, ASTM D226/D226M, Type I (No. 15); or polyethylene sheeting, ASTM D4397, 4.0 mils (0.1 mm) thick.
2. Reinforcing Wire Fabric: Galvanized, welded-wire fabric, 2 by 2 inches (50.8 by 50.8 mm) by 0.062-inch (1.57-mm) diameter; comply with ASTM A185/A185M and ASTM A82/A82M, except for minimum wire size.
3. Latex Additive: Manufacturer's standard acrylic resin water emulsion, serving as replacement for part or all of gaging water, of type specifically recommended by latex-additive manufacturer for use with field-mixed portland cement and aggregate mortar bed.

B. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Atlas Minerals & Chemicals, Inc.
b. Boiardi Products Corporation, a QEP Company.
c. Bonsal American, an Oldcastle Company.

d. Bostik, inc.
e. C-Cure.
f. Custom Building Products.
g. Jamo, Inc.
h. Laticrete International, Inc.
i. MAPEI Corporation.
j. Merkrete Systems; Parex USA, Inc.
k. Southern Grouts & Mortars, Inc.
l. Summitville Tiles, Inc.
m. TEC, H. B. Fuller Construction Products, Inc.

2. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to the other requirements in ANSI A118.15.

2.7 GROUT MATERIALS

A. Sand-Portland Cement Grout: ANSI A108.10, consisting of white or gray cement and white or colored aggregate as required to produce color indicated.

B. High-Performance Tile Grout: ANSI A118.7.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Atlas Minerals & Chemicals, Inc.
b. Boiardi Products Corporation, a QEP Company.
c. Bonsal American, an Oldcastle Company.
d. Bostik, inc.
e. C-Cure.
f. Custom Building Products.
g. Jamo, Inc.
h. Laticrete International, Inc.
i. MAPEI Corporation.
j. Merkrete Systems; Parex USA, Inc.
k. Southern Grouts & Mortars, Inc.
l. Summitville Tiles, Inc.
m. TEC, H. B. Fuller Construction Products, Inc.

C. Water-Cleanable Epoxy Grout: ANSI A118.3, with a VOC content of 65 g/L or less.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Atlas Minerals & Chemicals, Inc.
b. Boiardi Products Corporation, a QEP Company.
c. Bonsal American, an Oldcastle Company.
d. Bostik, inc.
e. C-Cure.
f. Custom Building Products.
g. Jamo, Inc.

h. Laticrete International, Inc.
i. MAPEI Corporation.
j. Merkrete Systems; Parex USA, Inc.
k. Southern Grouts & Mortars, Inc.
l. Summitville Tiles, Inc.
m. TEC, H. B. Fuller Construction Products, Inc.

2. Provide product capable of withstanding continuous and intermittent exposure to temperatures of up to 140 and 212 deg F (60 and 100 deg C), respectively, and certified by manufacturer for intended use.

2.8 MISCELLANEOUS MATERIALS

A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.

A. Metal Edge Strips: Angle or L-shaped, height to match tile and setting-bed thickness, metallic or combination of metal and PVC or neoprene base, designed specifically for flooring applications; stainless steel, ASTM A276/A276M or ASTM A666, 300 Series exposed-edge material.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Schluter Systems, L.P.; DILEX and SCHIENE Series, or comparable products by one of the following:

a. Blanke Corporation.
b. Ceramic Tool Company, Inc.
c. Profilitec, SpA.

B. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

C. Floor Sealer: Manufacturer's standard product for sealing grout joints and that does not change color or appearance of grout.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Bonsal American, an Oldcastle Company; Grout Sealer.
b. Custom Building Products; Surfaceguard Sealer.
c. Jamo, Inc.; Surfaceguard Sealer.
d. Southern Grouts & Mortars, Inc.; Clear Penetrating Sealer & Grout Release.
e. Summitville Tiles, Inc.; SL-5, Invisible Seal.
f. TEC, H. B. Fuller Construction Products, Inc.; Guard All Invisible Penetrating Sealer.

2. Grout sealers shall comply with requirements of FloorScore certification.
3. Grout sealers shall comply with the testing and product requirements of the California Department of Public Health’s (formerly the California Department of Health Service’s)

"Standard Method of Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Small-Scale Environmental Chambers."

2.9 MIXING MORTARS AND GROUT

A. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.

B. Add materials, water, and additives in accurate proportions.

C. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
2. Verify that concrete substrates for tile floors installed with bonded mortar bed or thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.

    a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.
    b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.

3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.

B. Where indicated, prepare substrates to receive waterproof membrane by applying a reinforced mortar bed that complies with ANSI A108.1A and is sloped 1/4 inch per foot (1:50) toward drains.

C. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

3.3 INSTALLATION OF CERAMIC TILE

A. Comply with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.

1. For the following installations, follow procedures in the ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:

    a. Tile floors in wet areas.
    b. Tile floors consisting of rib-backed tiles.

B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.

C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.

D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.

E. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.

1. For tile mounted in sheets, make joints between tile sheets same width as joints within tile sheets so joints between sheets are not apparent in finished work.
2. Where adjoining tiles on floor, base, walls, or trim are specified or indicated to be same size, align joints.
3. Where tiles are specified or indicated to be whole integer multiples of adjoining tiles on floor, base, walls, or trim, align joints unless otherwise indicated.

F. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:

1. Ceramic Mosaic Tile: 1/16 inch (1.6 mm).
2. Porcelain Tile: 1/4 inch (6.4 mm).

G. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated.

H. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.

1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.

I. Thresholds: Install thresholds in same type of setting bed as adjacent floor unless otherwise indicated.

1. At locations where mortar bed (thickset) would otherwise be exposed above adjacent floor finishes, set thresholds in improved modified dry-set mortar (thinset).
2. Do not extend cleavage membrane or waterproof membrane under thresholds set in standard dry-set, modified dry-set, or improved modified dry-set mortar. Fill joints between such thresholds and adjoining tile set on cleavage membrane or waterproof membrane with elastomeric sealant.

J. Floor Sealer: Apply floor sealer to cementitious grout joints in tile floors according to floor-sealer manufacturer's written instructions. As soon as floor sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

3.4 INSTALLATION OF TILE BACKING PANEL

A. Install panels and treat joints according to ANSI A108.11 and manufacturer's written instructions for type of application indicated. Use modified dry-set mortar for bonding material unless otherwise directed in manufacturer's written instructions.

3.5 INSTALLATION OF WATERPROOF MEMBRANE

A. Install waterproof membrane to comply with ANSI A108.13 and manufacturer's written instructions to produce waterproof membrane of uniform thickness that is bonded securely to substrate.

B. Allow waterproof membrane to cure and verify by testing that it is watertight before installing tile or setting materials over it.

3.6 ADJUSTING AND CLEANING

A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.

B. Cleaning: On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.

1. Remove grout residue from tile as soon as possible.

2. Clean grout smears and haze from tile according to tile and grout manufacturer's written instructions but no sooner than 10 days after installation. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

3.7 PROTECTION

A. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.

B. Prohibit foot and wheel traffic from tiled floors for at least seven days after grouting is completed.

C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

3.8 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

A. Interior Floor Installations, Concrete Subfloor:

1. Ceramic Tile Installation A: TCNA F114 and ANSI A108.1C; cement mortar bed (thickset) with cleavage membrane; epoxy grout.

    a. Ceramic Tile Type: CT-1.
    b. Bond Coat for Cured-Bed Method: Improved modified dry-set mortar.
    c. Grout: Water-cleanable epoxy grout.

2. Ceramic Tile Installation B: TCNA F122; thinset mortar on waterproof membrane.

    a. Ceramic Tile Type: CT-1.
    b. Thinset Mortar: Improved modified dry-set mortar.
    c. Grout: High-performance unsanded grout.

B. Interior Wall Installations, Wood or Metal Studs or Furring:

1. Ceramic Tile Installation C: TCNA W245 or TCNA W248; thinset mortar on glass-mat, water-resistant gypsum backer board.

    a. Ceramic Tile Type: CT-2.
    b. Thinset Mortar: Improved modified dry-set mortar.
    c. Grout: High-performance sanded grout.

END OF SECTION 093013

OPTIONSSECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes acoustical panels and exposed suspension systems for interior ceilings.

B. Related Requirements:

1. Section 097700 "Special Wall and Ceiling Surfacing" for ceilings consisting of vinyl composite ceiling panels to be installed in suspension systems specified in this Section.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

1. Product Data: For products having recycled content, submit documentation indicating percentages by weight of postconsumer and preconsumer recycled content.

a. Include statement indicating cost for each product having recycled content.

2. Product Data: For ceiling products indicating compliance with General Emissions evaluation.

C. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of sizes indicated below:

1. Acoustical Panels: Set of 6-inch- (150-mm-) square Samples of each type, color, pattern, and texture.
2. Exposed Suspension-System Members, Moldings, and Trim: Set of 12-inch- (300-mm-) long Samples of each type, finish, and color.

1.5 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Ceiling suspension-system members.
2. Structural members to which suspension systems will be attached.
3. Method of attaching hangers to building structure.
4. Carrying channels or other supplemental support for hanger-wire attachment where conditions do not permit installation of hanger wires at required spacing.
5. Size and location of initial access modules for acoustical panels.
6. Items penetrating finished ceiling and ceiling-mounted items including the following:

    a. Lighting fixtures.
    b. Diffusers.
    c. Grilles.
    d. Speakers.
    e. Sprinklers.
    f. Perimeter moldings.

7. Minimum Drawing Scale: 1/4 inch = 1 foot (1:48).

B. Product Test Reports: For each acoustical panel ceiling, for tests performed by a qualified testing agency.

C. Evaluation Reports: For each acoustical panel ceiling suspension system and anchor and fastener type, from ICC-ES.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For finishes to include in maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Acoustical Ceiling Units: Full-size panels equal to 2 percent of quantity installed.
2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver acoustical panels, suspension-system components, and accessories to Project site and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.

B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.

1.9 FIELD CONDITIONS

A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Ceilings, Walls, and Thermal Insulation: Shall comply with requirements of California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

B. Seismic Performance: Suspended ceilings shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

C. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: Class A according to ASTM E1264.
2. Smoke-Developed Index: 450 or less.

2.3 ACOUSTICAL PANELS, AP-1

A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong World Industries, Inc.; Cortega 703, or comparable product by one of the following:

1. Celotex Corporation; Architectural Ceilings Marketing Dept.
2. USG Interiors, Inc.

B. Acoustical Panel Standard: Provide manufacturer's standard panels according to ASTM E1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.

C. Classification: Provide panels as follows:

1. Type and Form: Type III, mineral base with painted finish; Form 2, water felted.

2. Pattern: CD (perforated, small holes and fissured).

D. Color: White.

E. Light Reflectance (LR): Not less than 0.80.

F. Ceiling Attenuation Class (CAC): Not less than 33.

G. Noise Reduction Coefficient (NRC): Not less than 0.55.

H. Edge/Joint Detail: Angled tegular.

I. Thickness: 5/8 inch (15 mm).

J. Modular Size: 24 by 48 inches (610 by 1220 mm).

K. Antimicrobial Treatment: Manufacturer's standard broad spectrum, antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D3273, ASTM D3274, or ASTM G21 and evaluated according to ASTM D3274 or ASTM G21.

2.4 METAL SUSPENSION SYSTEM

A. Products: Subject to requirements, provide one of the following:

1. Armstrong World Industries, Inc.: Prelude ML 15/16” Exposed Tee.
2. Chicago Metallic Corporation; Matrix.
3. USG Interiors, Inc.; Donn Brand DX.

B. Metal Suspension-System Standard: Provide manufacturer's standard, direct-hung, metal suspension system and accessories according to ASTM C635/C635M and designated by type, structural classification, and finish indicated.

1. High-Humidity Finish: Where indicated, provide coating tested and classified for "severe environment performance" according to ASTM C635/C635M.

C. Wide-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 (Z90) coating designation; with prefinished 15/16-inch- (24-mm-) wide metal caps on flanges.

1. Structural Classification: Heavy-duty system.
2. End Condition of Cross Runners: Override (stepped) type.
3. Face Design: Flat, flush.
4. Cap Material: Cold-rolled steel.
5. Cap Finish: Painted white.

2.5 ACCESSORIES

A. Attachment Devices: Size for five times the design load indicated in ASTM C635/C635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.

1. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing according to ASTM E1190, conducted by a qualified testing and inspecting agency.

B. Wire Hangers, Braces, and Ties: Provide wires as follows:

1. Zinc-Coated, Carbon-Steel Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper.
2. Size: Wire diameter sufficient for its stress at three times hanger design load (ASTM C635/C635M, Table 1, "Direct Hung") will be less than yield stress of wire, but not less than 0.106-inch- (2.69-mm-) diameter wire.

C. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.

D. Flat Hangers: Mild steel, zinc coated or protected with rust-inhibitive paint.

E. Seismic Clips: Manufacturer's standard seismic clips designed to secure acoustical panels in place during a seismic event.

F. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.

G. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.

2.6 METAL EDGE MOLDINGS AND TRIM

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Armstrong World Industries, Inc.
2. Celotex Corporation; Architectural Ceilings Marketing Dept.
3. USG Interiors, Inc.

B. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.

1. Edge moldings shall fit acoustical panel edge details and suspension systems indicated and match width and configuration of exposed runners unless otherwise indicated.

2. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
3. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.

C. Extruded-Aluminum Edge Moldings and Trim: Where indicated, provide manufacturer's extruded-aluminum edge moldings and trim of profile indicated or referenced by manufacturer's designations, including splice plates, corner pieces, and attachment and other clips, complying with seismic design requirements.

1. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of 1.5 mils (0.04 mm). Comply with ASTM C635/C635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

2.7 ACOUSTICAL SEALANT

A. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.

B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders unless otherwise indicated, and comply with layout shown on reflected ceiling plans.

B. Layout openings for penetrations centered on the penetrating items.

3.3 INSTALLATION

A. Install acoustical panel ceilings according to ASTM C636/C636M, seismic design requirements, and manufacturer's written instructions.

B. Suspend ceiling hangers from building's structural members and as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
4. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly to structure or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
5. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both the structure to which hangers are attached and the type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
6. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
7. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
8. Do not attach hangers to steel deck tabs.
9. Do not attach hangers to steel roof deck. Attach hangers to structural members.
10. Space hangers not more than 48 inches (1200 mm) o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches (200 mm) from ends of each member.
11. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.

C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.

D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.

1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
2. Screw attach moldings to substrate at intervals not more than 16 inches (400 mm) o.c. and not more than 3 inches (75 mm) from ends. Miter corners accurately and connect securely.
3. Do not use exposed fasteners, including pop rivets, on moldings and trim.

E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.

F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide precise fit.

1. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
2. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
3. Install hold-down clips in areas indicated; space according to panel manufacturer's written instructions unless otherwise indicated.

a. Hold-Down Clips: Space 24 inches (610 mm) o.c. on all cross runners.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

B. Acoustical panel ceiling hangers, anchors, and fasteners will be considered defective if they do not pass tests and inspections.

3.5 CLEANING

A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.

B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095113

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Thermoplastic rubber base.
2. Rubber molding accessories.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For each exposed product and for each color and texture specified, not less than 12 inches (300 mm) long.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Furnish not less than 10 linear feet (3 linear m) for every 500 linear feet (150 linear m) or fraction thereof, of each type, color, pattern, and size of resilient product installed.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C).

1.6 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C), in spaces to receive resilient products during the following periods:

1. 48 hours before installation.

2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).

C. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 THERMOPLASTIC-RUBBER BASE

A. Products: Subject to compliance with requirements, provide one of the following:

1. Armstong Flooring, Inc.; Commercial Wall Base.
2. Flexco Corporation; 2000 Wall Base.
3. Mannington Commercial; Burke Rubber Wall Base.
4. Mohawk Group; Elemental Edges Rubber Wall Base.
5. Roppe Corporation; 700 Series Base.
6. Tarkett North America; Johnsonite Wall Base DC.

B. Product Standard: ASTM F1861, Type TP (rubber, thermoplastic).

1. Group: I (solid, homogeneous).
2. Style and Location:

a. Style A, Straight: Provide in areas with carpet.
b. Style B, Cove: Provide in areas with resilient floor coverings.

C. Thickness: 0.125 inch (3.2 mm).

D. Height: 4 inches (102 mm).

E. Lengths: Cut lengths 48 inches (1219 mm) long or coils in manufacturer's standard length.

F. Outside Corners: Preformed.

G. Inside Corners: Preformed.

H. Colors: <**Insert colors**>.

2.2 RUBBER MOLDING ACCESSORY

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Armstong Flooring, Inc.

2. Ecore.
3. Flexco Corporation.
4. Mannington Commercial.
5. Mohawk Group.
6. Tarkett North America.

B. Description: Rubber reducer strip for resilient floor covering.

C. Profile and Dimensions: As indicated.

D. Locations: Provide rubber molding accessories where resilient floor coverings adjoin uncovered concrete floors.

E. Colors and Patterns: <**Insert colors and patterns**>.

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

1. VOC Content Requirements for Wet Applied Products: All adhesives and sealants wet-applied on site must meet the applicable chemical content requirements of SCAQMD Rule 1168, amended October 26, 2017, Adhesive and Sealant Applications, as analyzed by the methods specified in Rule 1168. The provisions of SCAQMD Rule 1168 do not apply to adhesives and sealants subject to state or federal consumer product VOC regulations.
2. Do not use adhesives that contain urea formaldehyde.

C. Metal Edge Strips: Extruded aluminum with mill finish, nominal 2 inches (50.8 mm) wide, of height required to protect exposed edges of flooring, and in maximum available lengths to minimize running joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.

B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

C. Do not install resilient products until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 RESILIENT BASE INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient base.

B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.

C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.

E. Do not stretch resilient base during installation.

F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.

G. Preformed Corners: Install preformed corners before installing straight pieces.

3.4 RESILIENT ACCESSORY INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient accessories.

B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

3.5 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.

B. Perform the following operations immediately after completing resilient-product installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum horizontal surfaces thoroughly.
3. Damp-mop horizontal surfaces to remove marks and soil.

C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

SECTION 096519 - RESILIENT TILE FLOORING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Luxury vinyl plank flooring.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For each type of resilient floor tile.

1. Include floor tile layouts, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
2. Show details of special patterns.

C. Samples for Initial Selection: For each type of floor tile indicated.

D. Samples for Verification: Full-size units of each color and pattern of floor tile required.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of floor tile to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Floor Tile: Furnish one box for every 50 boxes or fraction thereof, of each type, color, and pattern of floor tile installed.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for floor tile installation and seaming method indicated.

1. Engage an installer who employs workers for this Project who are trained or certified by floor tile manufacturer for installation techniques required.

B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.

1. Coordinate mockups in this Section with mockups specified in other Sections.

a. Size: Minimum 100 sq. ft. (9.3 sq. m) for each type, color, and pattern in locations directed by Architect.

2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store floor tile and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F (10 deg C) or more than 90 deg F (32 deg C). Store floor tiles on flat surfaces.

1.9 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C), in spaces to receive floor tile during the following periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).

C. Close spaces to traffic during floor tile installation.

D. Close spaces to traffic for 48 hours after floor tile installation.

E. Install floor tile after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For resilient floor tile, as determined by testing identical products according to ASTM E648 or NFPA 253 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

2.2 SOLID VINYL FLOOR TILE

A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstong Flooring, Inc.; Unify LVT or comparable product from one of the following:

1. Ecore.
2. Flexco Corporation.
3. Gerflor USA.
4. Mannington Commercial.
5. Mohawk Group.
6. Philadelphia Commercial.
7. Shaw Contract.
8. Tarkett North America.

B. Tile Standard: ASTM F1700.

1. Class: As indicated by product designations.
2. Type: A, Smooth Surface.

C. Thickness: 0.100 inch (2.5 mm).

D. Size: 6 by 36 inches (152 by 914 mm) or 6 by 48 inches (142 by 1824 mm).

E. Colors and Patterns: As selected by Architect from manufacturer’s full range.

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.

1. VOC Content Requirements for Wet Applied Products: All adhesives and sealants wet-applied on site must meet the applicable chemical content requirements of SCAQMD Rule 1168, amended October 26, 2017, Adhesive and Sealant Applications, as analyzed by the methods specified in Rule 1168. The provisions of SCAQMD Rule 1168 do not

apply to adhesives and sealants subject to state or federal consumer product VOC regulations.

2. Do not use adhesives that contain urea formaldehyde.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor tile.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.

B. Concrete Substrates: Prepare according to ASTM F710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 7 or more than 9 pH.
4. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft. (18.6 sq. m), and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
    b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Do not install floor tiles until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient floor tile and installation materials into spaces where they will be installed.

E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor tile.

3.3 FLOOR TILE INSTALLATION

A. Comply with manufacturer's written instructions for installing floor tile.

B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.

1. Lay tiles square with room axis.

C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.

D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.

E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.

G. Install floor tiles on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of tile installed on covers and adjoining tiles. Tightly adhere tile edges to substrates that abut covers and to cover perimeters.

H. Adhere floor tiles to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.4 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.

B. Perform the following operations immediately after completing floor tile installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum surfaces thoroughly.
3. Damp-mop surfaces to remove marks and soil.

C. Protect floor tile from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

D. Cover floor tile until Substantial Completion.

END OF SECTION 096519

SECTION 096723 - RESINOUS FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes resinous flooring systems.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include manufacturer's technical data, application instructions, and recommendations for each resinous flooring component required.

B. Samples for Initial Selection: For each type of exposed finish required.

C. Samples for Verification: For each resinous flooring system required, 6 inches (150 mm) square, applied to a rigid backing by Installer for this Project.

1.4 INFORMATIONAL SUBMITTALS

A. Installer Certificates: Signed by manufacturer certifying that installers comply with specified requirements.

B. Material Certificates: For each resinous flooring component, from manufacturer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For resinous flooring to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

B. Engage an installer who is certified in writing by resinous flooring manufacturer as qualified to apply resinous flooring systems indicated.

C. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Apply full-thickness mockups on 96-inch- (2400-mm-) square floor area selected by Architect.

    a. Include 96-inch (2400-mm) length of integral cove base with inside and outside corner.

2. Simulate finished lighting conditions for Architect's review of mockups.
3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in original packages and containers, with seals unbroken, bearing manufacturer's labels indicating brand name and directions for storage and mixing with other components.

1.8 FIELD CONDITIONS

A. Environmental Limitations: Comply with resinous flooring manufacturer's written instructions for substrate temperature, ambient temperature, moisture, ventilation, and other conditions affecting resinous flooring application.

B. Lighting: Provide permanent lighting or, if permanent lighting is not in place, simulate permanent lighting conditions during resinous flooring application.

C. Close spaces to traffic during resinous flooring application and for 24 hours after application unless manufacturer recommends a longer period.

PART 2 - PRODUCTS

2.1 PERORMANCE REQUIREMENTS

A. VOC Content of Liquid-Applied Flooring Components: Not more than 100 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Flammability: Self-extinguishing according to ASTM D 635.

2.2 MANUFACTURERS

A. Source Limitations: Obtain primary resinous flooring materials, including primers, resins, hardening agents, grouting coats, and topcoats, from single source from single manufacturer. Obtain secondary materials, including patching and fill material, joint sealant, and repair materials, of type and from manufacturer recommended in writing by manufacturer of primary materials.

2.3 RESINOUS FLOORING

A. Resinous Flooring System: Abrasion-, impact-, and chemical-resistant, aggregate-filled, and resin-based monolithic floor surfacing designed to produce a seamless floor and integral cove base.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Sherwin Williams Company; Hybri-Flex EC or a comparable product from one of the following:

    a. BASF Corporation-Construction Systems.
    b. Garland Company, Inc. (The).
    c. ITW Polymers Sealants North America (formerly Pacific Polymers, Inc.).
    d. Key Resin Company.
    e. Neogard; a division of Jones-Blair, Inc.
    f. Stonhard, Inc.
    g. Tamms; a brand of Euclid Chemical Company; an RPM Company.
    h. Tennant Company.
    i. Tnemec Company, Inc.
    j. Tufco International Inc.

2. System Materials:

    a. Topping: Sherwin-Williams Poly-Crete SL resin, hardener and SL aggregate.
    b. Broadcast Aggregate: Sherwin-Williams; Macro chip
    c. Broadcast Coat: Sherwin-Williams; Resuflor Glaze epoxy based two-component resin.
    d. Grout Coat: Sherwin-Williams; Resuflor Glaze epoxy-based, two-component resin.
    e. Top Coat: Sherwin-Williams; Resutile AT aliphatic urethane two- component resin with grit.

3. Fill and Patching Materials:

    a. Shallow Fill and Patching: Sherwin-Williams; Poly-Crete MD, up to 1/4 inch (6 mm).
    b. Deep Fill and Sloping Material: Sherwin-Williams; Poly-Crete WR.

B. System Characteristics:

1. Color and Pattern: Hybri-Flex EC "Cobalt."
2. Wearing Surface: Textured for slip resistance.
3. Overall System Thickness: 1/8 inch to 3/16 inch (3.2 mm to 4.8 mm).

C. System Physical Properties: Provide resinous flooring system with the following minimum physical property requirements when tested according to test methods indicated:

1. Compressive Strength: 16,000 psi minimum according to ASTM C 579.
2. Tensile Strength: 3,700 psi minimum according to ASTM C 307.
3. Flexural Strength: 4,700 psi minimum according to ASTM C 580.
4. Water Absorption: 0.04 percent maximum according to ASTM C 413.
5. Indentation: 0.05 percent maximum according to MIL-D-3134J.

6. Impact Resistance: No chipping, cracking, or delamination and not more than 1/16-inch (1.6-mm) permanent indentation according to MIL-D-3134J.
7. Resistance to Elevated Temperature: No slip or flow of more than 1/16 inch (1.6 mm) according to MIL-D-3134J.
8. Abrasion Resistance: 12 mg maximum weight loss according to ASTM D 4060.
9. Hardness: 75-80, Shore D according to ASTM D 2240.
10. Critical Radiant Flux: 0.22 W/sq. cm or greater according to NFPA 253.

PART 3 - EXECUTION

3.1 PREPARATION

A. Prepare and clean substrates according to resinous flooring manufacturer's written instructions for substrate indicated. Provide clean, dry substrate for resinous flooring application.

B. Concrete Substrates: Provide sound concrete surfaces free of laitance, glaze, efflorescence, curing compounds, form-release agents, dust, dirt, grease, oil, and other contaminants incompatible with resinous flooring.

1. Roughen concrete substrates as follows:

    a. Shot-blast surfaces with an apparatus that abrades the concrete surface, contains the dispensed shot within the apparatus, and recirculates the shot by vacuum pickup.

2. Repair damaged and deteriorated concrete according to resinous flooring manufacturer's written instructions.
3. Verify that concrete substrates are dry and moisture-vapor emissions are within acceptable levels according to manufacturer's written instructions.

    a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with application of resinous flooring only after substrates have maximum moisture-vapor-emission rate of 20 lb of water/1000 sq. ft. (9.07 kg of water/92.9 sq. m) of slab area in 24 hours.
    b. Relative Humidity Test: Use in situ probes, ASTM F 2170. Proceed with installation only after substrates have a maximum 99 percent relative humidity level measurement.

4. Alkalinity and Adhesion Testing: Verify that concrete substrates have pH within acceptable range. Perform tests recommended by manufacturer. Proceed with application only after substrates pass testing.

C. Patching and Filling: Use patching and fill material to fill holes and depressions in substrates according to manufacturer's written instructions.

1. Control Joint Treatment: Treat control joints and other nonmoving substrate cracks to prevent cracks from reflecting through resinous flooring according to manufacturer's written instructions.

D. Resinous Materials: Mix components and prepare materials according to resinous flooring manufacturer's written instructions.

3.2 APPLICATION

A. Apply components of resinous flooring system according to manufacturer's written instructions to produce a uniform, monolithic wearing surface of thickness indicated.

1. Coordinate application of components to provide optimum adhesion of resinous flooring system to substrate, and optimum intercoat adhesion.
2. Cure resinous flooring components according to manufacturer's written instructions. Prevent contamination during application and curing processes.
3. Expansion and Isolation Joint Treatment: At substrate expansion and isolation joints, comply with resinous flooring manufacturer's written instructions.

B. Integral Cove Base: Apply cove base mix to wall surfaces before applying flooring. Apply according to manufacturer's written instructions and details, including those for taping, mixing, priming, troweling, sanding, and topcoating of cove base. Round internal and external corners.

1. Integral Cove Base: 4 inches (100 mm).

C. Self-Leveling Body Coats: Apply self-leveling slurry body coats in thickness indicated for flooring system.

1. Aggregates: Broadcast aggregates at rate recommended by manufacturer and, after resin is cured, remove excess aggregates to provide surface texture indicated.

D. Troweled or Screeded Body Coats: Apply troweled or screeded body coats in thickness indicated for flooring system. Hand or power trowel and grout to fill voids. When body coats are cured, remove trowel marks and roughness using method recommended by manufacturer.

E. Grout Coat: Apply grout coat, of type recommended by resinous flooring manufacturer, to fill voids in surface of final body coat.

F. Topcoats: Apply topcoats in number indicated for flooring system and at spreading rates recommended in writing by manufacturer and to produce wearing surface indicated.

3.3 PROTECTION

A. Protect resinous flooring from damage and wear during the remainder of construction period. Use protective methods and materials, including temporary covering, recommended in writing by resinous flooring manufacturer.

END OF SECTION 096723

SECTION 099113 - EXTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes surface preparation and the application of paint systems on exterior substrates.

B. Related Requirements:

1. Section 051200 "Structural Steel Framing" for shop priming of metal substrates with primers specified in this section.
2. Section 099123 "Interior Painting" for surface preparation and the application of paint systems on interior substrates.
3. Section 099600 "High-Performance Coatings" for tile-like coatings.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

1. Indicate VOC content.

B. Samples for Verification: For each type of paint system and each color and gloss of topcoat.

1. Submit Samples on rigid backing, 8 inches (200 mm) square.
2. Label each coat of each Sample.
3. Label each Sample for location and application area.

C. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. Indicate VOC content.

1.4 CLOSEOUT SUBMITTALS

A. Coating Maintenance Manual: Provide coating maintenance manual including area summary with finish schedule, area detail designating location where each product/color/finish was used, product data pages, material safety data sheets, care and cleaning instructions, touch-up procedures, and color samples of each color and finish used.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: 1 gal. (3.8 L) of each material and color applied.

1.6 QUALITY ASSURANCE

A. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.

a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft. (9 sq. m).
b. Other Items: Architect will designate items or areas required.

2. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.

3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Delivery and Handling: Deliver products to Project site in an undamaged condition in manufacturer's original sealed containers, complete with labels and instructions for handling, storing, unpacking, protecting, and installing. Packaging shall bear the manufacture’s label with the following information:

1. Product name and type (description).
2. Batch date.
3. Color number.
4. VOC content.
5. Environmental handling requirements.
6. Surface preparation requirements.
7. Application instructions.

B. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F (7 deg C).

1. Maintain containers in clean condition, free of foreign materials and residue.

2. Remove rags and waste from storage areas daily.

1.8 FIELD CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F (10 and 35 deg C).

B. Do not apply paints in snow, rain, fog, or mist; when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Sherwin-Williams Company (The); products indicated or comparable product from one of the following:

1. Behr Paint.
2. Benjamim Moore.
3. Pittsburgh Paint Company.

B. Comparable Products: Comparable products of approved manufacturers will be considered in accordance with Section 016000 "Product Requirements," and the following:

1. Products are approved by manufacturer in writing for application specified.
2. Products meet performance and physical characteristics of basis of design product including published ratio of solids by volume, plus or minus two percent.

C. Source Limitations: Obtain paint materials from single source from single listed manufacturer.

1. Manufacturer's designations listed on a separate color schedule are for color reference only and do not indicate prior approval.

2.2 PAINT, GENERAL

A. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.

B. VOC Content: For field applications, provide paints and coatings that complies with VOC content limits of authorities having jurisdiction.

C. Colors: As indicated in a color schedule.

1. [**10**] [**20**] [**30**] percent of surface area will be painted with deep tones.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers. Where acceptability of substrate conditions is in question, apply samples and perform in-situ testing to verify compatibility, adhesion, and film integrity of new paint application.

1. Report, in writing, conditions that may affect application, appearance, or performance of paint.

B. Substrate Conditions:

1. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

a. Concrete: 12 percent.
b. Fiber-Cement Board: 12 percent.
c. Masonry (Clay and CMU): 12 percent.
d. Wood: 15 percent.
e. Gypsum Board: 12 percent.

2. Exterior Gypsum Board Substrates: Verify that finishing compound is sanded smooth.

C. Proceed with coating application only after unsatisfactory conditions have been corrected; application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates and paint systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

E. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceeds that permitted in manufacturer's written instructions.

F. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer but not less than the following:

1. SSPC-SP 2, "Hand Tool Cleaning."

G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

I. Aluminum Substrates: Remove loose surface oxidation.

J. Wood Substrates:

1. Scrape and clean knots. Before applying primer, apply coat of knot sealer recommended in writing by topcoat manufacturer for exterior use in paint system indicated.
2. Sand surfaces that will be exposed to view, and dust off.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

K. Plastic Trim Fabrication Substrates: Remove dust, dirt, and other foreign material that might impair bond of paints to substrates.

3.3 APPLICATION

A. Apply paints according to manufacturer's written instructions and recommendations in "MPI Manual."

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable items same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed items with prime coat only.
3. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
4. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.

B. Tint undercoats same color as topcoat, but tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

E. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:

1. Paint the following work where exposed to view:

a. Equipment, including panelboards and switch gear.
b. Uninsulated metal piping.
c. Uninsulated plastic piping.
d. Pipe hangers and supports.
e. Metal conduit.
f. Plastic conduit.
g. Tanks that do not have factory-applied final finishes.

3.4 FIELD QUALITY CONTROL

A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.

1. Contractor shall touch up and restore painted surfaces damaged by testing.
2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.6 EXTERIOR PAINTING SCHEDULE

A. [**Concrete**] [**Cementitious Siding**], Nontraffic Surfaces:

1. Latex System:

a. Prime Coat: Primer sealer, latex.

1) S-W Loxon Concrete & Masonry Primer Sealer, A24W8300, at 8.0 mils (0.203 mm) wet, 3.2 mils (0.081 mm) dry.

b. Prime Coat: Latex, exterior, matching topcoat.
c. Intermediate Coat: Latex, exterior, matching topcoat.
d. Topcoat: Latex, exterior, flat.

1) S-W A-100 Exterior Latex Flat, A6 Series, at 4.0 mils (0.102 mm) wet, 1.2 mils (0.030 mm) dry, per coat.

e. Topcoat: Latex, exterior, low sheen.

1) S-W A-100 Exterior Latex Low Sheen, A12 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

f. Topcoat: Latex, exterior, satin.

1) S-W A-100 Exterior Latex Satin, A82 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

g. Topcoat: Latex, exterior, semi-gloss.

1) S-W Solo Acrylic Semi-Gloss, A76 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

h. Topcoat: Latex, exterior, gloss.

1) S-W A-100 Exterior Latex Gloss, A8 Series, at 4.0 mils (0.102 mm) wet, 1.3 mils (0.033 mm) dry, per coat.

2. Latex over Latex Aggregate System:

a. Prime Coat: Block Filler, Latex, Interior/Exterior.

1) S-W Loxon Block Surfacer, A24W200, at 50 to 100 sq. ft. per gal. (1.23 to 2.45 sq. m per liter).

b. Topcoat: Latex, exterior flat, [**fine**] [**medium**] [**coarse**] texture.

1) S-W UltraCrete Textured Masonry Topcoat, A44-800 Series, 50 to 80 sq. ft. per gal. (1.23 to 1.96 sq. m per liter).

B. CMU Substrates:

1. Latex System:

   a. Block Filler: Block filler, latex, interior/exterior:

      1) S-W PrepRite Block Filler, B25W25, at 75 to 125 sq. ft. per gal. (1.84 to 3.07 sq. m per liter).

   b. Intermediate Coat: Latex, exterior, matching topcoat.
   c. Topcoat: Latex, exterior, flat.

      1) S-W A-100 Exterior Latex Flat, A6 Series, at 4.0 mils (0.102 mm) wet, 1.2 mils (0.030 mm) dry, per coat.

   d. Topcoat: Latex, exterior, low sheen.

      1) S-W A-100 Exterior Latex Low Sheen, A12 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

   e. Topcoat: Latex, exterior, satin.

      1) S-W A-100 Exterior Latex Satin, A82 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

   f. Topcoat: Latex, exterior, semi-gloss.

      1) S-W Solo Acrylic Semi-Gloss, A76 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

   g. Topcoat: Latex, exterior, gloss.

      1) S-W A-100 Exterior Latex Gloss, A8 Series, at 4.0 mils (0.102 mm) wet, 1.3 mils (0.033 mm) dry, per coat.

2. CMU Stain System (Water-Based):

   a. First Coat: Low-luster opaque finish matching topcoat.
   b. Topcoat: Low-luster opaque finish.

      1) S-W H&C Colortop Water-Based Solid Color Concrete Stain, at 50 to 250 sq. ft. per gal. (1.23 to 6.14 sq. m per liter).

C. Ferrous Metal, Galvanized-Metal, and Aluminum Substrates:

1. Water-Based Light Industrial Coating System:

   a. Prime Coat: Primer, water based.

      1) S-W Pro Industrial Pro-Cryl Universal Primer, B66-310 Series, 5.0 to 10.0 mils (0.127 to 0.254 mm) wet, 2.0 to 4.0 mils (0.051 to 0.102 mm) dry.

   b. Intermediate Coat: Light industrial coating, exterior, water based, matching topcoat.
   c. Topcoat: Light industrial coating, exterior, water based eggshell.

1) S-W Pro Industrial Eg-Shel Acrylic B66-660 Series, at 2.5 to 4.0 mils (0.064 to 0.102 mm) dry, per coat.

d. Topcoat: Light industrial coating, exterior, water based, semi-gloss.

1) S-W Pro Industrial Acrylic Semi-Gloss Coating, B66-650 Series, at 2.5 to 4.0 mils (0.064 to 0.102 mm) dry, per coat.

e. Topcoat: Light industrial coating, exterior, water based, gloss.

1) S-W Pro Industrial Acrylic Gloss Coating, B66-600 Series, at 2.5 to 4.0 mils (0.064 to 0.102 mm) dry, per coat.

D. Wood Substrates: Including exposed wood items not indicated to receive shop-applied finish.

1. Latex System:

a. Prime Coat: Primer, latex for exterior wood.

1) S-W Exterior Latex Primer, B42, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry, per coat.

b. Intermediate Coat: Latex, exterior, matching topcoat.
c. Topcoat: Latex, exterior, flat:

1) S-W A-100 Exterior Latex Flat, A6 Series, at 4.0 mils (0.102 mm) wet, 1.2 mils (0.030 mm) dry, per coat.

d. Topcoat: Latex, exterior, low-sheen:

1) S-W A-100 Exterior Latex Low Sheen, A12 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

e. Topcoat: Latex, exterior, satin:

1) S-W A-100 Exterior Latex Satin, A82 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

f. Topcoat: Latex, exterior, semi-gloss:

1) S-W Solo Acrylic Semi-Gloss, A76 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

g. Topcoat: Latex, exterior, gloss:

1) S-W A-100 Exterior Latex Gloss, A8 Series, at 4.0 mils (0.102 mm) wet, 1.3 mils (0.033 mm) dry, per coat.

E. Plastic Trim Fabrication Substrates: Including architectural PVC, plastic, and fiberglass items.

1. Latex System:

a. Prime Coat: Primer, bonding, water-based:

1) S-W PrepRite ProBlock Latex Primer/Sealer, B57-620 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry.

b. Intermediate Coat: Latex, exterior, matching topcoat.

a. Topcoat: Latex, exterior, flat:

1) S-W A-100 Exterior Latex Flat, A6 Series, at 4.0 mils (0.102 mm) wet, 1.2 mils (0.030 mm) dry, per coat.

b. Topcoat: Latex, exterior, low-sheen:

1) S-W A-100 Exterior Latex Low Sheen, A12 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

c. Topcoat: Latex, exterior, satin:

1) S-W A-100 Exterior Latex Satin, A82 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

d. Topcoat: Latex, exterior, semi-gloss:

1) S-W Solo Acrylic Semi-Gloss, A76 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

e. Topcoat: Latex, exterior, gloss:

1) S-W A-100 Exterior Latex Gloss, A8 Series, at 4.0 mils (0.102 mm) wet, 1.3 mils (0.033 mm) dry, per coat.

END OF SECTION 099113

SECTION 099123 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes surface preparation and the application of paint systems on interior substrates.

B. Related Requirements:

1. Section 051200 "Structural Steel Framing" for shop priming of metal substrates with primers specified in this section.
2. Section 099113 "Exterior Painting" for surface preparation and the application of paint systems on exterior substrates.
3. Section 099600 "High-Performance Coatings" for tile-like coatings.
4. Section 131250 "Metal Building Systems" for shop priming structural steel framing of pre-engineered metal building with primers specified in this section.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

1. Indicate VOC content.

B. Samples for Verification: For each type of paint system and in each color and gloss of topcoat.

1. Submit Samples on rigid backing, 8 inches (200 mm) square.
2. Label each coat of each Sample.
3. Label each Sample for location and application area.

C. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. Indicate VOC content.

1.4 CLOSEOUT SUBMITTALS

1. Coating Maintenance Manual: Provide coating maintenance manual including area summary with finish schedule, area detail designating location where each

product/color/finish was used, product data pages, material safety data sheets, care and cleaning instructions, touch-up procedures, and color samples of each color and finish used.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: 1 gal. (3.8 L) of each material and color applied.

1.6 QUALITY ASSURANCE

A. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.

a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft. (9 sq. m).
b. Other Items: Architect will designate items or areas required.

2. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.

3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Delivery and Handling: Deliver products to Project site in an undamaged condition in manufacturer's original sealed containers, complete with labels and instructions for handling, storing, unpacking, protecting, and installing. Packaging shall bear the manufacturer’s label with the following information:

1. Product name and type (description).
2. Batch date.
3. Color number.
4. VOC content.
5. Environmental handling requirements.
6. Surface preparation requirements.
7. Application instructions.

B. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F (7 deg C).

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.8 FIELD CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F (10 and 35 deg C).

B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Sherwin-Williams Company (The); products indicated or comparable product from one of the following:

1. Behr Paint.
2. Benjamim Moore.
3. Pittsburgh Paint Company.

B. Comparable Products: Comparable products of approved manufacturers will be considered in accordance with Section 016000 "Product Requirements," and the following:

1. Products are approved by manufacturer in writing for application specified.
2. Products meet performance and physical characteristics of basis of design product including published ratio of solids by volume, plus or minus two percent.

C. Source Limitations: Obtain paint materials from single source from single listed manufacturer.

1. Manufacturer's designations listed on a separate color schedule are for color reference only and do not indicate prior approval.

2.2 PAINT, GENERAL

A. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.

B. VOC Content: For field applications that are inside the weatherproofing system, paints and coatings shall provide materials that comply with VOC limits of authorities having jurisdiction and for interior paints and coatings applied at Project site, the following VOC limits exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

1. Flat Paints and Coatings: 50 g/L.
2. Nonflat Paints and Coatings: 150 g/L.
3. Primers, Sealers, and Undercoaters: 200 g/L.
4. Anticorrosive and Antirust Paints Applied to Ferrous Metals: 250 g/L.
5. Floor Coatings: 100 g/L.

C. Colors: As indicated in a color schedule.

1. [**10**] [**20**] [**30**] percent of surface area will be painted with deep tones.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers. Where acceptability of substrate conditions is in question, apply samples and perform in-situ testing to verify compatibility, adhesion, and film integrity of new paint application.

1. Report, in writing, conditions that may affect application, appearance, or performance of paint.

B. Substrate Conditions:

1. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

a. Concrete: 12 percent.
b. Masonry (Clay and CMU): 12 percent.
c. Wood: 15 percent.
d. Gypsum Board: 12 percent.

2. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.

C. Proceed with coating application only after unsatisfactory conditions have been corrected; application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

1. Concrete Floors: Remove oil, dust, grease, dirt, and other foreign materials. Comply with SSPC-SP-13/NACE 6 or ICRI 03732.

E. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceed that permitted in manufacturer's written instructions.

F. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer but not less than the following:

1. SSPC-SP 3, "Power Tool Cleaning."

G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal fabricated from coil stock by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

I. Aluminum Substrates: Remove loose surface oxidation.

J. Wood Substrates:

1. Scrape and clean knots, and apply coat of knot sealer before applying primer.
2. Sand surfaces that will be exposed to view, and dust off.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

K. Cotton or Canvas Insulation Covering Substrates: Remove dust, dirt, and other foreign material that might impair bond of paints to substrates.

3.3 APPLICATION

A. Apply paints according to manufacturer's written instructions and to recommendations in "MPI Manual."

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.

B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

E. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:

1. Paint the following work where exposed in equipment rooms:

a. Equipment, including panelboards and switch gear.
b. Uninsulated metal piping.
c. Uninsulated plastic piping.
d. Pipe hangers and supports.
e. Metal conduit.
f. Plastic conduit.
g. Tanks that do not have factory-applied final finishes.
h. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.

2. Paint the following work where exposed in occupied spaces:

a. Equipment, including panelboards.
b. Uninsulated metal piping.
c. Uninsulated plastic piping.
d. Pipe hangers and supports.
e. Metal conduit.
f. Plastic conduit.

g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
h. Other items as directed by Architect.

3. Paint portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets that are visible from occupied spaces.

3.4 FIELD QUALITY CONTROL

A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.

1. Contractor shall touch up and restore painted surfaces damaged by testing.
2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.6 INTERIOR PAINTING SCHEDULE

A. Concrete Substrates, Pedestrian Traffic Surfaces:

1. Epoxy- and Urethane- Based Aggregate-Filled Floor Surfacing: Refer to Section 09 67 23 "Resinous Flooring."

B. CMU Substrates:

1. Latex System:

a. Block Filler: Block filler, latex, interior/exterior:

1) S-W PrepRite Block Filler, B25W25, at 75-125 sq. ft. per gal. (1.84 to 3.07 sq. m per liter).

b. Intermediate Coat: Latex, interior, matching topcoat.

c. Topcoat: Latex, interior, flat:

1) S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

d. Topcoat: Latex, interior, low sheen:

1) S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

e. Topcoat: Latex, interior, eggshell:

1) S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series, at 4.0 mils (0.102 mm) wet, 1.7 mils (0.043 mm) dry, per coat.

f. Topcoat: Latex, interior, semi-gloss:

1) S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

g. Topcoat: Latex, interior, gloss:

1) S-W ProMar 200 Zero VOC Gloss, B21-12650 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

2. Water-Based Light Industrial Coating System:

a. Block Filler: Block filler, latex, interior/exterior:

1) S-W PrepRite Block Filler, B25W25, at 75-125 sq. ft. per gal. (1.84 to 3.07 sq. m per liter).

b. Intermediate Coat: Light industrial coating, interior, water based, matching topcoat.
c. Topcoat: Light industrial coating, interior, water based, eggshell:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K45-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

d. Topcoat: Light industrial coating, interior, water based, semi-gloss:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K46-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

3. Two-Component Epoxy and Epoxy High Build Systems for Non-Traffic Surfaces: Refer to Section 099600 "High-Performance Coatings."
4. Epoxy and Urethane Coatings: Refer to Section 099600 "High-Performance Coatings."

C. Metal Substrates (Aluminum, Steel, Galvanized Steel):

1. Latex System:

a. Prime Coat: Primer, rust-inhibitive, water based:

1) S-W Pro Industrial Pro-Cryl Universal Primer, B66-310 Series, at 5.0 to 10 mils (0.127 to 0.254 mm) wet, 2.0 to 4.0 mils (0.051 to 0.102 mm) dry.

b. Intermediate Coat: Water-based acrylic, interior, matching topcoat.
c. Topcoat: Water-based acrylic, semi-gloss:

1) S-W Pro Industrial Acrylic Semi-Gloss Coating, B66-650 Series, at 2.5 to 4.0 mils (0.064 to 0.102 mm) dry, per coat.

d. Topcoat: Water-based acrylic, gloss:

1) S-W Pro Industrial Acrylic Gloss Coating, B66-660 Series, at 2.5 to 4.0 mils (0.064 to 0.102 mm) dry, per coat.

2. Water-Based Dry-Fall System:

a. Top Coat: Dry-fall latex, flat:

1) S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-181 Series, at 6.0 mils (0.152 mm) wet, 1.5 mils (0.038 mm) dry.

b. Top Coat: Dry-fall latex, eggshell:

1) S-W Pro Industrial Waterborne Acrylic DryFall Eg-Shel, B42-82, at 6.0 mils (0.152 mm) wet, 1.9 mils (0.048 mm) dry.

c. Top Coat: Dry-fall latex, semi-gloss:

1) S-W Pro Industrial Waterborne Acrylic DryFall Semi-Gloss, B42-83, at 5.8 mils (0.147 mm) wet, 2.3 mils (0.058 mm) dry.

3. Water-Based Light Industrial Coating System:

a. Prime Coat: Primer, rust-inhibitive, water based:

1) S-W Pro Industrial Pro-Cryl Universal Primer, B66-310 Series, at 5.0 to 10 mils (0.127 to 0.254 mm) wet, 2.0 to 4.0 mils (0.051 to 0.102 mm) dry.

b. Intermediate Coat: Light industrial coating, interior, water based, matching topcoat.
c. Topcoat: Light industrial coating, interior, water based, eggshell:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K45-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

d. Topcoat: Light industrial coating, interior, water based, semi-gloss:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K46-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

4. Two-Component Epoxy and Epoxy High Build Systems: Refer to Section 099600 "High-Performance Coatings."
5. Waterbased/Alkyd Urethane System:

a. Prime Coat:

1) S-W Pro Industrial Pro-Cryl Universal Primer, B66-310 Series, at 5.0 to 10 mils (0.127 to 0.254 mm) wet, 2.0 to 4.0 mils (0.051 to 0.102 mm) dry.

b. Intermediate Coat: Water-based acrylic-alkyd, interior, matching topcoat.
c. Topcoat: Water-based alkyd-urethane, semi-gloss, interior:

1) S-W Pro Industrial Waterbased Alkyd Urethane Semi-Gloss, B53-1150 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry, per coat.

d. Topcoat: Water-based alkyd-urethane, gloss, interior:

1) S-W Pro Industrial Waterbased Alkyd Urethane Gloss, B53-1050 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry, per coat.

D. Wood Substrates: Including exposed wood items not indicated to receive shop-applied finish.

1. Latex System:

a. Prime Coat: Primer sealer, latex, interior:

1) S-W PrepRite ProBlock Primer Sealer, B51-620 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry.

b. Intermediate Coat: Latex, interior, matching topcoat.
c. Topcoat: Latex, interior, eggshell:

1) S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series, at 4.0 mils (0.102 mm) wet, 1.7 mils (0.043 mm) dry, per coat.

d. Topcoat: Latex, interior, semi-gloss:

1) S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

e. Topcoat: Latex, interior, gloss:

1) S-W ProMar 200 Zero VOC Gloss, B21-12650 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

2. Waterbased/Alkyd Urethane System:

a. Prime Coat: Primer sealer, latex, interior:

1) S-W Premium Wall & Wood Primer, B28W8111, at 4.0 mils (0.102 mm) wet, 1.8 mils (0.046 mm) dry.

b. Intermediate Coat: Water-based alkyd-urethane, interior, matching topcoat.
c. Topcoat: Water-based alkyd-urethane, semi-gloss, interior:

1) S-W Pro Industrial Waterbased Alkyd Urethane Semi-Gloss, B53-1150 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry, per coat.

d. Topcoat: Water-based alkyd-urethane, gloss, interior:

1) S-W Pro Industrial Waterbased Alkyd Urethane Gloss, B53-1050 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry, per coat.

3. Water-Based Light Industrial Coating System:

a. Prime Coat: Primer sealer, latex, interior:

1) S-W PrepRite ProBlock Primer Sealer, B51-620 Series, at 4.0 mils (0.102 mm) wet, 1.4 mils (0.036 mm) dry.

b. Intermediate Coat: Light industrial coating, interior, water based, matching topcoat.
c. Topcoat: Light industrial coating, interior, water based, eggshell:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K45-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

d. Topcoat: Light industrial coating, interior, water based, semi-gloss:

1) S-W Pro Industrial Pre-Catalyzed Water Based Epoxy, K46-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

4. Two-Component Epoxy and Epoxy High Build Systems: Refer to Section 099600 "High-Performance Coatings."

E. Gypsum Board Substrates:

1. Latex System:

a. Prime Coat: Primer, latex, interior:

1) S-W ProMar 200 Zero VOC Latex Primer, B28W2600, at 4.0 mils (0.102 mm) wet, 1.0 mils (0.025 mm) dry.

b. Intermediate Coat: Latex, interior, matching topcoat.
c. Topcoat: Latex, interior, flat:

1) S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

d. Topcoat: Latex, interior, low sheen:

1) S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

e. Topcoat: Latex, interior, eggshell:

1) S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series, at 4.0 mils (0.102 mm) wet, 1.7 mils (0.043 mm) dry, per coat.

f. Topcoat: Latex, interior, semi-gloss:

1) S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series, at 4.0 mils (0.102 mm) wet, 1.6 mils (0.041 mm) dry, per coat.

g. Topcoat: Latex, interior, gloss:

1) S-W ProMar 200 Zero VOC Gloss, B21-12650 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

2. Water-Based Light Industrial Coating System:

a. Prime Coat: Primer sealer, latex, interior:

1) S-W ProMar 200 Zero VOC Latex Primer, B28W2600, at 4.0 mils (0.102 mm) wet, 1.0 mils (0.025 mm) dry.

b. Intermediate Coat: Light industrial coating, interior, water based, matching topcoat.
c. Topcoat: Light industrial coating, interior, water based, eggshell:

1) S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

d. Topcoat: Light industrial coating, interior, water based, semi-gloss:

1) S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-151 Series, at 4.0 mils (0.102 mm) wet, 1.5 mils (0.038 mm) dry, per coat.

3. Two-Component Epoxy and Epoxy High Build Systems for Non-Traffic Surfaces: Refer to Section 099600 "High-Performance Coatings."

END OF SECTION 099123

SECTION 101100 - VISUAL DISPLAY UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Visual display board assemblies.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, finishes, and accessories for visual display units.
2. Include electrical characteristics for motorized units.

B. Shop Drawings: For visual display units.

1. Include plans, elevations, sections, details, and attachment to other work.
2. Show locations and layout of special-purpose graphics.
3. Include sections of typical trim members.

C. Samples for Initial Selection: For each type of visual display unit indicated, for units with factory-applied color finishes, and as follows:

1. Samples of facings for each visual display panel type, indicating color and texture.
2. Fabric swatches of fabric facings for tackboards.
3. Include accessory Samples to verify color selected.

D. Samples for Verification: For each type of visual display unit indicated.

1. Visual Display Panel: Not less than 8-1/2 by 11 inches (215 by 280 mm), with facing, core, and backing indicated for final Work. Include one panel for each type, color, and texture required.
2. Trim: 6-inch- (150-mm-) long sections of each trim profile.
3. Accessories: Full-size Sample of each type of accessory.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Product Test Reports: For each visual display unit, for tests performed by manufacturer and witnessed by a qualified testing agency.

C. Sample Warranties: For manufacturer's special warranties.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For visual display units to include in maintenance manuals.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver factory-fabricated visual display units completely assembled in one piece. If dimensions exceed maximum manufactured unit size, or if unit size is impracticable to ship in one piece, provide two or more pieces with joints in locations indicated on approved Shop Drawings.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install visual display units until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.8 WARRANTY

A. Special Warranty for Porcelain-Enamel Face Sheets: Manufacturer agrees to repair or replace porcelain-enamel face sheets that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

    a. Surfaces lose original writing and erasing qualities.
    b. Surfaces exhibit crazing, cracking, or flaking.

2. Warranty Period: Life of the building.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 450 or less.

2.2 VISUAL DISPLAY BOARD ASSEMBLY

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. AARCO Products, Inc.
2. ADP/Lemco, Inc.
3. Bangor Cork Company, Inc.
4. Best-Rite Manufacturing.
5. Claridge Products & Equipment, Inc.
6. Egan Visual, Inc.
7. Ghent Manufacturing, Inc.
8. Marsh Industries, Inc.
9. Platinum Visual Systems; Division of ABC School Equipment, Inc.
10. PolyVision Corporation.

B. Visual Display Board Assembly: Factory fabricated.

1. Assembly: Markerboard and tackboard.
2. Corners: Square.
3. Width: As indicated on Drawings.
4. Height: As indicated on Drawings.
5. Mounting Method: Direct to wall.

C. Markerboard Panel: Porcelain-enamel-faced markerboard panel on core indicated.

1. Color: White.

D. Tackboard Panel: Vinyl-fabric-faced tackboard panel on core indicated.

1. Fabric Wrapped Edge: Wrap edge of tackboard panel with fabric facing.
2. Color and Pattern: As selected by Architect from full range of industry colors.

E. Aluminum Frames and Trim: Fabricated from not less than 0.062-inch- (1.57-mm-) thick, extruded aluminum; standard size and shape.

1. Aluminum Finish: Clear anodic finish.

F. Combination Assemblies: Provide hidden spline between abutting sections of visual display panels.

G. Chalktray: Manufacturer's standard; continuous.

1. Box Type: Extruded aluminum with slanted front, grooved tray, and cast-aluminum end closures.
2. Solid Type: Extruded aluminum with ribbed section and smoothly curved exposed ends.

H. Display Rail: Manufacturer's standard, extruded-aluminum display rail with plastic-impregnated-cork insert, end stops, designed to hold accessories.

1. Size: 1 inch (25 mm) to 2 inches (50 mm) high by full length of visual display unit.
2. Map Hooks and Clips: Two map hooks with flexible metal clips for every 48 (1200) inches (mm) of display rail or fraction thereof.
3. Tackboard Insert Color: Match color of tackboard panel.
4. Aluminum Color: Match finish of visual display assembly trim.

2.3 MARKERBOARD PANELS

A. Porcelain-Enamel Markerboard Panels: Balanced, high-pressure, factory-laminated markerboard assembly of three-ply construction, consisting of moisture-barrier backing, core material, and porcelain-enamel face sheet with high-gloss finish. Laminate panels under heat and pressure with manufacturer's standard, flexible waterproof adhesive.

1. Manufacturer's Standard Core: Minimum 1/4 inch (6 mm) thick, with manufacturer's standard moisture-barrier backing.
2. Laminating Adhesive: Manufacturer's standard moisture-resistant thermoplastic type.

2.4 TACKBOARD PANELS

A. Tackboard Panels:

1. Facing: Vinyl fabric factory laminated to 1/8-inch- (3-mm-) thick, cork sheet.
2. Core: Manufacturer's standard.

2.5 MATERIALS

A. Porcelain-Enamel Face Sheet: PEI-1002, with face sheet manufacturer's standard two- or three-coat process.

B. Natural-Cork Sheet: Seamless, single-layer, compressed fine-grain cork sheet; bulletin board quality; face sanded for natural finish; with surface-burning characteristics indicated.

C. Plastic-Impregnated-Cork Sheet: Seamless, homogeneous, self-sealing sheet consisting of granulated cork, linseed oil, resin binders, and dry pigments that are mixed and calendared onto fabric backing; with washable vinyl finish and integral color throughout; with surface-burning characteristics indicated.

D. Vinyl Fabric: Mildew resistant, washable, complying with ASTM F793/F793M, Type II, burlap weave; weighing not less than 13 oz./sq. yd. (440 g/sq. m); with surface-burning characteristics indicated.

E. Fiberboard: ASTM C208 cellulosic fiber insulating board.

F. Extruded Aluminum: ASTM B221 (ASTM B221M), Alloy 6063.

G. Adhesives for Field Application: Mildew-resistant, nonstaining adhesive for use with specific type of panels, sheets, or assemblies; and for substrate application; as recommended in writing by visual display unit manufacturer.

H. Primer/Sealer: Mildew-resistant primer/sealer complying with requirements in Section 099123 "Interior Painting" and recommended in writing by visual display unit manufacturer for intended substrate.

2.6 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM/NOMMA 500 for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.7 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, surface conditions of wall, and other conditions affecting performance of the Work.

B. Examine roughing-in for electrical power systems to verify actual locations of connections before installation of motorized, sliding visual display units.

C. Examine walls and partitions for proper preparation and backing for visual display units.

D. Examine walls and partitions for suitable framing depth where sliding visual display units will be installed.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Comply with manufacturer's written instructions for surface preparation.

B. Clean substrates of substances, such as dirt, mold, and mildew, that could impair the performance of and affect the smooth, finished surfaces of visual display boards.

C. Prepare surfaces to achieve a smooth, dry, clean surface free of flaking, unsound coatings, cracks, defects, projections, depressions, and substances that will impair bond between visual display units and wall surfaces.

D. Prime wall surfaces indicated to receive visual display units and as recommended in writing by primer/sealer manufacturer and visual display unit manufacturer.

E. Prepare recesses for sliding visual display units as required by type and size of unit.

3.3 INSTALLATION

A. General: Install visual display surfaces in locations and at mounting heights indicated on Drawings, or if not indicated, at heights indicated below. Keep perimeter lines straight, level, and plumb. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.

B. Factory-Fabricated Visual Display Board Assemblies: Attach concealed clips, hangers, and grounds to wall surfaces and to visual display board assemblies with fasteners at not more than 16 inches (400 mm) o.c. Secure tops and bottoms of boards to walls.

C. Visual Display Board Assembly Mounting Heights: Install visual display units at mounting heights indicated on Drawings, or if not indicated, at heights indicated below.

1. Mounting Height: 36 (914) inches (mm) above finished floor to top of chalktray.

3.4 CLEANING AND PROTECTION

A. Clean visual display units in accordance with manufacturer's written instructions. Attach one removable cleaning instructions label to visual display unit in each room.

B. Touch up factory-applied finishes to restore damaged or soiled areas.

C. Cover and protect visual display units after installation and cleaning.

END OF SECTION 101100

SECTION 101419 - DIMENSIONAL LETTER SIGNAGE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Cast dimensional characters.

1.3 ALLOWANCES

A. Allowances for signage are specified in Section 012100 "Allowances."

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For signs.

1. Include fabrication and installation details and attachments to other work.
2. Show sign mounting heights, locations of supplementary supports to be provided by other installers, and accessories.
3. Show message list, typestyles, graphic elements, and layout for each sign.

C. Samples for Initial Selection: For each type of sign assembly, exposed component, and exposed finish.

D. Samples for Verification: For each type of sign assembly showing all components and with the required finish(es), in manufacturer's standard size unless otherwise indicated and as follows:

1. Dimensional Characters: Full-size Sample of each type of dimensional character.
2. Full-size Samples, if approved, will be returned to Contractor for use in the Project.

E. Product Schedule: For dimensional letter signs. Use same designations indicated on Drawings or specified.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Sample Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For signs to include in maintenance manuals.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors with a minimum of five years of experience in successful installation of work similar to that required.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Deterioration of finishes beyond normal weathering.
b. Separation or delamination of sheet materials and components.

2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 DIMENSIONAL CHARACTERS

A. Cast Characters: Characters with uniform faces, sharp corners, and precisely formed lines and profiles, and as follows:

1. Character Material: Cast aluminum.
2. Character Height: As indicated.
3. Thickness: Manufacturer's standard for size of character.
4. Finishes:

a. Powder-Coat Finish: Manufacturer's standard, in color as selected by Architect from manufacturer's full range.

5. Mounting: Projecting studs.
6. Typeface: Arial Narrow.
7. Number of Letters: Provide a minimum of 45 letters, see drawings for exact wording.

2.2 DIMENSIONAL CHARACTER MATERIALS

A. Aluminum Castings: ASTM B26/B26M, alloy and temper recommended by sign manufacturer for casting process used and for type of use and finish indicated.

B. Paints and Coatings for Sheet Materials: Inks, dyes, and paints that are recommended by manufacturer for optimum adherence to surface and are UV and water resistant for colors and exposure indicated.

2.3 ACCESSORIES

A. Fasteners and Anchors: Manufacturer's standard as required for secure anchorage of signs, noncorrosive and compatible with each material joined, and complying with the following:

1. Use concealed fasteners and anchors unless indicated to be exposed.
2. Exposed Metal-Fastener Components, General:

    a. Fabricated from same basic metal and finish of fastened metal unless otherwise indicated.

3. Sign Mounting Fasteners:

    a. Projecting Studs: Threaded studs with sleeve spacer, welded or brazed to back of sign material, screwed into back of sign assembly, or screwed into tapped lugs cast integrally into back of cast sign material, unless otherwise indicated.

B. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

2.4 FABRICATION

A. General: Provide manufacturer's standard sign assemblies according to requirements indicated.

1. Comply with AWS for recommended practices in welding and brazing. Provide welds and brazes behind finished surfaces without distorting or discoloring exposed side. Clean exposed welded and brazed connections of flux, and dress exposed and contact surfaces.
2. Provide rabbets, lugs, and tabs necessary to assemble components and to attach to existing work. Drill and tap for required fasteners. Use concealed fasteners where possible; use exposed fasteners that match sign finish.
3. Castings: Fabricate castings free of warp, cracks, blowholes, pits, scale, sand holes, and other defects that impair appearance or strength. Grind, wire brush, sandblast, and buff castings to remove seams, gate marks, casting flash, and other casting marks before finishing.

2.5 GENERAL FINISH REQUIREMENTS

A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.6 ALUMINUM FINISHES

A. Baked-Enamel or Powder-Coat Finish: AAMA 2603 except with a minimum dry film thickness of 1.5 mils (0.04 mm). Comply with coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance.

B. Verify that sign-support surfaces are within tolerances to accommodate signs without gaps or irregularities between backs of signs and support surfaces unless otherwise indicated.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install signs using mounting methods indicated and according to manufacturer's written instructions.

1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.
2. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.
3. Corrosion Protection: Coat concealed surfaces of exterior aluminum in contact with grout, concrete, masonry, wood, or dissimilar metals, with a heavy coat of bituminous paint.

B. Mounting Methods:

1. Projecting Studs: Using a template, drill holes in substrate aligning with studs on back of sign. Remove loose debris from hole and substrate surface.

a. Masonry Substrates: Fill holes with adhesive. Leave recess space in hole for displaced adhesive. Place spacers on studs, place sign in position, and push until spacers are pinched between sign and substrate, embedding the stud ends in holes. Temporarily support sign in position until adhesive fully sets.
b. Thin or Hollow Surfaces: Place spacers on studs, place sign in position with spacers pinched between sign and substrate, and install washers and nuts on stud ends projecting through opposite side of surface, and tighten.

3.3 ADJUSTING AND CLEANING

A. Remove and replace damaged or deformed characters and signs that do not comply with specified requirements. Replace characters with damaged or deteriorated finishes or

components that cannot be successfully repaired by finish touchup or similar minor repair procedures.

B. Remove temporary protective coverings and strippable films as signs are installed.

C. On completion of installation, clean exposed surfaces of signs according to manufacturer's written instructions, and touch up minor nicks and abrasions in finish. Maintain signs in a clean condition during construction and protect from damage until acceptance by Owner.

END OF SECTION 101419

SECTION 102113.19 - PLASTIC TOILET COMPARTMENTS

PART 1 - GENERAL

1.1 GENERAL

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Solid-plastic toilet compartments configured as toilet enclosures and urinal screens.

B. Related Requirements:

1. Section 092216 "Non-Structural Metal Framing" for blocking.
2. Section 102800 "Toilet, Bath, and Laundry Accessories" for accessories mounted on toilet compartments.

1.3 COORDINATION

A. Coordinate requirements for overhead supports, blocking, reinforcing, and other supports concealed within wall.

1.4 ACTION SUBMITTALS

A. Product Data:

1. Solid-plastic toilet compartments:

a. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for toilet compartments.

B. Shop Drawings: For solid-plastic toilet compartments.

1. Include plans, elevations, sections, details, and attachment details.
2. Show locations of cutouts for compartment-mounted toilet accessories.
3. Show locations of centerlines of toilet fixtures.
4. Show locations of floor drains.

C. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of toilet compartment material indicated.

1. Include Samples of hardware and accessories involving material and color selection.

D. Samples for Verification: Actual sample of finished products for each type of toilet compartment indicated.

1. Size: Manufacturers? standard size.

1.5 INFORMATIONAL SUBMITTALS

A. Certificates:

1. Product Certificates: For each type of toilet compartment by manufacturer.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For toilet compartments.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Door Hinges: One hinge(s) with associated fasteners.
2. Latch and Keeper: One latch(es) and keeper(s) with associated fasteners.
3. Door Bumper: One bumper(s) with associated fasteners.
4. Door Pull: One door pull(s) with associated fasteners.
5. Fasteners: 10 fasteners of each size and type.

1.8 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of toilet fixtures, walls, columns, ceilings, and other construction contiguous with toilet compartments by field measurements, and coordinate before fabrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire Performance: Tested in accordance with, and pass the acceptance criteria of, NFPA 286.

B. Regulatory Requirements: Comply with applicable provisions in ICC A117.1 for toilet compartments designated as accessible.

2.2 SOLID-PLASTIC TOILET COMPARTMENTS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Accurate Partitions, Inc. (ASI).
2. AccuTec Manufacturing, Inc.
3. All American Metal Corporation (AAMCO).
4. American Sanitary Partition Corporation
5. Bradley Corporation; Bradmar Partitions.
6. Hadrian.
7. Metpar Corporation.
8. Rockville Partitions.
9. Santana products, Inc.

B. Toilet-Enclosure Style: Overhead braced.

C. Urinal-Screen Style: Wall hung.

D. Door, Panel, and Pilaster Construction: Solid, high-density polyethylene (HDPE) panel material, not less than 1 inch (25 mm) thick, seamless, with eased edges, and with homogenous color and pattern throughout thickness of material.

1. Heat-Sink Strip: Manufacturer's standard continuous, extruded-aluminum or stainless steel strip fastened to exposed bottom edges of solid-plastic components to hinder malicious combustion.
2. Color and Pattern: Two colors and patterns in each room as selected by Architect from manufacturer's full range.

E. Pilaster Shoes and Sleeves (Caps): Manufacturer's standard design; polymer or stainless steel.

1. Polymer Color and Pattern: Matching pilaster.

F. Brackets (Fittings):

1. Full-Height (Continuous) Type: Manufacturer's standard design; polymer or extruded aluminum.

a. Polymer Color and Pattern: Matching panel.

2.3 HARDWARE AND ACCESSORIES

A. Hardware and Accessories, Heavy Duty: Manufacturer's heavy-duty operating hardware and accessories.

1. Hinges: Manufacturer's minimum 0.062-inch- (1.59-mm-) thick stainless steel paired, self-closing type that can be adjusted to hold doors open at any angle up to 90 degrees, allowing emergency access by lifting door. Mount with through bolts.
2. Latch and Keeper: Manufacturer's heavy-duty, surface-mounted, cast-stainless steel latch unit, designed to resist damage due to slamming, with combination rubber-faced door strike and keeper, and with provision for emergency access. Provide units that comply with regulatory requirements for accessibility at compartments designated as accessible. Mount with through bolts.

3. Coat Hook: Manufacturer's heavy-duty combination cast-stainless steel hook and rubber-tipped bumper, sized to prevent inswinging door from hitting compartment-mounted accessories. Mount with through bolts.
4. Door Bumper: Manufacturer's heavy-duty, rubber-tipped, cast-stainless steel bumper at outswinging doors. Mount with through bolts.
5. Door Pull: Manufacturer's heavy-duty, cast-stainless steel pull at outswinging doors that complies with regulatory requirements for accessibility. Provide units on both sides of doors at compartments designated as accessible. Mount with through bolts.

B. Overhead Bracing: Manufacturer's standard continuous, extruded-aluminum head rail with antigrip profile and in manufacturer's standard finish.

C. Anchorages and Fasteners: Manufacturer's standard exposed fasteners of stainless steel, finished to match the items they are securing, with theft-resistant-type heads. Provide sex-type bolts for through-bolt applications. For concealed anchors, use stainless steel, hot-dip galvanized steel, or other rust-resistant, protective-coated steel compatible with related materials.

2.4 MATERIALS

A. Aluminum Castings: ASTM B26/B26M.

B. Aluminum Extrusions: ASTM B221 (ASTM B221M).

C. Stainless Steel Sheet: ASTM A240/A240M or ASTM A666, Type 304, stretcher-leveled standard of flatness.

D. Stainless Steel Castings: ASTM A743/A743M.

E. Zamac: ASTM B86, commercial zinc-alloy die castings.

2.5 FABRICATION

A. Fabrication, General: Fabricate toilet compartment components to sizes indicated. Coordinate requirements and provide cutouts for through-partition toilet accessories where required for attachment of toilet accessories.

B. Overhead-Braced Units: Provide manufacturer's standard corrosion-resistant supports, leveling mechanism, and anchors at pilasters to suit floor conditions. Provide shoes at pilasters to conceal supports and leveling mechanism.

C. Door Size and Swings: Unless otherwise indicated, provide 24-inch- (610-mm-) wide, inswinging doors for standard toilet compartments and 36-inch- (914-mm-) wide, outswinging doors with a minimum 32-inch- (813-mm-) wide, clear opening for compartments designated as accessible.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions, with Installer present, for compliance with requirements for fastening, support, alignment, operating clearances, and other conditions affecting performance of the Work.

1. Confirm location and adequacy of blocking and supports required for installation.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF PLASTIC TOILET COMPARTMENTS

A. General: Comply with manufacturer's written installation instructions. Install units rigid, straight, level, and plumb. Secure units in position with manufacturer's recommended anchoring devices.

1. Maximum Clearances:

a. Pilasters and Panels: 1/2 inch (13 mm).
b. Panels and Walls: 1 inch (25 mm).

2. Full-Height (Continuous) Brackets: Secure panels to walls and to pilasters with full-height brackets.

a. Locate bracket fasteners, so holes for wall anchors occur in masonry or tile joints.
b. Align brackets at pilasters with brackets at walls.

B. Overhead-Braced Units: Secure pilasters to floor and level, plumb, and tighten. Set pilasters with anchors penetrating not less than 1-3/4 inches (44 mm) into structural floor unless otherwise indicated in manufacturer's written instructions. Secure continuous head rail to each pilaster with no fewer than two fasteners. Hang doors to align tops of doors with tops of panels and adjust, so tops of doors are parallel with overhead brace when doors are in closed position.

C. Urinal Screens: Attach with anchoring devices to suit supporting structure. Set units level and plumb, rigid, and secured to resist lateral impact.

3.3 ADJUSTING

A. Hardware Adjustment: Adjust and lubricate hardware according to hardware manufacturer's written instructions for proper operation. Set hinges on inswinging doors to hold doors open approximately 30 degrees from closed position when unlatched. Set hinges on outswinging doors to return doors to fully closed position.

END OF SECTION 102113.19

SECTION 102239 - FOLDING PANEL PARTITIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Manually operated, acoustical panel partitions.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for supports that attach supporting tracks to overhead structural system.
2. Section 092900 "Gypsum Board" for sound barrier construction above the ceiling at track.

1.3 DEFINITIONS

A. NRC: Noise Reduction Coefficient.

B. STC: Sound Transmission Class.

1.4 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For operable panel partitions.

1. Include plans, elevations, sections, attachment details, and numbered panel installation sequence.
2. Indicate stacking and operating clearances. Indicate location and installation requirements for hardware and track, blocking, and direction of travel.

C. Samples for Initial Selection: For each type of exposed material, finish, covering, or facing.

1. Include Samples of accessories involving color selection.

D. Samples for Verification: For each type of exposed material, finish, covering, or facing, prepared on Samples of size indicated below:

1. Panel Facing Material: Manufacturer's standard-size unit, not less than 3 inches (75 mm) square.
2. Panel Edge Material: Not less than 3 inches (75 mm) long.
3. Hardware: One of each exposed door-operating device.

E. Delegated-Design Submittal: For operable panel partitions.

1. Include design calculations for seismic restraints that brace tracks to structure above.

1.6 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Partition track, track supports and bracing, switches, turning space, and storage layout.
2. Suspended ceiling components.
3. Structural members to which suspension systems will be attached.
4. Size and location of initial access modules for acoustical tile.
5. Items penetrating finished ceiling including the following:

a. Lighting fixtures.
b. HVAC ductwork, outlets, and inlets.
c. Speakers.
d. Sprinklers.
e. Smoke detectors.
f. Access panels.

B. Setting Drawings: For embedded items and cutouts required in other work, including support-beam, mounting-hole template.

C. Qualification Data: For Installer.

D. Seismic Qualification Certificates: For operable panel partitions, tracks, accessories, and components, from manufacturer. Include seismic capacity of partition assemblies to remain in vertical position during a seismic event and the following:

1. Basis for Certification: Indicate whether certification is based on analysis, testing, or experience data, according to ASCE/SEI 7.
2. Detailed description of partition anchorage devices on which the certification is based and their installation requirements.

E. Product Certificates: For each type of operable panel partition.

F. Product Test Reports: For each operable panel partition, for tests performed by a qualified testing agency.

G. Sample Warranty: For manufacturer's special warranty.

1.7 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For operable panel partitions to include in maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

a. Panel finish facings and finishes for exposed trim and accessories. Include precautions for cleaning materials and methods that could be detrimental to finishes and performance.
b. Seals, hardware, track, track switches, carriers, and other operating components.

1.8 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Panel Finish-Facing Material: Furnish full width in quantity to cover both sides of two panels when installed.

1.9 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer, and who have no fewer than five years of experience installing products similar to those required for this Project.

1.10 DELIVERY, STORAGE, AND HANDLING

A. Protectively package and sequence panels in order for installation. Clearly mark packages and panels with numbering system used on Shop Drawings. Do not use permanent markings on panels.

1.11 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of operable panel partitions that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Faulty operation of operable panel partitions.
b. Deterioration of metals, metal finishes, and other materials beyond normal use.

2. Warranty Period: Three years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design seismic bracing of tracks to structure above.

B. Seismic Performance: Operable panel partitions shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

1. The term "withstand" means "the partition panels will remain in place without separation of any parts when subjected to the seismic forces specified."

C. Acoustical Performance: Provide operable panel partitions tested by a qualified testing agency for the following acoustical properties according to test methods indicated:

1. Sound-Transmission Requirements: Operable panel partition assembly tested for laboratory sound-transmission loss performance according to ASTM E90, determined by ASTM E413, and rated for not less than the STC indicated.
2. Noise-Reduction Requirements: Operable panel partition assembly, identical to partition tested for STC, tested for sound-absorption performance according to ASTM C423, and rated for not less than the NRC indicated.

D. Fire-Test-Response Characteristics: Provide panels with finishes complying with one of the following as determined by testing identical products by a testing and inspecting agency acceptable to authorities having jurisdiction:

1. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

a. Flame-Spread Index: 25 or less.
b. Smoke-Developed Index: 450 or less.

2. Fire Growth Contribution: Complying with acceptance criteria of local code and authorities having jurisdiction when tested according to NFPA 265 Method B Protocol or NFPA 286.

2.2 OPERABLE ACOUSTICAL PANELS

A. Operable Acoustical Panels: Partition system, including panels, seals, finish facing, suspension system, operators, and accessories.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Modernfold, Inc.; Acousti-Seal® Encore™ Single Panel, or comparable product from one of the following:

a. Kwik-Wall Company.

b. Moderco, Inc.
c. Panel Systems Manufacturing, Inc.

B. Panel Operation: Manually operated, individual panels.

C. Panel Construction: As required to support panel from suspension components and with reinforcement for hardware attachment. Fabricate panels with tight hairline joints and concealed fasteners. Fabricate panels so finished in-place partition is rigid; level; plumb; aligned, with tight joints and uniform appearance; and free of bow, warp, twist, deformation, and surface and finish irregularities.

D. Dimensions: Fabricate operable acoustical panel partitions to form an assembled system of dimensions indicated and verified by field measurements.

1. Panel Width: Standard widths.

E. STC: Not less than 56.

F. Panel Weight: 12 lb/sq. ft. (56 kg/sq. m) maximum.

G. Panel Thickness: Nominal dimension of 4.25 inches (88 mm).

H. Panel Materials:

1. VOC Content Requirements for Wet Applied Products: All adhesives and sealants wet-applied on site must meet the applicable chemical content requirements of SCAQMD Rule 1168, amended October 26, 2017, Adhesive and Sealant Applications, as analyzed by the methods specified in Rule 1168. The provisions of SCAQMD Rule 1168 do not apply to adhesives and sealants subject to state or federal consumer product VOC regulations.

a. Do not use adhesives that contain urea formaldehyde.

2. Steel Frame: Steel sheet, manufacturer's standard nominal minimum thickness for uncoated steel.
3. Steel Face/Liner Sheets: Tension-leveled steel sheet, 0.0598-inch (1.5-mm) minimum nominal thickness for uncoated steel.

I. Panel Closure: Manufacturer's standard unless otherwise indicated.

1. Initial Closure: Fixed jamb at back of storage pocket.
2. Final Closure: Constant-force, lever-operated mechanical closure expanding from panel edge to create a constant-pressure acoustical seal.

J. Hardware: Manufacturer's standard as required to operate operable panel partition and accessories; with decorative, protective finish.

1. Hinges: Manufacturer's standard.

K. Finish Facing: Vinyl-coated fabric wall covering.

2.3 SEALS

A. Description: Seals that produce operable panel partitions complying with performance requirements and the following:

1. Manufacturer's standard seals unless otherwise indicated.
2. Seals made from materials and in profiles that minimize sound leakage.
3. Seals fitting tight at contact surfaces and sealing continuously between adjacent panels and between operable panel partition perimeter and adjacent surfaces, when operable panel partition is extended and closed.

B. Vertical Seals: Deep-nesting, interlocking steel astragals mounted on each edge of panel, with continuous, resilient acoustical seal.

C. Horizontal Top Seals: Resilient, mechanical, retractable, constant-force-contact seal exerting uniform constant pressure on track when extended.

D. Horizontal Bottom Seals: Resilient, mechanical, retractable, constant-force-contact seal exerting uniform constant pressure on floor when extended, ensuring horizontal and vertical sealing and resisting panel movement.

1. Automatically Operated for Acoustical Panels: Extension and retraction of bottom seal automatically operated by movement of partition, with operating range not less than 2 inches (50 mm) between retracted seal and floor finish.

2.4 PANEL FINISH FACINGS

A. Description: Finish facings for panels that comply with indicated fire-test-response characteristics and that are factory applied to operable panel partitions with appropriate backing, using mildew-resistant nonstaining adhesive as recommended by facing manufacturer's written instructions.

1. Apply one-piece, seamless facings free of air bubbles, wrinkles, blisters, and other defects, with no gaps or overlaps. Horizontal seams are not permitted. Tightly secure and conceal raw and selvage edges of facing for finished appearance.
2. Where facings with directional or repeating patterns or directional weave are indicated, mark facing top and attach facing in same direction.

B. Vinyl-Coated Fabric Wall Covering: Manufacturer's standard, mildew-resistant, washable, vinyl-coated fabric wall covering; complying with WA-101, Type III-Heavy Duty; Class A.

1. Total Weight: 30 oz. (850 g) per lineal foot.
2. Antimicrobial Treatment: Additives capable of inhibiting growth of bacteria, fungi, and yeasts.
3. Color/Pattern: As selected by Architect from manufacturer's full range.

C. Cap-Trimmed Edges: Protective perimeter-edge trim with tight hairline joints concealing edges of panel and finish facing, finished as follows:

1. Steel, Painted: Finished with manufacturer's standard neutral color.

2.5 SUSPENSION SYSTEMS

A. Tracks: Steel or aluminum with adjustable steel hanger rods for overhead support, designed for operation, size, and weight of operable panel partition indicated. Size track to support partition operation and storage without damage to suspension system, operable panel partitions, or adjacent construction. Limit track deflection to no more than 0.10 inch (2.54 mm) between bracket supports. Provide a continuous system of track sections and accessories to accommodate configuration and layout indicated for partition operation and storage.

1. Panel Guide: Aluminum guide on both sides of the track to facilitate straightening of the panels; finished with factory-applied, decorative, protective finish.
2. Head Closure Trim: As required for acoustical performance; with factory-applied, decorative, protective finish.

B. Carriers: Trolley system as required for configuration type, size, and weight of partition and for easy operation; with ball-bearing wheels.

1. Multidirectional Carriers: Capable of negotiating intersections without track switches.

C. Track Intersections, Switches, and Accessories: As required for operation, storage, track configuration, and layout indicated for operable panel partitions, and compatible with partition assembly specified. Fabricate track intersections and switches from steel or aluminum.

1. Center carrier stop.

D. Aluminum Finish: Mill finish or manufacturer's standard, factory-applied, decorative finish unless otherwise indicated.

E. Steel Finish: Manufacturer's standard, factory-applied, corrosion-resistant, protective coating unless otherwise indicated.

2.6 ACCESSORIES

A. Storage Pocket Door: Full height at end of partition runs to conceal stacked partition; of same materials, finish, construction, thickness, and acoustical qualities as panels; complete with operating hardware. Hinges in finish to match other exposed hardware.

1. Manufacturer's standard method to secure storage pocket door in closed position.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine flooring, floor levelness, structural support, and opening, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of operable panel partitions.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install operable panel partitions and accessories after other finishing operations, including painting, have been completed in area of partition installation.

B. Install panels in numbered sequence indicated on Shop Drawings.

C. Broken, cracked, chipped, deformed, or unmatched panels are not acceptable.

D. Broken, cracked, deformed, or unmatched gasketing or gasketing with gaps at butted ends is not acceptable.

E. Light-Leakage Test: Illuminate one side of partition installation and observe vertical joints and top and bottom seals for voids. Adjust partitions for alignment and full closure of vertical joints and full closure along top and bottom seals. Perform test and make adjustments before NIC testing.

3.3 ADJUSTING

A. Adjust operable panel partitions, hardware, and other moving parts to function smoothly, and lubricate as recommended by manufacturer.

B. Adjust storage pocket doors to operate smoothly and easily, without binding or warping.

C. Verify that safety devices are properly functioning.

3.4 MAINTENANCE SERVICE

A. Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by manufacturer's authorized service representative. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operable-partition operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain operable panel partitions.

END OF SECTION 102239

SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.
2. Hand dryers.
3. Underlavatory guards.
4. Custodial accessories.

B. Related Requirements:

1. Section 093013 "Ceramic Tiling" for ceramic toilet and bath accessories.

1.3 COORDINATION

A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.

B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
3. Include electrical characteristics.

B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

1. Identify locations using room designations indicated.
2. Identify accessories using designations indicated.

1.5 INFORMATIONAL SUBMITTALS

A. Sample Warranty: For manufacturer's special warranties.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For accessories to include in maintenance manuals.

1.7 WARRANTY

A. Manufacturer's Special Warranty for Mirrors: Manufacturer agrees to repair or replace mirrors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, visible silver spoilage defects.
2. Warranty Period: 10 years from date of Substantial Completion.

B. Manufacturer's Special Warranty for Hand Dryers: Manufacturer agrees to repair or replace hand dryers that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 OWNER-FURNISHED MATERIALS

A. Owner-Furnished Materials:

1. Toilet tissue dispensers, TA-6.
2. Paper towel dispensers, TA-8.
3. Waste receptacles TA-9.
4. Liquid soap dispensers, TA-10.

2.2 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Structural Performance: Design accessories and fasteners to comply with the following requirements:

1. Grab Bars: Installed units are able to resist 250 lbf (1112 N) concentrated load applied in any direction and at any point.

2.3 PUBLIC-USE WASHROOM ACCESSORIES

A. Source Limitations: Obtain public-use washroom accessories from single source from single manufacturer.

B. Grab Bar TA-1:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc.
c. Bradley Corporation.
d. Bobrick Washroom Equipment,Inc.

2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch (1.3 mm) thick.

a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. Outside Diameter: 1-1/2 inches (38 mm).
5. Configuration and Length: Straight, 18 inches (457 mm) long.

C. Grab Bar TA-2:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc.
c. Bradley Corporation.
d. Bobrick Washroom Equipment, Inc.

2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch (1.3 mm) thick.

a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. Outside Diameter: 1-1/2 inches (38 mm).
5. Configuration and Length: Straight, 36 inches (914 mm) long.

D. Grab Bar TA-3:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc.
c. Bradley Corporation.
d. Bobrick Washroom Equipment, Inc.

2. Mounting: Flanges with concealed fasteners.

3. Material: Stainless steel, 0.05 inch (1.3 mm) thick.

    a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. Outside Diameter: 1-1/2 inches (38 mm).
5. Configuration and Length: Straight, 42 inches (1066 mm) long.

E. Grab Bar TA-4:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch (1.3 mm) thick.

    a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. Outside Diameter: 1-1/2 inches (38 mm).
5. Configuration and Length: Two-wall grab bar, 16 by 31 inches (405 by 785 mm).

F. Sanitary-Napkin Disposal Unit TA-7:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Mounting: Surface mounted.
3. Door or Cover: Self-closing, disposal-opening cover and hinged face panel with tumbler lockset.
4. Receptacle: Removable.
5. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

G. Robe Hook TA-12:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Description: Double-prong unit.

3. Mounting: Concealed.
4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

H. Purse Shelf TA-15:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Description: Fixed rectangular unit.
3. Nominal Size: 15 inches (381 mm) long by 5-1/2 inches (140 mm) wide.
4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

I. Mirror Unit TA-13:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Frame: Stainless steel channel.

    a. Corners: Welded and ground smooth.

3. Size: 24 inches by 36 inches (610 mm by 914 mm).

4. Hangers: Manufacturer's standard rigid, tamper and theft resistant.

J. Mirror Unit T-11:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

    a. AJW Architectural Products.
    b. American Specialties, Inc.
    c. Bradley Corporation.
    d. Bobrick Washroom Equipment, Inc.

2. Frame: Stainless steel channel.

    a. Corners: Welded and ground smooth.

3. Size: 24 inches by 60 inches (610 mm by 1014 mm).
4. Hangers: Manufacturer's standard rigid, tamper and theft resistant.

2.4 PUBLIC-USE SHOWER ROOM ACCESSORIES

A. Source Limitations: Obtain public-use shower room accessories from single source from single manufacturer.

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. A&J Washroom Accessories, Inc.
b. American Specialties, Inc.
c. Bobrick Washroom Equipment, Inc.
d. Bradley Corporation.

B. Shower Curtain Rod TA-17:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. A&J Washroom Accessories, Inc.
b. American Specialties, Inc.
c. Bobrick Washroom Equipment, Inc.
d. Bradley Corporation.

2. Description: 1-1/4-inch- (32-mm-) outside diameter, straight rod.
3. Mounting Flanges: Concealed fasteners; in manufacturer's standard material and finish.
4. Rod Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

C. Shower Curtain TA-18:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. A&J Washroom Accessories, Inc.
b. American Specialties, Inc.
c. Bobrick Washroom Equipment, Inc.
d. Bradley Corporation.

2. Size: Minimum 6 inches (152 mm) wider than opening by 72 inches (1829 mm) high.
3. Material: Nylon-reinforced vinyl, minimum 9 oz. (255 g) or 0.008-inch- (0.2-mm-) thick vinyl, with integral antibacterial and flame-retardant agents.
4. Color: White.
5. Grommets: Corrosion resistant at minimum 6 inches (152 mm) o.c. through top hem.
6. Shower Curtain Hooks: Chrome-plated or stainless steel, spring wire curtain hooks with snap fasteners, sized to accommodate specified curtain rod. Provide one hook per curtain grommet.

D. Folding Shower Seat TA-16:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. A&J Washroom Accessories, Inc.
b. American Specialties, Inc.
c. Bobrick Washroom Equipment, Inc.
d. Bradley Corporation.

2. Configuration: L-shaped seat, designed for wheelchair access.
3. Seat: Phenolic or polymeric composite of slat-type or one-piece construction in color as selected by Architect. Reversible for right- or left-hand installation.
4. Mounting Mechanism: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

E. Towel Pin (#11):

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. A&J Washroom Accessories, Inc.
b. American Specialties, Inc.
c. Bobrick Washroom Equipment, Inc.
d. Bradley Corporation.

2. Basis-of-Design Product: American Specialties, Inc.; 7301-S.
3. Description: Projecting minimum of 3-1/2 inches (89 mm) from wall surface.
4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

2.5 UNDERLAVATORY GUARDS

A. Underlavatory Guard TA-20:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. IPS Corporation.
b. Plumberex Specialty Products.

2. Description: Insulating pipe covering for supply and drain piping assemblies that prevents direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.6 CUSTODIAL ACCESSORIES

A. Source Limitations: Obtain custodial accessories from single source from single manufacturer.

B. Custodial Utility Shelf TA-22:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc.

c. Bradley Corporation.

2. Description: With exposed edges turned down not less than 1/2 inch (13 mm) and supported by two triangular brackets welded to shelf underside.
3. Size: 16 inches (406 mm) long by 6 inches (152 mm) deep.
4. Material and Finish: Not less than nominal 0.05-inch- (1.3-mm-) thick stainless steel, ASTM A480/A480M No. 4 finish (satin).

C. Custodial Mop and Broom Holder TA-21:

1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings, or comparable product by one of the following:

a. AJW Architectural Products.
b. American Specialties, Inc.
c. Bradley Corporation.

2. Description: Unit with shelf, hooks, holders, and rod suspended beneath shelf.
3. Length: 36 inches (914 mm).
4. Hooks: Three.
5. Mop/Broom Holders: Four, spring-loaded, rubber hat, cam type.
6. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

a. Shelf: Not less than nominal 0.05-inch- (1.3-mm-) thick stainless steel.
b. Rod: Approximately 1/4-inch- (6-mm-) diameter stainless steel.

2.7 MATERIALS

A. Stainless Steel: ASTM A240/A240M or ASTM A666, Type 304, 0.031-inch- (0.8-mm-) minimum nominal thickness unless otherwise indicated.

B. Steel Sheet: ASTM A1008/A1008M, Designation CS (cold rolled, commercial steel), 0.036-inch- (0.9-mm-) minimum nominal thickness.

C. Galvanized-Steel Sheet: ASTM A653/A653M, with G60 (Z180) hot-dip zinc coating.

D. Galvanized-Steel Mounting Devices: ASTM A153/A153M, hot-dip galvanized after fabrication.

E. Fasteners: Screws, bolts, and other devices of same material as accessory unit, unless otherwise recommended by manufacturer or specified in this Section, and tamper and theft resistant where exposed, and of stainless or galvanized steel where concealed.

F. Chrome Plating: ASTM B456, Service Condition Number SC 2 (moderate service).

G. Mirrors: ASTM C1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.

2.8 FABRICATION

A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

1. Remove temporary labels and protective coatings.

B. Grab Bars: Install to comply with specified structural-performance requirements.

3.2 ADJUSTING AND CLEANING

A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.

B. Clean and polish exposed surfaces according to manufacturer's written instructions.

END OF SECTION 102800

SECTION 104413 - FIRE PROTECTION CABINETS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Fire-protection cabinets for the following:

a. Portable fire extinguisher.

B. Related Requirements:

1. Section 104416 "Fire Extinguishers" for portable, hand-carried fire extinguishers accommodated by fire-protection cabinets.

1.3 UNIT PRICES

A. Work of this Section is affected by unit prices specified in Section 012200 "Unit Prices."

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Show door hardware, cabinet type, trim style, and panel style. Include roughing-in dimensions and details showing recessed-, semirecessed-, or surface-mounting method and relationships of box and trim to surrounding construction.

B. Shop Drawings: For fire-protection cabinets.

1. Include plans, elevations, sections, details, and attachments to other work.

C. Samples for Verification: For each type of exposed finish required, prepared on samples 6 by 6 inches (150 by 150 mm) square.

D. Product Schedule: For fire-protection cabinets. Indicate whether recessed, semirecessed, or surface mounted. Coordinate final fire-protection cabinet schedule with fire-extinguisher schedule to ensure proper fit and function.[**Use same designations indicated on Drawings.**]

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For fire-protection cabinets to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain fire-protection cabinets, accessories, and fire extinguishers from single source from single manufacturer.

2.2 FIRE-PROTECTION CABINET

A. Cabinet Type: Suitable for fire extinguisher.

B. Products: Subject to compliance with requirements, provide one of the following:

1. Croker Corporation; Member of Morris Group International; 1600 Series.
2. Guardian Fire Equipment, Inc.; 1800 Series.
3. JL Industries, Inc.; Academy Series.
4. Larsen's Manufacturing Company; Architectural Series.
5. Potter Roemer; Member of Morris Group International; 7000 (Alta) Series..

C. Cabinet Construction: Nonrated.

D. Cabinet Material: Cold-rolled steel sheet.

E. Semirecessed Cabinet FEC-1: One-piece combination trim and perimeter door frame overlapping surrounding wall surface, with exposed trim face and wall return at outer edge (backbend).

1. Square-Edge Trim: 1-1/4- to 1-1/2-inch (32- to 38-mm) backbend depth.
2. Rolled-Edge Trim: 2-1/2-inch (64-mm) backbend depth.

F. Surface-Mounted Cabinet FEC-2: Cabinet box fully exposed and mounted directly on wall with no trim.

G. Cabinet Trim Material: Steel sheet.

H. Door Material: Steel or aluminum sheet.

I. Door Style: Vertical duo panel with frame.

J. Door Glazing: Tempered float glass (clear).

K. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.

1. Provide projecting lever handle with cam-action latch.

2. Provide continuous hinge, of same material and finish as trim, permitting door to open 180 degrees.

L. Accessories:

1. Mounting Bracket: Manufacturer's standard steel, designed to secure fire extinguisher to fire-protection cabinet, of sizes required for types and capacities of fire extinguishers indicated, with plated or baked-enamel finish.
2. Door Lock: Cam lock that allows door to be opened during emergency by pulling sharply on door handle.
3. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated.

    a. Identify fire extinguisher in fire-protection cabinet with the words "FIRE EXTINGUISHER."

        1) Location: Applied to cabinet door.
        2) Application Process: Engraved.
        3) Lettering Color: Black.
        4) Orientation: Vertical.

M. Materials:

1. Cold-Rolled Steel: ASTM A1008/A1008M, Commercial Steel (CS), Type B.

    a. Finish: Baked enamel, TGIC polyester powder coat, HAA polyester powder coat, epoxy powder coat, or polyester/epoxy hybrid powder coat, complying with AAMA 2603.
    b. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
    c. Color: White.

2. Aluminum: ASTM B221 (ASTM B221M) for extruded shapes and aluminum sheet, with strength and durability characteristics of not less than Alloy 6063-T5 for aluminum sheet.

    a. Finish: Clear anodic.

3. Tempered Float Glass: ASTM C1048, Kind FT, Condition A, Type I, Quality q3, 3 mm thick, Class 1 (clear).

2.3 FABRICATION

A. Fire-Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.

1. Weld joints and grind smooth.
2. Miter corners and grind smooth.
3. Provide factory-drilled mounting holes.
4. Install door locks at factory.

B. Cabinet Doors: Fabricate doors according to manufacturer's standards, from materials indicated and coordinated with cabinet types and trim styles.

1. Fabricate door frames with tubular stiles and rails and hollow-metal design, minimum 1/2 inch (13 mm) thick.
2. Fabricate door frames of one-piece construction with edges flanged.
3. Miter and weld perimeter door frames and grind smooth.

C. Cabinet Trim: Fabricate cabinet trim in one piece with corners mitered, welded, and ground smooth.

2.4 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM's AMP 500, "Metal Finishes Manual for Architectural and Metal Products," for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces of fire-protection cabinets from damage by applying a strippable, temporary protective covering before shipping.

C. Finish fire-protection cabinets after assembly.

D. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine walls and partitions for suitable framing depth and blocking where semirecessed cabinets will be installed.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare recesses for semirecessed fire-protection cabinets as required by type and size of cabinet and trim style.

3.3 INSTALLATION

A. General: Install fire-protection cabinets in locations and at mounting heights indicated or, if not indicated, at heights acceptable to authorities having jurisdiction.

B. Fire-Protection Cabinets: Fasten cabinets to structure, square and plumb.

1. Fasten mounting brackets to inside surface of fire-protection cabinets, square and plumb.

3.4 ADJUSTING AND CLEANING

A. Remove temporary protective coverings and strippable films, if any, as fire-protection cabinets are installed unless otherwise indicated in manufacturer's written installation instructions.

B. Adjust fire-protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

C. On completion of fire-protection cabinet installation, clean interior and exterior surfaces as recommended by manufacturer.

D. Touch up marred finishes, or replace fire-protection cabinets that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by fire-protection cabinet and mounting bracket manufacturers.

E. Replace fire-protection cabinets that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 104413

SECTION 104416 - FIRE EXTINGUISHERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes portable, hand-carried fire extinguishers and mounting brackets for fire extinguishers.

B. Related Requirements:

1. Section 104413 "Fire Protection Cabinets."

1.3 UNIT PRICES

A. Work of this Section is affected by unit prices specified in Section 012200 "Unit Prices."

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product. Include rating and classification, material descriptions, dimensions of individual components and profiles, and finishes for fire extinguisher and mounting brackets.

1.5 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fire extinguishers to include in maintenance manuals.

1.7 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure of hydrostatic test according to NFPA 10 when testing interval required by NFPA 10 is within the warranty period.
b. Faulty operation of valves or release levers.

2. Warranty Period: Six years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."

B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.

1. Provide fire extinguishers approved, listed, and labeled by FM Global.

2.2 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

A. Fire Extinguishers: Type, size, and capacity for each fire-protection cabinet and mounting bracket indicated.

1. Manufacturers: Subject to compliance with requirements, provide products from one of the following:

a. Amerex Corporation.
b. Ansul Incorporated.
c. Badger Fire Protection.
d. Buckeye Fire Equipment Company.
e. Croker Corporation; Div. of Morris Group International.
f. JL Industries; Part of Activar Construction Products Group.
g. Kidde Fyrnetics.
h. Larsen's Manufacturing Company; Div. of Morris Group International.
i. Modern Metal Products; Div. of Technico.
j. Moon American.
k. Nystrom Building Products, Inc.
l. Potter Roemer; Div. of Morris Group International.
m. Safety One Industries

2. Source Limitations: Obtain fire extinguishers, fire-protection cabinets, and accessories, from single source from single manufacturer.
3. Valves: Manufacturer's standard.
4. Handles and Levers: Manufacturer's standard.
5. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B**,** and bar coding for documenting fire-extinguisher location, inspections, maintenance, and recharging.

B. Multipurpose Dry-Chemical Type in Steel Container: UL-rated 4-A:60-B:C, 10-lb (4.5-kg) nominal capacity, with monoammonium phosphate-based dry chemical in enameled-steel container.

2.3 MOUNTING BRACKETS

A. Mounting Brackets: Manufacturer's standard galvanized steel, designed to secure fire extinguisher to wall or structure, of sizes required for types and capacities of fire extinguishers indicated, with plated or black baked-enamel finish.

1. Source Limitations: Obtain mounting brackets and fire extinguishers from single source from single manufacturer.

B. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by Architect.

1. Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.

a. Orientation: Vertical.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine fire extinguishers for proper charging and tagging.

1. Remove and replace damaged, defective, or undercharged fire extinguishers.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install fire extinguishers and mounting brackets in locations indicated and in compliance with requirements of authorities having jurisdiction.

1. Mounting Brackets: Top of fire extinguisher to be at 42 inches (1067 mm) above finished floor.

B. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.

END OF SECTION 104416

SECTION 105113 - METAL LOCKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Welded corridor lockers.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of metal locker.

B. Shop Drawings: For metal lockers.

1. Include plans, elevations, sections, and attachment details.
2. Show locker trim and accessories.
3. Include locker identification system and numbering sequence.

C. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available.

D. Samples for Verification: For the following products, in manufacturer's standard size:

1. Lockers and equipment.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For adjusting, repairing, and replacing locker doors and latching mechanisms to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. The following metal locker hardware items equal to 10 percent of amount installed for each type and finish installed, but no fewer than five units:

a. Locks.
b. Blank identification plates.
c. Hooks.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver metal lockers until spaces to receive them are clean, dry, and ready for their installation.

B. Deliver combination control charts to Owner by registered mail or overnight package service**.**

1.8 FIELD CONDITIONS

A. Field Measurements: Verify actual dimensions of recessed openings by field measurements before fabrication.

1.9 COORDINATION

A. Coordinate sizes and locations of concrete bases for metal lockers.

B. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of work specified in other Sections to ensure that metal lockers can be supported and installed as indicated.

1.10 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of metal lockers that fail in materials or workmanship, excluding finish, within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures.
b. Faulty operation of latches and other door hardware.

2. Damage from deliberate destruction and vandalism is excluded.
3. Warranty Period for Welded Metal Lockers: Lifetime from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain metal lockers and accessories from single source from single locker manufacturer.

1. Obtain locks from single lock manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: For lockers indicated to be accessible, comply with applicable provisions in ICC A117.1.

2.3 WELDED CORRIDOR LOCKERS

A. Products: Subject to compliance with requirements, provide one of the following:

1. Art Metal Products, Div. of Fort Knox Storage Co.; Bulldog Corridor Lockers.
2. DeBourgh Mfg. Co.; Sentry III Corridor/Personnel Lockers.
3. List Industries Inc.; The Graduate Single-Point Latch Corridor Lockers.
4. Lyon Workspace Products; Integrated Frame All-Welded Lockers.
5. Penco Products, Inc., Subsidiary of Vesper Corporation; All-Welded Defiant SPL Lockers.

B. Doors: One piece; fabricated from 0.075-inch (1.90-mm) nominal-thickness steel sheet; formed into channel shape with double bend at vertical edges and with right-angle single bend at horizontal edges.

1. Reinforcement: Manufacturer's standard reinforcing angles, channels, or stiffeners for doors more than 15 inches (381 mm) wide; welded to inner face of doors.
2. Door Style: Vented panel as follows:

a. Louvered Vents: No fewer than six louver openings at top and bottom for single-tier lockers.

C. Body: Assembled by welding body components together. Fabricate from unperforated steel sheet with thicknesses as follows:

1. Tops, Bottoms, and Sides: 0.060-inch (1.52-mm) nominal thickness.
2. Backs: 0.048-inch (1.21-mm) nominal thickness.
3. Shelves: 0.060-inch (1.52-mm) nominal thickness, with double bend at front and single bend at sides and back.

D. Frames: Channel formed; fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet; lapped and factory welded at corners; with top and bottom main frames factory welded into vertical main frames. Form continuous, integral, full-height door strikes on vertical main frames.

E. Hinges: Welded to door and attached to door frame with no fewer than two factory-installed rivets per hinge that are completely concealed and tamper resistant when door is closed; fabricated to swing 180 degrees; self-closing.

1. Hinges: Manufacturer's standard, steel, continuous or knuckle type.

F. Recessed Door Handle and Latch: Stainless steel cup with integral door pull, recessed so locking device does not protrude beyond door face; pry and vandal resistant.

1. Single-Point Latching: Nonmoving latch hook with steel padlock loop that projects through recessed cup and is finished to match metal locker body.

a. Latch Hook: Equip each door with one latch hook, fabricated from 0.120-inch (3.04-mm) nominal-thickness steel sheet; welded midway up full-height door strike; with resilient silencer.

G. Locks: Combination padlocks.

H. Identification Plates: Manufacturer's standard, etched, embossed, or stamped aluminum plates, with numbers and letters at least 3/8 inch (9 mm) high.

I. Hooks: Manufacturer's standard ball-pointed, aluminum or steel; zinc plated.

J. Coat Rods: **3**/4-inch- (19-mm-) diameter steel, nickel plated.

K. Continuous Sloping Tops: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet, with a pitch of approximately 20 degrees.

1. Closures: Vertical-end type.

L. Filler Panels: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.

M. Materials:

1. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B, suitable for exposed applications.

N. Finish: Baked enamel or powder coat.

1. Color: As selected by Architect from manufacturer's full range.

2.4 LOCKS

A. Combination Padlock: Provided by Owner.

2.5 FABRICATION

A. Fabricate metal lockers square, rigid, without warp, and with metal faces flat and free of dents or distortion. Make exposed metal edges safe to touch and free of sharp edges and burrs.

1. Form body panels, doors, shelves, and accessories from one-piece steel sheet unless otherwise indicated.
2. Provide fasteners, filler plates, supports, clips, and closures as required for complete installation.

B. Fabricate each metal locker with an individual door and frame; individual top, bottom, and back; and common intermediate uprights separating compartments.

C. Equipment: Provide each locker with an identification plate and the following equipment:

1. Single-Tier Units: Shelf, one double-prong ceiling hook, and two single-prong wall hooks.
2. Coat Rods: In lieu of ceiling hook for metal lockers 24 inches (610 mm) high or more.

D. Welded Construction: Factory preassemble metal lockers by welding all joints, seams, and connections; with no bolts, nuts, screws, or rivets used in assembly of main locker groups. Factory weld main locker groups into one-piece structures. Grind exposed welds smooth and flush.

E. Accessible Lockers: Fabricate as follows:

1. Locate bottom shelf no lower than 15 inches (381 mm) above the floor.
2. Where hooks, coat rods, or additional shelves are provided, locate no higher than 48 inches (1219 mm) above the floor.

F. Continuous Sloping Tops: Fabricated in lengths as long as practical, without visible fasteners at splice locations; finished to match lockers.

G. Filler Panels: Fabricated in an unequal leg angle shape; finished to match lockers. Provide slip-joint filler angle formed to receive filler panel.

2.6 ACCESSORIES

A. Fasteners: Zinc- or nickel-plated steel, slotless-type, exposed bolt heads; with self-locking nuts or lock washers for nuts on moving parts.

B. Anchors: Material, type, and size required for secure anchorage to each substrate.

1. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls, and elsewhere as indicated, for corrosion resistance.
2. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine walls and floors or support bases, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install lockers level, plumb, and true; shim as required, using concealed shims.

1. Anchor locker runs at ends and at intervals recommended by manufacturer, but not more than 36 inches (910 mm) o.c. Using concealed fasteners, install anchors through backup reinforcing plates, channels, or blocking as required to prevent metal distortion.
2. Anchor single rows of metal lockers to walls near top and bottom of lockers.
3. Anchor back-to-back metal lockers to floor.

B. Welded Lockers: Connect groups together with manufacturer's standard fasteners, with no exposed fasteners on face frames.

C. Equipment:

1. Attach hooks with at least two fasteners.
2. Attach door locks on doors using security-type fasteners.
3. Identification Plates: Identify metal lockers with identification indicated on Drawings.

    a. Attach plates to each locker door, near top, centered, with at least two aluminum rivets.
    b. Attach plates to upper shelf of each open-front metal locker, centered, with a least two aluminum rivets.

D. Trim: Fit exposed connections of trim, fillers, and closures accurately together to form tight, hairline joints, with concealed fasteners and splice plates.

1. Attach recess trim to recessed metal lockers with concealed clips.
2. Attach filler panels with concealed fasteners. Locate filler panels where indicated on Drawings.
3. Attach sloping-top units to metal lockers, with closures at exposed ends.

3.3 ADJUSTING

A. Clean, lubricate, and adjust hardware. Adjust doors and latches to operate easily without binding.

3.4 PROTECTION

A. Protect metal lockers from damage, abuse, dust, dirt, stain, or paint. Do not permit use during construction.

B. Touch up marred finishes, or replace metal lockers that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by locker manufacturer.

END OF SECTION 105113

SECTION 117000 - EQUIPMENT SCHEDULE

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

A. The General Provisions of the Contract, including General and Special Conditions and the requirements of Division 1, apply to the Work in this Section.

1.02 SUMMARY

A. The following Equipment Schedule provides information on equipment shown on the Q drawings. Equipment is listed numerically by mark number with the following information:

1. Mark # - All identical equipment items are assigned the same number. The Equipment Mark Number coordinates this schedule with The Q drawings and the specifications.
2. Item Description.
3. Spec Section - Identifies division or section where technical specifications for the equipment item can be found. NIC means "Not in Contract".
4. Procurement Method

    a. CF/CI = Contractor Furnished/Contractor Installed.
    b. OF/OI = Owner Furnished/Owner Installed.
    c. OF/CI = Owner Furnished/Contractor Installed.

PART 2 - PRODUCTS

Not Used

PART 3 - EXECUTION

Not Used

SECTION 117001 - STORAGE EQUIPMENT

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

A. The General Provisions of the Contract, including General and Special Conditions and the requirements of Division 1, apply to the Work in this Section.

1.02 SUMMARY

A. This Section includes equipment items as listed below by Equipment Mark Number:

1. 1113 CABINET, 9 DRAWER, 59 INCH (Ref. Part 2.01)
2. 1140 CABINET, FLAMMABLE MATERIALS, LARGE (Ref. Part 2.02)
3. 1185 CABINET, STORAGE, SHOP, 18 INCH (Ref. Part 2.03)
4. 1190 CABINET, STORAGE, SHOP, 24 INCH (Ref. Part 2.04)
5. 1410 PICK/BIN RACK, 9 ROWS (Ref. Part 2.05)
6. 1411 PICK/BIN RACK, 4 ROWS (Ref. Part 2.06)
7. 1456 RACK, BULK STORAGE, WITH DECK (Ref. Part 2.07)
8. 1531 RACK, PALLET, 36 INCH DEEP, 12 FOOT HIGH, 6000 POUND, WITH DECK (Ref. Part 2.8)
9. 1640 RACK, TIRE, STACKABLE (Ref. Part 2.9)
10. 1670 SHELVING UNIT, 12 INCH (Ref. Part 2.10)
11. 1680 SHELVING UNIT, 18 INCH (Ref. Part 2.11)
12. 1683 SHELVING UNIT, 24 INCH (Ref. Part 2.12)
13. 1772 TABLE, LAYOUT, WOOD TOP, 96 BY 36 INCHES (Ref. Part 2.13)
14. 1795 TABLE, WELDING, HEAVY DUTY (Ref. Part 2.14)

B. Installation of equipment with labor, services, and incidentals necessary for complete and operational equipment installation.

C. Utilities to be roughed in at location recommended by manufacturer.

1.03 ALTERNATIVE BIDS

A. Section 012300 "Alternates" may apply to Work of this Section.

1.04 PRODUCT SUBSTITUTIONS

A. Submit requests for substitutions according to Section 012500 "Substitution Requirements".

B. Additional costs resulting from substitution of products other than those specified, including drawing changes and construction, will be at the expense of the Contractor.

C. Substitution Approval: Manufacturers listed for each equipment item may bid without submittal for that item. Manufacturers not listed shall submit for approval in accordance with "Instructions to Bidders". Prior to installation, submittals for each equipment item by Mark Number shall be provided in accordance with Division 1 - General Requirements.

1.05 SUBMITTALS

A. Product Data:

1. Submit Product Data in accordance with Section 013300 "Submittal Procedures".
2. Restrict submitted material to pertinent data. For instance, do not include manufacturer's complete catalog when pertinent information is contained on a single page.

1.06 QUALITY ASSURANCE

A. Equipment shall be produced by a manufacturer of established reputation with a minimum of five years experience supplying specified equipment.

1.07 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver equipment in manufacturer's containers, appropriately packaged and/or crated for protection during domestic shipment and storage in humid, dusty conditions. Equipment shall be stored per manufacturer's recommendation.

B. Indelibly label all containers, including those contained in others, on outside with item description(s) per title and Mark Number of this specification.

C. Provide equipment and materials specified complete in one shipment for each equipment item. Split or partial shipments are not permissible.

1.08 WARRANTY

A. Warrant work specified herein for one year from substantial completion against defects in materials, function and workmanship.

B. Warranty shall include materials and labor necessary to correct defects.

C. Defects shall include, but not be limited to loose, damaged and missing parts and abnormal deterioration of finish.

D. Submit warranties in accordance with Section 013300 "Submittal Procedures"

E. All parts shall be readily available locally in the United States.

PART 2 – PRODUCTS

2.01 CABINET, 9 DRAWER, 59 INCH
Equipment Mark Number: 1113

A. Capacities and Dimensions:

1. Overall dimensions, nominal:

a. Width: 30 inches.
b. Depth: 27-3/4 inches.
c. Height: 59 inches.

2. Quantity of drawers: 9.
3. Drawer capacity: 400 pounds each.
4. Drawer dimensions:

a. Usable width: 25-1/8 inches.
b. Usable depth: 25-1/8 inches.
c. Drawer usable height (Drawers numbered top to bottom):

1) Drawers 1, 2, 3 and 4: 3-7/8 inches.
2) Drawers 5, 6, 7 and 8: 5-3/8 inches.
3) Drawer 9: 8-1/2 inches.

5. Partition configurations:

a. Drawer 1: 24 compartments, 3-1/2 by 6-1/8 inches.
b. Drawer 2: 20 compartments, 4-1/4 by 6-1/8 inches.
c. Drawer 3: 16 compartments, 5-7/8 by 6-1/8 inches.
d. Drawer 4: 12 compartments, 7-1/2 by 6-1/8 inches.
e. Drawer 5: 20 compartments, 4-1/4 by 6-1/8 inches.
f. Drawer 6: 16 compartments, 5-7/8 by 6-1/8 inches.
g. Drawer 7: 12 compartments, 7-1/2 by 6-1/8 inches.
h. Drawer 8: 8 compartments, 12-1/4 by 6-1/8 inches.
i. Drawer 9: 12 compartments, 7-1/2 by 6-1/8 inches.

B. Features and Construction:

1. Cabinet: Heavy gauge sheet steel cabinet shall be channel formed with mountings permitting installation of various height drawers, front columns with drilled and tapped bolt holes. Cabinet shall come complete with a keyed lock capable of securing all drawers within unit.
2. Base: Design of base shall include front and rear forklift openings of ample strength to permit moving of fully loaded cabinet. Front base plate shall be provided to prevent dirt buildup. Base shall be drilled for bolting to floor.
3. Drawer suspension: Cabinet shall be designed for total interchangeability for all drawer heights. Sealed steel roller bearing system shall permit full drawer extension at rated capacity without sagging.

4. Drawer walls: Slotted walls on 3/4 inch centers shall be provided for mounting dividers and partitions.
5. Drawer pulls: Drawer faces shall be fitted with nominal 3/4 drawer width drawer pulls with 1 inch high label holder provided with paper labels and protective vinyl shields and end caps.
6. Drawer dividers: All drawer dividers shall be factory installed.
7. Drawer heights: For adaptability to changing inventory needs drawers shall be available in usable heights of 2-1/4 to 13-1/4 inches in not over 1 inch increments.

C. Accessories:

1. Overhead cabinet: Stanley Vidmar No. OS-135, one each.
2. Adjustable shelf: Stanley Vidmar No. CS-40, one each.
3. Floor attachment kit: Stanley Vidmar No. CAK-1, one each.

D. Finish: Phosphate primer covered by durable enamel in Owner's choice of manufacturer's standard colors.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Stanley Vidmar
      Queen City Airport Park
      11 Grammes Road
      Allentown, PA 18103
      Phone: (610) 797-6600, (800) 523-9462
      Fax: (610) 776-3895
      Website: www.stanleyvidmar.com

   b. Model: SEP 3144-AL with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

   a. Equipto
      4550 Beltway Drive
      Addison, TX 75001
      Phone: (214) 443-9800, (800) 323-0801
      Fax: (888) 859-2121
      Website: www.equipto.com

   b. Lyon Workspace Products
      420 North Main
      Montgomery, IL 60538
      Phone: (630) 892-8941, (800) 433-8488

Fax: (800) 367-6681
Website: www.lyonworkspace.com

2.02 CABINET, FLAMMABLE MATERIALS, LARGE
Equipment Mark Number: 1140

A. Capacities and Dimensions:

1. Storage capacity: Up to nine each, 5 gallon containers.
2. Overall dimensions, nominal:

a. Width: 43 inches.
b. Depth: 18 inches.
c. Height: 65-5/8 inches.

3. Shipping weight, nominal: 360 pounds.

B. Features and Construction:

1. Standards: The cabinet shall comply with the latest requirements of NFPA combustible liquids Code No. 30 and OSHA safety requirements.
2. Walls and doors: Construction shall consist of double wall 18 gauge sheet steel with 1-1/2 inch air space between inner and outer walls.
3. Containment: Cabinet shall have a 2 inch pan-type bottom.
4. Screened flame arrester vent: Two vents per cabinet, one each at left side bottom and right side top, shall be threaded for and provided with 2 inch NPT steel plugs.
5. Adjustment: Leveling feet shall be provided at all four corners.
6. Ground: Electrical grounding attachments shall be provided on each side.
7. Closure: Double doors with full-length piano hinges and 3-point latch mechanism with key lock.
8. Shelf: Two each adjustable shelves shall be provided between 5-3/8 inches from top and 7-5/16 inches from bottom on 1/2 inch centers.

C. Finish: Durable enamel in safety yellow with "FLAMMABLE - KEEP FIRE AWAY" in minimum 4 inch bright red letters across doors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Lyon Workspace Products
420 North Main
Montgomery, IL 60538
Phone: (630) 892-8941, (800) 433-8488
Fax: (800) 367-6681
Website: www.lyonworkspace.com

b. Model: 5444N

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Equipto
4550 Beltway Drive
Addison, TX 75001
Phone: (214) 443-9800, (800) 323-0801
Fax: (888) 859-2121
Website: www.equipto.com

b. Republic Storage Systems Company
1038 Beldon Avenue, Northeast
Canton, OH 44705
Phone: (330) 438-5800, (800) 477-1255
Fax: (330) 454-7772
Website: www.republicstorage.com

2.03 CABINET, STORAGE, SHOP, 18 INCH
Equipment Mark Number: 1185

A. Capacities and Dimensions:

1. Shelving: Full width shelves, five each.
2. Shelf capacity: 200 pounds, minimum.
3. Overall dimensions:

a. Width: 36 inches.
b. Depth: 18 inches.
c. Height: 78 inches.

4. Weight: 140 pounds, nominal.

B. Features and Construction:

1. Shelves: Four box edge full-length shelves shall be adjustable on maximum 2 inch centers without removing fasteners.
2. Doors: Three point box edge latching doors shall have common locks and two keys for each cabinet. Doors shall open a full 180 degrees and be flush mounted when closed with latching actuated by grip-type satin chrome plated steel handle.
3. Base: Cabinet shall be pedestal mounted for protection from moisture.
4. Assembly: Back, front, and sides shall be flush with no bolt heads on front or sides.
5. Locks: All cabinets covered by this specification shall be keyed alike.

C. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Equipto
4550 Beltway Drive
Addison, TX 75001
Phone: (214) 443-9800, (800) 323-0801
Fax: (888) 859-2121
Website: www.equipto.com

b. Model: 1710

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Lyon Workspace Products
420 North Main
Montgomery, IL 60538
Phone: (630) 892-8941, (800) 433-8488
Fax: (800) 367-6681
Website: www.lyonworkspace.com

b. Republic Storage Systems Company
1038 Beldon Avenue, Northeast
Canton, OH 44705
Phone: (330) 438-5800, (800) 477-1255
Fax: (330) 454-7772
Website: www.republicstorage.com

2.04 CABINET, STORAGE, SHOP, 24 INCH
Equipment Mark Number: 1190

A. Capacities and Dimensions:

1. Shelving: Full width shelves, five each.
2. Shelf capacity: 200 pounds, minimum.
3. Overall dimensions:

a. Width: 36 inches.
b. Depth: 24 inches.
c. Height: 78 inches.

4. Weight: 180 pounds, nominal.

B. Features and Construction:

1. Shelves: Four box edge full-length shelves shall be adjustable on maximum 2 inch centers without removing fasteners.
2. Doors: Three point box edge latching doors shall have common locks and two keys for each cabinet. Doors shall open a full 180 degrees and be flush mounted when closed with latching actuated by grip-type satin chrome plated steel handle.
3. Base: Cabinet shall be pedestal mounted for protection from moisture.
4. Assembly: Back, front, and sides shall be flush with no bolt heads on front or sides.

C. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Equipto
   4550 Beltway Drive
   Addison, TX 75001
   Phone: (214) 443-9800, (800) 323-0801
   Fax: (888) 859-2121
   Website: www.equipto.com

   b. Model: 1715

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

   a. Lyon Workspace Products
   420 North Main
   Montgomery, IL 60538
   Phone: (630) 892-8941, (800) 433-8488
   Fax: (800) 367-6681
   Website: www.lyonworkspace.com

   b. Republic Storage Systems Company
   1038 Beldon Avenue, Northeast
   Canton, OH 44705
   Phone: (330) 438-5800, (800) 477-1255
   Fax: (330) 454-7772
   Website: www.republicstorage.com

2.05 PICK/BIN RACK, 9 ROWS
Equipment Mark Number: 1410

A. Capacities and Dimensions:

1. Shelving: Full width shelves, nine each.
2. Shelf capacity: 200 pounds, minimum.
3. Overall dimensions:

a. Width: 36 inches.
b. Depth: 12 inches.
c. Height: 73 inches.

4. Weight: 80 pounds, nominal.

B. Features and Construction:

1. Shelves: Box edge full-length shelves shall be adjustable on maximum 2 inch centers without removing fasteners.
2. Construction: Unit shall be constructed of heavy gauge steel with three brace panels and four cross braces.

C. Accessories

1. Bins: Shall be hard plastic, Type ‘A’ bin, provide 90.

D. Finish: Durable enamel in manufacturer's standard color.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Global Equipment Co.
Website: www.globalindustrial.com

b. Model: WG603267BL with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.06 PICK/BIN RACK, 4 ROWS
Equipment Mark Number: 1411

A. Capacities and Dimensions:

1. Shelving: Full width shelves, nine each.
2. Shelf capacity: 200 pounds, minimum.
3. Overall dimensions:

a. Width: 36 inches.
b. Depth: 18 inches.
c. Height: 73 inches.

4. Weight: 80 pounds, nominal.

B. Features and Construction:

1. Shelves: Box edge full-length shelves shall be adjustable on maximum 2 inch centers without removing fasteners.
2. Construction: Unit shall be constructed of heavy gauge steel with three brace panels and four cross braces.

C. Accessories

1. Bins: Shall be hard plastic, Type ‘C’ bin, provide 36.

D. Finish: Durable enamel in manufacturer's standard color.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Global Equipment Co.
Website: www.globalindustrial.com

b. Model: WG603269BL with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.07 RACK, BULK STORAGE, WITH DECK
Equipment Mark Number: 1456

A. Capacities and Dimensions:

1. Beams:

a. Minimum capacity: 1,600 pounds per pair of beams.
b. Dimensions:

1) Length: 72 inches.
2) Width: 1-1/2 inches.
3) Depth: 2-7/8 inches.

c. Quantity: 4 pair.

2. Uprights:

a. Capacity: 10,500 pounds per upright.
b. Dimensions:

1) Width: 1-5/8 inches.
2) Depth: 24 inches.
3) Height: 96 inches.

3. Decking:

a. Minimum capacity: 2,778 pounds.
b. Thickness: 5/8 inch.

4. Overall dimensions, nominal:

a. Length: 72 inches.
b. Depth: 24 inches.
c. Height: 96 inches.

B. Features and Construction:

1. Beams:

a. Construction: Beams shall be welded 16 gauge steel, with 5/8 by 3/4 inch wide recess for decking.
b. Attachment: Beam hooks shall be provided for insertion into upright slots.
c. Tie bars: Two tie bars shall be provided for each pair of beams.

2. Uprights:

a. Construction: Uprights shall be welded 16 gauge steel with zee-shaped angle steel cross and diagonal members.

b. Adjustment: Tapered slots on 1-1/2 inch centers shall be provided for vertical beam adjustment.
c. Row ends: Extra upright assembly shall be provided to finish each row.

C. Accessories:

1. Floor anchor: Equipto No. 7695L, one each per upright.
2. Floor anchor: Equipto No. 7695R, one each per upright.

D. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Equipto
4550 Beltway Drive
Addison, TX 75001
Phone: (214) 443-9800, (800) 323-0801
Fax: (888) 859-2121
Website: www.equipto.com

b. Model: 1018D62S Rack with Accessories and 9316 Rack End as required

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Lyon Workspace Products
420 North Main
Montgomery, IL 60538
Phone: (630) 892-8941, (800) 433-8488
Fax: (800) 367-6681
Website: www.lyonworkspace.com

b. Republic Storage Systems Company
1038 Beldon Avenue, Northeast
Canton, OH 44705
Phone: (330) 438-5800, (800) 477-1255
Fax: (330) 454-7772
Website: www.republicstorage.com

2.08 RACK, PALLET, 36 INCH DEEP, 12 FOOT HIGH, 6000 POUND, WITH DECK
Equipment Mark Number: 1531

A. Capacities and Dimensions:

1. Uprights:

a. Capacity: 26,700 pounds.
b. Dimensions:

1) Thickness: 2-1/4 inches.
2) Depth: 36 inches.
3) Height: 144 inches.

2. Beams:

a. Minimum capacity: 6000 pounds per pair of beams.
b. Dimensions:

1) Length: 108 inches.
2) Depth: 4-1/2 inches.
3) Thickness: 2-3/4 inches.

c. Installed beam height from finished floor (Verify beam heights with Owner prior to installation):

1) Top beams: 144 inches.
2) Second beams: 96 inches.
3) Third beams: 48 inches.

3. Overall dimensions:

a. Width: 112-1/2 inches.
b. Depth: 36 inches.
c. Height: 144 inches.

B. Features and Construction:

1. Uprights:

a. Construction: Upright frames shall be continuously arc welded, heavy gauge steel box section uprights with deep channel cross and diagonal members.
b. Adjustment: Tapered keyhole slots shall be punched on 2 inch centers on both sides for vertical beam adjustments.
c. Base plate: Heavy gauge steel plates with holes for anchoring to floor shall be arc welded to uprights.

2. Beams:

   a. Construction: Beams shall be welded, step-type heavy gauge steel box channel.
   b. Attachment: Three high tensile studs shall be provided on each end to engage tapered keyhole slots in uprights, locking flush by means of spring loaded lock snaps.

C. Accessories: 52 inches wide by 36 inches deep wire decking, Lyon No. WD5236H, two per shelf.

D. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Lyon Workspace Products
   420 North Main
   Montgomery, IL 60538
   Phone: (630) 892-8941, (800) 433-8488
   Fax: (800) 367-6681
   Website: www.lyonworkspace.com

   b. Model: 36M144 Uprights and N108 Beams with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

   a. Republic Storage Systems Company
   1038 Beldon Avenue, Northeast
   Canton, OH 44705
   Phone: (330) 438-5800, (800) 477-1255
   Fax: (330) 454-7772
   Website: www.republicstorage.com

   b. Edsal Manufacturing Company
   4400 South Packers Avenue
   Chicago, IL 60609
   Phone: (773) 254-0600
   Fax: (773) 254-1303
   Website: www.edsal.com

2.09 RACK, TIRE, STACKABLE
Equipment Mark Number: 1640

A. Capacities and Dimensions:

1. Rack capacity: 4,000 pounds.
2. Overall dimensions:

a. Length: 60 inches.
b. Width: 26 inches.
c. Height: 47-1/2 inches.

3. Distance between front posts: 55 inches.
4. Shipping weight, nominal: 128 pounds.

B. Features and Construction:

1. Design: Rack shall be designed for secure stacking of racks up to three high. Positive nesting shall provide a formed nesting plug on top of each post that fits into a hole at the bottom of each post.
2. Construction: Rack posts and braces shall be fabricated of 11 gauge tubular steel. All joints shall be continuous welded.
3. Gussets: Posts shall be reinforced with continuously welded gussets at side braces and at front and rear braces.
4. Handling: Rack shall be designed for forklift handling without disturbing tires stored in rack.

C. Finish: Durable enamel in manufacturer's standard color.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Jarke Corporation
6333 West Howard Street
Niles, IL 60714
Phone: (800) 722-5255, (847) 647-9633
Fax: (847) 647-9766
Website: www.jarke.com

b. Model: TW 3943

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. BCI, Incorporated
5655 F Street, Suite 3

Omaha, NE 68117
Phone: (800) 331-7013, (402) 733-5995
Fax: (800) 338-3546, (402) 733-6116
Website: www.bciomaha.com

b. Global Industrial Equipment
120B Satellite Blvd.
Suwanee, GA 30024
Phone: (770) 995-0007, (800) 645-1232
Fax: (800) 336-3818
Website: www.globalindustrial.com

2.10 SHELVING UNIT, 12 INCH
Equipment Mark Number: 1670

A. Capacities and Dimensions:

1. Number of shelves: Seven total.
2. Shelf capacity: 1000 pounds per shelf.
3. Overall dimensions, nominal:

a. Width: 36 inches.
b. Depth: 12 inches.
c. Height: 84 inches.

4. Installed shelf height from finished floor, nominal:

a. Top shelf: 84 inches.
b. Bottom shelf: 1 inch.
c. Remaining shelves: Evenly spaced, approximately 12 inches center to center.

B. Features and Construction:

1. Shelf construction: Shelves shall be constructed of 18 gauge steel with double flanged, box-formed edges on all four sides and front and rear shelf edge reinforcing channels.
2. Uprights: Uprights shall be double flanged with tapered bracket slots punched on 1-1/2 inch centers for vertical shelf adjustment.
3. Shelf securement: Slip-in shelf brackets shall reinforce and securely lock shelf into place on all four corners.
4. Commonality: Units shall have the capability of sharing common end and back panels with adjoining units.
5. Assembly: Unit shall be designed for complete, rigid assembly and adjustment without tools.

C. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Equipto
   4550 Beltway Drive
   Addison, TX 75001
   Phone: (214) 443-9800, (800) 323-0801
   Fax: (888) 859-2121
   Website: www.equipto.com

   b. Model: 773-7S shelving unit with 773-7A add-on as required

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers may be considered as equal.

   a. Lyon Workspace Products
   420 North Main
   Montgomery, IL 60538
   Phone: (630) 892-8941, (800) 433-8488
   Fax: (800) 367-6681
   Website: www.lyonworkspace.com

   b. Republic Storage Systems Company
   1038 Beldon Avenue, Northeast
   Canton, OH 44705
   Phone: (330) 438-5800, (800) 477-1255
   Fax: (330) 454-7772
   Website: www.republicstorage.com

2.11 SHELVING UNIT, 18 INCH
Equipment Mark Number: 1680

A. Capacities and Dimensions:

1. Number of shelves: Seven total.
2. Shelf capacity: 1000 pounds per shelf.
3. Overall dimensions, nominal:

   a. Width: 36 inches.
   b. Depth: 18 inches.
   c. Height: 84 inches.

4. Installed shelf height from finished floor, nominal:

   a. Top shelf: 84 inches.

b. Bottom shelf: 1 inch.
c. Remaining shelves: Evenly spaced, approximately 12 inches center to center.

B. Features and Construction:

1. Shelf construction: Shelves shall be constructed of 18 gauge steel with double flanged, box-formed edges on all four sides and front and rear shelf edge reinforcing channels.
2. Uprights: Uprights shall be double flanged with tapered bracket slots punched on 1-1/2 inch centers for vertical shelf adjustment.
3. Shelf securement: Slip-in shelf brackets shall reinforce and securely lock shelf into place on all four corners.
4. Commonality: Units shall have the capability of sharing common end and back panels with adjoining units.
5. Assembly: Unit shall be designed for complete, rigid assembly and adjustment without tools.

C. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Equipto
4550 Beltway Drive
Addison, TX 75001
Phone: (214) 443-9800, (800) 323-0801
Fax: (888) 859-2121
Website: www.equipto.com

b. Model: 773-7S shelving unit with 773-7A add-on as required

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers may be considered as equal.

a. Lyon Workspace Products
420 North Main
Montgomery, IL 60538
Phone: (630) 892-8941, (800) 433-8488
Fax: (800) 367-6681
Website: www.lyonworkspace.com

b. Republic Storage Systems Company
1038 Beldon Avenue, Northeast
Canton, OH 44705
Phone: (330) 438-5800, (800) 477-1255
Fax: (330) 454-7772
Website: www.republicstorage.com

2.12 SHELVING UNIT, 24 INCH
Equipment Mark Number: 1683

A. Capacities and Dimensions:

1. Number of shelves: Seven total.
2. Shelf capacity: 1000 pounds per shelf.
3. Overall dimensions:

a. Width: 36 inches.
b. Depth: 24 inches.
c. Height: 84 inches.

4. Installed shelf height from finished floor:

a. Top shelf: 84 inches.
b. Bottom shelf: 1 inch.
c. Remaining shelves: Evenly spaced, approximately 12 inches center to center.

B. Features and Construction:

1. Shelf construction: Shelves shall be constructed of 18 gauge steel with double flanged, box-formed edges on all four sides and front and rear shelf edge reinforcing channels.
2. Uprights: Uprights shall be double flanged with tapered bracket slots punched on 1-1/2 inch centers for vertical shelf adjustment.
3. Shelf securement: Slip-in shelf brackets shall reinforce and securely lock shelf into place on all four corners.
4. Commonality: Units shall have the capability of sharing common end and back panels with adjoining units.
5. Assembly: Unit shall be designed for complete, rigid assembly and adjustment without tools.

C. Finish: Durable enamel in Owner's choice of manufacturer's standard colors.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Equipto
4550 Beltway Drive
Addison, TX 75001
Phone: (214) 443-9800, (800) 323-0801
Fax: (888) 859-2121
Website: www.equipto.com

b. Model: 775-7S shelving unit with 775-7A Add-on as required

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Lyon Workspace Products
420 North Main
Montgomery, IL 60538
Phone: (630) 892-8941, (800) 433-8488
Fax: (800) 367-6681
Website: www.lyonworkspace.com

b. Republic Storage Systems Company
1038 Beldon Avenue, Northeast
Canton, OH 44705
Phone: (330) 438-5800, (800) 477-1255
Fax: (330) 454-7772
Website: www.republicstorage.com

2.13 TABLE, LAYOUT, WOOD TOP, 96 BY 36 INCHES
Equipment Mark Number: 1772

A. Capacities and Dimensions:

1. Table:

a. Length: 96 inches.
b. Depth: 36 inches.
c. Height: 34 inches.

B. Features and Construction:

1. Work surface: 1-3/4 inch laminated maple top shall be bolted to bench legs.
2. Bench legs: Table legs shall be constructed of 14 gauge welded and braced steel channel with base plates punched for bolting to floor. Pre-punched for attachment of top, stringer, and shelf. Height shall be adjustable from 28 to 42 inches on 2 inch centers, two of each.

C. Accessories:

1. Stringer: Added rigidity shall be provided through use of full length stringer. 14 gauge sheet steel flanged and pre-punched for attachment to bench legs, one of each.
2. Shelf: Added rigidity shall be provided through use of full length shelf. 14 gauge sheet steel flanged and pre-punched for attachment to bench legs, one of each.

D. Finish: Durable enamel in manufacturer's standard color.

E. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

    a. Hodge Manufacturing Company, Inc.
    55 Fisk Avenue
    Springfield, MA 01107
    Phone: (413) 781-6800, (800) 262-4634
    Fax: (413) 733-6573, (888) 262-4634
    Website: www.hodgemfg.com

    b. Model: LMT3696-975 Work Surface and WB-LEG-31-95 Bench Legs with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

    a. Equipto
    4550 Beltway Drive
    Addison, TX 75001
    Phone: (214) 443-9800, (800) 323-0801
    Fax: (888) 859-2121
    Website: www.equipto.com

    b. Lyon Workspace Products
    420 North Main
    Montgomery, IL 60538
    Phone: (630) 892-8941, (800) 433-8488
    Fax: (800) 367-6681
    Website: www.lyonworkspace.com

2.14 TABLE, WELDING, HEAVY DUTY

Equipment Mark Number: 1795

A. Capacities and Dimensions:

1. Dimensions:

    a. Width: 96 inches.
    b. Depth: 60 inches.
    c. Height: 30 inches (with stand).

2. Weight, nominal:

    a. Platen: 3,200 pounds.
    b. Stand: 360 pounds.

3. Loading capacity on stand: 6 tons.

B. Features and Construction:

1. Platen:

a. Construction: Platen shall be constructed of semi-steel casting.
b. Surface: Top surface and side ledges shall be machined to within .005 inches of flatness per linear foot.
c. Holes: 1-3/4 inch square holes shall be spaced 3-1/2 inches center to center.

2. Stand: Platen stand shall be constructed of structural steel with flanges for anchoring to floor.

C. Accessories:

1. Stand: Acorn No. 5080, one each.
2. Other accessories: Table shall be furnished with various fixtures including horizontal clamps, two each; tapered drift pin, 10 inch, ten each; vise, one each; gooseneck hold-down, two each; bending post, five each; burning pyramid, four each; arm clamp, two each.

D. Manufacturer's Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Acorn Iron & Supply Company, Inc.
915 North Delaware Avenue
Philadelphia, PA 19123
Phone: (215) 922-7070
Fax: (215) 922-2522
Website: www.acorniron.com

b. Model: 5080 with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Weldsale Company
Division of J. A. Cunningham Equipment, Inc.
2151 Dreer Street
Philadelphia, PA 19125
Phone: (215) 739-7474
Fax: (215)-426-1260
Website: www.weldsale.com

b. Brodhead-Garrett
100 Paragon Parkway
Mansfield, OH 43903
Phone: (419) 589-8222

Fax: (877) 256-3739
Website: www.brodheadgarret.com

PART 3 - EXECUTION

3.01 INSPECTION

A. Coordinate location of rough-in work and utility stub-outs to assure match and/or non-interference with equipment to be installed.

B. Inspect delivered equipment for damage from shipping and exposure to weather. Compare delivered equipment with packing lists and specifications to assure receipt of all items.

3.02 INSTALLATION

A. Perform work under direct supervision of Foreman or Construction Superintendent with authority to coordinate installation of scheduled equipment with Architect.

B. Install equipment in accordance with plans, shop drawings, and manufacturer's instructions:

1. Positioning: Place equipment in accordance with any noted special positioning requirements generally level, plumb and at right angles to adjacent work.
2. Fitting: Where field cutting or trimming is necessary, perform in a neat, accurate, professional manner without damaging equipment or adjacent work.
3. Anchorage: Attach equipment securely to floor, per manufacturer's instructions and as directed by Architect, to prevent damage resulting from inadequate fastening. Installation fasteners shall be installed to avoid scratching or damaging adjacent surfaces.
4. Upon completion of work, finish surfaces shall be free of tool marks, scratches, blemishes, and stains.

3.03 TESTING

A. After final installation is complete and prior to authorizing payment, specified equipment shall be checked for compliance with specifications in the presence of the Architect using acceptance procedures provided by the manufacturer.

3.04 CLEANUP

A. Touch-up damage to painted finishes.

B. Wipe and clean equipment of any oil, grease, and solvents, and make ready for use.

C. Clean area around equipment installation and remove packing or installation debris from job site.

D. Notify Architect for acceptance inspection.

END OF SECTION 117001

SECTION 117310 - VEHICLE LIFTS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

A. The General Provisions of the Contract, including General and Special Conditions and the requirements of Division 1, apply to the Work in this Section.

1.02 SUMMARY

A. This Section includes equipment items as listed below by Equipment Mark Number:

1. 5690 LIFT, COLUMN, SET OF 4, 66,000 LB CAPACITY, HYDRAULIC (Ref. Part 2.01)
2. 5650 LIFT, 2-POST, HYDRAULIC (Ref. Part 2.02)

B. Roughing-in, installation of equipment and final connection of utilities, with labor, services, and incidentals necessary for complete and operational equipment installation.

C. Piping, wiring, and switching between equipment and utilities.

1.03 ALTERNATIVE BIDS

A. Section 012300 "Alternates" may apply to Work of this Section.

1.04 PRODUCT SUBSTITUTIONS

A. Submit requests for substitutions according to Section 012500 "Substitution Requirements".

B. Additional costs resulting from substitution of products other than those specified, including drawing changes and construction, will be at the expense of the Contractor.

C. Substitution Approval: Manufacturers listed for each equipment item may bid without submittal for that item. Manufacturers not listed shall submit for approval in accordance with "Instructions to Bidders". Prior to installation, submittals for each equipment item by Mark Number shall be provided in accordance with Division 1 - General Requirements.

1.05 ACTION SUBMITTALS

A. Product Data:

1. Submit Product Data in accordance with Section 013300 "Submittal Procedures".
2. Restrict submitted material to pertinent data. For instance, do not include manufacturer's complete catalog when pertinent information is contained on a single page.

B. Shop Drawings: Submit Shop Drawings in accordance with Section 013300 "Submittal Procedures".

1.06 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Manual:

1. Provide complete parts, operating and maintenance manual covering equipment at time of installation including, but not limited to:

a. Description of system and components.
b. Schematic diagrams of electrical and plumbing systems.
c. Manufacturer's printed operating instructions.
d. Printed listing of periodic preventive maintenance items and recommended frequency required to validate warranties. Failure to provide maintenance information will indicate that preventive maintenance is not a condition for validation of warranties.
e. List of original manufacturer's parts, including suppliers' part numbers and cuts, recommended spare parts stockage quantity and local parts and service source.

2. Assemble and provide copies of manual in 8-1/2 by 11 inch format. Foldout diagrams and illustrations are acceptable. Manual to be reproducible by dry copy method. Provide copies per provisions of Division 1 - General Requirements.

1.07 QUALITY ASSURANCE

A. Experience: Equipment shall be produced by a manufacturer of established reputation with a minimum of five years of experience supplying specified equipment.

B. Manufacturer's Representative:

1. Installation: Provide a qualified manufacturer's representative at site to supervise work related to equipment installation, check out and start up.
2. Training: Provide technical representative to train Owner's maintenance personnel in operation and maintenance of specified equipment.

1.08 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver equipment in manufacturer's containers, appropriately packaged and/or crated for protection during domestic shipment and storage in humid or dusty conditions.

B. Indelibly label all containers, including those contained in others, on outside with item description(s) per title and Mark Number of this specification.

C. Provide equipment and materials specified complete in one shipment for each equipment item. Split or partial shipments are not permissible.

1.09 LABELING

A. Nameplate: Manufacturer shall securely attach in a prominent location on each major item of equipment a noncorrosive nameplate with stamped figures showing manufacturer's name, address, model number, serial number and pertinent utility or operating data.

B. A.L.I. label: Manufacturer shall securely attach the A.L.I. label of the Automotive Lift Institute.

C. All electrical equipment and materials shall be new and shall be listed by Underwriter's Laboratories, Inc. (U.L.) in categories for which standards have been set by that agency and labeled as such in the manufacturer's plant.

1.10 WARRANTY

A. Warrant work specified herein for one year from substantial completion against defects in materials, function and workmanship.

B. Warranty shall include materials and labor necessary to correct defects.

C. Defects shall include, but not be limited to noisy, rough or substandard operation; loose, damaged, and missing parts; and abnormal deterioration of finish.

D. Submit warranties in accordance with Section 013300 "Submittal Procedures".

E. All parts shall be readily available locally in the United States.

PART 2 – PRODUCTS

2.01 LIFT, COLUMN, SET OF 4, 66,000 LB CAPACITY, HYDRAULIC
Equipment Mark Number: 5690

A. Capacities and Dimensions:

1. Lifting capacity: 16,500 pounds per column, 66,000 pounds total capacity (minimum).
2. Lifting height: 67 inches.
3. Lifting speed: minimum 31 inches per minute.
4. Turning radius: 45 inches.
5. Tire size: 13 inches to 22.5 inches.
6. Power Supply

    a. 24 V DC
    b. Power charging with 100v power receptacle.

7. Individual jack dimensions:

    a. Height: 88-1/2 inches.
    b. Width: 45-3/4 inches.
    c. Depth: 43-5/16 inches front to back at the base.

B. Features and Construction:

1. Lifting Unit Assemblies:

a. Each of the lifting units shall contain a mechanical locking latch mechanism completely separate from the drive system.
b. The lifting units shall be easily movable on three wheels consisting of two fixed heavy duty steel wheels and a single rubber steering wheel mounted at the rear of the column.
c. Lifting forks shall be 12 inches in overall length (minimum).

2. Hydraulic System:

a. Each lifting unit shall be equipped with an electric hydraulic power unit. The motors shall be suitable for outdoor use and enclosed to protect from dirt and water.
b. The direct drive lifting cylinder shall be installed in such a manner as to push the carriage up, using no chains or cables. The extension of the cylinder shall occur inside of the carriage as to keep the plunger of the cylinder protected from dirt, sand, or any possible mechanical damage.
c. Hydraulic check valve shall hold load at any position of the cylinder. Redundant mechanical safety lock shall be continuously engaged except while lift is being lowered.
d. Solid galvanized steel pipes are used to pipe all hydraulic fluids in the system.
e. Pressure relief valve shall prevent overloading of the lifting unit.
f. Unit shall be equipped with regulator valve that shall control the lowering speed.

3. Controls:

a. A red “EMERGENCY STOP” lockable button shall be provided on each lifting unit’s control panel to permit manual shut down of all lifting units.
b. Simple and reliable control system based on plug-in boards that can be easily exchanged. Boards equipped with durable electro-mechanical safety relays.
c. Control system suitable for common operation of up to four columns.
d. Indication lamps at each column to show individual or all operation.
e. “UP” and “DOWN” motive buttons, shall be of the “dead-man” type. When one columns button is being pushed, no other column’s control can function.
f. Selection switch on master column for operation in either Individual / All.
g. Automatic synchronization for absolute synchronizing during lifting and lowering of all columns during entire stroke. (At different loads, tolerance maximum 1/8 inch).
h. Safety control for supervision of all operation functions, safety stop of whole lifting set after maximum 1-inch difference, in case of irregularity or failure.
i. Two safety roller switches.

4. Cables:

a. Interconnect cables shall be supplied to electrically connect the master lifting unit to the slave lifting units. Dummy plugs are not acceptable.

5. Accessories:

   a. Remote control pendant for controlling “UP”, “DOWN”, and “EMERGENCY STOP” functions of the lifting units. Control shall have a minimum of 33 feet of cable.

6. Utilities Available: 110v for charging.
7. Finish: Durable enamel in manufacturer’s standard color.

C. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Stertil Koni
   200 Log Canoe Circle
   Stevensville, MD 21666
   Phone: (800) 336-6637, (410) 643-9001
   Fax: (410) 643-8901
   Website: www.stertil-koni.com

   b. Model: ST-1075-FSF

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

   a. Mohawk Lifts
   PO Box 110, Vrooman Avenue
   Mohawk Industrial Park
   Amsterdam, NY 12010
   Phone: (800) 833-2006, (518) 842-1431
   Fax (518) 842-1289

   b. Rotary Lift, A Dover Industries Company
   2700 Lanier Drive
   Madison, IN 47250
   Phone: (812) 445-5438, (800) 445-5438
   Fax: (812) 273-6502, (800) 578-5438
   Website: www.rotarylift.com

2.02 LIFT, 2-POST, HYDRAULIC
Equipment Mark Number: 5650

A. Capacities and Dimensions:

1. Motor: 3 HP.
2. Lifting capacity: 18,000 pounds (minimum).
3. Lifting height: 85 inches.

4. Drive-through Clearance: 104 inches
5. Lifting time: 60 seconds.
6. Overall dimensions:

    a. Height: 16 feet, 6 inches.
    b. Width: 12 feet, 11 inches.

B. Features and Construction:

1. Lift Features:

    a. Single point air actuated lock release.
    b. Standard combination stack screw pads and storage brackets.
    c. Oversized steel pulley.
    d. Padded overhead shut off system
    e. 60" lifting carriage

2. Hydraulic System:

    a. Each lifting unit shall be equipped with an electric hydraulic power unit, consisting of a 3 HP electric motor, gear pump, reservoir, valves for up, down, pressure relief, regulator valve, and check valve.
    b. The direct drive lifting cylinder shall be installed in such a manner as to push the carriage up, using no chains or cables. The extension of the cylinder shall occur inside of the carriage as to keep the plunger of the cylinder protected from dirt, sand, or any possible mechanical damage.
    c. Hydraulic check valve shall hold load at any position of the cylinder. Redundant mechanical safety lock shall be continuously engaged except while lift is being lowered.
    d. Solid galvanized steel pipes are used to pipe all hydraulic fluids in the system.
    e. Pressure relief valve shall prevent overloading of the lifting unit.
    f. Unit shall be equipped with regulator valve that shall control the lowering speed.

3. Controls:

    a. A red “EMERGENCY STOP” lockable button shall be provided on each lifting unit’s control panel to permit manual shut down of all lifting units.
    b. Simple and reliable control system based on plug-in boards that can be easily exchanged. Boards equipped with durable electro-mechanical safety relays. No electronic or computerized system that would be sensitive to water, condensation, voltage alteration, and external influence shall be used.
    c. “UP” and “DOWN” motive buttons, shall be of the “dead-man” type.

4. Finish: Durable enamel in manufacturer’s standard color.

C. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Challenger Lifts
200 Cabel Street
Louisville, KY 40206
Website: www.challengerlifts.com

b. Model: 18002

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Mohawk Lifts
PO Box 110, Vrooman Avenue
Mohawk Industrial Park
Amsterdam, NY 12010
Phone: (800) 833-2006, (518) 842-1431
Fax (518) 842-1289

b. Stertil Koni
200 Log Canoe Circle
Stevensville, MD 21666
Phone: (800) 336-6637, (410) 643-9001
Fax: (410) 643-8901
Website: www.stertil-koni.com

PART 3 - EXECUTION

3.01 INSPECTION

A. Coordinate location of rough-in work and utility stub-outs to assure match with equipment to be installed.

B. Inspect delivered equipment for damage from shipping and exposure to weather. Compare delivered equipment with packing lists and specifications to assure receipt of all items.

3.02 INSTALLATION

A. Perform work under direct supervision of Foreman or Construction Superintendent with authority to coordinate installation of scheduled equipment with Architect.

B. Install equipment in accordance with plans, shop drawings and manufacturer's instructions:

1. Positioning: Place equipment in accordance with any noted special positioning requirements generally level, plumb and at right angles to adjacent work.
2. Fitting: Where field cutting or trimming is necessary, perform in a neat, accurate, professional manner without damaging equipment or adjacent work.
3. Anchorage: Attach equipment securely to prevent damage resulting from inadequate fastenings. Installation fasteners shall be installed to avoid scratching or damaging adjacent surfaces.
4. Upon completion of work, finish surfaces shall be free of tool marks, scratches, blemishes, and stains.

3.03 TESTING

A. After final connections are made and prior to authorizing payment, specified equipment shall be tested for compliance with specifications in the presence of the Architect using acceptance procedures provided by the manufacturer.

3.04 CLEANUP

A. Touch-up damage to painted finishes.

B. Wipe and clean equipment of any oil, grease, and solvents, and make ready for use.

C. Clean area around equipment installation and remove packing or installation debris from job site.

D. Notify Architect for acceptance inspection.

3.05 TRAINING

A. Direct the technical representative to provide specified hours of training to designated Owner's maintenance personnel in operation and maintenance of the following equipment. Coordinate, with Owner, training schedule and list of personnel to be trained.

1. 5650 LIFT, 2-POST, 18,000 LB CAPACITY, HYDRAULIC: 4 hours.
2. 5690 LIFT, COLUMN, SET OF 4, 60,000 LB CAPACITY, HYDRAULIC: 4 hours.

B. Demonstrate lift operation utilizing each of the vehicle types operated by Owner.

C. Obtain, from technical representative, a list of Owner's personnel trained in equipment operations and maintenance.

END OF SECTION 117310

SECTION 117510 - SHOP EQUIPMENT

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

A. The General Provisions of the Contract, including General and Special Conditions and the requirements of Division 1, apply to the Work in this Section.

1.02 SUMMARY

A. This Section includes equipment items as listed below by Equipment Mark Number:

1. 2085 BUFFER/GRINDER, 8 INCH, WITH PEDESTAL (Ref. Part 2.01)
2. 2110 CAGE, INFLATION, TIRE (Ref. Part 2.02)
3. 2205 DRILL PRESS, VARIABLE SPEED, 15 INCH (Ref. Part 2.03
4. 2403 AUTOMOTIVE TIRE SPIN BALANCER (Ref. Part. 2.04)
5. 2404 AUTOMOTIVE TIRE MOUNTER/DEMOUNTER (Ref. Part. 2.05)
6. 2419 PEDESTAL-MOUNTED OIL FILTER PRESS (Ref. Part. 2.06)
7. 2443 TRANSMISSION REBUILD TABLE WITH DRAIN (Ref. Part 2.07)
8. 2450 MOUNTER/DEMOUNTER, TIRE, TRUCK (Ref. Part 2.08)
9. 2532 PRESS, ELECTRIC/HYDRAULIC, 50 TON (Ref. Part 2.09)
10. 2832 VISE, COMBINATION, SWIVEL BASE, 5 INCH (Ref. Part 2.10)
11. NOT USED
12. 3515 TANK, PARTS CLEANING, AIR OPERATED, SMALL (Ref. Part 2.12)
13. 3720 WASHER, HI-PRESSURE/HOT WATER, NG (Ref. Part 2.13)
14. 8160 DRAIN PAN, PIT, ROLLING (Ref. Part 2.14)
15. 8170 REFRIGERANT RECYCLING MACHINE (Ref. Part 2.15)
16. 8180 ANTIFREEZE EXCHANGER (Ref. Part 2.16)

B. Roughing-in, installation of equipment, and final connection of utilities, with labor, services, and incidentals necessary for complete and operational equipment installation.

C. Piping, wiring, and switching between equipment and utilities.

1.03 ALTERNATIVE BIDS

A. Section 012300 "Alternates" may apply to Work of this Section.

1.04 PRODUCT SUBSTITUTIONS

A. Submit requests for substitutions in accordance with Section 012500 "Substitution Requirements".

B. Additional costs resulting from substitution of products other than those specified, including drawing changes and construction, will be at the expense of the Contractor.

C. Substitution Approval: Manufacturers listed for each equipment item may bid without submittal for that item. Manufacturers not listed shall submit for approval in accordance with Document 00500 "Procurement Substitution Procedures". Prior to installation, submittals for each equipment item by Mark Number shall be provided in accordance with Section 013300 "Submittal Procedures".

1.05 QUALITY ASSURANCE

A. Experience: Equipment shall be produced by a manufacturer of established reputation with a minimum of five years experience supplying specified equipment.

B. Manufacturer's Representative:

1. Installation: Provide a qualified manufacturer's representative at site to supervise work related to equipment installation, check out and start up.
2. Training: Provide technical representative to train Owner's maintenance personnel in operation and maintenance of specified equipment.

1.06 ACTTION SUBMITTALS

A. Product Data:

1. Submit Product Data in accordance with Section 013300 "Submittal Procedures".
2. Restrict submitted material to pertinent data. For instance, do not include manufacturer's complete catalog when pertinent information is contained on a single page.

B. Shop Drawings: Submit Shop Drawings in accordance with Section 013300 "Submittal Procedures".

1.07 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Manual:

1. Provide complete parts, operating, and maintenance manual covering equipment at time of installation including, but not limited to:

a. Description of system and components.
b. Schematic diagrams of electrical, plumbing and compressed air systems.
c. Manufacturer's printed operating instructions.
d. Printed listing of periodic preventive maintenance items and recommended frequency required to validate warranties. Failure to provide maintenance information will indicate that preventive maintenance is not a condition for validation of warranties.
e. List of original manufacturer's parts, including suppliers' part numbers and cuts, recommended spare parts stockage quantity and local parts and service source.

2. Assemble and provide copies of manual in 8-1/2 by 11 inch format. Foldout diagrams and illustrations are acceptable. Manual to be reproducible by dry copy method. Provide copies per provisions of Section 017823 "Operations and Maintenance Data".

1.08 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver equipment in manufacturer's containers, appropriately packaged and/or crated for protection during domestic shipment and storage in humid, dusty conditions.

B. Indelibly label all containers, including those contained in others, on outside with item description(s) per title and Mark Number of this specification.

C. Provide equipment and materials specified complete in one shipment for each equipment item. Split or partial shipments are not permissible.

1.09 LABELING

A. Manufacturer shall securely attach in a prominent location on each major item of equipment a noncorrosive nameplate showing manufacturer's name, address, model number, serial number, and pertinent utility or operating data.

B. All electrical equipment and materials shall be new and shall be listed by Underwriter's Laboratories, Inc. (U.L.) in categories for which standards have been set by that agency and labeled as such in the manufacturer's plant.

1.10 WARRANTY

A. Warrant work specified herein for one year from substantial completion against defects in materials, function and workmanship.

B. Warranty shall include materials and labor necessary to correct defects.

C. Defects shall include, but not be limited to noisy, rough, or substandard operation; loose, damaged, and missing parts; and abnormal deterioration of finish.

D. Submit warranties in accordance with Division 1 - General Requirements of these specifications.

E. All parts shall be readily available locally in the United States.

PART 2 – PRODUCTS

2.01 BUFFER/GRINDER, 8 INCH, WITH PEDESTAL
Equipment Mark Number: 2085

A. Capacities and Dimensions:

1. Buffer/grinder:

a. Motor: 3/4 HP, 3600 RPM.
b. Wheel:

1) Diameter: 8 inches.
2) Thickness: 1 inch.
3) Bore: 3/4 inch.

c. Wheel spacing: 17 inches.
d. Height to center of spindle: 39 inches.

2. Overall dimensions:

a. Width: 22 inches.
b. Depth: 10-7/8 inches.

3. Weight: 255 pounds, nominal.

B. Features and Construction:

1. Motor: Totally enclosed, direct drive motor rated for continuous service, with permanently lubricated ball bearings.
2. Wheels: One each, medium grit and general purpose wire wheel.
3. Wheel guards: Adjustable for wheel wear, provided with exhaust outlets, adjustable work rests and spark breakers.
4. Pedestal: Provide pedestal base with tool tray and water pot.
5. Power supply: Connections for hookup to junction box.

C. Controls: ON/OFF toggle switch and other electrical controls meeting applicable National Electrical Code requirements.

D. Accessories:

1. Illuminated eyeshields: Installed, Cincinnati No. 000-131, one set of two each per grinder.
2. Wire wheel: Factory installed, general purpose, 8 by 1 inch wire wheel, one each.

E. Utilities Available: 460 VAC, 3 phase, 3/4 HP.

F. Finish: Durable enamel in manufacturer's standard color.

G. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Cincinnati Electrical Tool, Inc.
5928 State Route 128
Cleves, Ohio 45002
Phone: (513) 941-5000
Fax: (513) 353-4040
Website: www.cincinnatielectrical.com

b. Model: 102-134 with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Delta International Machinery Corp.
246 Alpha Drive
Pittsburgh, PA 15238
Phone: (412) 963-2400, (800) 223-7278
Website: www.deltawoodworking.com

b. Baldor Electric Company
5711 R.S. Boreham, Jr. Street
Fort Smith, AK 72908
Phone: (501) 646-4711
Fax: (501) 648-5785
Website: www.baldor.com

2.02 CAGE, INFLATION, TIRE
Equipment Mark Number: 2110

A. Capacities and Dimensions:

1. Tire capacity: 12.00-24 inches (50-inch diameter).
2. Cage: Five 2-1/4 inch bars.
3. Overall dimensions:

a. Width: 21-3/4 inches.
b. Depth: 36 inches.
c. Height: 50 inches.

4. Weight, nominal: 167 pounds.

B. Features and Construction: All welded steel construction with high tensile steel tubing, base plate, and side plates.

C. Finish: Durable enamel in manufacturer's standard color.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Branick Industries, Incorporated
4245 Main Ave.
Fargo, ND 58102
Phone: (701) 281-8888, (800) 437-4394
Fax: (701) 281-5900
Website: www.branick.com

b. Model: 2250

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Myers Tire Supply
1293 South Main Street
Akron, OH 44301
Phone: (330) 253-5592
Fax: (330) 761-6226
Website: www.myerstiresupply.com

b. Ken-Tool
768 E. North Street
Akron, OH 44305
Phone: (330) 535-7177
Fax: (330) 535-1345
Website: www.kentool.com

2.03 DRILL PRESS, VARIABLE SPEED, 15 INCH
Equipment Mark Number: 2205

A. Capacities and Dimensions:

1. Motor: 3/4 HP, 1,725 RPM.
2. Overall dimensions, nominal:

a. Width: 15-1/2 inches.
b. Depth: 28 inches.
c. Height: 74 inches.

3. Working dimensions:

    a. Spindle to table: 43-1/8 inches.
    b. Spindle to base: 47 inches.

4. Table working surface:

    a. Width: 14 inches.
    b. Depth: 11 inches.
    c. Tilt range: 90 degrees to left and right.

5. Base working surface:

    a. Width: 11-1/4 inches.
    b. Depth: 14 inches.

6. Quill:

    a. Stroke: 6 inches.
    b. Diameter: 2 inches.

7. Capacities:

    a. Key chuck: 0 to 1/2 inch.
    b. Diameter hole:

        1) In steel: 5/8 inch.
        2) In cast iron: 1/2 inch.

    c. Throat: 7-1/2 inches.

8. Spindle speed: Infinitely variable 300 to 3,100 RPM.
9. Column:

    a. Wall thickness: 5/32 inch.
    b. Diameter: 2-3/4 inches.

10. Overhang, center of spindle to center of column: 8-7/8 inches.
11. Pulley bearings: 2 inch diameter, minimum.
12. Power cord length: 96 inches.
13. Weight, nominal: 245 pounds.

B. Features and Construction:

1. Speed control: Speed control shall permit positive speed changing while machine is running and hold speed setting constant under all load conditions.
2. Belt drive: Belt drive shall remain aligned and automatically maintain full power transmission to spindle at all times.
3. Bearings: Spindle and spindle pulley shall be supported by not fewer than four permanently lubricated ball bearings.

4. Work table: Slots, side ledges, and machined front apron with mounting holes shall be provided for clamping of work with mounting holes.
5. Table tilt features: Tilt scale shall provide accurate readings to 90 degrees right and left with index pin at level and 90 degrees left and right positions.
6. Table lock: Expanding bushing table lock shall provide rigid positioning of table at any angle.
7. Table adjustment: Hand gear crank shall be provided for table elevation.
8. Floor base: Two full-length T-bolt slots shall permit insertion of T-bolts from front and rear.
9. Safety features: Safety features shall include self ejecting chuck key and completely enclosed drive belt and pulleys.
10. Chuck: Chuck shall be jacobs type for use with standard bits.
11. Motor: Motor shall be totally enclosed fan cooled.
12. Depth control: Self locking, adjustable depth stop shall be provided for feed.
13. Function controls: Knobbed spoke wheels shall provide manual speed selection and feed.
14. Power cord: Three wire grounding cord shall have standard three prong plug.

C. Controls: 24 volt pushbutton control station with shrouded START button and protruding STOP button, magnetic starter with transformer and no voltage/low voltage and three leg overload protection. Switches and other electrical controls shall meet applicable National Electrical Code requirements.

D. Utilities Available: 120 VAC, 3/4 HP.

E. Finish: Durable enamel in manufacturer's standard color.

F. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

    a. Delta Machinery
    4825 Hwy. 45 North
    P.O. Box 2468
    Jackson, TN 38302-2468
    Phone: (800) 223-7278
    Fax: (800) 382-2922
    Website: www.deltamachinery.com

    b. Model: 15-332

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

    a. Clausing Industrial
    1819 North Pitcher Street
    Kalamazoo, MI 49007
    Phone: (616) 345-7155

Fax: (616) 345-5945
Website: www.clausing-industrial.com

b. Powermatic
427 Sanford Road
LaVergne, TN 37086
Phone: (931) 473-5551, (888) 804-7129
Fax: (800) 274-6840
Website: www.powermatic.com

2.04 AUTOMOTIVE TIRE SPIN BALANCER
Equipment Mark Number: 2403

A. General Description:

1. Automotive Tire Balancer.
2. OSHA requirements: The system shall meet or exceed all applicable OSHA standards.
3. Electrical wiring: Electrical wiring shall be in accordance with the latest edition of the National Electric Code and the appropriate sections of Division 26.

B. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Hennessey Industries, Inc.
1601 J.P. Hennessy Drive
La Vergne, TN 37086
Toll-free Phone: (800) 688-6359
Fax: (800) 688-3659
Website: www.ammcoats.com

b. Model: Vero Series, V200

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.05 AUTOMOTIVE TIRE MOUNTER/DEMOUNTER
Equipment Mark Number: 2404

A. Capacities and Dimensions:

1. Rim diameter capacity: 10” – 32”.
2. Rim width: 16 inches.
3. Tire diameter, maximum: 47 inches.
4. Drive system: Manual.

5. Overall dimensions, nominal: 46"w x 77"d x 83"h

B. Features and Construction:

1. Operation: 1st Loosen Bead, 2nd Mount/Demount
2. Mount / Demount: Tilt Back.
3. Table Shape: Center Post.
4. Wheel Clamping Method: Pneumatic Locking Center Cone.
5. Wheel Clamping Method: Pneumatic Locking.
6. Bead Loosening System: Roller Disc
7. Bead Lifting: System Leverless
8. Electric Drive System: 230v, 1phase, 20amp (1-1.5HP two speed

C. Finish: Durable enamel in manufacturer's standard color.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Hennessy Industries
1601 J.P. Hennessy Drive
LaVergne, TN 37086
Phone: (800) 688-6359, (615) 641-7533
Fax: (615) 641-5104
Website: www.ammcoats.com

b. Model: Coats PROGUARD PLUS L

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. SICE USA Ltd
879 Broadway
Albany, NY 12207
Phone: (518) 462-1384
Fax: (518) 434-8310
Website: www.siceusa.com

b. McCourt Industries
1314 Centerview Circle
Akron, OH 44321
Phone: (800) 232-2190, (330) 666-0149
Fax: (330) 666-3432
Website: www.mccourtindustries.com

2.06 PEDESTAL-MOUNTED OIL FILTER PRESS
Equipment Mark Number: 2419

A. General Description:

1. Heavy duty oil filter press/crusher.
2. OSHA requirements: The system shall meet or exceed all applicable OSHA standards.
3. Electrical wiring: Electrical wiring shall be in accordance with the latest edition of the National Electric Code and the appropriate sections of Division 26.

B. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Bedford Industries, Inc.
14512 167th Avenue SE, Suite 192
Monroe, Washington 98272
Toll Free (800) 848-8228
Phone (360) 805-9099
Website: www.oberg-crushers.com

b. Model: P-200L

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.07 TRANSMISSION REBUILD TABLE WITH DRAIN
Equipment Mark Number: 2443

A. General Description:

1. 10 foot long transmission rebuild table with drain.
2. OSHA requirements: The system shall meet or exceed all applicable OSHA standards.
3. Electrical wiring: Electrical wiring shall be in accordance with the latest edition of the National Electric Code and the appropriate sections of Division 16.

B. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. J-Mar Metal Fabrications, Inc.
1025 Washington Avenue
Croydon, PA 19021
Phone: (215) 785-6521

Fax: (215) 785-6545
Website: www.j-marmetal.com

b. Model: RB-100-10 feet

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.08 MOUNTER/DEMOUNTER, TIRE, TRUCK
Equipment Mark Number: 2450

A. Capacities and Dimensions:

1. Motor: 3 HP.
2. Wheel capacity:

a. Width: 6 to 15 inches.
b. Diameter, tubeless: 16-1/2 to 24-1/2 inches.

3. Overall dimensions, nominal:

a. Length: 85 inches.
b. Width: 51 inches.
c. Height, excluding handles: 20 inches.

4. Weight, nominal: 1,150 pounds.

B. Features and Construction:

1. Adaptability: Changer shall be capable of mounting and demounting tubeless tires for all 15 degree single piece highway truck rims demountable (Dayton), standard disc wheels, and reverse disc (Budd) wheels and shall also break beads for tube type tires.
2. Positioning: Pivoting work table shall permit operation at any angle.
3. Wheel locking: Pneumatically driven clamping mechanism shall be independent of wheel center design, and require no adapters.
4. Rotation: Mounting/demounting rotates in either direction at 6 RPM.
5. Bead breaking: Designed with pinch action to loosen both beads simultaneously.
6. Function controls: Two way foot pedal for bead loosening; PUSH/PULL control stick for table pivot; twist control stick for wheel clamping; dual two way foot pedals for mounting/demounting.
7. Air connection: 1/4 inch NPT(M) fitting.
8. Power supply: Connections for hookup to junction box.

C. Controls: ON/OFF switching and other electrical controls shall meet applicable National Electrical Code requirements.

D. Utilities Available:

1. Electrical: 208 VAC, 1 phase, 3 HP.
2. Air: 1/4-inch, 125 PSI.

E. Finish: Durable enamel in manufacturer's standard color.

F. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Hennessy Industries
1601 J.P. Hennessy Drive
LaVergne, TN 37086
Phone: (800) 688-6359, (615) 641-7533
Fax: (615) 641-5104
Website: www.ammcoats.com

b. Model: Coats H.I.T. 6000

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Hunter Engineering Company
11250 Hunter Drive
Bridgeton, MO 63044
Phone: (888) 450-7200, (314) 731-3020
Fax: (888) 532-3622
Website: www.hunter.com

b. John Bean
309 Exchange Avenue
Conway, AR 72032
Phone: (800) 362-4618, (501) 450-1500
Fax: (501) 450-2085
Website: www.johnbean.com

2.09 PRESS, ELECTRIC/HYDRAULIC, 50 TON
Equipment Mark Number: 2532

A. Capacities and Dimensions:

1. Capacity: 50 tons.
2. Inside width: 34 inches.
3. Width between table rails: 7 inches.
4. Table travel: 36 inches.

5. Maximum vertical clearance: 41-1/2 inches
6. Ram travel: 14 inches.
7. Ram speed:

    a. No load: 24 IPM.
    b. Half load: 17 IPM.
    c. Full load: 13.3 IPM.

8. Ram diameter: 2-3/4 inches.
9. Cylinder bore: 3-1/2 inches.
10. Table spacing increments: 4 inches.
11. Left to right cylinder movement: 24 inches.
12. Pump motor size: 7.5 HP.
13. Overall dimensions:

    a. Width: 67 inches.
    b. Depth: 30 inches.
    c. Height: 82 inches.

14. Shipping weight, nominal: 880 pounds.

B. Features and Construction:

1. Hydraulic pump and motor: The hydraulic pump, motor, and reservoir shall be contained in module located outside the press frame.

    a. Pump: The hydraulic pump shall be a high quality, constant flow, radial piston type without packing and shall be direct coupled to the drive motor.
    b. Motor: The pump drive motor shall be a 5 HP pump flange mounted motor with a 1.15 service duty rating.

2. Movable cylinder: The press head and cylinder (ram) shall be movable from side to side of the head rails. Quick acting 90 degree locking cams shall lock the head at desired location.
3. Table: The press table shall be vertically adjustable with a self-locking table winch and cable that is mounted outside of frame.
4. Construction: Press shall have all channel ends and corners cut and ground for safety.

    a. Frame uprights: The press frame uprights shall be fabricated of 7 inch steel channels.
    b. Head and table rails: Head and table rails shall be fabricated of 8 inch steel.
    c. Base members: Both press and pump module base members shall be fabricated of 3 by 2 inch steel angle.
    d. Table locking pins: Press shall have a minimum of four, 7/8 inch diameter locking pins.

5. Equipment protection: The press shall have a ram travel limit valve to prevent overextension of ram and a maximum capacity relief valve to prevent loading more than 110 percent of press capacity. An adjustable pressure relief valve shall also be provided to allow press operator to set maximum pressure at any point between zero and maximum capacity.

6. Controls: Press controls shall be mounted on the pump module located outside the press frame so that the front of the press is clear.

    a. Hydraulic controls: There shall be two hand operated hydraulic valves.
    b. ON-OFF control: Pump motor shall be controlled by a pushbutton magnetic starter with overload protection.
    c. Gauge: A large, dial type pressure gauge shall be mounted on the outside of the press frame to isolate gauge from mechanical shock.

7. Standard accessories: Press shall include two flat parallels with "V" grooves, two "V" ram noses, and two flat ram noses as standard accessories.

C. Accessories: Round ram nose, Hypress No. FRN-50, one each.

D. Utilities Available: 460 VAC, 3 phase, 5 HP.

E. Finish: Durable enamel in manufacturer's standard color.

F. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

    a. Nugier Press Company, Inc.
    18031 La Salle Avenue
    Gardena, CA 90248
    Phone: (310) 515-6025
    Fax: (310) 527-7362
    Website: www.nugier.com

    b. Model: H50-14MD7.5 with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

    a. Dake, Division of JSJ Corporation
    724 Robbins Road
    Grand Haven, MI 49417
    Phone: (616) 842-7110, (800) 937-3253
    Fax: (800) 846-3253
    Website: dake-div-jsjcorp.com

    b. OTC Division of SPX
    655 Eisenhower Drive
    Owatonna, MN 55060
    Phone: (507) 455-7000, (800) 533-6127
    Fax: (507) 455-8354
    Website: www.otctools.com

2.10 VISE, COMBINATION, SWIVEL BASE, 5 INCH
Equipment Mark Number: 2832

A. Capacities and Dimensions:

1. Jaw width: 5 inches.
2. Jaw opening: 6 inches.
3. Throat depth: 6-1/4 inches.
4. Pipe capacity: 1/8 to 4-1/2 inches.
5. Overall dimensions, nominal:

a. Length: 14 inches.
b. Width: 8 inches.
c. Height: 10 inches.

6. Weight, nominal: 95 pounds.

B. Features and Construction:

1. Slide bar: Machined steel slide bar with oil port shall operate in machined channel.
2. Base: 360 degree swivel base shall include locking device.
3. Construction: Semi-steel cast body shall include hardened tool steel nut and screw.
4. Jaws: Main and pipe jaw facings shall be replaceable.
5. Wear compensation: Adjustable collar shall eliminate handle slack.

C. Finish: Durable enamel in manufacturer's standard color.

D. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Reed Manufacturing Company
1425 West 8th Street
Erie, PA 16502
Phone: (814) 452-3691, (800) 666-3691
Fax: (814) 455-1697, (800) 456-1697
Website: www.reedmfgco.com

b. Model: 3CA

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Ridge Tool Company
400 Clark Street
Elyria, OH 44036
Phone: (440) 323-5581, (888) 743-4333

Fax: (800) 873-2160
Website: www.ridgid.com

b. WMH Tool Group, Inc.
2420 Vantage Drive
Elgin, Illinois 60123
Phone: 847-851-1000, 1-800-274-6848
Fax: 847-851-1045
Website: www.wmhtoolgroup.com

2.11 NOT USED

2.12 TANK, PARTS CLEANING, AIR OPERATED, SMALL
Equipment Mark Number: 3515

A. Capacities and Dimensions:

1. Overall dimensions:

a. Width: 36 inches.
b. Depth: 22 inches.
c. Height: cover upright: 60 inches.

2. Fluid capacity: 8-1/2 to 15 gallons.
3. Tank shelf area:

a. Length: 36 inches.
b. Depth: 22 inches.

4. Soak tank:

a. Length: 29-1/2 inches.
b. Width: 15-1/2 inches.
c. Depth of solvent: 6 inches, nominal.

B. Features and Construction:

1. Motor: Variable speed air operated pump motor with screened intake.
2. Flush hose: Flexible metal with stream nozzle.
3. Shelf adjustment: Removable work shelf for choice of tank depth and work area.
4. Filtration: Sludge collector and filter tray assembly easily removed for cleaning.
5. Safety: Spring loaded fusible link safety cover automatically closes at 165 degrees F.
6. Construction: 18 gauge steel front and side panels with 16 gauge steel bottom and rear panels.
7. Cleanout: Bottom drain for cleaning.

C. Accessories: External drain shelf, Model No. L-61, one each.

D. Utilities Available: Air, 120 PSI, 6 CFM.

E. Finish: Durable enamel in manufacturer's standard color.

F. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Graymills Corporation
3705 North Lincoln Avenue
Chicago, IL 60613
Phone: (773) 248-6825, (773) 477-4100
Fax: (800) 478-8673
Website: www.graymills.com

b. Model: PL36-GAM with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Kansas Instruments
1100 Union Street
Council Grove, KS 66846
Phone: (800) 835-3528, (316) 767-6721
Fax: (620) 767-6415
Website: www.kidiv.com

b. Precision Metal Works
703 E. Platt Street
Maquoketa, IA 52060
Phone: (319) 652-6707, (800) 272-5438
Fax: (563) 652-4126
Website: www.pmwequipment.com

2.13 WASHER, HI-PRESSURE/HOT WATER, PROPANE
Equipment Mark Number: 3720

A. General Description:

1. Hi-pressure/hot water propane-fired washer shall be designed for effective cleaning of vehicle exteriors through the use of handheld wash wands. Washer shall be complete and operable with all equipment items necessary for a complete wash system.
2. OSHA requirements: The system shall meet or exceed all applicable OSHA standards.
3. Electrical wiring: Electrical wiring shall be in accordance with the latest edition of the National Electric Code and the appropriate sections of Division 16.

B. Capacities and Dimensions:

1. Pump motor: 15 HP, 1725 RPM.
2. Overall dimensions:

    a. Length: 57 inches.
    b. Width: 32 inches.
    c. Height: 50 inches.

3. Maximum discharge capacity: 8 GPM.
4. Operating pressure: 3000 PSI.
5. Float tank capacity: 6 gallons.
6. Heat rise capability: 140 degrees F at 8 GPM.
7. Hose:

    a. Inside diameter: 1/2 inch.
    b. Length: 50 feet.
    c. Burst pressure: 12,000 PSI, minimum.
    d. Quantity: One each.

8. Net weight: 870 pounds, nominal.

C. Features and Construction:

1. Fabrication: Welded angle iron frame shall have heavy gauge tank and cabinets.
2. Water pump: Triplex water pump shall have positive displacement with ceramic plungers, brass manifold, and oil bath crankcase.
3. Burner: 657,000 BTU/hour ring type propane draft gas burner shall have aspirating spuds and AGA-listed controls.
4. Heating coil: Vertically fired water heating coil shall be fabricated with 168 feet of 1 inch, hydrostatic pressure tested tubing, 14,900 PSI burst pressure rated. Coil shall be sheathed in a full-length sheet metal wrap without outer insulation wrap.
5. Wand assembly: Trigger gun control with 48-inch wand and insulated grips.
6. Nozzles: Three stainless steel nozzles shall be provided, one each 0 degree, 15 degree, and 40 degree patterns.
7. Pump drive motor: 15 HP, 460 VAC, 3 phase, drip proof motor shall be provided.
8. Float tank: Float tank shall be composed of polyethylene plastic with automatic nonplugging float valve.
9. Unloader valve: Pressure maintenance during multiple gun operation shall be provided by unloader valve.
10. Pressure switch: Automatic burner shut-off protection shall be provided by pressure switch.
11. Relief valve: Pressure relief valve shall provide protection for washer component.
12. Thermostat: Adjustable thermostat shall control water temperature to a maximum of 248 degrees F.
13. Chemical metering: Calibrated metering of chemicals shall be controlled by valve.

D. Controls: ON/OFF electric motor switch shall include overload protection and ON/OFF water heater switch, adjustable temperature controller, safety and pressure relief value, pressure switch.

E. Accessories:

1. Draft diverter, 10 inch, natural gas, Hotsy No. 835525, one each.
2. Automatic spark ignition pilot light, Hotsy No. 280391, one each.
3. Pump, by-pass temperature sensor kit, Hotsy No. 921422, one each.

F. Utilities Available:

1. Electrical: 460 VAC, 3 phase, 15 HP.
2. Water: 3/4 inch, 8 GPM.
3. Natural gas: 2 inch, 657 CFH.
4. Exhaust: 10 inch with draft diverter.

G. Finish: Durable enamel in manufacturer's standard color.

H. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

   a. Hotsy Corporation
   21 Inverness Way East
   Englewood, CO 80112
   Phone: (303) 792-5200, (800) 525-1976
   Fax: (303) 792-0547
   Website: www.hotsy.com

   b. Model: S-5735-3 with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

   a. Hydro Engineering, Incorporated
   865 West 2600 South
   Salt Lake City, UT 84119
   Phone: (801) 972-1181, (800) 247-8424
   Fax: (801) 972-3265
   Website: www.hydroblaster.com

   b. Jenny Products, Inc.
   850 North Pleasant Ave.
   Somerset, PA 15501
   Phone: (814) 445-3400
   Fax: (814) 445-2280
   Website: www.steamjenny.com

2.14 DRAIN PAN, PIT, ROLLING
Equipment Mark Number: 8160

A. Capacities and Dimensions:

1. Capacity: 20 gallons, minimum.
2. Overall dimensions, nominal:

a. Length: 35 inches.
b. Width: 33 inches.
c. Depth: 11 inches.

B. Features and Construction:

1. Adjustment: Drain pan wheels shall be adjustable to fit pit opening width of 37-1/2 to 46 inches.
2. Wheels: Drain pan shall be equipped with four wheels, each having a 3 inch diameter minimum suitable for rolling in 4 inch high by 2-1/2 inch deep steel channels recessed in repair pit walls below the top edge of the finished shop floor.
3. Drain: The drain pan shall be equipped with 1/4 turn shut-off valve and dry break quick disconnect coupler with 6 feet of 1-1/2 inch hose for emptying pan. Hose shall be hard plumbed to waste oil line in pit. Contractor shall provide a wall mounted hook for storing hose/coupler assembly when not in use.
4. Construction: The pan shall have metal construction and shall have a metal screen to prevent parts from falling into pan.
5. Labeling: Provide WASTE OIL label on two sides of drain pan in minimum 3 inch letters in easily readable location when drain pan is installed.

C. Accessories: 12 foot section of 1-1/2 inch oil proof synthetic rubber drain hose with a drain pan compatible dry break quick disconnect coupler on one end and a 1-1/2 inch NPTF hose fitting on the other, one each assembly.

D. Finish: Durable enamel in Owner’s choice of color. Note that waste oil and coolant drain pans must be painted a different color from each other, if applicable.

E. Utilities Available: Oil drain plumbed to waste oil tank.

F. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Lincoln Industrial Corporation
One Lincoln Way
St. Louis, MO 63120
Phone: (314) 679-4200
Fax: (314) 679-4359, (800) 424-5359
Website: www.lincolnindustrial.com

b. Model: 3614 with Accessories

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

a. Graco Inc.
P.O. Box 1441
Minneapolis, MN 55440
Phone: (612) 623-6000, (800) 533-9655
Fax: (612) 623-6777, (800) 533-9656
Website: www.graco.com

b. Ingersoll-Rand, Fluid Products
One Aro Center
Bryan, OH 43506
Phone: (419) 636-4242
Fax: (419) 633-1674
Website: www.arozone.com

2.15 REFRIGERANT RECYCLING MACHINE
Equipment Mark Number: 8170

A. Features and Construction:

1. UV dye injection system.
2. Automatic oil measure and injection system.
3. A/C flush system.

B. Finish: Durable enamel in standard color.

C. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Robinair
Bosch Automotive Service Solutions
28635 Mound Road
Warren, MI 48092
Phone: (800) 533-6127
Website: www.robinair.com

b. Model: 34988

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

2.16 ANTIFREEZE EXCHANGER
Equipment Mark Number: 8180

A. Features and Construction:

1. 10 minute exchange process
2. Vacuum mode
3. Hands-off transfer
4. Graduations on tank

B. Finish: Durable enamel in standard color.

C. Manufacturers Reference:

1. Prime manufacturer: Specifications are based on equipment identified herein by manufacturer's name and model to establish acceptable standards of quality, performance, features, and construction.

a. Robinair
Bosch Automotive Service Solutions
28635 Mound Road
Warren, MI 48092
Phone: (800) 533-6127
Website: www.robinair.com

b. Model: 75700

2. Other manufacturers: Contingent upon compliance with these specifications and documentation requirements set forth in SUBMITTALS, equipment produced by other manufacturers, including the following, may be considered as equal.

PART 3 - EXECUTION

3.01 INSPECTION

A. Coordinate location of rough-in work and utility stub-outs to assure match with equipment to be installed.

B. Inspect delivered equipment for damage from shipping and exposure to weather. Compare delivered equipment with packing lists and specifications to assure receipt of all items.

3.02 INSTALLATION

A. Perform work under direct supervision of Foreman or Construction Superintendent with authority to coordinate installation of scheduled equipment with Architect.

B. Install equipment in accordance with plans, shop drawings and manufacturer's instructions:

1. Positioning: Place equipment in accordance with any noted special positioning requirements generally level, plumb and at right angles to adjacent work.
2. Fitting: Where field cutting or trimming is necessary, perform in a neat, accurate, professional manner without damaging equipment or adjacent work.
3. Anchorage: Attach equipment securely to floor, as directed by Architect, to prevent damage resulting from inadequate fastening. Installation fasteners shall be installed to avoid scratching or damaging adjacent surfaces.
4. Upon completion of work, finish surfaces shall be free of tool marks, scratches, blemishes, and stains.

3.03 TESTING

A. After final connections are made and prior to authorizing payment, specified equipment shall be tested for compliance with all specified features in the presence of the Architect using acceptance procedures provided by the manufacturer.

3.04 CLEANUP

A. Touch-up damage to painted finishes.

B. Wipe and clean equipment of any oil, grease, and solvents, and make ready for use.

C. Clean area around equipment installation and remove packing or installation debris from job site.

D. Notify Architect for acceptance inspection.

3.05 TRAINING

A. Direct the technical representative to provide specified hours of training to designated Owner's maintenance personnel in operation and maintenance of the following equipment. Coordinate, with Owner, training schedule and list of personnel to be trained.

1. 2085 BUFFER/GRINDER, 8 INCH, WITH PEDESTAL: 1/2 hour.
2. 2205 DRILL PRESS, VARIABLE SPEED, 15 INCH: 1/2 hour.
3. 2403 AUTOMOTIVE TIRE SPIN BALANCER: 1 hour.
4. 2404 AUTOMOTIVE TIRE MOUNTER/DEMOUNTER: 1 hour.
5. 2419 PEDESTAL-MOUNTED OIL FILTER PRESS: 1/2 hour.
6. 2450 MOUNTER/DEMOUNTER, TIRE, TRUCK: 1/2 hour.
7. 2532 PRESS, ELECTRIC/HYDRAULIC, 50 TON: 1/2 hour.
8. 3720 WASHER, HI-PRESSURE/HOT WATER, NG: 1 hour.
9. 8170 REFRIGERANT RECYCLING MACHINE: 1 hour.
10. 8180 ANTIFREEZE EXCHANGER: 1 hour.

B. Obtain, from technical representative, a list of Owner's personnel trained in equipment operations and maintenance.

END OF SECTION 117510

SECTION 117900 - RELOCATION OF EXISTING EQUIPMENT

PART 1 - GENERAL

1. RELATED DOCUMENTS

A. The General Provisions of the Contract, including General and Special Conditions and the requirements of Division 1, apply to the Work in this Section.

2. SUMMARY

A. This Section includes the following:

1. Disconnecting and relocating existing equipment delineated in Section 117000 -Equipment Schedule from existing facilities to new facility.
2. Roughing-in, installation of equipment, and final connection of utilities, with labor, services, repairs, and incidentals necessary for complete and operational equipment installation.
3. Piping, wiring, and switching between equipment and utilities.
4. Coordination and scheduling of examination, relocation, installation, and testing of existing equipment to be relocated as described in Section 11000 - Equipment Schedule shall be the responsibility of the Contractor.

B. Existing equipment to be relocated is listed in Section 11000 by Equipment Mark Number and shall be located and installed as shown on the Equipment Layout Drawings.

PART 2 – PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.01 GENERAL

A. Scheduling: Downtime of the equipment is critical to the Owner. The Contractor shall prepare for approval a schedule indicating dates for removing each item of equipment and the dates the equipment will be relocated and ready for operation. Relocation of equipment shall be accomplished only after beneficial occupancy of new facility by Owner. No item shall be out of operation for more than 48 hours.

B. Equipment Schedule: Owner furnished equipment to be relocated by the Contractor is delineated in Section 117000 - Equipment Schedule and is indicated as OF/CI (Owner Furnished/Contractor Installed).

3.02 PREPARATION

A. Equipment Preparation: Cleaning, degreasing, or painting of equipment for relocation will be accomplished by the Owner prior to examination and operation by the Contractor.

B. Equipment Examination: Before each equipment item is removed from the existing locations, it shall be examined and operated in the presence of the Owner, and any damage shall be recorded. Contractor shall submit a written report noting the condition of all equipment. No damaged items shall be removed unless approved by the Owner. All additional damage shall be the responsibility of the Contractor, and affected parts shall be repaired or replaced.

3.03 RELOCATION

A. When moving equipment, Contractor shall be responsible for removing bolts and other fastening devices as required.

B. Contractor shall provide all miscellaneous hardware and material required for final installation.

3.04 INSTALLATION AND TESTING

A. Operating Tests: After relocation and reconnection of each piece of equipment, the Contractor shall operate each piece of equipment in the presence of the Owner. Any damage to equipment, except that which was recorded prior to relocation, shall be corrected by the Contractor.

END OF SECTION 117900

SECTION 133419 - METAL BUILDING SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Structural-steel framing.
2. Metal wall panels.
3. Foamed-insulation-core metal wall panels.
4. Thermal insulation.
5. Personnel doors and frames.
6. Windows.
7. Accessories.

B. Related Requirements:

1. Section 077253 "Snow Guards" for prefabricated devices designed to hold snow on the roof surface.
2. Section 083323 "Overhead Coiling Doors" for coiling vehicular doors in metal building systems.

1.3 DEFINITIONS

A. Terminology Standard: See MBMA's "Metal Building Systems Manual" for definitions of terms for metal building system construction not otherwise defined in this Section or in standards referenced by this Section.

1.4 COORDINATION

A. Coordinate sizes and locations of concrete foundations and casting of anchor-rod inserts into foundation walls and footings. Anchor rod installation, concrete, reinforcement, and formwork requirements are specified in Section 033000 "Cast-in-Place Concrete."

B. Coordinate metal panel assemblies with rain drainage work, flashing, trim, and construction of supports and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.5 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to metal building systems including, but not limited to, the following:

    a. Condition of foundations and other preparatory work performed by other trades.
    b. Structural load limitations.
    c. Construction schedule. Verify availability of materials and erector's personnel, equipment, and facilities needed to make progress and avoid delays.
    d. Required tests, inspections, and certifications.
    e. Unfavorable weather and forecasted weather conditions and impact on construction schedule.

2. Review methods and procedures related to metal roof panel assemblies including, but not limited to, the following:

    a. Compliance with requirements for purlin and rafter conditions, including flatness and attachment to structural members.
    b. Structural limitations of purlins and rafters during and after roofing.
    c. Flashings, special roof details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that will affect metal roof panels.
    d. Temporary protection requirements for metal roof panel assembly during and after installation.
    e. Roof observation and repair after metal roof panel installation.

3. Review methods and procedures related to metal wall panel assemblies including, but not limited to, the following:

    a. Compliance with requirements for support conditions, including alignment between and attachment to structural members.
    b. Structural limitations of girts and columns during and after wall panel installation.
    c. Flashings, special siding details, wall penetrations, openings, and condition of other construction that will affect metal wall panels.
    d. Temporary protection requirements for metal wall panel assembly during and after installation.
    e. Wall observation and repair after metal wall panel installation.

1.6 ACTION SUBMITTALS

A. Product Data: For each type of metal building system component.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for the following:

    a. Metal roof panels.
    b. Metal wall panels.
    c. Foamed-insulation-core metal panels.
    d. Metal soffit panels.

e. Thermal insulation and vapor-retarder facings.
f. Personnel doors and frames.
g. Windows.

B. Shop Drawings: Indicate components by others. Include full building plan, elevations, sections, details and the following:

1. Anchor-Rod Plans: Submit anchor-rod plans and templates before foundation work begins. Include location, diameter, and minimum required projection of anchor rods required to attach metal building to foundation. Indicate column reactions at each location.
2. Structural-Framing Drawings: Show complete fabrication of primary and secondary framing; include provisions for openings. Indicate welds and bolted connections, distinguishing between shop and field applications. Include transverse cross-sections.
3. Metal Roof and Wall Panel Layout Drawings: Show layouts of panels including methods of support. Include details of edge conditions, joints, panel profiles, corners, anchorages, clip spacing, trim, flashings, closures, and special details. Distinguish between factory- and field-assembled work; show locations of exposed fasteners.

    a. Show roof-mounted items including roof hatches, equipment supports, pipe supports and penetrations, lighting fixtures, and items mounted on roof curbs.
    b. Show wall-mounted items including personnel doors, vehicular doors, windows, louvers, and lighting fixtures.

4. Accessory Drawings: Include details of the following items, at a scale of not less than 1-1/2 inches per 12 inches (1:8):

    a. Flashing and trim.
    b. Gutters.
    c. Downspouts.

C. Samples for Verification: For the following products:

1. Panels: Nominal 12 inches (300 mm) long by actual panel width. Include fasteners, closures, and other exposed panel accessories.
2. Flashing and Trim: Nominal 12 inches (300 mm) long. Include fasteners and other exposed accessories.
3. Vapor-Retarder Facings: Nominal 6-inch- (150-mm-) square Samples.
4. Windows: Full-size, nominal 12-inch- (300-mm-) long frame Samples showing typical profile.
5. Accessories: Nominal 12-inch- (300-mm-) long Samples for each type of accessory.

D. Door Schedule: For doors and frames. Use same designations indicated on Drawings. Include details of reinforcement.

E. Delegated-Design Submittal: For metal building systems.

1. Include analysis data indicating compliance with performance requirements and design data signed and sealed by the qualified professional engineer responsible for their preparation.

1.7 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer and erector.

B. Welding certificates.

C. Letter of Design Certification: Signed and sealed by a qualified professional engineer. Include the following:

1. Name and location of Project.
2. Order number.
3. Name of manufacturer.
4. Name of Contractor.
5. Building dimensions including width, length, height, and roof slope.
6. Indicate compliance with AISC standards for hot-rolled steel and AISI standards for cold-rolled steel, including edition dates of each standard.
7. Governing building code and year of edition.
8. Design Loads: Include dead load, roof live load, collateral loads, roof snow load, deflection, wind loads/speeds and exposure, seismic design category or effective peak velocity-related acceleration/peak acceleration, and auxiliary loads (cranes).
9. Load Combinations: Indicate that loads were applied acting simultaneously with concentrated loads, according to governing building code.
10. Building-Use Category: Indicate category of building use and its effect on load importance factors.

D. Erector Certificates: For qualified erector, from manufacturer.

E. Material Test Reports: For each of the following products:

1. Structural steel including chemical and physical properties.
2. Bolts, nuts, and washers including mechanical properties and chemical analysis.
3. Tension-control, high-strength, bolt-nut-washer assemblies.
4. Shop primers.
5. Nonshrink grout.

F. Source quality-control reports.

G. Sample Warranties: For special warranties.

1.8 CLOSEOUT SUBMITTALS

A. Maintenance Data: For metal panel finishes to include in maintenance manuals.

1.9 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer.

1. Accreditation: Manufacturer's facility accredited according to the International Accreditation Service's AC472, "Accreditation Criteria for Inspection Programs for Manufacturers of Metal Building Systems."
2. Engineering Responsibility: Preparation of comprehensive engineering analysis and Shop Drawings by a professional engineer who is legally qualified to practice in jurisdiction where Project is located.

B. Erector Qualifications: An experienced erector who specializes in erecting and installing work similar in material, design, and extent to that indicated for this Project and who is acceptable to manufacturer.

C. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
2. AWS D1.3, "Structural Welding Code - Sheet Steel."

1.10 DELIVERY, STORAGE, AND HANDLING

A. Deliver components, sheets, panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.

B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.

C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.

D. Protect foam-plastic insulation as follows:

1. Do not expose to sunlight, except to extent necessary for period of installation and concealment.
2. Protect against ignition at all times. Do not deliver foam-plastic insulation materials to Project site before installation time.
3. Complete installation and concealment of foam-plastic materials as rapidly as possible in each area of construction.

1.11 FIELD CONDITIONS

A. Weather Limitations: Proceed with panel installation only when weather conditions permit metal panels to be installed according to manufacturers' written instructions and warranty requirements.

1.12 WARRANTY

A. Special Warranty on Metal Panel Finishes: Manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Hunter units when tested according to ASTM D2244.
b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.

2. Finish Warranty Period: 25 years from date of Substantial Completion.

B. Special Weathertightness Warranty for Standing-Seam Metal Roof Panels: Manufacturer agrees to repair or replace standing-seam metal roof panel assemblies that leak or otherwise fail to remain weathertight within specified warranty period.

1. Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following:

1. Allied Steel Buildings.
2. American Buildings Co., a Nucor Company.
3. ARCO Building Systems.
4. CBC Steel Buildings, a Nucor Company.
5. Kirby Building Systems, a Nucor Company.
6. Nucor Building Systems.
7. Varco Pruden, a Division of BlueScope Buildings North America.
8. Vulcan Steel Structures, Inc.

B. Source Limitations: Obtain metal building system components, including primary and secondary framing and metal panel assemblies, from single source from single manufacturer.

2.2 SYSTEM DESCRIPTION

A. Provide a complete, integrated set of mutually dependent components and assemblies that form a metal building system capable of withstanding structural and other loads, thermally induced movement, and exposure to weather without failure or infiltration of water into building interior.

B. Primary-Frame Type:

1. Rigid Clear Span: Solid-member, structural-framing system without interior columns.

C. End-Wall Framing: Manufacturer's standard, for buildings not required to be expandable, consisting of primary frame, capable of supporting one-half of a bay design load, and end-wall columns.

D. End-Wall Framing: Engineer end walls to be expandable. Provide primary frame, capable of supporting full-bay design loads, and end-wall columns.

E. Secondary-Frame Type: Manufacturer's standard purlins and joists and exterior-framed (bypass) girts.

F. Eave Height: 21 feet, 10 inches (6.65 m).

G. Bay Spacing: As indicated on Drawings.

H. Roof Slope: 2 inch per 12 inches (2:12).

I. Roof System: Manufacturer's standard standing-seam, trapezoidal-rib**,** metal roof panels.

1. Liner Panels: Tapered rib.

J. Exterior Wall System: Manufacturer's standard foamed-insulation-core metal wall panels.

1. Liner Panels: Flush profile.

2.3 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design metal building system.

B. Structural Performance: Metal building systems shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated according to procedures in MBMA's "Metal Building Systems Manual."

1. Design Loads: As indicated on Drawings.
2. Deflection and Drift Limits: No greater than the following:

a. Purlins and Rafters: Vertical deflection of 1/240 of the span.
b. Girts: Horizontal deflection of 1/180 of the span.
c. Metal Roof Panels: Vertical deflection of 1/240 of the span.
d. Metal Wall Panels: Horizontal deflection of [**1/180**] [**1/240**] of the span.
e. Design secondary-framing system to accommodate deflection of primary framing and construction tolerances, and to maintain clearances at openings.
f. Lateral Drift: Maximum of [**1/120**] [**1/240**] of the building height.

C. Seismic Performance: Metal building system shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

E. Fire-Resistance Ratings: Where assemblies are indicated to have a fire-resistance rating, provide metal panel assemblies identical to those of assemblies tested for fire resistance per ASTM E119 or ASTM E108 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Indicate design designations from UL's "Fire Resistance Directory," FM Global's "Approval Guide," or from the listings of another qualified testing agency.

F. Fire Propagation Characteristics: Exterior wall assemblies containing foam plastics pass NFPA 285 fire test.

G. Structural Performance for Metal Roof and Wall Panels: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:

1. Wind Loads: As indicated on Drawings.

H. Air Infiltration for Metal Roof Panels: Air leakage of not more than 0.06 cfm/sq. ft. (0.3 L/s per sq. m) when tested according to ASTM E1680 at the following test-pressure difference:

1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).

I. Air Infiltration for Metal Wall Panels: Air leakage of not more than 0.06 cfm/sq. ft. (0.3 L/s per sq. m) when tested according to ASTM E283 at the following test-pressure difference:

1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).

J. Water Penetration for Metal Roof Panels: No water penetration when tested according to ASTM E1646 at the following test-pressure difference:

1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).

K. Water Penetration for Metal Wall Panels: No water penetration when tested according to ASTM E331 at the following test-pressure difference:

1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).

L. Wind-Uplift Resistance: Provide metal roof panel assemblies that comply with UL 580 for wind-uplift-resistance class indicated.

1. Uplift Rating: UL 90.

M. FM Global Listing: Provide metal roof panels and component materials that comply with requirements in FM Global 4471 as part of a panel roofing system and that are listed in FM

Global's "Approval Guide" for Class 1 or noncombustible construction, as applicable. Identify materials with FM Global markings.

1. Fire/Windstorm Classification: Class 1A-165.
2. Hail Resistance: SH.

N. Thermal Performance for Opaque Elements: Provide the following maximum U-factors and minimum R-values when tested according to ASTM C1363 or ASTM C518:

1. Roof:

   a. U-Factor: U-0.037 maximum.
   b. R-Value: R-19 plus R-11 Liner System or R-25 plus R-8 Liner System.

2. Walls:

   a. U-Factor: U-0.060 maximum.
   b. R-Value: R-0 plus R-15.8 continuous insulation.

2.4 STRUCTURAL-STEEL FRAMING

A. Structural Steel: Comply with AISC 360, "Specification for Structural Steel Buildings."

B. Bolted Connections: Comply with RCSC's "Specification for Structural Joints Using High-Strength Bolts."

C. Cold-Formed Steel: Comply with AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members" for design requirements and allowable stresses.

D. Primary Framing: Manufacturer's standard primary-framing system, designed to withstand required loads and specified requirements. Primary framing includes transverse and lean-to frames; rafters, rake, and canopy beams; sidewall, intermediate, end-wall, and corner columns; and wind bracing.

1. General: Provide frames with attachment plates, bearing plates, and splice members. Factory drill for field-bolted assembly. Provide frame span and spacing indicated.

   a. Slight variations in span and spacing may be acceptable if necessary to comply with manufacturer's standard, as approved by Architect.

2. Rigid Clear-Span Frames: I-shaped frame sections fabricated from shop-welded, built-up steel plates or structural-steel shapes. Interior columns are not permitted.
3. Frame Configuration: Single gable.
4. Exterior Column: Tapered.
5. Rafter: Tapered.

E. Secondary Framing: Manufacturer's standard secondary framing, including purlins, girts, eave struts, flange bracing, base members, gable angles, clips, headers, jambs, and other miscellaneous structural members. Unless otherwise indicated, fabricate framing from either

cold-formed, structural-steel sheet or roll-formed, metallic-coated steel sheet, prepainted with coil coating, to comply with the following:

1. Purlins: C- or Z-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes; minimum 2-1/2-inch- (64-mm-) wide flanges.

    a. Depth: As needed to comply with system performance requirements.

2. Girts: C- or Z-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes. Form ends of Z-sections with stiffening lips angled 40 to 50 degrees from flange, with minimum 2-1/2-inch- (64-mm-) wide flanges.

    a. Depth: As indicated on Drawings.

3. Eave Struts: Unequal-flange, C-shaped sections; fabricated from built-up steel plates, steel sheet, or structural-steel shapes; to provide adequate backup for metal panels.
4. Flange Bracing: Minimum 2-by-2-by-1/8-inch (51-by-51-by-3-mm) structural-steel angles or 1-inch- (25-mm-) diameter, cold-formed structural tubing to stiffen primary-frame flanges.
5. Sag Bracing: Minimum 1-by-1-by-1/8-inch (25-by-25-by-3-mm) structural-steel angles.
6. Base or Sill Angles: Manufacturer's standard base angle, minimum 3-by-2-inch (76-by-51-mm), fabricated from zinc-coated (galvanized) steel sheet.
7. Purlin and Girt Clips: Manufacturer's standard clips fabricated from steel sheet. Provide galvanized clips where clips are connected to galvanized framing members.
8. Framing for Openings: Channel shapes; fabricated from cold-formed, structural-steel sheet or structural-steel shapes. Frame head and jamb of door openings and head, jamb, and sill of other openings.
9. Miscellaneous Structural Members: Manufacturer's standard sections fabricated from cold-formed, structural-steel sheet; built-up steel plates; or zinc-coated (galvanized) steel sheet; designed to withstand required loads.

F. Bracing: Provide adjustable wind bracing using any method as follows:

1. Rods: ASTM A36/A36M; ASTM A572/A572M, Grade 50 (345); or ASTM A529/A529M, Grade 50 (345); minimum 1/2-inch- (13-mm-) diameter steel; threaded full length or threaded a minimum of 6 inches (152 mm) at each end.
2. Cable: ASTM A475, minimum 1/4-inch- (6-mm-) diameter, extra-high-strength grade, Class B, zinc-coated, seven-strand steel; with threaded end anchors.
3. Angles: Fabricated from structural-steel shapes to match primary framing, of size required to withstand design loads.
4. Rigid Portal Frames: Fabricated from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.
5. Fixed-Base Columns: Fabricated from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.

G. Anchor Rods: Headed anchor rods as indicated in Anchor Rod Plan for attachment of metal building to foundation.

H. Materials:

1. W-Shapes: ASTM A992/A992M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
2. Channels, Angles, M-Shapes, and S-Shapes: ASTM A36/A36M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
3. Plate and Bar: ASTM A36/A36M; ASTM A572/A572M, Grade 50 or 55 (345 or 380); or ASTM A529/A529M, Grade 50 or 55 (345 or 380).
4. Structural-Steel Sheet: Hot-rolled, ASTM A1011/A1011M, Structural Steel (SS), Grades 30 through 55 (205 through 380), or High-Strength Low-Alloy Steel (HSLAS) or High-Strength Low-Alloy Steel with Improved Formability (HSLAS-F), Grades 45 through 70 (310 through 480); or cold-rolled, ASTM A1008/A1008M, Structural Steel (SS), Grades 25 through 80 (170 through 550), or HSLAS, Grades 45 through 70 (310 through 480).
5. Metallic-Coated Steel Sheet: ASTM A653/A653M, SS, Grades 33 through 80 (230 through 550), or HSLAS or HSLAS-F, Grades 50 through 80 (340 through 550); with G60 (Z180) coating designation; mill phosphatized.
6. Metallic-Coated Steel Sheet Prepainted with Coil Coating: Steel sheet, metallic coated by the hot-dip process and prepainted by the coil-coating process to comply with ASTM A755/A755M.

    a. Zinc-Coated (Galvanized) Steel Sheet: ASTM A653/A653M, SS, Grades 33 through 80 (230 through 550), or HSLAS or HSLAS-F, Grades 50 through 80 (340 through 550); with G90 (Z275) coating designation.
    b. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A792/A792M, SS, Grade 50 or 80 (340 or 550); with Class AZ50 (AZM150) coating.

7. Non-High-Strength Bolts, Nuts, and Washers: ASTM A307, Grade A, carbon-steel, hex-head bolts; ASTM A563 (ASTM A563M) carbon-steel hex nuts; and ASTM F844 plain (flat) steel washers.

    a. Finish: Hot-dip zinc coating, ASTM F2329, Class C.

8. High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M,Grade A325 (Grade A325M), Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, (ASTM A563M, Class 10S) heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers.

    a. Finish: Hot-dip zinc coating, ASTM F2329, Class C.

9. High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A490 (Grade A490M), Type 1, heavy-hex steel structural bolts; ASTM A563, Grade DH, (ASTM A563M, Class 10S) heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers; all with plain finish.

10. Unheaded Anchor Rods: ASTM A572/A572M, Grade 50 (345).

    a. Configuration: Straight.
    b. Nuts: ASTM A563 (ASTM A563M) hex carbon steel.
    c. Plate Washers: ASTM A36/A36M carbon steel.
    d. Washers: ASTM F436 (ASTM F436M) hardened carbon steel.
    e. Finish: Hot-dip zinc coating, ASTM F2329, Class C.

11. Headed Anchor Rods: ASTM A307, Grade A.

    a. Configuration: Straight.
    b. Nuts: ASTM A563 (ASTM A563M) heavy-hex carbon steel.
    c. Plate Washers: ASTM A36/A36M carbon steel.
    d. Washers: ASTM F436 (ASTM F436M) hardened carbon steel.
    e. Finish: Hot-dip zinc coating, ASTM F2329, Class C.

12. Threaded Rods: ASTM A307, Grade A.

    a. Nuts: ASTM A563 (ASTM A563M) hex carbon steel.
    b. Washers: ASTM F436 (ASTM F436M) hardened carbon steel.
    c. Finish: Hot-dip zinc coating, ASTM F2329, Class C.

I. Finish: Factory primed. Apply specified primer immediately after cleaning and pretreating.

1. Clean and prepare in accordance with SSPC-SP2.
2. Coat with manufacturer's standard primer. Apply primer to primary and secondary framing to a minimum dry film thickness of 1 mil (0.025 mm).

    a. Prime secondary framing formed from uncoated steel sheet to a minimum dry film thickness of 0.5 mil (0.013 mm) on each side.

2.5 METAL ROOF PANELS

A. Standing-Seam, Vertical-Rib, Metal Roof Panels: Formed with vertical ribs at panel edges and flat pan between ribs; designed for sequential installation by mechanically attaching panels to supports using concealed clips located under one side of panels and engaging opposite edge of adjacent panels.

1. Material: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.024-inch (0.61-mm) nominal uncoated steel thickness. Prepainted by the coil-coating process to comply with ASTM A755/A755M.

    a. Exterior Finish: Two-coat fluoropolymer.
    b. Color: As selected by Architect from manufacturer's full range.

2. Clips: Two-piece floating to accommodate thermal movement.
3. Joint Type: Mechanically seamed.
4. Panel Coverage: 16 to 18 inches (406 to 457 mm).
5. Panel Height: 2 inches (51 mm).

B. Finishes:

1. Exposed Coil-Coated Finish:

    a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

2. Concealed Finish: Apply pretreatment and manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with a minimum total dry film thickness of 0.5 mil (0.013 mm).

2.6 METAL WALL PANELS

A. Concealed-Fastener, Flush-Profile, Metal Wall Panels: Formed with vertical panel edges and flush surface; with flush joint between panels; with 1-inch- (25-mm-) wide flange for attaching interior finish; designed to be installed by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners and factory-applied sealant in side laps.

1. Material: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.030-inch (0.76-mm) nominal uncoated steel thickness. Prepainted by the coil-coating process to comply with ASTM A755/A755M.

   a. Exterior Finish: Fluoropolymer.
   b. Color: As selected by Architect from manufacturer's full range.

2. Panel Coverage: 16 inches (406 mm).

B. Finishes:

1. Exposed Coil-Coated Finish:

   a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

2. Concealed Finish: Apply pretreatment and manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with a minimum total dry film thickness of 0.5 mil (0.013 mm).

2.7 FOAMED-INSULATION-CORE METAL WALL PANELS

A. Concealed-Fastener, Foamed-Insulation-Core Metal Wall Panels MWP-1: Formed with tongue-and-groove panel edges; designed for sequential installation by interlocking panel edges and mechanically attaching panels to supports using concealed clips or fasteners.

1. Panel Thermal-Resistance Value (R-Value): 17.5.
2. Facing Material: Fabricate panel with exterior and interior facings of same material and thickness. Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.024-inch (0.61-mm) nominal uncoated steel thickness. Prepainted by the coil-coating process to comply with ASTM A755/A755M.

   a. Exterior Surface: Smooth, flat.
   b. Exterior Finish: Two-coat fluoropolymer.
   c. Color: As selected by Architect from manufacturer's full range.

3. Panel Coverage: 36 inches (914 mm) nominal.
4. Panel Thickness: 2 inches (51 mm).
5. Insulation Core: Modified polyisocyanurate or polyurethane foam using a non-CFC blowing agent, foamed-in-place or board type, with maximum flame-spread and smoke-developed indexes of 25 and 450, respectively.

    a. Closed-Cell Content: 90 percent when tested according to ASTM D6226.
    b. Density: 2.0 to 2.6 lb/cu. ft. (32 to 42 kg/cu. m) when tested according to ASTM D1622.
    c. Compressive Strength: Minimum 20 psi (140 kPa) when tested according to ASTM D1621.
    d. Shear Strength: 26 psi (179 kPa) when tested according to ASTM C273/C273M.

6. Fire-Test-Response Characteristics: Class A according to ASTM E108.
7. Surface-Burning Characteristics: Flame-spread index of 25 or less and a smoke-developed index of 450 or less, per ASTM E84.

B. Concealed-Fastener, Foamed-Insulation-Core Metal Wall Panels MWP-2: Formed with tongue-and-groove panel edges; designed for sequential installation by interlocking panel edges and mechanically attaching panels to supports using concealed clips or fasteners.

1. Panel Thermal-Resistance Value (R-Value): 17.5.
2. Facing Material: Fabricate panel with exterior and interior facings of same material and thickness. Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.024-inch (0.61-mm) nominal uncoated steel thickness. Prepainted by the coil-coating process to comply with ASTM A755/A755M.

    a. Exterior Surface: Shallow ribs.
    b. Exterior Finish: Two-coat fluoropolymer.
    c. Color: As selected by Architect from manufacturer's full range..

3. Panel Coverage: 36 inches (914 mm) nominal.
4. Panel Thickness: 2 inches (51 mm).
5. Insulation Core: Modified polyisocyanurate or polyurethane foam using a non-CFC blowing agent, foamed-in-place or board type, with maximum flame-spread and smoke-developed indexes of 25 and 450, respectively.

    a. Closed-Cell Content: 90 percent when tested according to ASTM D6226.
    b. Density: 2.0 to 2.6 lb/cu. ft. (32 to 42 kg/cu. m) when tested according to ASTM D1622.
    c. Compressive Strength: Minimum 20 psi (140 kPa) when tested according to ASTM D1621.
    d. Shear Strength: 26 psi (179 kPa) when tested according to ASTM C273/C273M.

6. Fire-Test-Response Characteristics: Class A according to ASTM E108.
7. Surface-Burning Characteristics: Flame-spread index of 25 or less and a smoke-developed index of 450 or less, per ASTM E84.

C. Finishes:

1. Exposed Coil-Coated Finish:

a. Two-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

2. Concealed Finish: Apply pretreatment and manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with a minimum total dry film thickness of 0.5 mil (0.013 mm).

2.8 THERMAL INSULATION

A. Faced Metal Building Insulation: ASTM C991, Type II, glass-fiber-blanket insulation; 0.5-lb/cu. ft. (8-kg/cu. m) density; 2-inch- (51-mm-) wide, continuous, vapor-tight edge tabs; with a flame-spread index of 25 or less.

B. Retainer Strips: For securing insulation between supports, 0.025-inch (0.64-mm) nominal-thickness, formed, metallic-coated steel or PVC retainer clips colored to match insulation facing.

C. Vapor-Retarder Facing: ASTM C1136, with permeance not greater than 0.02 perm (1.15 ng/Pa x s x sq. m) when tested according to ASTM E96/E96M, Desiccant Method.

2.9 PERSONNEL DOORS AND FRAMES

A. Swinging Personnel Doors and Frames: As specified in Section 081113 "Hollow Metal Doors and Frames."

2.10 WINDOWS

A. Aluminum Windows: Metal building system manufacturer's standard, with self-flashing mounting fins, and as follows:

1. Type, Performance Class, and Performance Grade: Comply with AAMA/WDMA/CSA 101/I.S.2/A440 and as follows:

a. Fixed Units: FW-CW30.

2. Aluminum Extrusions: ASTM B221 (ASTM B221M), alloy and temper recommended by manufacturer for strength, corrosion resistance, and application of required finish, but not less than 0.064-inch (1.63-mm) thickness at any location for main frame and sash members.

a. Thermally Improved Construction: Fabricate window units with an integral, concealed, low-conductance thermal barrier; located between exterior materials

and window members exposed on interior side; in a manner that eliminates direct metal-to-metal contact.

3. Mullions: Between adjacent windows, fabricated of extruded aluminum matching finish of window units.
4. Fasteners, Anchors, and Clips: Nonmagnetic stainless steel, aluminum, or other noncorrosive material, compatible with aluminum window members, trim, hardware, anchors, and other components of window units. Fasteners shall not be exposed, except for attaching hardware.

    a. Reinforcement: Where fasteners screw-anchor into aluminum less than 0.128 inch (3.26 mm) thick, reinforce interior with aluminum or nonmagnetic stainless steel to receive screw threads, or provide standard, noncorrosive, pressed-in, spline grommet nuts.

B. Glazing: Comply with requirements specified in Section 088000 "Glazing."

C. Finish:

1. Baked-Enamel Finish, Organic Coating: Thermosetting, modified-acrylic enamel primer/topcoat system complying with AAMA 2603 except with a minimum dry film thickness of 0.7 mil (0.02 mm), medium gloss.

    a. Color: As selected by Architect from manufacturer's full range.

2.11 ACCESSORIES

A. General: Provide accessories as standard with metal building system manufacturer and as specified. Fabricate and finish accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes. Comply with indicated profiles and with dimensional and structural requirements.

1. Form exposed sheet metal accessories that are without excessive oil-canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.

B. Roof Panel Accessories: Provide components required for a complete metal roof panel assembly including copings, fasciae, corner units, ridge closures, clips, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal roof panels unless otherwise indicated.

1. Closures: Provide closures at eaves and ridges, fabricated of same material as metal roof panels.
2. Clips: Manufacturer's standard, formed from stainless-steel sheet, designed to withstand negative-load requirements.
3. Cleats: Manufacturer's standard, mechanically seamed cleats formed from stainless-steel sheet or nylon-coated aluminum sheet.
4. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.

5. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- (25-mm-) thick, flexible closure strips; cut or premolded to match metal roof panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.
6. Thermal Spacer Blocks: Where metal panels attach directly to purlins, provide thermal spacer blocks of thickness required to provide 1-inch (25-mm) standoff; fabricated from extruded polystyrene.

C. Wall Panel Accessories: Provide components required for a complete metal wall panel assembly including copings, fasciae, mullions, sills, corner units, clips, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal wall panels unless otherwise indicated.

1. Closures: Provide closures at eaves and rakes, fabricated of same material as metal wall panels.
2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- (25-mm-) thick, flexible closure strips; cut or premolded to match metal wall panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.

D. Flashing and Trim: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating; finished to match adjacent metal panels.

1. Provide flashing and trim as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, eaves, rakes, corners, bases, framed openings, ridges, fasciae, and fillers.
2. Opening Trim: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating. Trim head and jamb of door openings, and head, jamb, and sill of other openings.

E. Gutters: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating; finished to match roof fascia and rake trim. Match profile of gable trim, complete with end pieces, outlet tubes, and other special pieces as required. Fabricate in minimum 96-inch- (2438-mm-) long sections, sized according to SMACNA's "Architectural Sheet Metal Manual."

1. Gutter Supports: Fabricated from same material and finish as gutters.
2. Strainers: Bronze, copper, or aluminum wire ball type at outlets.

F. Downspouts: Zinc-coated (galvanized) or aluminum-zinc alloy-coated steel sheet, 0.018-inch (0.46-mm) nominal uncoated steel thickness, prepainted with coil coating; finished to match metal wall panels. Fabricate in minimum 10-foot- (3-m-) long sections, complete with formed elbows and offsets.

1. Mounting Straps: Fabricated from same material and finish as gutters.

G. Pipe Flashing: Premolded, EPDM pipe collar with flexible aluminum ring bonded to base.

H. Materials:

1. Fasteners: Self-tapping screws, bolts, nuts, self-locking rivets and bolts, end-welded studs, and other suitable fasteners designed to withstand design loads. Provide fasteners with heads matching color of materials being fastened by means of plastic caps or factory-applied coating.

    a. Fasteners for Metal Roof Panels: Self-drilling, Type 410 stainless steel or self-tapping, Type 304 stainless-steel or zinc-alloy-steel hex washer head, with EPDM washer under heads of fasteners bearing on weather side of metal panels.
    b. Fasteners for Metal Wall Panels: Self-drilling, Type 410 stainless steel or self-tapping, Type 304 stainless-steel or zinc-alloy-steel hex washer head, with EPDM sealing washers bearing on weather side of metal panels.
    c. Fasteners for Flashing and Trim: Blind fasteners or self-drilling screws with hex washer head.
    d. Blind Fasteners: High-strength aluminum or stainless-steel rivets.

2. Corrosion-Resistant Coating: Cold-applied asphalt mastic, compounded for 15-mil (0.4-mm) dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.
3. Nonmetallic, Shrinkage-Resistant Grout: ASTM C1107/C1107M, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.
4. Metal Panel Sealants:

    a. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene-compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape of manufacturer's standard size.
    b. Joint Sealant: ASTM C920; one part elastomeric polyurethane or polysulfide; of type, grade, class, and use classifications required to seal joints in metal panels and remain weathertight; and as recommended by metal building system manufacturer.

2.12 FABRICATION

A. General: Design components and field connections required for erection to permit easy assembly.

1. Mark each piece and part of the assembly to correspond with previously prepared erection drawings, diagrams, and instruction manuals.
2. Fabricate structural framing to produce clean, smooth cuts and bends. Punch holes of proper size, shape, and location. Members shall be free of cracks, tears, and ruptures.

B. Tolerances: Comply with MBMA's "Metal Building Systems Manual" for fabrication and erection tolerances.

C. Primary Framing: Shop fabricate framing components to indicated size and section, with baseplates, bearing plates, stiffeners, and other items required for erection welded into place. Cut, form, punch, drill, and weld framing for bolted field assembly.

1. Make shop connections by welding or by using high-strength bolts.

2. Join flanges to webs of built-up members by a continuous, submerged arc-welding process.
3. Brace compression flange of primary framing with steel angles or cold-formed structural tubing between frame web and purlin web or girt web, so flange compressive strength is within allowable limits for any combination of loadings.
4. Weld clips to frames for attaching secondary framing if applicable, or punch for bolts.
5. Shop Priming: Prepare surfaces for shop priming according to SSPC-SP 2. Shop prime primary framing with specified primer after fabrication.

D. Secondary Framing: Shop fabricate framing components to indicated size and section by roll forming or break forming, with baseplates, bearing plates, stiffeners, and other plates required for erection welded into place. Cut, form, punch, drill, and weld secondary framing for bolted field connections to primary framing.

1. Make shop connections by welding or by using non-high-strength bolts.
2. Shop Priming: Prepare uncoated surfaces for shop priming according to SSPC-SP 2. Shop prime uncoated secondary framing with specified primer after fabrication.

E. Metal Panels: Fabricate and finish metal panels at the factory to greatest extent possible, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements. Comply with indicated profiles and with dimensional and structural requirements.

1. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of metal panel.

2.13 SOURCE QUALITY CONTROL

A. Special Inspection: Owner will engage a qualified special inspector to perform source quality control inspections and to submit reports.

1. Accredited Manufacturers: Special inspections will not be required if fabrication is performed by an IAS AC472-accredited manufacturer approved by authorities having jurisdiction to perform such Work without special inspection.

a. After fabrication, submit copy of certificate of compliance to authorities having jurisdiction, certifying that Work was performed according to Contract requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with erector present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Before erection proceeds, survey elevations and locations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments to receive

structural framing, with erector present, for compliance with requirements and metal building system manufacturer's tolerances.

1. Engage land surveyor to perform surveying.

C. Proceed with erection only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean and prepare surfaces to be painted according to manufacturer's written instructions for each particular substrate condition.

B. Provide temporary shores, guys, braces, and other supports during erection to keep structural framing secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural framing, connections, and bracing are in place unless otherwise indicated.

3.3 ERECTION OF STRUCTURAL FRAMING

A. Erect metal building system according to manufacturer's written instructions and drawings.

B. Do not field cut, drill, or alter structural members without written approval from metal building system manufacturer's professional engineer.

C. Set structural framing accurately in locations and to elevations indicated, according to AISC specifications referenced in this Section. Maintain structural stability of frame during erection.

D. Base and Bearing Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.

1. Set plates for structural members on wedges, shims, or setting nuts as required.
2. Tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
3. Promptly pack grout solidly between bearing surfaces and plates so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for shrinkage-resistant grouts.

E. Align and adjust structural framing before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that will be in permanent contact with framing. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.

1. Level and plumb individual members of structure.
2. Make allowances for difference between temperature at time of erection and mean temperature when structure will be completed and in service.

F. Primary Framing and End Walls: Erect framing level, plumb, rigid, secure, and true to line. Level baseplates to a true even plane with full bearing to supporting structures, set with double-

nutted anchor bolts. Use grout to obtain uniform bearing and to maintain a level base-line elevation. Moist-cure grout for not less than seven days after placement.

1. Make field connections using high-strength bolts installed according to RCSC's "Specification for Structural Joints Using High-Strength Bolts" for bolt type and joint type specified.

    a. Joint Type: Snug tightened or pretensioned as required by manufacturer.

G. Secondary Framing: Erect framing level, plumb, rigid, secure, and true to line. Field bolt secondary framing to clips attached to primary framing.

1. Provide rake or gable purlins with tight-fitting closure channels and fasciae.
2. Locate and space wall girts to suit openings such as doors and windows.
3. Provide supplemental framing at entire perimeter of openings, including doors, windows, louvers, ventilators, and other penetrations of roof and walls.

H. Bracing: Install bracing in roof and sidewalls where indicated on erection drawings.

1. Tighten rod and cable bracing to avoid sag.
2. Locate interior end-bay bracing only where indicated.

I. Framing for Openings: Provide shapes of proper design and size to reinforce openings and to carry loads and vibrations imposed, including equipment furnished under mechanical and electrical work. Securely attach to structural framing.

J. Erection Tolerances: Maintain erection tolerances of structural framing within AISC 303.

3.4 METAL PANEL INSTALLATION, GENERAL

A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.

B. On-Site Fabrication: Subject to compliance with requirements of this Section, metal panels may be fabricated on-site using UL-certified, portable roll-forming equipment if panels are of same profile and warranted by manufacturer to be equal to factory-formed panels. Fabricate according to equipment manufacturer's written instructions and to comply with details shown.

C. Examination: Examine primary and secondary framing to verify that structural-panel support members and anchorages have been installed within alignment tolerances required by manufacturer.

1. Examine roughing-in for components and systems penetrating metal panels, to verify actual locations of penetrations relative to seams before metal panel installation.

D. General: Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.

1. Field cut metal panels as required for doors, windows, and other openings. Cut openings as small as possible, neatly to size required, and without damage to adjacent metal panel finishes.

a. Field cutting of metal panels by torch is not permitted unless approved in writing by manufacturer.

2. Install metal panels perpendicular to structural supports unless otherwise indicated.
3. Flash and seal metal panels with weather closures at perimeter of openings and similar elements. Fasten with self-tapping screws.
4. Locate and space fastenings in uniform vertical and horizontal alignment.
5. Locate metal panel splices over structural supports with end laps in alignment.
6. Lap metal flashing over metal panels to allow moisture to run over and off the material.

E. Lap-Seam Metal Panels: Install screw fasteners using power tools with controlled torque adjusted to compress EPDM washers tightly without damage to washers, screw threads, or metal panels. Install screws in predrilled holes.

1. Arrange and nest side-lap joints so prevailing winds blow over, not into, lapped joints. Lap ribbed or fluted sheets one full rib corrugation. Apply metal panels and associated items for neat and weathertight enclosure. Avoid "panel creep" or application not true to line.

F. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with corrosion-resistant coating, by applying rubberized-asphalt underlayment to each contact surface, or by other permanent separation as recommended by metal roof panel manufacturer.

G. Joint Sealers: Install gaskets, joint fillers, and sealants where indicated and where required for weatherproof performance of metal panel assemblies. Provide types of gaskets, fillers, and sealants indicated; or, if not indicated, provide types recommended by metal panel manufacturer.

1. Seal metal panel end laps with double beads of tape or sealant the full width of panel. Seal side joints where recommended by metal panel manufacturer.
2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

3.5 METAL ROOF PANEL INSTALLATION

A. General: Provide metal roof panels of full length from eave to ridge unless otherwise indicated or restricted by shipping limitations.

1. Install ridge caps as metal roof panel work proceeds.
2. Flash and seal metal roof panels with weather closures at eaves and rakes. Fasten with self-tapping screws.

B. Standing-Seam Metal Roof Panels: Fasten metal roof panels to supports with concealed clips at each standing-seam joint, at location and spacing and with fasteners recommended by manufacturer.

1. Install clips to supports with self-drilling or self-tapping fasteners.
2. Install pressure plates at locations indicated in manufacturer's written installation instructions.
3. Snap Joint: Nest standing seams and fasten together by interlocking and completely engaging factory-applied sealant.
4. Seamed Joint: Crimp standing seams with manufacturer-approved motorized seamer tool so that clip, metal roof panel, and factory-applied sealant are completely engaged.
5. Rigidly fasten eave end of metal roof panels and allow ridge end free movement for thermal expansion and contraction. Predrill panels for fasteners.
6. Provide metal closures at peaks, rake edges and each side of ridge caps.

C. Lap-Seam Metal Roof Panels: Fasten metal roof panels to supports with exposed fasteners at each lapped joint, at location and spacing recommended by manufacturer.

1. Provide metal-backed sealing washers under heads of exposed fasteners bearing on weather side of metal roof panels.
2. Provide sealant tape at lapped joints of metal roof panels and between panels and protruding equipment, vents, and accessories.
3. Apply a continuous ribbon of sealant tape to weather-side surface of fastenings on end laps and on side laps of nesting-type metal panels, on side laps of ribbed or fluted metal panels, and elsewhere as needed to make metal panels weatherproof to driving rains.
4. At metal panel splices, nest panels with minimum 6-inch (152-mm) end lap, sealed with butyl-rubber sealant and fastened together by interlocking clamping plates.

D. Metal Fascia Panels: Align bottom of metal panels and fasten with blind rivets, bolts, or self-drilling or self-tapping screws. Flash and seal metal panels with weather closures where fasciae meet soffits, along lower panel edges, and at perimeter of all openings.

E. Metal Roof Panel Installation Tolerances: Shim and align metal roof panels within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m) on slope and location lines and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.

3.6 METAL WALL PANEL INSTALLATION

A. General: Install metal wall panels in orientation, sizes, and locations indicated on Drawings. Install panels perpendicular to girts, extending full height of building, unless otherwise indicated. Anchor metal wall panels and other components of the Work securely in place, with provisions for thermal and structural movement.

1. Unless otherwise indicated, begin metal panel installation at corners with center of rib lined up with line of framing.
2. Shim or otherwise plumb substrates receiving metal wall panels.
3. When two rows of metal panels are required, lap panels 4 inches (102 mm) minimum.
4. When building height requires two rows of metal panels at gable ends, align lap of gable panels over metal wall panels at eave height.

5. Rigidly fasten base end of metal wall panels and allow eave end free movement for thermal expansion and contraction. Predrill panels.
6. Flash and seal metal wall panels with weather closures at eaves and rakes, and at perimeter of all openings. Fasten with self-tapping screws.
7. Install screw fasteners in predrilled holes.
8. Install flashing and trim as metal wall panel work proceeds.
9. Apply elastomeric sealant continuously between metal base channel (sill angle) and concrete, and elsewhere as indicated on Drawings; if not indicated, as necessary for waterproofing.
10. Align bottom of metal wall panels and fasten with blind rivets, bolts, or self-drilling or self-tapping screws.
11. Provide weatherproof escutcheons for pipe and conduit penetrating exterior walls.

B. Metal Wall Panels: Install metal wall panels on exterior side of girts. Attach metal wall panels to supports with fasteners as recommended by manufacturer.

C. Insulated Metal Wall Panels: Install insulated metal wall panels on exterior side of girts. Attach panels to supports at each panel joint using concealed clip and fasteners at maximum 42 inches (1067 mm) o.c., spaced not more than manufacturer's recommendation. Fully engage tongue and groove of adjacent insulated metal wall panels.

1. Install clips to supports with self-tapping fasteners.
2. Apply continuous ribbon of sealant to panel joint on concealed side of insulated metal wall panels as vapor seal; apply sealant to panel joint on exposed side of panels as weather seal.

D. Installation Tolerances: Shim and align metal wall panels within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m), noncumulative; level, plumb, and on location lines; and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.

3.7 THERMAL INSULATION INSTALLATION

A. General: Install insulation concurrently with metal panel installation, in thickness indicated to cover entire surface, according to manufacturer's written instructions.

1. Set vapor-retarder-faced units with vapor retarder toward warm side of construction unless otherwise indicated. Do not obstruct ventilation spaces except for firestopping.
2. Tape joints and ruptures in vapor retarder, and seal each continuous area of insulation to the surrounding construction to ensure airtight installation.
3. Install factory-laminated, vapor-retarder-faced blankets straight and true in one-piece lengths, with both sets of facing tabs sealed, to provide a complete vapor retarder.

B. Blanket Roof Insulation: Comply with the following installation method:

1. Two-Layers-between-Purlin-with-Spacer-Block Installation: Extend insulation and vapor retarder between purlins. Carry vapor-retarder-facing tabs up and over purlin, overlapping adjoining facing of next insulation course and maintaining continuity of retarder. Install layer of filler insulation over first layer to fill space between purlins formed by thermal spacer blocks. Hold in place with bands and crossbands below insulation.

a. Thermal Spacer Blocks: Where metal roof panels attach directly to purlins, install thermal spacer blocks.

2. Retainer Strips: Install retainer strips at each longitudinal insulation joint, straight and taut, nesting with secondary framing to hold insulation in place.

3.8 DOOR AND FRAME INSTALLATION

A. General: Install doors and frames plumb, rigid, properly aligned, and securely fastened in place according to manufacturers' written instructions. Coordinate installation with wall flashings and other components. Seal perimeter of each door frame with elastomeric sealant used for metal wall panels.

B. Personnel Doors and Frames: Install doors and frames according to NAAMM-HMMA 840. Fit non-fire-rated doors accurately in their respective frames, with the following clearances:

1. Between Doors and Frames at Jambs and Head: 1/8 inch (3 mm).
2. At Door Sills with Threshold: 3/8 inch (9.5 mm).

3.9 WINDOW INSTALLATION

A. General: Install windows plumb, rigid, properly aligned, without warp or rack of frames or sash, and securely fasten in place according to manufacturer's written instructions. Coordinate installation with wall flashings and other components. Seal perimeter of each window frame with elastomeric sealant used for metal wall panels.

1. Separate dissimilar materials from sources of corrosion or electrolytic action at points of contact with other materials by complying with requirements specified in AAMA/WDMA/CSA 101/I.S.2/A440.

B. Set sill members in bed of sealant or with gaskets, for weathertight construction.

C. Install windows and components to drain condensation, water penetrating joints, and moisture migrating within windows to the exterior.

D. Mount screens directly to frames with tapped screw clips.

3.10 ACCESSORY INSTALLATION

A. General: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

1. Install components required for a complete metal roof panel assembly, including trim, copings, ridge closures, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items.
2. Install components for a complete metal wall panel assembly, including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items.

3. Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with corrosion-resistant coating, by applying rubberized-asphalt underlayment to each contact surface, or by other permanent separation as recommended by manufacturer.

B. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.

1. Install exposed flashing and trim that is without excessive oil-canning, buckling, and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof and weather-resistant performance.
2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet (3 m) with no joints allowed within 24 inches (600 mm) of corner or intersection. Where lapped or bayonet-type expansion provisions cannot be used or would not be sufficiently weather resistant and waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with mastic sealant (concealed within joints).

C. Gutters: Join sections with riveted-and-soldered or lapped-and-sealed joints. Attach gutters to eave with gutter hangers spaced as required for gutter size, but not more than 36 inches (914 mm) o.c. using manufacturer's standard fasteners. Provide end closures and seal watertight with sealant. Provide for thermal expansion.

D. Downspouts: Join sections with 1-1/2-inch (38-mm) telescoping joints. Provide fasteners designed to hold downspouts securely 1 inch (25 mm) away from walls; locate fasteners at top and bottom and at approximately 60 inches (1524 mm) o.c. in between.

1. Tie downspouts to underground drainage system indicated.

E. Continuous Roof Ventilators: Set ventilators complete with necessary hardware, anchors, dampers, weather guards, rain caps, and equipment supports. Join sections with splice plates and end-cap skirt assemblies where required to achieve indicated length. Install preformed filler strips at base to seal ventilator to metal roof panels.

F. Pipe Flashing: Form flashing around pipe penetration and metal roof panels. Fasten and seal to panel as recommended by manufacturer.

3.11 FIELD QUALITY CONTROL

A. Special Inspections: Owner will engage a qualified special inspector to perform field quality control special inspections and to submit reports.

B. Product will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.12 ADJUSTING

A. Doors: After completing installation, test and adjust doors to operate easily, free of warp, twist, or distortion.

B. Roof Ventilators: After completing installation, including work by other trades, lubricate, test, and adjust units to operate easily, free of warp, twist, or distortion as needed to provide fully functioning units.

3.13 CLEANING AND PROTECTION

A. Repair damaged galvanized coatings on galvanized items with galvanized repair paint according to ASTM A780/A780M and manufacturer's written instructions.

B. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

C. Touchup Painting: After erection, promptly clean, prepare, and prime or reprime field connections, rust spots, and abraded surfaces of prime-painted structural framing, bearing plates, and accessories.

1. Clean and prepare surfaces by SSPC-SP 2, "Hand Tool Cleaning," or by SSPC-SP 3, "Power Tool Cleaning."
2. Apply a compatible primer of same type as shop primer used on adjacent surfaces.

D. Metal Panels: Remove temporary protective coverings and strippable films, if any, as metal panels are installed. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

1. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

E. Doors and Frames: Immediately after installation, sand rusted or damaged areas of prime coat until smooth and apply touchup of compatible air-drying primer.

1. Immediately before final inspection, remove protective wrappings from doors and frames.

F. Windows: Clean metal surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances. Clean factory-glazed glass immediately after installing windows.

END OF SECTION 133419